CORE JAVA

Early Release
RAW & UNEDITED

Volume II: Advanced Features

THIRTEENTH EDITION

ORACLE

Cay S. Horstmann

1. About This eBook

ePUB is an open, industry-standard format for eBooks. However, support of ePUB and its many features varies across reading devices and applications. Use your device or app settings to customize the presentation to your liking. Settings that you can customize often include font, font size, single or double column, landscape or portrait mode, and figures that you can click or tap to enlarge. For additional information about the settings and features on your reading device or app, visit the device manufacturer’s Web site.

Many titles include programming code or configuration examples. To optimize the presentation of these elements, view the eBook in single-column, landscape mode and adjust the font size to the smallest setting.

Core Java

Volume II—Advanced Features

Thirteenth Edition

Cay S. Horstmann

Hoboken, New Jersey

Cover image: Leyland/Shutterstock

Many of the designations used by manufacturers and sellers to distinguish their products are claimed as trademarks. Where those designations appear in this book, and the publisher was aware of a trademark claim, the designations have been printed with initial capital letters or in all capitals.

The author and publisher have taken care in the preparation of this book, but make no expressed or implied warranty of any kind and assume no responsibility for errors or omissions. No liability is assumed for incidental or consequential damages in connection with

or arising out of the use of the information or programs contained herein.

The views expressed in this book are those of the author and do not necessarily reflect the views of Oracle.

For information about buying this title in bulk quantities, or for special sales opportunities (which may include electronic versions; custom cover designs; and content particular to your business, training goals, marketing focus, or branding interests), please contact our corporate sales department at corpsales@pearsoned.com or (800) 382-3419.

For government sales inquiries, please contact governmentsales@pearsoned.com. For questions about sales outside the U.S., please contact intlcs@pearson.com.

Please contact us with concerns about any potential bias at pearson.com/report-bias.html.

Visit us on the Web: informit.com/aw

Copyright © 2024 Pearson Education, Inc.

Portions copyright © 1996-2013 Oracle and/or its affiliates. All Rights Reserved.

Oracle America Inc. does not make any representations or warranties as to the accuracy, adequacy or completeness of any information contained in this work, and is not responsible for any errors or omissions.

Microsoft and/or its respective suppliers make no representations about the suitability of the information contained in the documents and related graphics published as part of the services for any purpose. All such documents and related graphics are provided "as is" without warranty of any kind. Microsoft and/or its respective suppliers hereby disclaim all warranties and conditions with regard to this information, including all warranties and conditions of merchantability, whether express, implied or statutory, fitness for a particular purpose, title and non-infringement. In no event shall Microsoft and/or its respective suppliers be liable for any special, indirect or consequential damages or any damages whatsoever resulting from loss of use, data or profits, whether in an action of contract, negligence or other tortious action, arising out of or in connection with the use or performance of information available from the services. The documents and related graphics contained herein could include technical inaccuracies or typographical errors. Changes are periodically added to the information herein. Microsoft and/or its respective suppliers may make improvements and/or changes in the product(s) and/or the program(s) described herein at

any time. Partial screen shots may be viewed in full within the software version specified.

Microsoft® Windows®, and Microsoft Office® are registered trademarks of the Microsoft Corporation in the U.S.A. and other countries. This book is not sponsored or endorsed by or affiliated with the Microsoft Corporation.

All rights reserved. This publication is protected by copyright, and permission must be obtained from the publisher prior to any prohibited reproduction, storage in a retrieval system, or transmission in any form or by any means, electronic, mechanical, photocopying, recording, or likewise. For information regarding permissions, request forms and the appropriate contacts within the Pearson Education Global Rights & Permissions Department, please visit www.pearson.com/permissions.

ISBN-13: 978-0-13-537172-5
ISBN-10: 0-13-537172-4

1. Table of Contents

1. Preface
    1. To the Reader
    2. A Tour of This Book
    3. Conventions
2. Acknowledgments
    1. 1.1. From Iterating to Stream Operations
    2. 1.2. Stream Creation
    3. 1.3. The `filter`, `map`, and `flatMap` Methods
    4. 1.4. Extracting Substreams and Combining Streams
    5. 1.5. Other Stream Transformations
    6. 1.6. Simple Reductions
    7. 1.7. The Optional Type
    8. 1.8. Collecting Results
    9. 1.9. Collecting into Maps
    10. 1.10. Grouping and Partitioning
    11. 1.11. Downstream Collectors
    12. 1.12. Reduction Operations
    13. 1.13. Primitive Type Streams
    14. 1.14. Parallel Streams
3. 2. Input and Output
    1. 2.1. Input/Output Streams
    2. 2.2. Reading and Writing Binary Data

    3. 2.3. Object Input/Output Streams and Serialization
    4. 2.4. Working with Files
    5. 2.5. Memory-Mapped Files
    6. 2.6. File Locking
    7. 2.7. Regular Expressions
4. 3. XML
    1. 3.1. Introducing XML
    2. 3.2. The Structure of an XML Document
    3. 3.3. Parsing an XML Document
    4. 3.4. Validating XML Documents
    5. 3.5. Locating Information with XPath
    6. 3.6. Using Namespaces
    7. 3.7. Streaming Parsers
    8. 3.8. Generating XML Documents
    9. 3.9. XSL Transformations
5. 4. Networking
    1. 4.1. Connecting to a Server
    2. 4.2. Implementing Servers
    3. 4.3. Getting Web Data
    4. 4.4. The HTTP Client
    5. 4.5. The Simple HTTP Server
    6. 4.6. Sending E-Mail
6. 5. Database Programming
    1. 5.1. The Design of JDBC

2. 5.2. The Structured Query Language
3. 5.3. JDBC Configuration
4. 5.4. Working with JDBC Statements
5. 5.5. Query Execution
6. 5.6. Scrollable and Updatable Result Sets
7. 5.7. Row Sets
8. 5.8. Metadata
9. 5.9. Transactions
10. 5.10. Connection Management in Web and Enterprise Applications

7. 6. The Date and Time API
    1. 6.1. The Time Line
    2. 6.2. Local Dates
    3. 6.3. Date Adjusters
    4. 6.4. Local Time
    5. 6.5. Zoned Time
    6. 6.6. Formatting and Parsing
    7. 6.7. Interoperating with Legacy Code
8. 7. Internationalization
    1. 7.1. Locales
    2. 7.2. Number Formats
    3. 7.3. Date and Time
    4. 7.4. Collation and Normalization
    5. 7.5. Message Formatting

6. 7.6. Text Boundaries
7. 7.7. Text Input and Output
8. 7.8. Resource Bundles
9. 7.9. A Complete Example

9. 8. Compiling and Scripting
    1. 8.1. The Compiler API
    2. 8.2. Scripting for the Java Platform
10. 9. Security
    1. 9.1. Class Loaders
    2. 9.2. User Authentication
    3. 9.3. Digital Signatures
    4. 9.4. Encryption
11. 10. Graphical User Interface Programming
    1. 10.1. A History of Java User Interface Toolkits
    2. 10.2. Displaying Frames
    3. 10.3. Displaying Information in a Component
    4. 10.4. Event Handling
    5. 10.5. The Preferences API
12. 11. User Interface Components with Swing
    1. 11.1. Swing and the Model-View-Controller Design Pattern
    2. 11.2. Introduction to Layout Management
    3. 11.3. Text Input
    4. 11.4. Choice Components
    5. 11.5. Menus

6. 11.6. The Grid Bag Layout
7. 11.7. Custom Layout Managers
8. 11.8. Dialog Boxes

13. 12. Advanced Swing and Graphics
    1. 12.1. Tables
    2. 12.2. Working with Rows and Columns
    3. 12.3. Cell Rendering and Editing
    4. 12.4. Trees
    5. 12.5. Advanced AWT
    6. 12.6. Raster Images
    7. 12.7. Printing
14. 13. Native Methods
    1. 13.1. Calling a C Function from a Java Program
    2. 13.2. Numeric Parameters and Return Values
    3. 13.3. String Parameters
    4. 13.4. Accessing Fields
    5. 13.5. Encoding Signatures
    6. 13.6. Calling Java Methods
    7. 13.7. Accessing Array Elements
    8. 13.8. Handling Errors
    9. 13.9. Using the Invocation API
    10. 13.10. A Complete Example: Accessing the Windows Registry
    11. 13.11. Foreign Functions: A Glimpse into the Future

1. Preface

1.1. To the Reader

The book you have in your hands is the second volume of the thirteenth edition of *Core Java*, fully updated for Java 21. The first volume covers the essential features of the language; this volume deals with the advanced topics that a programmer needs to know for professional software development. Thus, as with the first volume and the previous editions of this book, we are still targeting programmers who want to put Java technology to work in real projects.

With the explosive growth of the Java class library, a one-volume treatment of all the features of Java that serious programmers need to know is simply not possible. Hence, the book is broken up into two volumes.

This first volume concentrates on the fundamental concepts of the Java language:

- Object-oriented programming
- Reflection and proxies
- Interfaces and inner classes
- Exception handling

- Generic programming
- The collections framework
- Concurrency
- Annotations
- The Java platform module system

This second volume goes further into the most important libraries. For twelve editions, user-interface programming was considered fundamental, but the time has come to recognize that it is no more, and to move it into the second volume. The volume includes detailed discussions of these topics:

- The Stream API
- File processing and regular expressions
- Databases
- XML processing
- Scripting and Compiling APIs
- Internationalization
- Network programming
- Graphical user interface design
- Graphics programming
- Native methods

As is the case with any book, errors and inaccuracies are inevitable. Should you find any in this book, we would very much like to hear

about them. Of course, we would prefer to hear about them only once. For this reason, we have put up a web site at https://horstmann.com/corejava with a FAQ, bug fixes, and workarounds. Strategically placed at the end of the bug report web page (to encourage you to read the previous reports) is a form that you can use to report bugs or problems and to send suggestions for improvements for future editions.

1.2. A Tour of This Book

The chapters in this book are, for the most part, independent of each other. You should be able to delve into whatever topic interests you the most and read the chapters in any order.

In **Chapter 1**, you will learn all about the Java stream library that brings a modern flavor to processing data, by specifying what you want without describing in detail how the result should be obtained. This allows the stream library to focus on an optimal evaluation strategy, which is particularly advantageous for executing computations in parallel with multiple cores.

The topic of **Chapter 2** is input and output handling (I/O). In Java, all input and output is handled through input/output streams. These streams (not to be confused with those in Chapter 1) let you deal, in a uniform manner, with communications among various sources of data, such as files, network connections, or memory blocks. We include detailed coverage of the reader and writer classes that make it easy to deal with Unicode. We show you what goes on under the hood when you use the object serialization mechanism, which makes saving and loading objects easy and convenient. We then move on to regular expressions and working with files and paths. Throughout this chapter, you will find welcome enhancements in recent Java versions.

Chapter 3 covers XML. We show you how to parse XML files, how to generate XML, and how to use XSL transformations. As a useful example, we show you how to specify the layout of a Swing form in XML. We also discuss the XPath API, which makes finding needles in XML haystacks much easier.

Chapter 4 covers the networking API. Java makes it phenomenally easy to do complex network programming. We show you how to make network connections to servers, how to implement your own servers, and how to make HTTP connections. This chapter includes coverage of the new HTTP client.

Chapter 5 covers database programming. The focus is on JDBC, the Java database connectivity API that lets Java programs connect to relational databases. We show you how to write useful programs to handle realistic database chores, using a core subset of the JDBC API. (A complete treatment of the JDBC API would require a book almost as big as this one.)

Java had two prior attempts at libraries for handling date and time. The third one was the charm in Java 8. In **Chapter 6**, you will learn how to deal with the complexities of calendars and time zones, using the new date and time library.

Chapter 7 discusses a feature that we believe can only grow in importance: internationalization. The Java programming language is one of the few languages designed from the start to handle Unicode, but the internationalization support on the Java platform goes much further. As a result, you can internationalize Java applications so that they cross not only platforms but country boundaries as well. For example, we show you how to write a retirement calculator that uses either English, German, or Chinese languages.

Chapter 8 discusses the scripting and compiler APIs that allow your program to call code in scripting languages such as JavaScript or Groovy, and to compile Java code.

Chapter 9 takes up the Java security model, user authentication, and the cryptographic functions in the Java security library. You will learn about important features such as message and code signing, authorization and authentication, and encryption. We conclude with examples that use the AES and RSA encryption algorithms.

Chapter 10 provides an introduction into GUI programming. I show how you can make windows, how to paint on them, how to draw with geometric shapes, how to format text in multiple fonts, and how to display images. Next, you'll see how to write code that responds to events, such as mouse clicks or key presses.

Chapter 11 discusses the Swing GUI toolkit in great detail. The Swing toolkit allows you to build cross-platform graphical user interfaces. You'll learn all about the various kinds of buttons, text components, borders, sliders, list boxes, menus, and dialog boxes.

Chapter 12 contains advanced Swing material, especially the important but complex tree and table components. We also cover the Java 2D API, which you can use to create realistic drawings and special effects. Of course, not many programmers need to program Swing user interfaces these days, so we pay particular attention to features that are useful for images that can be generated on a server.

Chapter 13 takes up native methods, which let you call methods written for a specific machine such as the Microsoft Windows API. Obviously, this feature is controversial: Use native methods, and the cross-platform nature of Java vanishes. Nonetheless, every serious programmer writing Java applications for specific platforms needs to know these techniques. At times, you need to turn to the operating system's API for your target platform when you interact with a device or service that is not supported by Java. We illustrate this by showing you how to access the registry API in Windows from a Java program. The chapter ends with a glimpse of the “Panama” API which will replace the current API in a future version of Java.

As always, all chapters have been completely revised for the latest version of Java. Outdated material has been removed, and the new APIs up to Java 21 are covered in detail.

1.3. Conventions

As is common in many computer books, I use `monospace type` to represent computer code.

Note: Notes are tagged with "note" icons that look like this.

Tip: Tips are tagged with "tip" icons that look like this.

Caution: When there is danger ahead, I warn you with a "caution" icon.

Preview Note: Preview features that are slated to become a part of the language or API in the future are labeled with this icon.

C++ Note: There are a number of C++ notes that explain the difference between the Java programming language and C++. You

can skip them if you aren't interested in C++.

Java comes with a large programming library, or Application Programming Interface (API). When using an API call for the first time, I add a short summary description at the end of the section. These descriptions are a bit more informal but, hopefully, also a little more informative than those in the official online API documentation. The names of interfaces are in italics, just like in the official documentation. The number after a class, interface, or method name is the JDK version in which the feature was introduced, as shown in the following example:

```
Application Programming Interface 1.2
```

Programs whose source code is included in the companion code for this book are listed as examples, for instance

---

Listing 1.1 NotHelloWorld.java

```
1 void main()
2 {
3    System.out.println("We will not use 'Hello,
4 }
```

You can download the companion code from https://horstmann.com/corejava.

1. Acknowledgments

Writing a book is always a monumental effort, and rewriting doesn't seem to be much easier, especially with such a rapid rate of change in Java technology. Making a book a reality takes many dedicated people, and it is my great pleasure to acknowledge the contributions of the entire *Core Java* team.

A large number of individuals at Pearson provided valuable assistance but managed to stay behind the scenes. I'd like them all to know how much I appreciate their efforts. As always, my warm thanks go to my editor, Greg Doench, for steering the book through the writing and production process, and for allowing me to be blissfully unaware of the existence of all those folks behind the scenes. I am very grateful to Julie Nahil for production support, and to Dmitry Kirsanov and Alina Kirsanova for copyediting the manuscript. I wrote the book using HTML and CSS, and Prince (https://princexml.com) turned it into PDF—a workflow that I highly recommend. My thanks also to my coauthor of earlier editions, Gary Cornell, who has since moved on to other ventures.

Thanks to the many readers of earlier editions who reported embarrassing errors and made lots of thoughtful suggestions for improvement. I am particularly grateful to the excellent reviewing

team that went over the manuscript with an amazing eye for detail and saved me from many more embarrassing errors.

Reviewers of this and earlier editions include Chuck Allison (Utah Valley University), Lance Andersen (Oracle), Gail Anderson (Anderson Software Group), Paul Anderson (Anderson Software Group), Alec Beaton (IBM), Cliff Berg, Andrew Binstock (Oracle), Joshua Bloch, David Brown, Corky Cartwright, Frank Cohen (PushToTest), Chris Crane (devXsolution), Dr. Nicholas J. De Lillo (Manhattan College), Rakesh Dhoopar (Oracle), Ahmad R. Elkomey, Robert Evans (Senior Staff, The Johns Hopkins University Applied Physics Lab), David Geary (Clarity Training), Jim Gish (Oracle), Brian Goetz (Oracle), Angela Gordon, Dan Gordon (Electric Cloud), Rob Gordon, John Gray (University of Hartford), Cameron Gregory (olabs.com), Andrzej Grzesik, Marty Hall (coreservlets.com, Inc.), Vincent Hardy (Adobe Systems), Dan Harkey (San Jose State University), Steve Haines, William Higgins (IBM), Marc Hoffmann (mtrail), Vladimir Ivanovic (PointBase), Jerry Jackson (CA Technologies), Heinz Kabutz (Java Specialists), Stepan V. Kalinin (I-Teco/Servionica LTD), Tim Kimmet (Walmart), John Kostaras, Jerzy Krolak, Chris Laffra, Charlie Lai (Apple), Angelika Langer, Jeff Langr (Langr Software Solutions), Doug Langston, Hang Lau (McGill University), Mark Lawrence, Doug Lea (SUNY Oswego), Gregory Longshore, Bob Lynch (Lynch Associates), Philip Milne (consultant), Mark Morrissey (The Oregon Graduate Institute), Mahesh Neelakanta

(Florida Atlantic University), José Paumard (Oracle), Hao Pham, Paul Philion, Blake Ragsdell, Ylber Ramadani (Ryerson University), Stuart Reges (University of Arizona), Simon Ritter (Azul Systems), Rich Rosen (Interactive Data Corporation), Peter Sanders (ESSI University, Nice, France), Dr. Paul Sanghera (San Jose State University and Brooks College), Paul Sevinc (Teamup AG), Devang Shah (Sun Microsystems), Yoshiki Shibata, Richard Slywczak (NASA/Glenn Research Center), Bradley A. Smith, Steven Stelting (Oracle), Christopher Taylor, Luke Taylor (Valtech), George Thiruvathukal, Kim Topley (StreamingEdge), Janet Traub, Paul Tyma (consultant), Christian Ullenboom, Peter van der Linden, Joe Wang (Oracle), Sven Woltmann, Burt Walsh, Dan Xu (Oracle), and John Zavgren (Oracle).

Cay Horstmann
Düsseldorf, Germany
October 2023

1. Streams

Compared to collections, streams provide a view of data that lets you specify computations at a higher conceptual level. With a stream, you specify what you want to have done, not how to do it. You leave the scheduling of operations to the implementation. For example, suppose you want to compute the average of a certain property. You specify the source of data and the property, and the stream library can then optimize the computation, for example by using multiple threads for computing sums and counts and combining the results.

In this chapter, you will learn how to use the Java stream library, which allows you to process sequences of values in a “what, not how” style.

1.1. From Iterating to Stream Operations

When you process a collection, you usually iterate over its elements and do some work with each of them. For example, suppose we want to count all long words in a book. First, let's put them into a list:

```
String contents =  Files.readString(Path.of("alice.tx
List<String> words = List.of(contents.split("\\PL+"))
   // Split into words; nonletters are delimiters
```

Now we are ready to iterate:

```
int count = 0;
for (String w : words)
{
   if (w.length() > 12) count++;
}
```

With streams, the same operation looks like this:

```
long count = words.stream()
   .filter(w -> w.length() > 12)
   .count();
```

Now you don't have to scan the loop for evidence of filtering and counting. The method names tell you right away what the code intends to do. Moreover, where the loop prescribes the order of operations in complete detail, a stream is able to schedule the operations any way it wants, as long as the result is correct.

Simply changing `stream` to `parallelStream` allows the stream library to do the filtering and counting in parallel.

```
long count = words.parallelStream()
   .filter(w -> w.length() > 12)
   .count();
```

Streams follow the "what, not how" principle. In our stream example, we describe what needs to be done: get the long words and count them. We don't specify in which order, or in which thread, this should happen. In contrast, the loop at the beginning of this section specifies exactly how the computation should work, and thereby forgoes any chances of optimization.

A stream seems superficially similar to a collection, allowing you to transform and retrieve data. But there are significant differences:

1. A stream does not store its elements. They may be stored in an underlying collection or generated on demand.
2. Stream operations don't mutate their source. For example, the `filter` method does not remove elements from a stream but yields a new stream in which they are not present.
3. Stream operations are *lazy* when possible. This means they are not executed until their result is needed. For example, if you only ask for the first five long words instead of all, the `filter`

method will stop filtering after the fifth match. As a consequence, you can even have infinite streams!

Let us have another look at the example. The `stream` and `parallelStream` methods yield a *stream* for the `words` list. The `filter` method returns another stream that contains only the words of length greater than 12. The `count` method reduces that stream to a result.

This workflow is typical when you work with streams. You set up a pipeline of operations in three stages:

1. Create a stream.
2. Specify *intermediate operations* for transforming the initial stream into others, possibly in multiple steps.
3. Apply a *terminal operation* to produce a result. This operation forces the execution of the lazy operations that precede it. Afterwards, the stream can no longer be used.

In the example in Listing 1.1, the stream is created with the `stream` or `parallelStream` methods. The `filter` method transforms it, and `count` is the terminal operation.

In the next section, you will see how to create a stream. The subsequent three sections deal with stream transformations. They are followed by five sections on terminal operations.

Listing 1.1 streams/CountLongWords.java

```
1  package streams;
2
3  import java.io.*;
4  import java.nio.file.*;
5  import java.util.*;
6
7  /**
8   * @version 1.02 2019-08-28
9   * @author Cay Horstmann
10  */
11 public class CountLongWords
12 {
13    public static void main(String[] args) throw
14    {
15       String contents = Files.readString(Path.
16       List<String> words = List.of(contents.spl
17
18       long count = 0;
19       for (String w : words)
20       {
21          if (w.length() > 12) count++;
22       }
23       System.out.println(count);
24
25       count = words.stream().filter(w -> w.leng
26       System.out.println(count);
```

```
27
28          count = words.parallelStream().filter(w -
29          System.out.println(count);
30       }
31    }
```

java.util.stream.Stream<T> **8**

- `Stream<T> filter(Predicate<? super T> p)`
  yields a stream containing all elements of this stream fulfilling `p`.
- `long count()`
  yields the number of elements of this stream. This is a terminal operation.

java.util.Collection<E> **1.2**

- `default Stream<E> stream()`
- `default Stream<E> parallelStream()`
  yield a sequential or parallel stream of the elements in this collection.

1.2. Stream Creation

You have already seen that you can turn any collection into a stream with the `stream` method of the `Collection` interface. If you have an array, use the static `Stream.of` method instead.

```
Stream<String> words = Stream.of(contents.split("\\PL
   // split returns a String[] array
```

The `of` method has a varargs parameter, so you can construct a stream from any number of arguments:

```
Stream<String> song = Stream.of("gently", "down", "th
```

Use `Arrays.stream(array, from, to)` to make a stream from a part of an array.

To make a stream with no elements, use the static `Stream.empty` method:

```
Stream<String> silence = Stream.empty();
   // Generic type <String> is inferred; same as Stre
```

The `Stream` interface has two static methods for making infinite streams. The `generate` method takes a function with no parameters (or, technically, an object of the `Supplier<T>` interface). Whenever a stream value is needed, that function is called to produce a value. You can get a stream of constant values as

```
Stream<String> echos = Stream.generate(() -> "Echo");
```

or a stream of random numbers as

```
Stream<Double> randoms = Stream.generate(Math::random
```

To produce sequences such as `0 1 2 3 . . .`, use the `iterate` method instead. It takes a "seed" value and a function (technically, a `UnaryOperator<T>`) and repeatedly applies the function to the previous result. For example,

```
Stream<BigInteger> integers
   = Stream.iterate(BigInteger.ZERO, n -> n.add(BigIn
```

The first element in the sequence is the seed `BigInteger.ZERO`. The second element is `f(seed)` which yields `1` (as a big integer). The next element is `f(f(seed))` which yields `2`, and so on.

To produce a finite stream instead, add a predicate that specifies when the iteration should finish:

```
var limit = new BigInteger("10000000");
Stream<BigInteger> integers
   = Stream.iterate(BigInteger.ZERO,
      n -> n.compareTo(limit) < 0,
      n -> n.add(BigInteger.ONE));
```

As soon as the predicate rejects an iteratively generated value, the stream ends.

Finally, the `Stream.ofNullable` method makes a really short stream from an object. The stream has length 0 if the object is `null` or length 1 otherwise, containing just the object. This is mostly useful in conjunction with `flatMap`—see Section 1.7.7 for an example.

A number of methods in the Java API yield streams. For example, the `String` class has a `lines` method that yields a stream of the lines contained in the string:

```
Stream<String> greetings = "Hello\nGuten Tag\nBonjour
```

The `Pattern` class has a method `splitAsStream` that splits a `CharSequence` by a regular expression. You can use the following statement to split a string into words:

```
Stream<String> words = Pattern.compile("\\PL+").split
```

The `Scanner.tokens` method yields a stream of tokens of a scanner. Another way to get a stream of words from a string is

```
Stream<String> words = new Scanner(contents).tokens()
```

The static `Files.lines` method returns a `Stream` of all lines in a file:

```
try (Stream<String> lines = Files.lines(path))
{
   Process lines
}
```

Note that the `try` -with-resources block is necessary to close the file.

It is becoming more common to offer data as streams in the Java API. For example, Java 21 added a static `availableLocales` method that yields a stream of `Locale` objects.

Note: To produce a finite stream, you can always add the elements to a list which you then turn into a

stream. The `Stream.Builder` interface is slightly more efficient for that purpose:

```
Stream<Integer> digits(int n)
{
   Stream.Builder<Integer> builder = Strea
   while (n != 0)
   {
      builder.add(n % 10);
      n = n / 10;
   }
   return builder.build();
}
```

To view the contents of one of the streams introduced in this section, use the `toList` method, which collects the stream's elements in a list. Like `count`, `toList` is a terminal operation. If the stream is infinite, first truncate it with the `limit` method:

```
System.out.println(Stream.generate(Math::random).limi
```

Note: In order to turn an `Iterator`, or a general `Iterable` that is not a collection, into a stream, you need to use helper methods for *spliterators*. A

spliterator is similar to an iterator, but it can be split so that each resulting spliterator yields a part of the elements. This splitting is used for processing elements in parallel—see Section 1.14.

If you have an `Iterator` and want a stream of its results, use

```
StreamSupport.stream(Spliterators.splitera
   iterator, Spliterator.ORDERED), false);
```

If you have an `Iterable` that is not a collection, you can turn it into a stream by calling

```
StreamSupport.stream(iterable.spliterator(
```

Caution: It is very important that you don't modify the collection backing a stream while carrying out a stream operation. Remember that streams don't collect their data—the data is always in a separate collection. If you modify that collection, the outcome of the stream operations becomes undefined. The JDK documentation refers to this requirement as *noninterference*.

To be exact, since intermediate stream operations are lazy, it is possible to mutate the collection up to the point where the terminal operation executes. For example, the following, while certainly not recommended, will work:

```
List<String> wordList = . . .;
Stream<String> words = wordList.stream();
wordList.add("END");
long n = words.distinct().count();
```

But this code is wrong:

```
Stream<String> words = wordList.stream();
words.forEach(s -> {if (s.length() < 12) wordList.rem
   // ERROR--interference
```

The example program in Listing 1.2 shows the various ways of creating a stream.

Listing 1.2 streams/CreatingStreams.java

```
1 package streams;
2
3 import java.io.*;
4 import java.math.*;
```

```
5  import java.nio.file.*;
6  import java.util.*;
7  import java.util.regex.Pattern;
8  import java.util.stream.*;
9
10 /**
11  * @version 1.03 2021-09-06
12  * @author Cay Horstmann
13  */
14 public class CreatingStreams
15 {
16    public static <T> void show(String title, St
17    {
18       final int SIZE = 10;
19       List<T> firstElements = stream
20          .limit(SIZE + 1)
21          .toList();
22       System.out.print(title + ": ");
23       for (int i = 0; i < firstElements.size();
24       {
25          if (i > 0) System.out.print(", ");
26          if (i < SIZE) System.out.print(firstEl
27          else System.out.print("...");
28       }
29       System.out.println();
30    }
31
32    public static void main(String[] args) throw
```

```
33    {
34       Path path = Path.of("../gutenberg/alice30
35       String contents = Files.readString(path);
36       Stream<String> words = Stream.of(contents
37
38       show("words", words);
39       Stream<String> song = Stream.of("gently",
40       show("song", song);
41       Stream<String> silence = Stream.empty();
42       show("silence", silence);
43
44       Stream<String> echos = Stream.generate(()
45       show("echos", echos);
46
47       Stream<Double> randoms = Stream.generate(
48       show("randoms", randoms);
49
50       Stream<BigInteger> integers = Stream.iter
51          n -> n.add(BigInteger.ONE));
52       show("integers", integers);
53
54       Stream<String> greetings = "Hello\nGuten
55       show("greetings", greetings);
56
57       Stream<String> wordsAnotherWay = Pattern
58       show("wordsAnotherWay", wordsAnotherWay);
59
60       try (Stream<String> lines = Files.lines(p
```

```
61          {
62             show("lines", lines);
63          }
64
65          Iterable<Path> iterable = FileSystems.get
66          Stream<Path> rootDirectories = StreamSupp
67          show("rootDirectories", rootDirectories);
68
69          Iterator<Path> iterator = Path.of("/usr/s
70          Stream<Path> pathComponents = StreamSuppo
71             iterator, Spliterator.ORDERED), false)
72          show("pathComponents", pathComponents);
73       }
74    }
```

java.util.stream.Stream **8**

- `static <T> Stream<T> of(T... values)`
  yields a stream whose elements are the given values.
- `static <T> Stream<T> empty()`
  yields a stream with no elements.
- `static <T> Stream<T> generate(Supplier<T> s)`
  yields an infinite stream whose elements are constructed by repeatedly invoking the function `s`.

- `static <T> Stream<T> iterate(T seed, UnaryOperator<T> f)`
- `static <T> Stream<T> iterate(T seed, Predicate<? super T> hasNext, UnaryOperator<T> f)`
  yield a stream whose elements are `seed`, `f` invoked on `seed`, `f` invoked on the preceding element, and so on. The first method yields an infinite stream. The stream of the second method comes to an end before the first element that doesn't fulfill the `hasNext` predicate.
- `static <T> Stream<T> ofNullable(T t)` **9**
  returns an empty stream if `t` is `null` or a stream containing `t` otherwise.

`java.util.Spliterators` **8**

- `static <T> Spliterator<T> spliteratorUnknownSize(Iterator<? extends T> iterator, int characteristics)`
  turns an iterator into a splittable iterator of unknown size with the given characteristics (a bit pattern containing constants such as `Spliterator.ORDERED`).

`java.util.Arrays` 1.2

- `static <T> Stream<T> stream(T[] array, int startInclusive, int endExclusive)` 8
  yields a stream whose elements are the specified range of the array.

`java.lang.String`

- `static Stream<String> lines()` 11
  yields a stream whose elements are the lines of this string.

`java.util.regex.Pattern` 1.4

- `Stream<String> splitAsStream(CharSequence input)` 8
  yields a stream whose elements are the parts of the input that are delimited by this pattern.

`java.nio.file.Files` 7

- `static Stream<String> lines(Path path)` 8
- `static Stream<String> lines(Path path, Charset cs)` 8
  yield a stream whose elements are the lines of the specified file, with the UTF-8 charset or the given charset.

`java.util.stream.StreamSupport` 8

- `static <T> Stream<T> stream(Spliterator<T> spliterator, boolean parallel)`
  yields a stream containing the values produced by the given splittable iterator.

java.lang.Iterable 5.0

- `Spliterator<T> spliterator()` 8
  yields a splittable iterator for this `Iterable`. The default implementation does not split and does not report a size.

`java.util.Scanner` 5.0

- `public Stream<String> tokens()` 9
  yields a stream of strings returned by calling the `next` method of this scanner.

java.util.function.Supplier<T> 8

- `T get()`
  supplies a value.

1.3. The `filter`, `map`, and `flatMap` Methods

A stream transformation produces a stream whose elements are derived from those of another stream. You have already seen the `filter` transformation that yields a new stream with those elements that match a certain condition. Here, we transform a stream of strings into another stream containing only long words:

```
List<String> words = . . .;
Stream<String> longWords = words.stream().filter(w ->
```

The parameter type of `filter` is `Predicate<T>` —that is, a function from `T` to `boolean`.

Often, you want to transform the values in a stream in some way. Use the `map` method and pass the function that carries out the transformation. For example, you can transform all words to lowercase like this:

```
Stream<String> lowercaseWords = words.stream().map(St
```

Here, we used `map` with a method reference. Often, you will use a lambda expression instead:

```
Stream<Character> firstCodeUnits = words.stream().map
```

The resulting stream contains the first code unit of each word.

When you use `map`, a function is applied to each element, and the result is a new stream with the results. Occasionally, you are faced with a mapping function that generates a stream of results. As an example, consider a method `graphemeClusters` that yields all grapheme clusters of a string. For example, `graphemeClusters("Ciao 🇮🇹")` is a stream of strings `"C"`, `"i"`, `"a"`, `"o"`, `" "`, `"🇮🇹"`. (Note that the flag consists of four `char` values, so the `graphemeClusters` method has to do some heavy lifting to make this happen. We will look at the implementation momentarily.)

Now let's map such a `graphemeClusters` method on a stream of strings:

```
Stream<Stream<String>> result = words.stream().map(w
```

You will get a stream of streams, like `[. . . ["y", "o", "u", "r"], ["b", "o", "a", "t"], . . .]`. To flatten it out to a single stream `[. . . "y", "o", "u", "r", "b", "o", "a", "t", . . .]`, use the `flatMap` method instead of `map`:

```
Stream<String> flatResult = words.stream().flatMap(w
   // Calls graphemeClusters on each word and flatten
```

Now that you have seen how to use the `graphemeClusters` method, how do you write it? One way is to use a regular expression that breaks along grapheme cluster boundaries:

```
public static Stream<String> graphemeClusters(String
{
   return new Scanner(s).useDelimiter("\\b{g}").token
}
```

Here we were lucky that it was easy to write a method that produces a new stream for every stream element. Sometimes that is not so easy. It can also be a little inefficient to create so many streams. The `mapMulti` method offers an alternative. Instead of producing a stream of results, you generate the results and pass them to a collector—an object of a class implementing the functional interface `Consumer`. For each result, invoke the collector's `accept` method.

Let's do this with an example. The following loop produces the grapheme clusters of a string `s`:

```
BreakIterator iter = BreakIterator.getCharacterInstan
. . .
iter.setText(s);
int start = iter.first();
int end = iter.next();
while (end != BreakIterator.DONE) {
   String gc = s.substring(start, end);
   start = end;
   end = iter.next();
   // Do something with gc
}
```

When calling `mapMulti`, you provide a function that is invoked with the stream element and the collector. In your function, pass your results to the collector.

```
Stream<String> result = words.stream().mapMulti((s, c
   {
      iter.setText(s);
      int start = iter.first();
      int end = iter.next();
      while (end != BreakIterator.DONE)
      {
         String gc = s.substring(start, end);
         start = end;
         end = iter.next();
```

```
            collector.accept(gc);
        }
    });
```

java.util.stream.Stream **8**

- `Stream<T> filter(Predicate<? super T> predicate)`
  yields a stream containing the elements of this stream that fulfill the predicate.
- `<R> Stream<R> map(Function<? super T,? extends R> mapper)`
  yields a stream containing the results of applying `mapper` to the elements of this stream.
- `<R> Stream<R> flatMap(Function<? super T,? extends Stream<? extends R>> mapper)`
  yields a stream obtained by concatenating the results of applying `mapper` to the elements of this stream. (Note that each `mapper` result is a stream.)
- `<R> Stream<R> mapMulti(BiConsumer<? super T,? super Consumer<R>> mapper)` **16**
  For each stream element, the `mapper` is invoked, and all elements passed to the `Consumer` during invocation are added to the result stream.

1.4. Extracting Substreams and Combining Streams

The call `stream.limit(n)` returns a new stream that ends after `n` elements (or when the original stream ends if it is shorter). This method is particularly useful for cutting infinite streams down to size. For example,

```
Stream<Double> randoms = Stream.generate(Math::random
```

yields a stream with 100 random numbers.

The call `stream.skip(n)` does the exact opposite. It discards the first `n` elements. This is handy in our book reading example where, due to the way the `split` method works, the first element is an unwanted empty string. We can make it go away by calling `skip`:

```
Stream<String> words = Stream.of(contents.split("\\PL
```

The `stream.takeWhile(predicate)` call takes all elements from the stream while the predicate is `true`, and then stops.

For example, suppose we use the `graphemeClusters` method of the preceding section to split a string into characters, and we want

to collect all initial digits. The `takeWhile` method can do this:

```
Stream<String> initialDigits = graphemeClusters(str).
   s -> "0123456789".contains(s));
```

The `dropWhile` method does the opposite, dropping elements while a condition is `true` and yielding a stream of all elements starting with the first one for which the condition was `false`. For example,

```
Stream<String> withoutInitialWhiteSpace = graphemeClu
   s -> s.strip().length() == 0);
```

You can concatenate two streams with the static `concat` method of the `Stream` class:

```
Stream<String> combined = Stream.concat(
   graphemeClusters("Hello"), graphemeClusters("World
   // Yields the stream ["H", "e", "l", "l", "o", "W"
```

Of course, the first stream should not be infinite—otherwise the second one wouldn’t ever get a chance.

java.util.stream.Stream 8

- `Stream<T> limit(long maxSize)`
  yields a stream with up to `maxSize` of the initial elements from this stream.
- `Stream<T> skip(long n)`
  yields a stream whose elements are all but the initial `n` elements of this stream.
- `Stream<T> takeWhile(Predicate<? super T> predicate)` 9
  yields a stream whose elements are the initial elements of this stream that fulfill the predicate.
- `Stream<T> dropWhile(Predicate<? super T> predicate)` 9
  yields a stream whose elements are the elements of this stream except for the initial ones that fulfill the predicate.
- `static <T> Stream<T> concat(Stream<? extends T> a, Stream<? extends T> b)`
  yields a stream whose elements are the elements of `a` followed by the elements of `b`.

1.5. Other Stream Transformations

The `distinct` method returns a stream that yields elements from the original stream, in the same order, except that duplicates are

suppressed. The duplicates need not be adjacent.

```
Stream<String> uniqueWords
   = Stream.of("merrily", "merrily", "merrily", "gent
   // Only one "merrily" is retained
```

For sorting a stream, there are several variations of the `sorted` method. One works for streams of `Comparable` elements, and another accepts a `Comparator`. Here, we sort strings so that the longest ones come first:

```
Stream<String> longestFirst
   = words.stream().sorted(Comparator.comparing(Strin
```

As with all stream transformations, the `sorted` method yields a new stream whose elements are the elements of the original stream in sorted order.

Of course, you can sort a collection without using streams. The `sorted` method is useful when the sorting process is part of a stream pipeline.

Finally, the `peek` method yields another stream with the same elements as the original, but a function is invoked every time an

element is retrieved. That is handy for debugging:

```
Object[] powers = Stream.iterate(1.0, p -> p * 2)
   .peek(e -> System.out.println("Fetching " + e))
   .limit(20).toArray();
```

When an element is actually accessed, a message is printed. This way you can verify that the infinite stream returned by `iterate` is processed lazily.

Tip: When you use a debugger to debug a stream computation, you can set a breakpoint in a method that is called from one of the transformations. With most IDEs, you can also set breakpoints in lambda expressions. If you just want to know what happens at a particular point in the stream pipeline, add

```
.peek(x ->
   {
      return;
   })
```

and set a breakpoint on the second line.

---

java.util.stream.Stream 8

- `Stream<T> distinct()`
  yields a stream of the distinct elements of this stream.
- `Stream<T> sorted()`
- `Stream<T> sorted(Comparator<? super T> comparator)`
  yield a stream whose elements are the elements of this stream in sorted order. The first method requires that the elements are instances of a class implementing `Comparable`.
- `Stream<T> peek(Consumer<? super T> action)`
  yields a stream with the same elements as this stream, passing each element to `action` as it is consumed.

1.6. Simple Reductions

Now that you have seen how to create and transform streams, we will finally get to the most important point—getting answers from the stream data. The methods covered in this section are called *reductions*. Reductions are *terminal operations*. They reduce the stream to a nonstream value that can be used in your program.

You have already seen a simple reduction: the `count` method that returns the number of elements of a stream.

Other simple reductions are `max` and `min` that return the largest or smallest value. There is a twist—these methods return an `Optional<T>` value that either wraps the answer or indicates that there is none (because the stream happened to be empty). In the olden days, it was common to return `null` in such a situation. But that can lead to null pointer exceptions when it happens in an incompletely tested program. The `Optional` type is a better way of indicating a missing return value. We discuss the `Optional` type in detail in the next section. Here is how you can get the maximum of a stream:

```
Optional<String> largest = words.max(String::compareT
System.out.println("largest: " + largest.orElse(""));
```

The `findFirst` returns the first value in a nonempty collection. It is often useful when combined with `filter`. For example, here we find the first word that starts with the letter Q, if it exists:

```
Optional<String> startsWithQ
   = words.filter(s -> s.startsWith("Q")).findFirst()
```

If you are OK with any match, not just the first one, use the `findAny` method. This is effective when you parallelize the stream,

since the stream can report any match that it finds instead of being constrained to the first one.

```
Optional<String> startsWithQ
   = words.parallel().filter(s -> s.startsWith("Q")).
```

If you just want to know if there is a match, use the terminal `anyMatch` operation with a predicate argument:

```
boolean aWordStartsWithQ
   = words.parallel().anyMatch(s -> s.startsWith("Q")
```

There are methods `allMatch` and `noneMatch` that return `true` if all or no elements match a predicate. These methods also benefit from being run in parallel.

java.util.stream.Stream **8**

- `Optional<T> max(Comparator<? super T> comparator)`
- `Optional<T> min(Comparator<? super T> comparator)`

  yield a maximum or minimum element of this stream, using the ordering defined by the given comparator, or an empty `Optional` if this stream is empty. These are terminal operations.

- `Optional<T> findFirst()`
- `Optional<T> findAny()`
  yield the first, or any, element of this stream, or an empty `Optional` if this stream is empty. These are terminal operations.
- `boolean anyMatch(Predicate<? super T> predicate)`
- `boolean allMatch(Predicate<? super T> predicate)`
- `boolean noneMatch(Predicate<? super T> predicate)`
  return `true` if any, all, or none of the elements of this stream match the given predicate. These are terminal operations.

1.7. The Optional Type

An `Optional<T>` object is a wrapper for either an object of type `T` or no object. In the former case, we say that the value is *present*. The `Optional<T>` type is intended as a safer alternative for a reference of type `T` that either refers to an object or is `null`. But it is only safer if you use it right. The next three sections shows you how.

1.7.1. Getting an Optional Value

The key to using `Optional` effectively is to use a method that either *produces an alternative* if the value is not present, or *consumes the value* only if it is present.

In this section, we look at the first strategy. Often, there is a default that you want to use when there was no match, perhaps the empty string:

```
String result = optionalString.orElse("");
   // The wrapped string, or "" if none
```

You can also invoke code to compute the default:

```
String result = optionalString.orElseGet(() -> System
   // The function is only called when needed
```

Or you can throw an exception if there is no value:

```
String result = optionalString.orElseThrow(IllegalSta
   // Supply a method that yields an exception object
```

`java.util.Optional` `8`

- `T orElse(T other)`
  yields the value of this `Optional`, or `other` if this `Optional` is empty.

- `T orElseGet(Supplier<? extends T> other)`
  yields the value of this `Optional`, or the result of invoking `other` if this `Optional` is empty.
- `<X extends Throwable> T orElseThrow(Supplier<? extends X> exceptionSupplier)`
  yields the value of this `Optional`, or throws the result of invoking `exceptionSupplier` if this `Optional` is empty.

1.7.2. Consuming an Optional Value

In the preceding section, you saw how to produce an alternative if no value is present. The other strategy for working with optional values is to consume the value only if it is present.

The `ifPresent` method accepts a function. If the optional value exists, it is passed to that function. Otherwise, nothing happens.

```
optionalValue.ifPresent(v -> Process v);
```

For example, if you want to add the value to a set if it is present, call

```
optionalValue.ifPresent(v -> results.add(v));
```

or simply

```
optionalValue.ifPresent(results::add);
```

If you want to take one action if the `Optional` has a value and another action if it doesn't, use `ifPresentOrElse`:

```
optionalValue.ifPresentOrElse(
   v -> System.out.println("Found " + v),
   () -> logger.warning("No match"));
```

`java.util.Optional` `8`

- `void ifPresent(Consumer<? super T> action)`
  If this `Optional` is nonempty, passes its value to `action`.
- `void ifPresentOrElse(Consumer<? super T> action, Runnable emptyAction)` `9`
  If this `Optional` is nonempty, passes its value to `action`, else invokes `emptyAction`.

1.7.3. Pipelining Optional Values

In the preceding sections, you saw how to get a value out of an `Optional` object. Another useful strategy is to keep the `Optional` intact. You can transform the value inside an `Optional` by using the `map` method:

```
Optional<Path> transformed = optionalString.map(Path:
```

If `optionalString` is empty, then `transformed` is also empty.

Note: This `map` method is the analog of the `map` method of the `Stream` interface that you have seen in Section 1.3. Simply imagine an optional value as a stream of size zero or one. The result again has size zero or one, and in the latter case, the function has been applied.

Similarly, you can use the `filter` method to only consider `Optional` values that fulfill a certain property before or after transforming it. If the property is not fulfilled, the pipeline yields an empty result:

```
Optional<Path> transformed = optionalString
   .filter(s -> s.endsWith(".txt"))
   .map(Path::of);
```

You can substitute an alternative `Optional` for an empty `Optional` with the `or` method. The alternative is computed lazily.

```
Optional<String> result = optionalString.or(() -> //
   alternatives.stream().findFirst());
```

If `optionalString` has a value, then `result` is `optionalString`. If not, the lambda expression is evaluated, and its result is used.

`java.util.Optional` `8`

- `<U> Optional<U> map(Function<? super T,? extends U> mapper)`
  yields an `Optional` whose value is obtained by applying the given function to the value of this `Optional` if present, or an empty `Optional` otherwise.
- `Optional<T> filter(Predicate<? super T> predicate)`
  yields an `Optional` with the value of this `Optional` if it fulfills the given predicate, or an empty `Optional` otherwise.
- `Optional<T> or(Supplier<? extends Optional<? extends T>> supplier)` `9`
  yields this `Optional` if it is nonempty, or the one produced by the supplier otherwise.

1.7.4. How Not to Work with Optional Values

If you don't use `Optional` values correctly, you have no benefit over the "something or `null`" approach of the past.

The `get` method gets the wrapped element of an `Optional` value if it exists, or throws a `NoSuchElementException` if it doesn't. Therefore,

```
Optional<T> optionalValue = . . .;
optionalValue.get().someMethod()
```

is no safer than

```
T value = . . .;
value.someMethod();
```

The `isPresent` and `isEmpty` methods report whether or not an `Optional<T>` object has a value. But

```
if (optionalValue.isPresent()) optionalValue.get().so
```

is no easier than

```
if (value != null) value.someMethod();
```

Tip: If you find yourself using the `get`, `isPresent`, or `isEmpty` methods, try to rethink your approach and use one of the strategies of the preceding two sections.

Note: The `orElseThrow` method is a scarier-sounding synonym for the `get` method. When you call `optionalValue.orElseThrow().someMethod()`, it becomes explicit that an exception will occur if the `optionalValue` is empty. The hope is that programmers will only use `orElseThrow` when it is absolutely clear that this cannot happen.

Here are a few more tips for the proper use of the `Optional` type:

- A variable of type `Optional` should *never* be `null`.
- Don't use fields of type `Optional`. The cost is an additional object. Inside a class, use `null` for an absent field. To discourage `Optional` fields, the class is not serializable.
- Method parameters of type `Optional` are questionable. They make the call unpleasant in the common case where the requested value is present. Instead, consider two overloaded versions of the method, with and without the parameter. (On the

other hand, returning an `Optional` is fine. It is the proper way to indicate that a function may not have a result.)

- Don't put `Optional` objects in a set, and don't use them as keys for a map. Collect the values instead.

`java.util.Optional` `8`

- `T get()`
- `T orElseThrow()` `10`
  yield the value of this `Optional`, or throw a `NoSuchElementException` if it is empty.
- `boolean isEmpty()` `11`
- `boolean isPresent()`
  return `true` if this `Optional` is empty or not empty.

1.7.5. Creating Optional Values

So far, we have discussed how to consume an `Optional` object someone else created. If you want to write a method that creates an `Optional` object, there are several static methods for that purpose, including `Optional.of(result)` and `Optional.empty()`. For example,

```
public static Optional<Double> inverse(Double x)
{
   return x == 0 ? Optional.empty() : Optional.of(1 /
}
```

The `ofNullable` method is intended as a bridge from possibly `null` values to optional values. `Optional.ofNullable(obj)` returns `Optional.of(obj)` if `obj` is not `null` and `Optional.empty()` otherwise.

`java.util.Optional` `8`

- `static <T> Optional<T> of(T value)`
- `static <T> Optional<T> ofNullable(T value)`
  yield an `Optional` with the given value. If `value` is `null`, the first method throws a `NullPointerException` and the second method yields an empty `Optional`.
- `static <T> Optional<T> empty()`
  yields an empty `Optional`.

1.7.6. Composing Optional Value Functions with `flatMap`

Suppose you have a method `f` yielding an `Optional<T>`, and the target type `T` has a method `g` yielding an `Optional<U>`. If they were normal methods, you could compose them by calling `s.f().g()`. But that composition doesn't work since `s.f()` has type `Optional<T>`, not `T`. Instead, call

```
Optional<U> result = s.f().flatMap(T::g);
```

If `s.f()` is present, then `g` is applied to it. Otherwise, an empty `Optional<U>` is returned.

Clearly, you can repeat that process if you have more methods or lambdas that yield `Optional` values. You can then build a pipeline of steps, simply by chaining calls to `flatMap`, that will succeed only when all parts do.

For example, consider the safe `inverse` method of the preceding section. Suppose we also have a safe square root:

```
public static Optional<Double> squareRoot(Double x)
{
   return x < 0 ? Optional.empty() : Optional.of(Math
}
```

Then you can compute the square root of the `inverse` as

```
Optional<Double> result = inverse(arg).flatMap(x -> s
```

We can make such a chain look a little more regular by starting out with an `Optional`:

```
Optional<Double> result
   = Optional.of(arg).flatMap(x -> inverse(x)).flatMa
```

It looks even neater with method expressions:

```
Optional<Double> result
   = Optional.of(arg).flatMap(MyMath::inverse).flatMa
```

If either the `inverse` method or the `squareRoot` returns `Optional.empty()`, the result is empty.

Note: You have already seen a `flatMap` method in the `Stream` interface (see Section 1.3). That method maps a stream-yielding method to all elements of a stream, and then flattens out the resulting stream of streams. The `Optional.flatMap` method works in the same way. By mapping an optional-yielding method

to an optional, you get an optional of optional, which is then flattened out.

`java.util.Optional` `8`

- `<U> Optional<U> flatMap(Function<? super T,? extends Optional<? extends U>> mapper)`
  yields the result of applying `mapper` to the value in this `Optional` if present, or an empty optional otherwise.

1.7.7. Turning an Optional into a Stream

The `stream` method turns an `Optional<T>` into a `Stream<T>` with zero or one element. Sure, why not, but why would you ever want that?

This becomes useful with methods that return an `Optional` result. Suppose you have a stream of user IDs and a method

```
Optional<User> lookup(String id)
```

How do you get a stream of users, skipping those IDs that are invalid?

Of course, you can filter out the invalid IDs and then apply `get` to the remaining ones:

```
Stream<String> ids = . . .;
Stream<User> users = ids.map(Users::lookup)
   .filter(Optional::isPresent)
   .map(Optional::get);
```

But that uses the `isPresent` and `get` methods that we warned about. It is more elegant to call

```
Stream<User> users = ids.map(Users::lookup)
   .flatMap(Optional::stream);
```

Each call to `stream` returns a stream with zero or one element. The `flatMap` method combines them all. That means the nonexistent users are simply dropped.

Note: In this section, we consider the happy scenario in which we have a method that returns an `Optional` value. These days, many methods return `null` when there is no valid result. Suppose `Users.classicLookup(id)` returns a `User` object or `null`, not an `Optional<User>`. Then you can of course filter out the `null` values:

```
Stream<User> users = ids.map(Users::classi
   .filter(Objects::nonNull);
```

But if you prefer the `flatMap` approach, you can use

```
Stream<User> users = ids.flatMap(
   id -> Stream.ofNullable(Users.classicLo
```

or

```
Stream<User> users = ids.map(Users::classi
   .flatMap(Stream::ofNullable);
```

The call `Stream.ofNullable(obj)` yields an empty stream if `obj` is `null` or a stream just containing `obj` otherwise.

The example program in Listing 1.3 demonstrates the `Optional` API.

Listing 1.3 optional/OptionalTest.java

```
1  package optional;
2
3  import java.io.*;
4  import java.nio.file.*;
5  import java.util.*;
6
7  /**
8   * @version 1.02 2019-08-28
9   * @author Cay Horstmann
10  */
11 public class OptionalTest
12 {
13    public static void main(String[] args) throw
14    {
15       String contents = Files.readString(Path.
16       List<String> wordList = List.of(contents
17
18       Optional<String> optionalValue = wordList
19          .filter(s -> s.contains("fred"))
20          .findFirst();
21       System.out.println(optionalValue.orElse("
22
23       Optional<String> optionalString = Optiona
24       String result = optionalString.orElse("N/
25       System.out.println("result: " + result);
26       result = optionalString.orElseGet(() -> l
```

```
27        System.out.println("result: " + result);
28        try
29        {
30           result = optionalString.orElseThrow(Il
31           System.out.println("result: " + result
32        }
33        catch (Throwable t)
34        {
35           t.printStackTrace();
36        }
37
38        optionalValue = wordList.stream()
39           .filter(s -> s.contains("red"))
40           .findFirst();
41        optionalValue.ifPresent(s -> System.out.p
42
43        var results = new HashSet<String>();
44        optionalValue.ifPresent(results::add);
45        Optional<Boolean> added = optionalValue.m
46        System.out.println(added);
47
48        System.out.println(inverse(4.0).flatMap(O
49        System.out.println(inverse(-1.0).flatMap(
50        System.out.println(inverse(0.0).flatMap(O
51        Optional<Double> result2 = Optional.of(-4
52           .flatMap(OptionalTest::inverse).flatMa
53        System.out.println(result2);
54     }
```

```
55
56    public static Optional<Double> inverse(Doubl
57    {
58       return x == 0 ? Optional.empty() : Optior
59    }
60
61    public static Optional<Double> squareRoot(Do
62    {
63       return x < 0 ? Optional.empty() : Optiona
64    }
65 }
```

`java.util.Optional` `8`

- `<U> Optional<U> flatMap(Function<? super T,Optional<U>> mapper)` `9`
  yields the result of applying `mapper` to the value of this `Optional`, or an empty `Optional` if this `Optional` is empty.

1.8. Collecting Results

When you are done with a stream, you will often want to look at the results. You can call the `iterator` method, which yields an old-fashioned iterator that you can use to visit the elements.

Alternatively, you can call the `forEach` method to apply a function to each element:

```
stream.forEach(System.out::println);
```

On a parallel stream, the `forEach` method traverses elements in arbitrary order. If you want to process them in stream order, call `forEachOrdered` instead. Of course, you might then give up some or all of the benefits of parallelism.

But more often than not, you will want to collect the result in a data structure. You have already seen the `toList` method that yields a list of the stream elements.

Call `toArray` to get an array of the stream elements.

Since it is not possible to create a generic array at runtime, the expression `stream.toArray()` returns an `Object[]` array. If you want an array of the correct type, pass in the array constructor:

```
String[] result = stream.toArray(String[]::new);
   // stream.toArray() has type Object[]
```

For collecting stream elements to another target, there is a convenient `collect` method that takes an instance of the `Collector` interface. A *collector* is an object that accumulates elements and produces a result. The `Collectors` class provides a large number of factory methods for common collectors. Before the

`toList` method was added in Java 16, you had to use the collector produced by `Collectors.toList()`:

```
List<String> result = stream.collect(Collectors.toLis
```

Similarly, here is how you can collect stream elements into a set:

```
Set<String> result = stream.collect(Collectors.toSet(
```

These calls give you a list or set, but you cannot make any further assumptions. The collection might not be mutable, serializable, or thread-safe. If you want to control which kind of collection you get, use the following call instead:

```
TreeSet<String> result = stream.collect(Collectors.to
```

Suppose you want to collect all strings in a stream by concatenating them. You can call

```
String result = stream.collect(Collectors.joining());
```

If you want a delimiter between elements, pass it to the `joining` method:

```
String result = stream.collect(Collectors.joining(",
```

If your stream contains objects other than strings, you need to first convert them to strings, like this:

```
String result = stream.map(Object::toString).collect(
```

If you want to reduce the stream results to a sum, count, average, maximum, or minimum, use one of the `summarizing`(`Int`|`Long`|`Double`) methods. These methods take a function that maps the stream objects to numbers and yield a result of type (`Int`|`Long`|`Double`)`SummaryStatistics`, simultaneously computing the sum, count, average, maximum, and minimum.

```
IntSummaryStatistics summary = stream.collect(
   Collectors.summarizingInt(String::length));
double averageWordLength = summary.getAverage();
double maxWordLength = summary.getMax();
```

The example program in Listing 1.4 shows how to collect elements from a stream.

Listing 1.4 collecting/CollectingResults.java

```
1  package collecting;
2
3  import java.io.*;
4  import java.nio.file.*;
5  import java.util.*;
6  import java.util.stream.*;
7
8  /**
9   * @version 1.02 2019-08-28
10  * @author Cay Horstmann
11  */
12 public class CollectingResults
13 {
14    public static Stream<String> noVowels() thro
15    {
16       String contents = Files.readString(Path.o
17       List<String> wordList = List.of(contents
18       Stream<String> words = wordList.stream();
19       return words.map(s -> s.replaceAll("[aeio
20    }
21
22    public static <T> void show(String label, Se
23    {
```

```
24          System.out.print(label + ": " + set.getCl
25          System.out.println("["
26             + set.stream().limit(10).map(Object::t
27             + "]");
28       }
29
30       public static void main(String[] args) throw
31       {
32          Iterator<Integer> iter = Stream.iterate(0
33          while (iter.hasNext())
34             System.out.println(iter.next());
35
36          Object[] numbers = Stream.iterate(0, n ->
37          System.out.println("Object array:" + numb
38             // Note it's an Object[] array
39
40          try
41          {
42             var number = (Integer) numbers[0]; //
43             System.out.println("number: " + number
44             System.out.println("The following stat
45             var numbers2 = (Integer[]) numbers; //
46          }
47          catch (ClassCastException e)
48          {
49             System.out.println(e);
50          }
51
```

```
52        Integer[] numbers3 = Stream.iterate(0, n
53           .limit(10)
54           .toArray(Integer[]::new);
55        System.out.println("Integer array: " + nu
56           // Note it's an Integer[] array
57
58        Set<String> noVowelSet = noVowels().colle
59        show("noVowelSet", noVowelSet);
60
61        TreeSet<String> noVowelTreeSet = noVowels
62           Collectors.toCollection(TreeSet::new))
63        show("noVowelTreeSet", noVowelTreeSet);
64
65        String result = noVowels().limit(10).coll
66        System.out.println("Joining: " + result);
67        result = noVowels().limit(10)
68           .collect(Collectors.joining(", "));
69        System.out.println("Joining with commas:
70
71        IntSummaryStatistics summary = noVowels()
72           Collectors.summarizingInt(String::leng
73        double averageWordLength = summary.getAve
74        double maxWordLength = summary.getMax();
75        System.out.println("Average word length:
76        System.out.println("Max word length: " +
77        System.out.println("forEach:");
```

```
78          noVowels().limit(10).forEach(System.out:
79       }
80    }
```

java.util.stream.BaseStream **8**

- `Iterator<T> iterator()`
  yields an iterator for obtaining the elements of this stream. This is a terminal operation.

java.util.stream.Stream **8**

- `List<T> toList()` **16**
  yields a list of the elements in this stream.
- `void forEach(Consumer<? super T> action)`
  invokes `action` on each element of the stream.
- `Object[] toArray()`
- `<A> A[] toArray(IntFunction<A[]> generator)`
  yield an array of objects, or of type `A` when passed a constructor reference `A[]::new`. These are terminal operations.
- `<R,A> R collect(Collector<? super T,A,R> collector)`
  collects the elements in this stream, using the given collector. The `Collectors` class has factory methods for many collectors.

`java.util.stream.Collectors` **8**

- `static <T> Collector<T,?,List<T>> toList()`
- `static <T> Collector<T,?,List<T>> toUnmodifiableList()` **10**
- `static <T> Collector<T,?,Set<T>> toSet()`
- `static <T> Collector<T,?,Set<T>> toUnmodifiableSet()` **10**

  yield collectors that collect elements in a list or set.
- `static <T,C extends Collection<T>> Collector<T,?,C> toCollection(Supplier<C> collectionFactory)`

  yields a collector that collects elements into an arbitrary collection. Pass a constructor reference such as `TreeSet::new`.
- `static Collector<CharSequence,?,String> joining()`
- `static Collector<CharSequence,?,String> joining(CharSequence delimiter)`
- `static Collector<CharSequence,?,String> joining(CharSequence delimiter, CharSequence prefix, CharSequence suffix)`

  yield a collector that joins strings. The delimiter is placed between strings, and the prefix and suffix before the first and after the last string. When not specified, these are empty.

- `static <T> Collector<T,?,IntSummaryStatistics> summarizingInt(ToIntFunction<? super T> mapper)`
- `static <T> Collector<T,?,LongSummaryStatistics> summarizingLong(ToLongFunction<? super T> mapper)`
- `static <T> Collector<T,?,DoubleSummaryStatistics> summarizingDouble(ToDoubleFunction<? super T> mapper)`

  yield collectors that produce an (`Int` | `Long` | `Double`) `SummaryStatistics` object, from which you can obtain the count, sum, average, maximum, and minimum of the results of applying `mapper` to each element.

```
IntSummaryStatistics 8
```

```
LongSummaryStatistics 8
```

```
DoubleSummaryStatistics 8
```

- `long getCount()`

  yields the count of the summarized elements.
- (`int` | `long` | `double`) `getSum()`
- `double getAverage()`

  yield the sum or average of the summarized elements, or zero if there are no elements.

- `(int|long|double) getMax()`
- `(int|long|double) getMin()`
  yield the maximum or minimum of the summarized elements, or `(Integer|Long|Double).(MAX|MIN)_VALUE` if there are no elements.

1.9. Collecting into Maps

Suppose you have a `Stream<Person>` and want to collect the elements into a map so that later you can look up people by their ID. Call `Collectors.toMap` with two functions that produce the map's keys and values. For example,

```
public record Person(int id, String name) {}
. . .
Map<Integer, String> idToName = people.collect(
   Collectors.toMap(Person::id, Person::name));
```

In the common case when the values should be the actual elements, use `Function.identity()` for the second function.

```
Map<Integer, Person> idToPerson = people.collect(
   Collectors.toMap(Person::id, Function.identity()))
```

If there is more than one element with the same key, there is a conflict, and the collector will throw an `IllegalStateException`. You can override that behavior by supplying a third function that resolves the conflict and determines the value for the key, given the existing and the new value. Your function could return the existing value, the new value, or a combination of them.

Here, we construct a map that contains, for each language in the available locales, as key its name in your default locale (such as `"German"`), and as value its localized name (such as `"Deutsch"`).

```
Map<String, String> languageNames = Locale.availableL
   Collectors.toMap(
      Locale::getDisplayLanguage,
      loc -> loc.getDisplayLanguage(loc),
      (existingValue, newValue) -> existingValue));
```

We don't care that the same language might occur twice (for example, German in Germany and in Switzerland), so we just keep the first entry.

Note: In this chapter, I use the `Locale` class as a source of an interesting data set. See Chapter 7 for more information on working with locales.

Now suppose we want to know all languages in a given country. Then we need a `Map<String, Set<String>>`. For example, the value for `"Switzerland"` is the set `[French, German, Italian]`. At first, we store a singleton set for each language. Whenever a new language is found for a given country, we form the union of the existing and the new set.

```
Map<String, Set<String>> countryLanguageSets = Locale
   Collectors.toMap(
      Locale::getDisplayCountry,
      l -> Collections.singleton(l.getDisplayLanguage
      (a, b) ->
         { // Union of a and b
            var union = new HashSet<String>(a);
            union.addAll(b);
            return union;
         }));
```

You will see a simpler way of obtaining this map in the next section.

If you want a `TreeMap`, supply the constructor as the fourth argument. You must provide a merge function. Here is one of the examples from the beginning of the section, now yielding a `TreeMap`:

```
Map<Integer, Person> idToPerson = people.collect(
   Collectors.toMap(
      Person::id,
      Function.identity(),
      (existingValue, newValue) -> { throw new Illega
      TreeMap::new));
```

Note: For each of the `toMap` methods, there is an equivalent `toConcurrentMap` method that yields a concurrent map. A single concurrent map is used in the parallel collection process. When used with a parallel stream, a shared map is more efficient than merging maps. Note that elements are no longer collected in stream order, but that doesn't usually make a difference.

The program in Listing 1.5 gives examples of collecting stream results into maps.

Listing 1.5 collecting/CollectingIntoMaps.java

```
1 package collecting;
2
3 import java.io.*;
```

```
4  import java.util.*;
5  import java.util.function.*;
6  import java.util.stream.*;
7
8  /**
9   * @version 1.02 2023-10-19
10  * @author Cay Horstmann
11  */
12 public class CollectingIntoMaps
13 {
14
15    public record Person(int id, String name) {}
16
17    public static Stream<Person> people()
18    {
19       return Stream.of(new Person(1001, "Peter"
20          new Person(1003, "Mary"));
21    }
22
23    public static void main(String[] args) throw
24    {
25       Map<Integer, String> idToName = people()
26          Collectors.toMap(Person::id, Person::n
27       System.out.println("idToName: " + idToNam
28
29       Map<Integer, Person> idToPerson = people(
30          Collectors.toMap(Person::id, Function
31       System.out.println("idToPerson: " + idToP
```

```
32          + idToPerson);
33
34       idToPerson = people().collect(
35          Collectors.toMap(Person::id, Function
36             (existingValue, newValue) -> { thro
37             TreeMap::new));
38       System.out.println("idToPerson: " + idToP
39          + idToPerson);
40
41       Map<String, String> languageNames = Local
42          Collectors.toMap(
43             Locale::getDisplayLanguage,
44             l -> l.getDisplayLanguage(l),
45             (existingValue, newValue) -> existi
46       System.out.println("languageNames: " + la
47
48       Map<String, Set<String>> countryLanguageS
49          Collectors.toMap(
50             Locale::getDisplayCountry,
51             l -> Set.of(l.getDisplayLanguage())
52             (a, b) ->
53             { // union of a and b
54                Set<String> union = new HashSet<
55                union.addAll(b);
56                return union;
57             }));
```

```
58          System.out.println("countryLanguageSets:
59      }
60  }
```

java.util.stream.Collectors 8

- static <T,K,U> Collector<T,?,Map<K,U>> toMap(Function<? super T,? extends K> keyMapper, Function<? super T,? extends U> valueMapper)
- static <T,K,U> Collector<T,?,Map<K,U>> toMap(Function<? super T,? extends K> keyMapper, Function<? super T,? extends U> valueMapper, BinaryOperator<U> mergeFunction)
- static <T,K,U,M extends Map<K,U>> Collector<T,?,M> toMap(Function<? super T,? extends K> keyMapper, Function<? super T,? extends U> valueMapper, BinaryOperator<U> mergeFunction, Supplier<M> mapSupplier)
- static <T,K,U> Collector<T,?,Map<K,U>> toUnmodifiableMap(Function<? super T,? extends K> keyMapper, Function<? super T,? extends U> valueMapper) 10
- static <T,K,U> Collector<T,?,Map<K,U>> toUnmodifiableMap(Function<? super T,? extends K>

`keyMapper, Function<? super T,? extends U> valueMapper, BinaryOperator<U> mergeFunction)` 10

- `static <T,K,U> Collector<T,?,ConcurrentMap<K,U>> toConcurrentMap(Function<? super T,? extends K> keyMapper, Function<? super T,? extends U> valueMapper)`
- `static <T,K,U> Collector<T,?,ConcurrentMap<K,U>> toConcurrentMap(Function<? super T,? extends K> keyMapper, Function<? super T,? extends U> valueMapper, BinaryOperator<U> mergeFunction)`
- `static <T,K,U,M extends ConcurrentMap<K,U>> Collector<T,?,M> toConcurrentMap(Function<? super T,? extends K> keyMapper, Function<? super T,? extends U> valueMapper, BinaryOperator<U> mergeFunction, Supplier<M> mapSupplier)`

yield a collector that produces a map, unmodifiable map, or concurrent map. The `keyMapper` and `valueMapper` functions are applied to each collected element, yielding a key/value entry of the resulting map. By default, an `IllegalStateException` is thrown when two elements give rise to the same key. You can instead supply a `mergeFunction` that merges values with the same key. By default, the result is a `HashMap` or `ConcurrentHashMap`. You can instead supply a `mapSupplier` that yields the desired map instance.

1.10. Grouping and Partitioning

In the preceding section, you saw how to collect all languages in a given country. But the process was a bit tedious. You had to generate a singleton set for each map value and then specify how to merge the existing and new values. Forming groups of values with the same characteristic is very common, so the `groupingBy` method supports it directly.

Let's look at the problem of grouping locales by country. First, form this map:

```
Map<String, List<Locale>> countryToLocales = Locale.a
   Collectors.groupingBy(Locale::getCountry));
```

The function `Locale::getCountry` is the *classifier function* of the grouping. You can now look up all locales for a given country code, for example

```
List<Locale> swissLocales = countryToLocales.get("CH"
   // Yields locales de_CH, fr_CH, it_CH, and maybe m
```

Note: A quick refresher on locales: Each locale has a language code (such as `en` for English) and a country

code (such as `US` for the United States). The locale `en_US` describes English in the United States, and `en_IE` is English in Ireland. Some countries have multiple locales. For example, `ga_IE` is Gaelic in Ireland, and, as the preceding example shows, the JDK knows at least three locales in Switzerland.

When the classifier function is a predicate function (that is, a function returning a `boolean` value), the stream elements are partitioned into two lists: those where the function returns `true` and the complement. In this case, it is more efficient to use `partitioningBy` instead of `groupingBy`. For example, here we split all locales into those that use English and all others:

```
Map<Boolean, List<Locale>> englishAndOtherLocales = L
   Collectors.partitioningBy(l -> l.getLanguage().equ
List<Locale> englishLocales = englishAndOtherLocales.
```

Note: If you call the `groupingByConcurrent` method, you get a concurrent map that, when used with a parallel stream, is concurrently populated. This is entirely analogous to the `toConcurrentMap` method.

`java.util.stream.Collectors` `8`

- `static <T,K> Collector<T,?,Map<K,List<T>>> groupingBy(Function<? super T,? extends K> classifier)`
- `static <T,K> Collector<T,?,ConcurrentMap<K,List<T>>> groupingByConcurrent(Function<? super T,? extends K> classifier)`
  yield a collector that produces a map or concurrent map whose keys are the results of applying `classifier` to all collected elements, and whose values are lists of elements with the same key.
- `static <T> Collector<T,?,Map<Boolean,List<T>>> partitioningBy(Predicate<? super T> predicate)`
  yields a collector that produces a map whose keys are `true` / `false`, and whose values are lists of the elements that fulfill/do not fulfill the predicate.

1.11. Downstream Collectors

The `groupingBy` method yields a map whose values are lists. If you want to process those lists in some way, supply a *downstream collector*. For example, if you want sets instead of lists, you can use the `Collectors.toSet` collector that you saw in the preceding section:

```
Map<String, Set<Locale>> countryToLocaleSet = Locale.
   groupingBy(Locale::getCountry, toSet()));
```

Note: In this example, as well as the remaining examples of this section, I assume a static import of `java.util.stream.Collectors.*` to make the expressions easier to read.

You can also apply `groupingBy` twice:

```
Map<String, Map<String, List<Locale>>> countryAndLang
   Locale.availableLocales().collect(
      groupingBy(Locale::getCountry,
         groupingBy(Locale::getLanguage)));
```

Then `countryAndLanguageToLocale.get("IN").get("hi")` is a list of the Hindi locales in India. (There are several variants.)

Several collectors are provided for reducing collected elements to numbers:

- `counting` produces a count of the collected elements. For example,

```
Map<String, Long> countryToLocaleCounts = Locale.av
   groupingBy(Locale::getCountry, counting()));
```

counts how many locales there are for each country.

- `summing(Int|Long|Double)` and `averaging(Int|Long|Double)` apply a provided function to the downstream elements and produce the sum or average of the function's results. For example,

```
public record City(String name, String state, int p
. . .
Map<String, Integer> stateToCityPopulation = cities
   groupingBy(City::state, averagingInt(City::popul
```

computes the average of populations per state in a stream of cities.

- `maxBy` and `minBy` take a comparator and produce maximum and minimum of the downstream elements. For example,

```
Map<String, Optional<City>> stateToLargestCity = ci
   groupingBy(City::state,
      maxBy(Comparator.comparing(City::population))
```

produces the largest city per state.

The `collectingAndThen` collector adds a final processing step behind a collector. For example, if you want to know how many distinct results there are, collect them into a set and then compute the size:

```
Map<Character, Integer> stringCountsByStartingLetter
   groupingBy(s -> s.charAt(0),
      collectingAndThen(toSet(), Set::size)));
```

The `mapping` collector does the opposite. It applies a function to each collected element and passes the results to a downstream collector.

```
Map<Character, Set<Integer>> stringLengthsByStartingL
   groupingBy(s -> s.charAt(0),
      mapping(String::length, toSet())));
```

Here, we group strings by their first character. Within each group, we produce the lengths and collect them in a set.

The `mapping` method also yields a nicer solution to a problem from the preceding section—gathering a set of all languages in a country.

```
Map<String, Set<String>> countryToLanguages = Locale.
   groupingBy(Locale::getDisplayCountry,
      mapping(Locale::getDisplayLanguage,
         toSet())));
```

There is a `flatMapping` method as well, for use with functions that return streams.

If the grouping or mapping function has return type `int`, `long`, or `double`, you can collect elements into a summary statistics object, as discussed in Section 1.8. For example,

```
Map<String, IntSummaryStatistics> stateToCityPopulati
   groupingBy(City::state,
      summarizingInt(City::population)));
```

Then you can get the sum, count, average, minimum, and maximum of the function values from the summary statistics objects of each group.

The `filtering` collector applies a filter to each group, for example:

```
Map<String, Set<City>> largeCitiesByState
   = cities.collect(
      groupingBy(City::state,
         filtering(c -> c.population() > 500000,
            toSet()))); // States without large citie
```

Finally, you can use the `teeing` collector to branch into two downstream collections. This is useful whenever you need to compute more than one result from a stream. Suppose you want to collect city names and also compute their average population. You can't read a stream twice, but `teeing` lets you carry out two computations. Specify two downstream collectors and a function that combines the results.

```
record Pair<S, T>(S first, T second) {}
Pair<List<String>, Double> result = cities.filter(c -
   .collect(teeing(
      mapping(City::name, toList()), // First downstr
      averagingDouble(City::population), // Second do
      (list, avg) -> new Pair(list,  avg))); // Combi
```

Note: There are also three versions of a `reducing` method that apply general reductions, as described in

the next section.

Composing collectors is powerful, but it can lead to very convoluted expressions. The best use is with `groupingBy` or `partitioningBy` to process the "downstream" map values. Otherwise, simply apply methods such as `map`, `reduce`, `count`, `max`, or `min` directly on streams.

The example program in Listing 1.6 demonstrates downstream collectors.

Listing 1.6 collecting/DownstreamCollectors.java

```
1  package collecting;
2
3  import static java.util.stream.Collectors.*;
4
5  import java.io.*;
6  import java.nio.file.*;
7  import java.util.*;
8  import java.util.stream.*;
9
10 /**
11  * @version 1.02 2023-10-19
12  * @author Cay Horstmann
```

```
 */
public class DownstreamCollectors
{
   public record City(String name, String state

   public static Stream<City> readCities(String
   {
      return Files.lines(Path.of(filename))
         .map(l -> l.split(", "))
         .map(a -> new City(a[0], a[1], Integer
   }

   public static void main(String[] args) throw
   {
      Map<String, Set<Locale>> countryToLocaleS
         Locale::getCountry, toSet()));
      System.out.println("countryToLocaleSet: "

      Map<String, Map<String, List<Locale>>> co
         Locale.availableLocales().collect(
            groupingBy(Locale::getCountry,
               groupingBy(Locale::getLanguage))
      System.out.println("Hindi locales in Indi
         + countryAndLanguageToLocale.get("IN")

      Map<String, Long> countryToLocaleCounts =
         Locale::getCountry, counting()));
      System.out.println("countryToLocaleCounts
```

```
41
42      Stream<City> cities = readCities("cities
43      Map<String, Integer> stateToCityPopulatio
44         City::state, summingInt(City::populati
45      System.out.println("stateToCityPopulation
46
47      cities = readCities("cities.txt");
48      Map<String, Optional<String>> stateToLong
49         .collect(groupingBy(City::state,
50            mapping(City::name, maxBy(Comparato
51      System.out.println("stateToLongestCityNam
52
53      Map<String, Set<String>> countryToLanguag
54         Locale::getDisplayCountry, mapping(Loc
55      System.out.println("countryToLanguages: "
56
57      cities = readCities("cities.txt");
58      Map<String, IntSummaryStatistics> stateTo
59         .collect(groupingBy(City::state, summa
60      System.out.println(stateToCityPopulationS
61
62      cities = readCities("cities.txt");
63      Map<String, String> stateToCityNames = ci
64         City::state,
65         reducing("", City::name, (s, t) -> s.l
66
67      cities = readCities("cities.txt");
68      stateToCityNames = cities.collect(groupin
```

```
69          mapping(City::name, joining(", "))));
70       System.out.println("stateToCityNames: " +
71
72       cities = readCities("cities.txt");
73       record Pair<S, T>(S first, T second) {}
74       Pair<List<String>, Double> result = citie
75          .collect(teeing(
76             mapping(City::name, toList()),
77             averagingDouble(City::population),
78             (names, avg) -> new Pair<>(names, a
79       System.out.println(result);
80    }
81 }
```

`java.util.stream.Collectors` **8**

- `public static <T,K,A,D> Collector<T,?,Map<K,D>> groupingBy(Function<? super T,? extends K> classifier, Collector<? super T,A,D> downstream)` yields a collector that produces a map. The keys are the results of applying `classifier` to all collected elements. The values are the results of collecting elements with the same key, using the downstream collector.
- `static <T> Collector<T,?,Long> counting()` yields a collector that counts the collected elements.

- `static <T> Collector<T,?,Integer> summingInt(ToIntFunction<? super T> mapper)`
- `static <T> Collector<T,?,Long> summingLong(ToLongFunction<? super T> mapper)`
- `static <T> Collector<T,?,Double> summingDouble(ToDoubleFunction<? super T> mapper)`
  yield a collector that computes the sum of the results of applying `mapper` to the collected elements.
- `static <T> Collector<T,?,Optional<T>> maxBy(Comparator<? super T> comparator)`
- `static <T> Collector<T,?,Optional<T>> minBy(Comparator<? super T> comparator)`
  yield a collector that computes the maximum or minimum of the collected elements, using the ordering specified by `comparator`.
- `static <T,A,R,RR> Collector<T,A,RR> collectingAndThen(Collector<T,A,R> downstream, Function<R,RR> finisher)`
  yields a collector that sends elements to the downstream collector and then applies the finisher function to its result.
- `static <T,U,A,R> Collector<T,?,R> mapping(Function<? super T,? extends U> mapper, Collector<? super U,A,R> downstream)`
  yields a collector that calls `mapper` on each element and passes the results to the downstream collector.

- `static <T,U,A,R> Collector<T,?,R> flatMapping(Function<? super T,? extends Stream<? extends U>> mapper, Collector<? super U,A,R> downstream)`
  yields a collector that calls `mapper` on each element and passes the elements of the results to the downstream collector.
- `static <T,A,R> Collector<T,?,R> filtering(Predicate<? super T> predicate, Collector<? super T,A,R> downstream)`
  yields a collector that passes the elements fulfilling the predicate to the downstream collector.

1.12. Reduction Operations

The `reduce` method is a general mechanism for computing a value from a stream. The simplest form takes a binary function and keeps applying it, starting with the first two elements. It's easy to explain this if the function is the sum:

```
List<Integer> values = . . .;
Optional<Integer> sum = values.stream().reduce((x, y)
```

In this case, the `reduce` method computes $v_0 + v_1 + v_2 + \ldots$, where v_i are the stream elements. The method returns an `Optional` because there is no valid result if the stream is empty.

Note: In this case, you can write `reduce(Integer::sum)` instead of `reduce((x, y) -> x + y)`.

More generally, you can use any operation that combines a partial result `x` with the next value `y` to yield a new partial result.

Here is another way of looking at reductions. Given a reduction operation op, the reduction yields v_0 op v_1 op v_2 op ..., where v_i op v_{i+1} denotes the function call op(v_i, v_{i+1}). There are many operations that might be useful in practice—such as sum, product, string concatenation, maximum and minimum, set union or intersection.

If you want to use reduction with parallel streams, the operation must be *associative*: It shouldn't matter in which order you combine the elements. In math notation, (x op y) op z must be equal to x op (y op z). An example of an operation that is not associative is subtraction. For example, (6 − 3) − 2 ≠ 6 − (3 − 2).

Often, there is an *identity* e such that e op x = x, and that element can be used as the start of the computation. For example, 0 is the identity for addition, and you can use the second form of `reduce`:

```
List<Integer> values = . . .;
Integer sum = values.stream().reduce(0, (x, y) -> x +
   // Computes 0 + v0 + v1 + v2 + . . .
```

The identity value is returned if the stream is empty, and you no longer need to deal with the `Optional` class.

Now suppose you have a stream of objects and want to form the sum of some property, such as lengths in a stream of strings. You can't use the simple form of `reduce`. It requires a function `(T, T) -> T`, with the same types for the parameters and the result, but in this situation you have two types: The stream elements have type `String`, and the accumulated result is an integer. There is a form of `reduce` that can deal with this situation.

First, you supply an "accumulator" function `(total, word) -> total + word.length()`. That function is called repeatedly, forming the cumulative total. But when the computation is parallelized, there will be multiple computations of this kind, and you need to combine their results. You supply a second function for that purpose. The complete call is

```
int result = words.reduce(0,
   (total, word) -> total + word.length(),
   (total1, total2) -> total1 + total2);
```

Note: In practice, you probably won't use the `reduce` method a lot. It is usually easier to map to a stream of numbers and use one of its methods to compute sum, maximum, or minimum. (We discuss streams of numbers in Section 1.13.) In this particular example, you could have called `words.mapToInt(String::length).sum()`, which is both simpler and more efficient since it doesn't involve boxing.

Note: There are times when `reduce` is not general enough. For example, suppose you want to collect the results in a `BitSet`. If the collection is parallelized, you can't put the elements directly into a single `BitSet` because a `BitSet` object is not thread-safe. For that reason, you can't use `reduce`. Each segment needs to start out with its own empty set, and `reduce` only lets you supply one identity value. Instead, use the three-parameter form of `collect`. You provide three functions:

1. A *supplier* to construct new instances of the target object

2. An *accumulator* that adds an element to the target

3. A *combiner* that merges two target objects into one

Here is how the `collect` method works for a bit set:

```
BitSet result = stream.collect(BitSet::new
```

---

java.util.Stream **8**

- `Optional<T> reduce(BinaryOperator<T> accumulator)`
- `T reduce(T identity, BinaryOperator<T> accumulator)`
- `<U> U reduce(U identity, BiFunction<U,? super T,U> accumulator, BinaryOperator<U> combiner)`
  form a cumulative total of the stream elements with the given `accumulator` function. If `identity` is provided, then it is the first value to be accumulated. If `combiner` is provided, it can be used to combine totals of segments that are accumulated separately.
- `<R> R collect(Supplier<R> supplier, BiConsumer<R,?`

`super T> accumulator, BiConsumer<R,R> combiner)` collects elements in a result of type `R`. On each segment, `supplier` is called to provide an initial result, `accumulator` is called to mutably add elements to it, and `combiner` is called to combine two results.

1.13. Primitive Type Streams

So far, we have collected integers in a `Stream<Integer>`, even though it is clearly inefficient to wrap each integer into a wrapper object. The same is true for the other primitive types— `double`, `float`, `long`, `short`, `char`, `byte`, and `boolean`. The stream library has specialized types `IntStream`, `LongStream`, and `DoubleStream` that store primitive values directly, without using wrappers. If you want to store `short`, `char`, `byte`, and `boolean`, use an `IntStream`; for `float`, use a `DoubleStream`.

To create an `IntStream`, call the `IntStream.of` and `Arrays.stream` methods:

```
IntStream stream = IntStream.of(1, 1, 2, 3, 5);
stream = Arrays.stream(values, from, to); // values i
```

As with object streams, you can also use the static `generate` and `iterate` methods. In addition, `IntStream` and `LongStream`

have static methods `range` and `rangeClosed` that generate integer ranges with step size one:

```
IntStream zeroToNinetyNine = IntStream.range(0, 100);
IntStream zeroToHundred = IntStream.rangeClosed(0, 10
```

The `CharSequence` interface has methods `codePoints` and `chars` that yield an `IntStream` of the Unicode codes of the characters or of the code units in the UTF-16 encoding. (See Chapter 2 for the sordid details.)

```
String greeting = "Ciao IT";
IntStream codes = greeting.codePoints();
   // The stream with values 67, 105, 97, 111, 32, 12
```

The `RandomGenerator` interface has methods `ints`, `longs`, and `doubles` that return primitive type streams of random numbers.

```
IntStream randomIntegers = RandomGenerator.getDefault
```

When you have a stream of objects, you can transform it to a primitive type stream with the `mapToInt`, `mapToLong`, or `mapToDouble` methods. For example, if you have a stream of

strings and want to process their lengths as integers, you might as well do it in an `IntStream`:

```
Stream<String> words = . . .;
IntStream lengths = words.mapToInt(String::length);
```

To convert a primitive type stream to an object stream, use the `boxed` method:

```
Stream<Integer> integers = IntStream.range(0, 100).bo
```

Generally, the methods on primitive type streams are analogous to those on object streams. Here are the most notable differences:

- The `toArray` methods return primitive type arrays.
- Methods that yield an optional result return an `OptionalInt`, `OptionalLong`, or `OptionalDouble`. These classes are analogous to the `Optional` class, but they have methods `getAsInt`, `getAsLong`, and `getAsDouble` instead of the `get` method.
- There are methods `sum`, `average`, `max`, and `min` that return the sum, count, average, maximum, and minimum. These methods are not defined for object streams.

- The `summaryStatistics` method yields an object of type `IntSummaryStatistics`, `LongSummaryStatistics`, or `DoubleSummaryStatistics` that can simultaneously report the sum, count, average, maximum, and minimum of the stream.

The program in Listing 1.7 gives examples for the API of primitive type streams.

Listing 1.7 streams/PrimitiveTypeStreams.java

```
1  package streams;
2
3  import java.io.*;
4  import java.nio.file.*;
5  import java.util.stream.*;
6
7  /**
8   * @version 1.02 2021-09-09
9   * @author Cay Horstmann
10  */
11 public class PrimitiveTypeStreams
12 {
13    public static void show(String title, IntStr
14    {
15       final int SIZE = 10;
16       int[] firstElements = stream.limit(SIZE +
17       System.out.print(title + ": ");
```

```
18          for (int i = 0; i < firstElements.length;
19          {
20             if (i > 0) System.out.print(", ");
21             if (i < SIZE) System.out.print(firstEl
22             else System.out.print("...");
23          }
24          System.out.println();
25       }
26
27       public static void main(String[] args) throw
28       {
29          IntStream is1 = IntStream.generate(() ->
30          show("is1", is1);
31          IntStream is2 = IntStream.range(5, 10);
32          show("is2", is2);
33          IntStream is3 = IntStream.rangeClosed(5,
34          show("is3", is3);
35
36          String contents = Files.readString(Path.o
37
38          Stream<String> words = Stream.of(contents
39          IntStream is4 = words.mapToInt(String::le
40          show("is4", is4);
41          String sentence = "\uD835\uDD46 is the se
42          System.out.println(sentence);
43          IntStream codes = sentence.codePoints();
44          System.out.println(codes.mapToObj(c -> "%
45             Collectors.joining()));
```

```
46
47          Stream<Integer> integers = IntStream.rang
48          IntStream is5 = integers.mapToInt(Integer
49          show("is5", is5);
50      }
51  }
```

java.util.stream.IntStream **8**

- `static IntStream range(int startInclusive, int endExclusive)`
- `static IntStream rangeClosed(int startInclusive, int endInclusive)`
  yield an `IntStream` with the integers in the given range.
- `static IntStream of(int... values)`
  yields an `IntStream` with the given elements.
- `int[] toArray()`
  yields an array with the elements of this stream.
- `int sum()`
- `OptionalDouble average()`
- `OptionalInt max()`
- `OptionalInt min()`
- `IntSummaryStatistics summaryStatistics()`
  yield the sum, average, maximum, or minimum of the elements in this stream, or an object from which all four of these values

can be obtained.

- `Stream<Integer> boxed()`
  yields a stream of wrapper objects for the elements in this stream.

java.util.stream.LongStream **8**

- `static LongStream range(long startInclusive, long endExclusive)`
- `static LongStream rangeClosed(long startInclusive, long endInclusive)`
  yield a `LongStream` with the integers in the given range.
- `static LongStream of(long... values)`
  yields a `LongStream` with the given elements.
- `long[] toArray()`
  yields an array with the elements of this stream.
- `long sum()`
- `OptionalDouble average()`
- `OptionalLong max()`
- `OptionalLong min()`
- `LongSummaryStatistics summaryStatistics()`
  yield the sum, average, maximum, or minimum of the elements in this stream, or an object from which all four of these values can be obtained.

- `Stream<Long> boxed()`
  yields a stream of wrapper objects for the elements in this stream.

java.util.stream.DoubleStream **8**

- `static DoubleStream of(double... values)`
  yields a `DoubleStream` with the given elements.
- `double[] toArray()`
  yields an array with the elements of this stream.
- `double sum()`
- `OptionalDouble average()`
- `OptionalDouble max()`
- `OptionalDouble min()`
- `DoubleSummaryStatistics summaryStatistics()`
  yield the sum, average, maximum, or minimum of the elements in this stream, or an object from which all four of these values can be obtained.
- `Stream<Double> boxed()`
  yields a stream of wrapper objects for the elements in this stream.

java.lang.CharSequence **1.0**

- `IntStream codePoints()` **8**
  yields a stream of all Unicode code points.

- `IntStream ints()`
- `IntStream ints(int randomNumberOrigin, int randomNumberBound)`
- `IntStream ints(long streamSize)`
- `IntStream ints(long streamSize, int randomNumberOrigin, int randomNumberBound)`
- `LongStream longs()`
- `LongStream longs(long randomNumberOrigin, long randomNumberBound)`
- `LongStream longs(long streamSize)`
- `LongStream longs(long streamSize, long randomNumberOrigin, long randomNumberBound)`
- `DoubleStream doubles()`
- `DoubleStream doubles(double randomNumberOrigin, double randomNumberBound)`
- `DoubleStream doubles(long streamSize)`
- `DoubleStream doubles(long streamSize, double randomNumberOrigin, double randomNumberBound)`

  yield streams of random numbers. If `streamSize` is provided, the stream is finite with the given number of elements. When bounds are provided, the elements are between

`randomNumberOrigin` (inclusive) and `randomNumberBound` (exclusive).

`java.util.Optional(Int|Long|Double)` `8`

- `static Optional(Int|Long|Double) of((int|long|double) value)`
  yields an optional object with the supplied primitive type value.
- `(int|long|double) getAs(Int|Long|Double)()`
  yields the value of this optional object, or throws a `NoSuchElementException` if it is empty.
- `(int|long|double) orElse((int|long|double) other)`
- `(int|long|double) orElseGet((Int|Long|Double)Supplier other)`
  yield the value of this optional object, or the alternative value if this object is empty.
- `void ifPresent((Int|Long|Double)Consumer consumer)`
  If this optional object is not empty, passes its value to `consumer`.

`java.util.(Int|Long|Double)SummaryStatistics` 8

- `long getCount()`
- `(int|long|double) getSum()`
- `double getAverage()`
- `(int|long|double) getMax()`
- `(int|long|double) getMin()`

  yield the count, sum, average, maximum, and minimum of the collected elements.

1.14. Parallel Streams

Streams make it easy to parallelize bulk operations. The process is mostly automatic, but you need to follow a few rules. First of all, you must have a parallel stream. You can get a parallel stream from any collection with the `Collection.parallelStream()` method:

```
Stream<String> parallelWords = words.parallelStream()
```

Moreover, the `parallel` method converts any sequential stream into a parallel one.

```
Stream<String> parallelWords = Stream.of(wordArray).p
```

As long as the stream is in parallel mode when the terminal method executes, all intermediate stream operations will be parallelized.

When stream operations run in parallel, the intent is that the same result is returned as if they had run serially. It is important that the operations are *stateless* and can be executed in an arbitrary order.

Here is an example of something you cannot do. Suppose you want to count all short words in a stream of strings:

```
var shortWords = new int[12];
words.parallelStream().forEach(
   s -> { if (s.length() < 12) shortWords[s.length()]
      // ERROR--race condition!
System.out.println(Arrays.toString(shortWords));
```

This is very, very bad code. The function passed to `forEach` runs concurrently in multiple threads, each updating a shared array. As you saw in Chapter 10 of Volume I, that's a classic *race condition*. If you run this program multiple times, you are quite likely to get a different sequence of counts in each run—each of them wrong.

It is your responsibility to ensure that any functions you pass to parallel stream operations are safe to execute in parallel. The best way to do that is to stay away from mutable state. In this example,

you can safely parallelize the computation if you group strings by length and count them:

```
Map<Integer, Long> shortWordCounts
   = words.parallelStream()
      .filter(s -> s.length() < 12)
      .collect(groupingBy(
         String::length,
         counting()));
```

By default, streams that arise from ordered collections (arrays and lists), from ranges, generators, and iterators, or from calling `Stream.sorted`, are *ordered*. Results are accumulated in the order of the original elements, and are entirely predictable. If you run the same operations twice, you will get exactly the same results.

Ordering does not preclude efficient parallelization. For example, when computing `stream.map(fun)`, the stream can be partitioned into n segments, each of which is concurrently processed. Then the results are reassembled in order.

Some operations can be more effectively parallelized when the ordering requirement is dropped. By calling the `Stream.unordered` method, you indicate that you are not interested in ordering. One operation that can benefit from this is `Stream.distinct`. On an

ordered stream, `distinct` retains the first of all equal elements. That impedes parallelization—the thread processing a segment can't know which elements to discard until the preceding segment has been processed. If it is acceptable to retain *any* of the unique elements, all segments can be processed concurrently (using a shared set to track duplicates).

You can also speed up the `limit` method by dropping ordering. If you just want any `n` elements from a stream and you don’t care which ones you get, call

```
Stream<String> sample = words.parallelStream().unorde
```

As discussed in Section 1.9, merging maps is expensive. For that reason, the `Collectors.groupingByConcurrent` method uses a shared concurrent map. To benefit from parallelism, the order of the map values will not be the same as the stream order.

```
Map<Integer, List<String>> result = words.parallelStr
   Collectors.groupingByConcurrent(String::length));
   // Values aren't collected in stream order
```

Of course, you won't care if you use a downstream collector that is independent of the ordering, such as

```
Map<Integer, Long> wordCounts
   = words.parallelStream()
      .collect(
         groupingByConcurrent(
            String::length,
            counting()));
```

Don't turn all your streams into parallel streams in the hope of speeding up operations. Keep these issues in mind:

- There is a substantial overhead to parallelization that will only pay off for very large data sets.
- Parallelizing a stream is only a win if the underlying data source can be effectively split into multiple parts.
- The thread pool that is used by parallel streams can be starved by blocking operations such as file I/O or network access.

Parallel streams work best with huge in-memory collections of data and computationally intensive processing.

Tip: If you process the lines of a huge file, parallelizing the stream may improve performance. The `Files.lines` method uses a memory-mapped file, to make splitting effective. (If you simply read

a line at a time, then you would have to read the first half of the file before the second half, and parallelization would not work.)

Note: If you need random numbers in parallel streams, obtain a generator from the `RandomGenerator.SplittableGenerator.of` factory method.

Note: By default, parallel streams use the global fork-join pool returned by `ForkJoinPool.commonPool`. That is fine if your operations don't block and you don't share the pool with other tasks. There is a trick to substitute a different fork-join pool. Execute the parallel stream operations in a thread from that pool:

```
ForkJoinPool customPool = . . .;
result = customPool.submit(() ->
   stream.parallel().map(. . .).collect(.
```

Or, asynchronously:

```
CompletableFuture.supplyAsync(() -> stream
```

```
      .thenAccept(result -> . . .);
```

This only works with a fork-join pool, not with arbitrary executors.

The example program in Listing 1.8 demonstrates how to work with parallel streams.

Listing 1.8 parallel/ParallelStreams.java

```
1  package parallel;
2
3  import static java.util.stream.Collectors.*;
4
5  import java.io.*;
6  import java.nio.file.*;
7  import java.util.*;
8  import java.util.stream.*;
9
10 /**
11  * @version 1.02 2019-08-28
12  * @author Cay Horstmann
13  */
14 public class ParallelStreams
15 {
16    public static void main(String[] args) throw
```

```
17    {
18       String contents = Files.readString(Path.o
19       List<String> wordList = List.of(contents
20
21       // Very bad code ahead
22       var shortWords = new int[10];
23       wordList.parallelStream().forEach(s ->
24          {
25             if (s.length() < 10) shortWords[s.l
26          });
27       System.out.println(Arrays.toString(shortW
28
29       // Try again--the result will likely be d
30       Arrays.fill(shortWords, 0);
31       wordList.parallelStream().forEach(s ->
32          {
33             if (s.length() < 10) shortWords[s.l
34          });
35       System.out.println(Arrays.toString(shortW
36
37       // Remedy: Group and count
38       Map<Integer, Long> shortWordCounts = word
39          .filter(s -> s.length() < 10)
40          .collect(groupingBy(String::length, co
41
42       System.out.println(shortWordCounts);
43
44       // Downstream order not deterministic
```

```
45          Map<Integer, List<String>> result = wordL
46             Collectors.groupingByConcurrent(String
47
48          System.out.println(result.get(14));
49
50          result = wordList.parallelStream().collec
51             Collectors.groupingByConcurrent(String
52
53          System.out.println(result.get(14));
54
55          Map<Integer, Long> wordCounts = wordList
56             groupingByConcurrent(String::length, c
57
58          System.out.println(wordCounts);
59       }
60    }
```

java.util.stream.BaseStream<T,S extends BaseStream<T,S>> **8**

- `S parallel()`
  yields a parallel stream with the same elements as this stream.
- `S unordered()`
  yields an unordered stream with the same elements as this stream.

java.util.Collection<E> **1.2**

- `Stream<E> parallelStream()` **8**
  yields a parallel stream with the elements of this collection.

In this chapter, you have learned how to put the stream library to use. The next chapter covers another important topic: processing input and output.

1. Input and Output

In this chapter, we cover the Java Application Programming Interfaces (APIs) for input and output. You will learn how to access files and directories and how to read and write data in binary and text format. This chapter also shows you the object serialization mechanism that lets you store objects as easily as you can store text or numeric data. We finish the chapter with a discussion of regular expressions, even though they are not actually related to input and output. We couldn't find a better place to handle that topic, and apparently neither could the Java team—the regular expression API specification was attached to a specification request for "new I/O" features.

1.1. Input/Output Streams

In the Java API, an object from which we can read a sequence of bytes is called an *input stream.* An object to which we can write a sequence of bytes is called an *output stream.* These sources and destinations of byte sequences can be—and often are—files, but they can also be network connections and even blocks of memory. The abstract classes `InputStream` and `OutputStream` are the basis for a hierarchy of input/output (I/O) classes.

Note: These input/output streams are unrelated to the streams that you saw in the preceding chapter. For clarity, we will use the terms input stream, output stream, or input/output stream whenever we discuss streams that are used for input and output.

Byte-oriented input/output streams are inconvenient for processing information stored in Unicode (recall that Unicode uses multiple bytes per character). Therefore, a separate hierarchy provides classes, inheriting from the abstract `Reader` and `Writer` classes, for processing Unicode characters. These classes have read and write operations that are based on two-byte `char` values (that is, UTF-16 code units) rather than `byte` values.

1.1.1. Reading and Writing Bytes

The `InputStream` class has an abstract method:

```
abstract int read()
```

This method reads one byte and returns the byte that was read, or `-1` if it encounters the end of the input source. The designer of a concrete input stream class overrides this method to provide useful functionality. For example, in the `FileInputStream` class, this

method reads one byte from a file. `System.in` is a predefined object of a subclass of `InputStream` that allows you to read information from "standard input," that is, the console or a redirected file.

The `InputStream` has a very useful method to read all bytes of a stream:

```
byte[] bytes = in.readAllBytes();
```

There are also methods to read a given number of bytes—see the API notes.

These methods call the abstract `read` method, so subclasses need to override only one method.

Similarly, the `OutputStream` class defines the abstract method

```
abstract void write(int b)
```

which writes one byte to an output location.

If you have an array of bytes, you can write them all at once:

```
byte[] values = . . .;
out.write(values);
```

The `transferTo` method transfers all bytes from an input stream to an output stream:

```
in.transferTo(out);
```

Both the `read` and `write` methods *block* until the byte is actually read or written. This means that if the input stream cannot immediately be accessed (usually because of a busy network connection), the current thread blocks. This gives other threads the chance to do useful work while the method is waiting for the input stream to become available again.

The `available` method lets you check the number of bytes that are currently available for reading. This means a fragment like the following is unlikely to block:

```
int bytesAvailable = in.available();
if (bytesAvailable > 0)
{
```

```
    var data = new byte[bytesAvailable];
    in.read(data);
}
```

When you have finished reading or writing to an input/output stream, close it by calling the `close` method. This call frees up the operating system resources that are in limited supply. If an application opens too many input/output streams without closing them, system resources can become depleted. Closing an output stream also *flushes* the buffer used for the output stream: Any bytes that were temporarily placed in a buffer so that they could be delivered as a larger packet are sent off. In particular, if you do not close a file, the last packet of bytes might never be delivered. You can also manually flush the output with the `flush` method.

Even if an input/output stream class provides concrete methods to work with the raw `read` and `write` functions, application programmers rarely use them. The data that you are interested in probably contain numbers, strings, and objects, not raw bytes.

Instead of working with bytes, you can use one of many input/output classes that build upon the basic `InputStream` and `OutputStream` classes.

`java.io.InputStream` **1.0**

- `abstract int read()`
  reads a byte of data and returns the byte read; returns `-1` at the end of the input stream.
- `int read(byte[] b)`
  reads into an array of bytes and returns the actual number of bytes read, or `-1` at the end of the input stream; this method reads at most `b.length` bytes.
- `int read(byte[] b, int off, int len)`
- `int readNBytes(byte[] b, int off, int len)` **9**
  read up to `len` bytes, if available without blocking (`read`), or blocking until all values have been read (`readNBytes`). Values are placed into `b` , starting at `off` . Returns the actual number of bytes read.
- `byte[] readAllBytes()` **9**
  yields an array of all bytes that can be read from this stream.
- `long transferTo(OutputStream out)` **9**
  transfers all bytes from this input stream to the given output stream, returning the number of bytes transferred. Neither stream is closed.
- `long skip(long n)`
  attempts to skip `n` bytes in the input stream, returns the actual number of bytes skipped (which, for any reason, may be less

than `n`).

- `long skipNBytes(long n)` **12**
  skips `n` bytes in the input stream, returns the actual number of bytes skipped (which may be less than `n` if the end of the input stream was encountered).
- `int available()`
  returns the number of bytes available, without blocking (recall that blocking means that the current thread loses its turn).
- `void close()`
  closes the input stream.
- `void mark(int readlimit)`
  puts a marker at the current position in the input stream (not all streams support this feature). If more than `readlimit` bytes have been read from the input stream, the stream is allowed to forget the marker.
- `void reset()`
  returns to the last marker. Subsequent calls to `read` reread the bytes. If there is no current marker, the input stream is not reset.
- `boolean markSupported()`
  returns `true` if the input stream supports marking.
- `static InputStream nullInputStream()` **11**
  returns an input stream with no bytes.

`java.io.OutputStream` 1.0

- `abstract void write(int n)`
  writes a byte of data.
- `void write(byte[] b)`
- `void write(byte[] b, int off, int len)`
  write all bytes, or `len` bytes starting at `off`, in the array `b`.
- `void close()`
  flushes and closes the output stream.
- `void flush()`
  flushes the output stream—that is, sends any buffered data to its destination.
- `static OutputStream nullOutputStream()` 11
  returns an output stream that discards all bytes.

1.1.2. The Complete Stream Zoo

Unlike C, which gets by just fine with a single type `FILE*`, Java has a whole zoo of more than 60 (!) classes and interfaces for input and output.



Figure 1.1: Input and output stream hierarchy



Figure 1.2: Reader and writer hierarchy

Let's divide the animals in the input/output zoo by how they are used. There are separate hierarchies for classes that process bytes and characters. As you saw, the `InputStream` and `OutputStream` classes let you read and write individual bytes and arrays of bytes. These classes form the basis of the hierarchy shown in #ch01fig01. To read and write strings and numbers, you need more capable subclasses. For example, `DataInputStream` and `DataOutputStream` let you read and write all the primitive Java types in binary format. Finally, there are input/output streams for

specialized tasks; for example, the `ZipInputStream` and `ZipOutputStream` let you read and write files in the familiar ZIP compression format.

For Unicode text, on the other hand, you can use subclasses of the abstract classes `Reader` and `Writer` (see #ch01fig02). The basic methods of the `Reader` and `Writer` classes are similar to those of `InputStream` and `OutputStream`.

```
abstract int read()
abstract void write(int c)
```

The `read` method returns either a UTF-16 code unit (as an integer between `0` and `65535`) or `-1` when you have reached the end of the file. The `write` method is called with a Unicode code unit. (See Chapter 3 of Volume I for a discussion of Unicode code units.)

There are four additional interfaces: `Closeable`, `Flushable`, `Readable`, and `Appendable` (see #ch01fig03). The first two interfaces are very simple, with methods

```
void close() throws IOException
```

and

```
void flush()
```

respectively. The classes `InputStream`, `OutputStream`, `Reader`, and `Writer` all implement the `Closeable` interface.

Note: The `java.io.Closeable` interface extends the `java.lang.AutoCloseable` interface. Therefore, you can use the `try`-with-resources statement with any `Closeable`. Why have two interfaces? The `close` method of the `Closeable` interface only throws an `IOException`, whereas the `AutoCloseable.close` method may throw any exception.

`OutputStream` and `Writer` implement the `Flushable` interface.



Figure 1.3: The `Closeable`, `Flushable`, `Readable`, and `Appendable` interfaces

The `Readable` interface has a single method

```
int read(CharBuffer cb)
```

The `CharBuffer` class has methods for sequential and random read/write access. It represents an in-memory buffer or a memory-mapped file. (See Section 2.5.2 for details.)

The `Appendable` interface has two methods for appending single characters and character sequences:

```
Appendable append(char c)
Appendable append(CharSequence s)
```

The `CharSequence` interface describes basic properties of a sequence of `char` values. It is implemented by `String`, `CharBuffer`, `StringBuilder`, and `StringBuffer`.

Of the input/output stream classes, only `Writer` implements `Appendable`.

java.io.Closeable **5.0**

- `void close()`
  closes this `Closeable`. This method may throw an `IOException`.

java.io.Flushable **5.0**

- `void flush()`
  flushes this `Flushable`.

java.lang.Readable **5.0**

- `int read(CharBuffer cb)`
  attempts to read as many `char` values into `cb` as it can hold. Returns the number of values read, or `-1` if no further values are available from this `Readable`.

java.lang.Appendable **5.0**

- `Appendable append(char c)`
- `Appendable append(CharSequence cs)`
  append the given code unit, or all code units in the given sequence, to this `Appendable`; return `this`.

java.lang.CharSequence **1.4**

- `char charAt(int index)`
  returns the code unit at the given index.
- `int length()`
  returns the number of code units in this sequence.
- `CharSequence subSequence(int startIndex, int endIndex)`
  returns a `CharSequence` consisting of the code units stored from index `startIndex` to `endIndex - 1`.

- `String toString()`
  returns a string consisting of the code units of this sequence.

1.1.3. Combining Input/Output Stream Filters

`FileInputStream` and `FileOutputStream` give you input and output streams attached to a disk file. You need to pass the file name or full path name of the file to the constructor. For example,

```
var fin = new FileInputStream("employee.dat");
```

looks for a file named `employee.dat`.

Note: Relative path names start from the *working directory*. You can get this directory by a call to `System.getProperty("user.dir")`. It is set when the virtual machine starts and cannot be changed afterwards. If you start your program from the command line, the working directory is the current directory in the terminal. In an IDE, you can set the working directory in the run configuration.

Caution: Since the backslash character is the escape character in Java strings, be sure to use `\\` for Windows-style path names (for example, `C:\\Windows\\win.ini`). In Windows, you can also use

a single forward slash (`C:/Windows/win.ini`) because most Windows file-handling system calls will interpret forward slashes as file separators. However, this is not recommended—the behavior of the Windows system functions is subject to change. Instead, for portable programs, use the file separator character for the platform on which your program runs. It is available as the constant string `java.io.File.separator` .

Like the abstract `InputStream` and `OutputStream` classes, these classes only support reading and writing at the byte level. That is, we can only read bytes and byte arrays from the object `fin` .

```
byte b = (byte) fin.read();
```

As you will see in the next section, if we just had a `DataInputStream` , we could read numeric types:

```
DataInputStream din = . . .;
double x = din.readDouble();
```

But just as the `FileInputStream` has no methods to read numeric types, the `DataInputStream` has no method to get data from a file.

Java uses a clever mechanism to separate two kinds of responsibilities. Some input streams (such as the `FileInputStream` and the input stream returned by the `openStream` method of the `URL` class) can retrieve bytes from files and other more exotic locations. Other input streams (such as the `DataInputStream`) can assemble bytes into more useful data types. The Java programmer has to combine the two. For example, to be able to read numbers from a file, first create a `FileInputStream` and then pass it to the constructor of a `DataInputStream`.

```
var fin = new FileInputStream("employee.dat");
var din = new DataInputStream(fin);
double x = din.readDouble();
```

If you look at #ch01fig01 again, you can see the classes `FilterInputStream` and `FilterOutputStream`. The subclasses of these classes are used to add capabilities to input/output streams that process bytes.

You can add multiple capabilities by nesting the filters. For example, by default, input streams are not buffered. That is, every call to `read` asks the operating system to dole out yet another byte. It is more efficient to request blocks of data instead and store them in a

buffer. If you want buffering *and* the data input methods for a file, use the following rather monstrous sequence of constructors:

```
var din = new DataInputStream(
   new BufferedInputStream(
      new FileInputStream("employee.dat")));
```

Notice that we put the `DataInputStream` *last* in the chain of constructors because we want to use the `DataInputStream` methods, and we want *them* to use the buffered `read` method.

Sometimes you'll need to keep track of the intermediate input streams when chaining them together. For example, when reading input, you often need to peek at the next byte to see if it is the value that you expect. Java provides the `PushbackInputStream` for this purpose.

```
var pbin = new PushbackInputStream(
   new BufferedInputStream(
      new FileInputStream("employee.dat")));
```

Now you can speculatively read the next byte

```
int b = pbin.read();
```

and throw it back if it isn’t what you wanted.

```
if (b != '<') pbin.unread(b);
```

Note: The `unread` method doesn't actually alter the source from which the stream reads its bytes. Unread bytes are stored in a buffer and are returned by the next `read` operation. By default, the buffer has length 1, but you can specify a longer buffer in the `PushbackInputStream` constructor.

Reading and unreading are the *only* methods that apply to a pushback input stream. If you want to look ahead and also read numbers, then you need both a pushback input stream and a data input stream reference.

```
var pbin = new PushbackInputStream(
   new BufferedInputStream(
      new FileInputStream("employee.dat")));
var din = new DataInputStream(pbin);
```

Of course, in the input/output libraries of other programming languages, niceties such as buffering and lookahead are automatically taken care of—so it is a bit of a hassle to resort, in

Java, to combining stream filters. However, the ability to mix and match filter classes to construct useful sequences of input/output streams does give you an immense amount of flexibility. For example, you can read numbers from a compressed ZIP file by using the following sequence of input streams (see #ch01fig04):

```
var zin = new ZipInputStream(new FileInputStream("emp
var din = new DataInputStream(zin);
```



Figure 1.4: A sequence of filtered input streams

(See Section 2.2.3 for more on Java's handling of ZIP files.)

`java.io.FileInputStream` **1.0**

- `FileInputStream(String name)`
- `FileInputStream(File file)`

  create a new file input stream using the file whose path name is specified by the `name` string or the object of the legacy `File` class.

`java.io.FileOutputStream` **1.0**

- `FileOutputStream(String name)`
- `FileOutputStream(String name, boolean append)`
- `FileOutputStream(File file)`
- `FileOutputStream(File file, boolean append)`

  create a new file output stream specified by the `name` string or the `file` object. (The `File` class is described at the end of this chapter.) If the `append` parameter is `true`, an existing file with the same name will not be deleted and data will be added at the end of the file. Otherwise, this method deletes any existing file with the same name.

`java.io.BufferedInputStream` **1.0**

- `BufferedInputStream(InputStream in)`
  creates a buffered input stream. A buffered input stream reads bytes from a stream without causing a device access every time. When the buffer is empty, a new block of data is read into the buffer.

`java.io.BufferedOutputStream` **1.0**

- `BufferedOutputStream(OutputStream out)`
  creates a buffered output stream. A buffered output stream collects bytes to be written without causing a device access every time. When the buffer fills up or when the stream is flushed, the data are written.

`java.io.PushbackInputStream` **1.0**

- `PushbackInputStream(InputStream in)`
- `PushbackInputStream(InputStream in, int size)`
  construct an input stream with one-byte lookahead or a pushback buffer of specified size.
- `void unread(int b)`
  pushes back a byte, which is retrieved again by the next call to `read`.

1.1.4. Text Input and Output

When saving data, you have the choice between binary and text formats. For example, if the integer 1234 is saved in binary, it is written as the sequence of bytes `00 00 04 D2` (in hexadecimal notation). In text format, it is saved as the string `"1234"`. Although binary I/O is fast and efficient, it is not easily readable by humans. We first discuss text I/O and cover binary I/O in Section 2.2.

When saving text strings, you need to consider the *character encoding*. In the UTF-16 encoding that Java uses internally, the string `"José"` is encoded as `00 4A 00 6F 00 73 00 E9` (in hex). However, many programs expect that text files use a different encoding. In UTF-8, the encoding most commonly used on the Internet, the string would be written as `4A 6F 73 C3 A9`, without the zero bytes for the first three letters and with two bytes for the é character.

The `OutputStreamWriter` class turns an output stream of Unicode code units into a stream of bytes. Conversely, the `InputStreamReader` class turns an input stream that contains bytes (specifying characters in some character encoding) into a reader that emits Unicode code units.

Since Java 18, these classes use the UTF-8 encoding by default. Before Java 18, or if you need to support an archaic encoding, specify the encoding in the constructor, for example:

```
var in = new InputStreamReader(new FileInputStream("d
```

See Section 2.1.8 for more information on character encodings.

The `Reader` and `Writer` classes have only basic methods to read and write individual characters. As with streams, you use subclasses for processing strings and numbers.

1.1.5. How to Read Text Input

The easiest way to process arbitrary text is the `Scanner` class that we used extensively in Volume I. You can construct a `Scanner` from any input stream.

Alternatively, you can read a short text file into a string like this:

```
String content = Files.readString(path, charset);
```

But if you want the file as a sequence of lines, call

```
List<String> lines = Files.readAllLines(path, charset
```

If the file is large, process the lines lazily as a `Stream<String>`:

```
try (Stream<String> lines = Files.lines(path, charset
{
   . . .
}
```

Note: If an `IOException` occurs as the stream fetches the lines, that exception is wrapped into an `UncheckedIOException` which is thrown out of the stream operation. This subterfuge is necessary because stream operations are not declared to throw any checked exceptions.

To read lines from an arbitrary input stream, use:

```
InputStream inputStream = . . .;
try (var reader = new BufferedReader(new InputStreamR
{
```

```
   Stream<String> lines = reader.lines();
   . . .
}
```

You can also use a scanner to read *tokens*—strings that are separated by a delimiter. The default delimiter is whitespace. You can change the delimiter to any regular expression. For example, here is how to configure a scanner so that it uses any non-Unicode letters as delimiters.

```
Scanner in = . . .;
in.useDelimiter("\\PL+");
```

This scanner now accepts tokens consisting only of Unicode letters.

Calling the `next` method yields the next token:

```
while (in.hasNext())
{
   String word = in.next();
   . . .
}
```

Alternatively, you can obtain a stream of all tokens as

```
Stream<String> words = in.tokens();
```

Note: In legacy code, you may find code that reads lines by repeatedly calling the `readLine` method of a `BufferedReader`. Nowadays, there is no good reason to do that.

1.1.6. How to Write Text Output

For text output, use a `PrintWriter`. That class has methods to print strings and numbers in text format. In order to print to a file, construct a `PrintWriter` from a file name:

```
var out = new PrintWriter("employee.txt");
```

Caution: Curiously, you cannot construct a `PrintWriter` from a `Path`!

Note: Before Java 18, be sure to specify the character encoding as a second argument:

```
var out = new PrintWriter("employee.txt",
```

> Otherwise, the platform encoding is used, making your program's behavior dependent on the configuration of the host operating system..

To write to a `PrintWriter`, use the same `print`, `println`, and `printf` methods that you used with `System.out`. You can use these methods to print numbers (`int`, `short`, `long`, `float`, `double`), characters, `boolean` values, strings, and objects.

For example, consider this code:

```
String name = "Harry Hacker";
double salary = 75000;
out.print(name);
out.print(' ');
out.println(salary);
```

This writes the characters

```
Harry Hacker 75000.0
```

to the writer `out`. The characters are then converted to bytes and end up in the file `employee.txt`.

The `println` method adds the correct end-of-line character for the target system (`"\r\n"` on Windows, `"\n"` on UNIX) to the line. This is the string obtained by the call `System.getProperty("line.separator")` .

If the writer is set to *autoflush mode*, all characters in the buffer are sent to their destination whenever `println` is called. (Print writers are always buffered.) By default, autoflushing is *not* enabled. You can enable or disable autoflushing by using the `PrintWriter(Writer writer, boolean autoFlush)` constructor:

```
var out = new PrintWriter(
   new OutputStreamWriter(
      new FileOutputStream("employee.txt")),
   true); // autoflush
```

The `print` methods don't throw exceptions. You can call the `checkError` method to see if something went wrong with the output stream.

Note: Java veterans might wonder what happened to the `PrintStream` class and to `System.out` . In Java 1.0, the `PrintStream` class simply truncated all Unicode characters to ASCII characters by dropping

the top byte. (At the time, Unicode was still a 16-bit encoding.) Clearly, that was not a clean or portable approach, and it was fixed with the introduction of readers and writers in Java 1.1. For compatibility with existing code, `System.in`, `System.out`, and `System.err` are still input/output streams, not readers and writers. But now the `PrintStream` class internally converts Unicode characters to the default character encoding in the same way the `PrintWriter` does. Objects of type `PrintStream` act exactly like print writers when you use the `print` and `println` methods, but unlike print writers they allow you to output raw bytes with the `write(int)` and `write(byte[])` methods.

`java.io.PrintWriter` **1.1**

- `PrintWriter(OutputStream out)`
- `PrintWriter(OutputStream out, boolean autoFlush)`
- `PrintWriter(Writer writer)`
- `PrintWriter(Writer writer, boolean autoFlush)`

create a new `PrintWriter` that writes to the given output stream or writer. If `autoFlush` is specified as `true`, `println` and `printf` flush the output.

- `PrintWriter(String filename, String encoding)`
- `PrintWriter(File file, String encoding)`
  create a new `PrintWriter` that writes to the given file, using the given character encoding.
- `void print(Object obj)`
  prints an object by printing the string resulting from `toString`.
- `void print(String s)`
  prints a string containing Unicode code units.
- `void println(String s)`
  prints a string followed by a line terminator. Flushes the output stream if it is in autoflush mode.
- `void print(char[] s)`
  prints all Unicode code units in the given array.
- `void print(char c)`
  prints a Unicode code unit.
- `void print(int i)`
- `void print(long l)`
- `void print(float f)`
- `void print(double d)`
- `void print(boolean b)`
  print the given value in text format.
- `void printf(String format, Object... args)`
  prints the given values as specified by the format string. See Chapter 3 of Volume I for the specification of the format string.

- `boolean checkError()`
  returns `true` if a formatting or output error occurred. Once the output stream has encountered an error, it is tainted and all calls to `checkError` return `true`.

1.1.7. Saving Objects in Text Format

In this section, we discuss an example program that stores an array of `Employee` records in a text file. Each record is stored in a separate line. Instance fields are separated from each other by delimiters. A vertical bar (`|`) is used as a delimiter. (A colon (`:`) is another popular choice. Part of the fun is that everyone uses a different delimiter.) Naturally, we punt on the issue of what might happen if a `|` actually occurs in one of the strings we save.

Here is a sample set of records:

```
Harry Hacker|35500.0|1989-10-01
Carl Cracker|75000.0|1987-12-15
Tony Tester|38000.0|1990-03-15
```

Writing records is simple. Since we write to a text file, we use the `PrintWriter` class. We simply write all fields, followed by either a `|` or, for the last field, a newline character. This work is done in the following method:

```
public static void writeEmployee(PrintWriter out, Emp
{
   out.println(e.getName() + "|" + e.getSalary() + "|
}
```

To read records, we read in a line at a time and separate the fields. We use a scanner to read each line and then split the line into tokens with the `String.split` method.

```
public static Employee readEmployee(Scanner in)
{
   String line = in.nextLine();
   String[] tokens = line.split("\\|");
   String name = tokens[0];
   double salary = Double.parseDouble(tokens[1]);
   LocalDate hireDate = LocalDate.parse(tokens[2]);
   int year = hireDate.getYear();
   int month = hireDate.getMonthValue();
   int day = hireDate.getDayOfMonth();
   return new Employee(name, salary, year, month, day
}
```

The parameter of the `split` method is a regular expression describing the separator. We discuss regular expressions in more detail at the end of this chapter. As it happens, the vertical bar

character has a special meaning in regular expressions, so it needs to be escaped with a `\` character. That character needs to be escaped by another `\`, yielding the `"\\|"` expression.

The complete program is in Listing 2.1. The static method

```
void writeData(Employee[] e, PrintWriter out)
```

first writes the length of the array, then writes each record. The static method

```
Employee[] readData(Scanner in)
```

first reads in the length of the array, then reads in each record. This turns out to be a bit tricky:

```
int n = in.nextInt();
in.nextLine(); // consume newline
var employees = new Employee[n];
for (int i = 0; i < n; i++)
{
   employees[i] = readEmployee(in);
}
```

The call to `nextInt` reads the array length but not the trailing newline character. We must consume the newline so that the `readEmployee` method can get the next input line when it calls the `nextLine` method.

Listing 1.1 textFile/TextFileTest.java

```
1  package textFile;
2
3  import java.io.*;
4  import java.time.*;
5  import java.util.*;
6
7  /**
8   * @version 1.16 2023-08-16
9   * @author Cay Horstmann
10  */
11 public class TextFileTest
12 {
13    public static void main(String[] args) throw
14    {
15       var staff = new Employee[3];
16
17       staff[0] = new Employee("Carl Cracker", 7
18       staff[1] = new Employee("Harry Hacker", 5
19       staff[2] = new Employee("Tony Tester", 40
20
```

```
21          // save all employee records to the file
22          try (var out = new PrintWriter("employee
23          {
24             writeData(staff, out);
25          }
26
27          // retrieve all records into a new array
28          try (var in = new Scanner(new FileInputSt
29          {
30             Employee[] newStaff = readData(in);
31
32             // print the newly read employee recor
33             for (Employee e : newStaff)
34                System.out.println(e);
35          }
36       }
37
38       /**
39        * Writes all employees in an array to a pri
40        * @param employees an array of employees
41        * @param out       a print writer
42        */
43       private static void writeData(Employee[] emp
44       {
45          // write number of employees
46          out.println(employees.length);
47
48          for (Employee e : employees)
```

```
49          writeEmployee(out, e);
50       }
51
52       /**
53        * Reads an array of employees from a scanne
54        * @param in the scanner
55        * @return the array of employees
56        */
57       private static Employee[] readData(Scanner i
58       {
59          // retrieve the array size
60          int n = in.nextInt();
61          in.nextLine(); // consume newline
62
63          var employees = new Employee[n];
64          for (int i = 0; i < n; i++)
65          {
66             employees[i] = readEmployee(in);
67          }
68          return employees;
69       }
70
71       /**
72        * Writes employee data to a print writer.
73        * @param out the print writer
74        * @param e the employee
75        */
76       public static void writeEmployee(PrintWriter
```

```
77       {
78          out.println(e.getName() + "|" + e.getSala
79       }
80
81       /**
82        * Reads employee data from a buffered reade
83        * @param in the scanner
84        * @return the employee
85        */
86       public static Employee readEmployee(Scanner
87       {
88          String line = in.nextLine();
89          String[] tokens = line.split("\\|");
90          String name = tokens[0];
91          double salary = Double.parseDouble(tokens
92          LocalDate hireDate = LocalDate.parse(toke
93          int year = hireDate.getYear();
94          int month = hireDate.getMonthValue();
95          int day = hireDate.getDayOfMonth();
96          return new Employee(name, salary, year, m
97       }
98    }
```

1.1.8. Character Encodings

Each Unicode "code point" has a 21-bit integer number. There are different *character encodings*—methods for packaging those 21-bit numbers into bytes.

The most common encoding is UTF-8, which encodes each Unicode code point into a sequence of one to four bytes (see Table 2.1). UTF-8 has the advantage that the characters of the traditional ASCII character set, which contains all characters used in English, only take up one byte each.

Table 1.1: UTF-8 Encoding

Character Range	Encoding
0. . .7F	$0a_6a_5a_4a_3a_2a_1a_0$
80. . .7FF	$110a_{10}a_9a_8a_7a_6\ 10a_5a_4a_3a_2a_1a_0$
800. . .FFFF	$1110a_{15}a_{14}a_{13}a_{12}\ 10a_{11}a_{10}a_9a_8a_7a_6\ 10a_5a_4a_3a_2a_1a_0$
10000. . .10FFFF	$11110a_{20}a_{19}a_{18}\ 10a_{17}a_{16}a_{15}a_{14}a_{13}a_{12}\ 10a_{11}a_{10}a_9a_8a_7a_6\ 10a_5a_4a_3a_2a_1a_0$

Table 1.2: UTF-16 Encoding

Character Range	Encoding

Character Range	Encoding
0. . .FFFF	$a_{15}a_{14}a_{13}a_{12}a_{11}a_{10}a_9a_8\ a_7a_6a_5a_4a_3a_2a_1a_0$
10000. . .10FFFF	$110110b_{19}b_{18}\ b_{17}b_{16}a_{15}a_{14}a_{13}a_{12}a_{11}a_{10}$ $110111a_9a_8\ a_7a_6a_5a_4a_3a_2a_1a_0$ where $b_{19}b_{18}b_{17}b_{16} = a_{20}a_{19}a_{18}a_{17}a_{16} - 1$

Another common encoding is UTF-16, which encodes each Unicode code point into one or two 16-bit values (see Table 2.2). This is the encoding used in Java strings. Actually, there are two forms of UTF-16, called "big-endian" and "little-endian." Consider the 16-bit value `0x2122`. In the big-endian format, the more significant byte comes first: `0x21` followed by `0x22`. In the little-endian format, it is the other way around: `0x22 0x21`. To indicate which of the two is used, a file can start with the "byte order mark," the 16-bit quantity `0xFEFF`. A reader can use this value to determine the byte order and then discard it.

Caution: Some programs, including Microsoft Notepad, add a byte order mark at the beginning of UTF-8 encoded files. Clearly, this is unnecessary since there are no byte ordering issues in UTF-8. But

the Unicode standard allows it, and even suggests that it's a pretty good idea since it leaves little doubt about the encoding. It is supposed to be removed when reading a UTF-8 encoded file. Sadly, Java does not do that, and bug reports against this issue are closed as "will not fix." Your best bet is to strip out any leading `\uFEFF` that you find in your input.

In addition to the UTF encodings, there are partial encodings that cover a character range suitable for a given user population. For example, ISO 8859-1 is a one-byte code that includes accented characters used in Western European languages. Shift-JIS is a variable-length code for Japanese characters. A number of these encodings are still in use.

There is no reliable way to automatically detect the character encoding from a stream of bytes. Sometimes, the encoding is specified elsewhere. For example, when reading a web page, check the `Content-Type` header.

The `StandardCharsets` class has static variables of type `Charset` for the character encodings that every Java virtual machine must support:

```
StandardCharsets.UTF_8
StandardCharsets.UTF_16
StandardCharsets.UTF_16BE
StandardCharsets.UTF_16LE
StandardCharsets.ISO_8859_1
StandardCharsets.US_ASCII
```

To obtain the `Charset` for another encoding, use the static `forName` method:

```
Charset shiftJIS = Charset.forName("Shift-JIS");
```

The static method `Charset.availableCharsets` returns all available `Charset` instances, as a map from canonical names to `Charset` objects.

Use a `Charset` object whenever you need to specify a character encoding. For example, you can turn an array of bytes into a string as

```
var str = new String(bytes, StandardCharsets.ISO_8859
```

Tip: Many methods allow you to specify a character encoding as a [illegible] instead of a `CharSet`. For the standard character encodings,

use the `StandardCharsets` constants, so that any spelling errors are caught at compile time.

Caution: Up to Java 17, calling `Charset.forName` with the name `"default"` yielded `StandardCharsets.US_ASCII`. This was surely a bad idea for a very long time. Nowadays, the call results in an `UnsupportedCharsetException`.

If you do not specify a character encoding, and an operation needs to convert between bytes and strings, it will pick a default. For many methods in the `java.nio.file` package, that default is UTF-8. But other methods use the *default charset* when no character encoding is specified. These include:

- The methods of the `java.io` reader and writer classes
- The `String(byte[])` constructor and the `getBytes` method of the `String` class
- `Scanner` and `Formatter` in the `java.util` package
- `URLEncoder` and `URLDecoder` in the `java.net` package

As of Java 18, the default charset is UTF-8. Prior to Java 18, the default charset was the *native encoding*, determined from the system executing the Java virtual machine. On Linux and Mac OS, that is usually (but not always) UTF-8. However, on Windows, the

native encoding is in most cases an archaic encoding such as Windows-1252.

Prior to Java 18, the Oracle implementation of Java had a system property `file.encoding` for overriding the platform default. This was not an officially supported property, but it was nevertheless widely used.

As of Java 18, this property has become standardized. You can set the `file.encoding` property on the command line to these values:

- `COMPAT` (as of Java 18): Sets the default charset to the native encoding, and the `file.encoding` system property to its name.
- `UTF-8`: Sets the default charset to UTF-8.
- Another character encoding such as `US-ASCII`: For some unspecified legacy charset names, it may set the default charset to the given one.

Caution: The `file.encoding` property must be set on the command line. Setting it via `System.setProperty` does not update the default charset.

The actually used default charset is returned by the static method `Charset.defaultCharset`. As of Java 17, the system property `native.encoding` yields the name of the native encoding, whether used or not.

Caution: When you start a Java program in a Windows terminal, the encoding used by `System.out` and `System.err` is derived from the "code page" of the terminal, which may be different from the default charset.

Your best bet is to change to the UTF-8 code page, with the Windows command:

```
chcp 65001
```

Alternatively, as of Java 18, you can set the system properties `stdout.encoding` and `stderr.encoding` on the command line to `UTF-8`. If the terminal code page is not UTF-8, then terminal messages may be garbled. But redirection to a file will work properly.

The naming of these system properties is perhaps confusing. The encoding does not apply to `stdout` and `stderr` (which are byte streams) but to the `System.out` and `System.err` objects. Both are instances of `PrintStream`, whose `print` and `println` methods need an encoding that turns characters to bytes.

Tip: To quickly see your current settings for the default charset and the various encodings, run:

```
java -XshowSettings:properties
```

Look for the properties whose names end in `.encoding`.

Finally, the system console, which can be used for reading strings and passwords from the terminal, has a charset that matches the terminal settings. You can obtain it as `System.console().charset()`. The only way to change that charset is to change the terminal code page.

Caution: A `new Scanner(System.in)` uses the default charset, which may be different from the console charset. This is a problem when launching a Java program from a Windows terminal that uses an archaic code page. It is best to change the terminal code page to UTF-8. If that is not an option, construct the scanner as:

```
Console console = System.console();
if (console != null) {
   var in = new Scanner(console.reader()):
   . . .
}
```

You need to guard against the possibility that there is no system console. This happens when running the program in some

development environments.

1.1.9. Reading Character Input

If you read a file with a structured format such as JSON or XML, you will use a parser that someone wrote who understands the fiddly details of that format. Such a parser typically reads a character at a time.

In the uncommon case that you need to write such a parser, use a `BufferedReader` for efficiency. Keep calling its `read` method, which yields a `char` value or -1 at the end of input. The reader converts the encoding of the input stream into UTF-16. You need to handle the UTF-16 encoding:

```
int ch = reader.read();
if (ch != -1)
{
   int codePoint;
   if (Character.isHighSurrogate((char) ch))
   {
      int ch2 = reader.read();
      if (Character.isLowSurrogate((char) ch2))
         codePoint = Character.toCodePoint(ch, ch2);
      else
         throw new MalformedInputException(2);
   }
```

```
   else
      codePoint = ch;
}
```

The `Character` class contains methods to tell whether a particular code point has a given property. For example,

```
Character.isLetter(codePoint)
```

returns `true` if `codePoint` is a letter in some language. Here are some other classification methods:

```
isUpperCase
isLowerCase
isDigit
isSpaceChar
isEmoji
```

These methods use the rules of the Unicode standard. Others refer to the rules of the Java language:

```
isJavaIdentifierStart
isJavaIdentifierPart
isWhitespace
```

After analyzing the code points, you often need to store them in strings, converting them back to UTF-16. The `appendCodePoint` method of the `StringBuilder` class turns a code point into one or two `char` values which are appended to the builder.

1.2. Reading and Writing Binary Data

Text format is convenient for testing and debugging because it is humanly readable, but it is not as efficient as transmitting data in binary format. In the following sections, you will learn how to perform input and output with binary data.

1.2.1. The `DataInput` and `DataOutput` Interfaces

The `DataOutput` interface defines the following methods for writing a number, a character, a `boolean` value, or a string in binary format:

```
writeChars          writeFloat
writeByte           writeDouble
writeInt            writeChar
writeShort          writeBoolean
writeLong           writeUTF
```

For example, `writeInt` always writes an integer as a 4-byte binary quantity regardless of the number of digits, and `writeDouble` always writes a `double` as an 8-byte binary quantity. The resulting output is not human-readable, but it will use the same space for each value of a given type and reading it back in will be faster than parsing text.

Note: There are two different methods of storing integers and floating-point numbers in memory, depending on the processor you are using. Suppose, for example, you are working with a 4-byte `int`, such as the decimal number 1234, or 4D2 in hexadecimal (1234 = 4 × 256 + 13 × 16 + 2). This value can be stored in such a way that the first of the four bytes in memory holds the most significant byte (MSB) of the value: `00 00 04 D2`. This is the so-called big-endian method. Or, we can start with the least significant byte (LSB) first: `D2 04 00 00`. This is called, naturally enough, the little-endian method. For example, the SPARC uses big-endian; Intel processors, little-endian. This can lead to problems. When a file is saved from a C or C++ file, the data are saved exactly as the processor stores them. That makes it challenging to move even the simplest data files from one platform to

> another. In Java, all values are written in the big-endian fashion, regardless of the processor. That makes Java data files platform-independent.

The `writeUTF` method writes string data using a modified version of the 8-bit Unicode Transformation Format. Instead of simply using the standard UTF-8 encoding, sequences of Unicode code units are first represented in UTF-16, and then the result is encoded using the UTF-8 rules. This modified encoding is different for characters with codes higher than `0xFFFF`. It is used for backward compatibility with virtual machines that were built when Unicode had not yet grown beyond 16 bits.

Since nobody else uses this modification of UTF-8, you should only use the `writeUTF` method to write strings intended for a Java virtual machine—for example, in a program that generates bytecodes. Use the `writeChars` method for other purposes.

To read the data back in, use the following methods defined in the `DataInput` interface:

```
readInt             readDouble
readShort           readChar
readLong            readBoolean
```

```
  readFloat          readUTF
```

The `DataInputStream` class implements the `DataInput` interface. To read binary data from a file, combine a `DataInputStream` with a source of bytes such as a `FileInputStream`:

```
  var in = new DataInputStream(new FileInputStream("emp
```

Similarly, to write binary data, use the `DataOutputStream` class that implements the `DataOutput` interface:

```
  var out = new DataOutputStream(new FileOutputStream("
```

java.io.DataInput **1.0**

- `boolean readBoolean()`
- `byte readByte()`
- `char readChar()`
- `double readDouble()`
- `float readFloat()`
- `int readInt()`
- `long readLong()`
- `short readShort()`

  read in a value of the given type.
- `void readFully(byte[] b)`

  reads bytes into the array `b`, blocking until all bytes are read.
- `void readFully(byte[] b, int off, int len)`

  places up to `len` bytes into the array `b`, starting at `off`, blocking until all bytes are read.
- `String readUTF()`

  reads a string of characters in the "modified UTF-8" format.
- `int skipBytes(int n)`

  skips `n` bytes, blocking until all bytes are skipped.

java.io.DataOutput **1.0**

- `void writeBoolean(boolean b)`
- `void writeByte(int b)`
- `void writeChar(int c)`
- `void writeDouble(double d)`
- `void writeFloat(float f)`
- `void writeInt(int i)`
- `void writeLong(long l)`
- `void writeShort(int s)`
  write a value of the given type.
- `void writeChars(String s)`
  writes all characters in the string.
- `void writeUTF(String s)`
  writes a string of characters in the "modified UTF-8" format.

1.2.2. Random-Access Files

The `RandomAccessFile` class lets you read or write data anywhere in a file. Disk files are random-access, but input/output streams that communicate with a network socket are not. You can open a random-access file either for reading only or for both reading and writing; specify the option by using the string `"r"` (for read access) or `"rw"` (for read/write access) as the second argument in the constructor.

```
var in = new RandomAccessFile("employee.dat", "r");
var inOut = new RandomAccessFile("employee.dat", "rw"
```

When you open an existing file as a `RandomAccessFile`, it does not get deleted.

A random-access file has a *file pointer* that indicates the position of the next byte to be read or written. The `seek` method can be used to set the file pointer to an arbitrary byte position within the file. The argument to `seek` is a `long` integer between zero and the length of the file in bytes.

The `getFilePointer` method returns the current position of the file pointer.

The `RandomAccessFile` class implements both the `DataInput` and `DataOutput` interfaces. To read and write from a random-access file, use methods such as `readInt` / `writeInt` and `readChar/writeChar` that we discussed in the preceding section.

Let's walk through an example program that stores employee records in a random-access file. Each record will have the same size. This makes it easy to read an arbitrary record. Suppose you want to position the file pointer to the third record. Simply set the file pointer to the appropriate byte position and start reading.

```
long n = 3;
in.seek((n - 1) * RECORD_SIZE);
var e = new Employee();
e.readData(in);
```

If you want to modify the record and save it back into the same location, remember to set the file pointer back to the beginning of the record:

```
in.seek((n - 1) * RECORD_SIZE);
e.writeData(out);
```

To determine the total number of bytes in a file, use the `length` method. The total number of records is the length divided by the size of each record.

```
long nbytes = in.length(); // length in bytes
int nrecords = (int) (nbytes / RECORD_SIZE);
```

Integers and floating-point values have a fixed size in binary format, but we have to work harder for strings. We provide two helper methods to write and read strings of a fixed size.

The `writeFixedString` writes the specified number of code units, starting at the beginning of the string. If there are too few code

units, the method pads the string, using zero values.

```
public static void writeFixedString(String s, int siz
      throws IOException
{
   for (int i = 0; i < size; i++)
   {
      char ch = 0;
      if (i < s.length()) ch = s.charAt(i);
      out.writeChar(ch);
   }
}
```

The `readFixedString` method reads characters from the input stream until it has consumed `size` code units or until it encounters a character with a zero value. Then, it skips past the remaining zero values in the input field. For added efficiency, this method uses the `StringBuilder` class to read in a string.

```
public static String readFixedString(int size, DataIn
      throws IOException
{
   var b = new StringBuilder(size);
   int i = 0;
   var done = false;
   while (!done && i < size)
```

```
    {
       char ch = in.readChar();
       i++;
       if (ch == 0) done = true;
       else b.append(ch);
    }
    in.skipBytes(2 * (size - i));
    return b.toString();
 }
```

We placed the `writeFixedString` and `readFixedString` methods inside the `DataIO` helper class.

To write a fixed-size record, we simply write all fields in binary.

```
DataIO.writeFixedString(e.getName(), Employee.NAME_SI
out.writeDouble(e.getSalary());
LocalDate hireDay = e.getHireDay();
out.writeInt(hireDay.getYear());
out.writeInt(hireDay.getMonthValue());
out.writeInt(hireDay.getDayOfMonth());
```

Reading the data back is just as simple.

```
String name = DataIO.readFixedString(Employee.NAME_SI
double salary = in.readDouble();
int y = in.readInt();
int m = in.readInt();
int d = in.readInt();
```

Let us compute the size of each record. We will use 40 characters for the name strings. Therefore, each record will contain 100 bytes:

- 40 characters = 80 bytes for the name
- 1 `double` = 8 bytes for the salary
- 3 `int` = 12 bytes for the date

The program shown in Listing 2.2 writes three records into a data file and then reads them from the file in reverse order. To do this efficiently requires random access—we need to get to the last record first.

Listing 1.2 randomAccess/RandomAccessTest.java

```
1 package randomAccess;
2
3 import java.io.*;
4 import java.time.*;
5
```

```
6  /**
7   * @version 1.14 2023-10-05
8   * @author Cay Horstmann
9   */
10 public class RandomAccessTest
11 {
12    public static final int NAME_SIZE = 40;
13    public static final int RECORD_SIZE = 2 * NA
14
15    public static void main(String[] args) throw
16    {
17       var staff = new Employee[3];
18
19       staff[0] = new Employee("Carl Cracker", 7
20       staff[1] = new Employee("Harry Hacker", 5
21       staff[2] = new Employee("Tony Tester", 40
22
23       try (var out = new DataOutputStream(new F
24       {
25          // save all employee records to the fi
26          for (Employee e : staff)
27             writeData(out, e);
28       }
29
30       try (var in = new RandomAccessFile("emplo
31       {
32          // retrieve all records into a new arr
33
```

```
34          // compute the array size
35          int n = (int) (in.length() / RECORD_SI
36          var newStaff = new Employee[n];
37
38          // read employees in reverse order
39          for (int i = 0; i < n; i++)
40          {
41             in.seek((n - 1 - i) * RECORD_SIZE);
42             newStaff[i] = readData(in);
43          }
44
45          // print the newly read employee recor
46          for (Employee e : newStaff)
47             System.out.println(e);
48       }
49    }
50
51    /**
52     * Writes employee data to a data output.
53     * @param out the data output
54     * @param e   the employee
55     */
56    public static void writeData(DataOutput out,
57    {
58       DataIO.writeFixedString(e.getName(), NAME
59       out.writeDouble(e.getSalary());
60
61       LocalDate hireDay = e.getHireDay();
```

```
62          out.writeInt(hireDay.getYear());
63          out.writeInt(hireDay.getMonthValue());
64          out.writeInt(hireDay.getDayOfMonth());
65       }
66
67       /**
68        * Reads employee data from a data input.
69        * @param in the data input
70        * @return the employee
71        */
72       public static Employee readData(DataInput in
73       {
74          String name = DataIO.readFixedString(NAME
75          double salary = in.readDouble();
76          int y = in.readInt();
77          int m = in.readInt();
78          int d = in.readInt();
79          return new Employee(name, salary, y, m, d
80       }
81    }
```

`java.io.RandomAccessFile` **1.0**

- `RandomAccessFile(String file, String mode)`
- `RandomAccessFile(File file, String mode)`

  open the given file for random access. The `mode` string is `"r"` for read-only mode, `"rw"` for read/write mode, `"rws"` for

read/write mode with synchronous disk writes of data and metadata for every update, and `"rwd"` for read/write mode with synchronous disk writes of data only.

- `long getFilePointer()`
  returns the current location of the file pointer.
- `void seek(long pos)`
  sets the file pointer to `pos` bytes from the beginning of the file.
- `long length()`
  returns the length of the file in bytes.

1.2.3. ZIP Archives

ZIP archives store one or more files in a (usually) compressed format. Each ZIP archive has a header with information such as the name of each file and the compression method that was used. In Java, you can use a `ZipInputStream` to read a ZIP archive. You need to look at the individual *entries* in the archive. The `getNextEntry` method returns an object of type `ZipEntry` that describes the entry. Read from the stream until the end, which is actually the end of the current entry. Then call `closeEntry` to read the next entry. Do not close the `ZipInputStream` until you read the last entry. Here is a typical code sequence to read through a ZIP file:

```
var zin = new ZipInputStream(new FileInputStream(zipn
boolean done = false;
while (!done)
{
   ZipEntry entry = zin.getNextEntry();
   if (entry == null) done = true;
   else
   {
      read the contents of zin
      zin.closeEntry();
   }
}
zin.close();
```

To write a ZIP file, use a `ZipOutputStream`. For each entry that you want to place into the ZIP file, create a `ZipEntry` object. Pass the file name to the `ZipEntry` constructor; it sets the other parameters such as file date and decompression method. You can override these settings if you like. Then, call the `putNextEntry` method of the `ZipOutputStream` to begin writing a new file. Send the file data to the ZIP output stream. When done, call `closeEntry`. Repeat for all the files you want to store. Here is a code skeleton:

```
var fout = new FileOutputStream("test.zip");
var zout = new ZipOutputStream(fout);
for all files
{
   var ze = new ZipEntry(filename);
   zout.putNextEntry(ze);
   send data to zout
   zout.closeEntry();
}
zout.close();
```

Note: JAR files (which were discussed in Chapter 4 of Volume I) are simply ZIP files with a special entry—the so-called manifest. Use the `JarInputStream` and `JarOutputStream` classes to read and write the manifest entry.

ZIP input streams are a good example of the power of the stream abstraction. When you read data stored in compressed form, you don't need to worry that the data are being decompressed as they are being requested. Moreover, the source of the bytes in a ZIP stream need not be a file—the ZIP data can come from a network connection.

Note: Section 2.4.8 shows how to access a ZIP archive without a special API, using the `FileSystem` class.

`java.util.zip.ZipInputStream` **1.1**

- `ZipInputStream(InputStream in)`
  creates a `ZipInputStream` that allows you to inflate data from the given `InputStream`.
- `ZipEntry getNextEntry()`
  returns a `ZipEntry` object for the next entry, or `null` if there are no more entries.
- `void closeEntry()`
  closes the current open entry in the ZIP file. You can then read the next entry by using `getNextEntry()`.

`java.util.zip.ZipOutputStream` **1.1**

- `ZipOutputStream(OutputStream out)`
  creates a `ZipOutputStream` that you can use to write compressed data to the specified `OutputStream`.
- `void putNextEntry(ZipEntry ze)`
  writes the information in the given `ZipEntry` to the output stream and positions the stream for the data. The data can then be written by calling the `write()` method.

- `void closeEntry()`
  closes the currently open entry in the ZIP file. Use the `putNextEntry` method to start the next entry.
- `void setLevel(int level)`
  sets the default compression level of subsequent `DEFLATED` entries to a value from `Deflater.NO_COMPRESSION` to `Deflater.BEST_COMPRESSION`. The default value is `Deflater.DEFAULT_COMPRESSION`. Throws an `IllegalArgumentException` if the level is not valid.
- `void setMethod(int method)`
  sets the default compression method for this `ZipOutputStream` for any entries that do not specify a method; can be either `DEFLATED` or `STORED`.

`java.util.zip.ZipEntry` **1.1**

- `ZipEntry(String name)`
  constructs a ZIP entry with a given name.
- `long getCrc()`
  returns the CRC32 checksum value for this `ZipEntry`.
- `String getName()`
  returns the name of this entry.
- `long getSize()`
  returns the uncompressed size of this entry, or `-1` if the uncompressed size is not known.

- `boolean isDirectory()`
  returns `true` if this entry is a directory.
- `void setMethod(int method)`
  sets the compression method for the entry to `DEFLATED` or `STORED`.
- `void setSize(long size)`
  sets the size of this entry. Only required if the compression method is `STORED`.
- `void setCrc(long crc)`
  sets the CRC32 checksum of this entry. Use the `CRC32` class to compute this checksum. Only required if the compression method is `STORED`.

`java.util.zip.ZipFile` **1.1**

- `ZipFile(String name)`
- `ZipFile(File file)`
- `ZipFile(String name, Charset charset)` **1.7**
- `ZipFile(File file, Charset charset)` **1.7**
  create a `ZipFile` for reading from the file with the given name or `File` object. If a `Charset` is provided, it indicates the encoding of the entry names. Otherwise they are assumed to be encoded as UTF-8.

- `Enumeration entries()`
  returns an `Enumeration` object that enumerates the `ZipEntry` objects that describe the entries of the `ZipFile`.
- `ZipEntry getEntry(String name)`
  returns the entry corresponding to the given name, or `null` if there is no such entry.
- `InputStream getInputStream(ZipEntry ze)`
  returns an `InputStream` for the given entry.
- `String getName()`
  returns the path of this ZIP file.

1.3. Object Input/Output Streams and Serialization

Using a fixed-length record format is a good choice if you need to store data of the same type. However, objects that you create in an object-oriented program are rarely all of the same type. For example, you might have an array called `staff` that is nominally an array of `Employee` records but contains objects that are actually instances of a subclass such as `Manager`.

It is certainly possible to come up with a data format that allows you to store such polymorphic collections—but, fortunately, we don't have to. The Java language supports a very general mechanism, called *object serialization*, that makes it possible to write any object

to an output stream and read it again later. (You will see in the following sections where the term “serialization” comes from.)

1.3.1. Saving and Loading Serializable Objects

To save object data, you first need to open an `ObjectOutputStream` object:

```
var out = new ObjectOutputStream(new FileOutputStream
```

Now, to save an object, simply use the `writeObject` method of the `ObjectOutputStream` class as in the following fragment:

```
var harry = new Employee("Harry Hacker", 50000, 1989,
var boss = new Manager("Carl Cracker", 80000, 1987, 1
out.writeObject(harry);
out.writeObject(boss);
```

To read the objects back in, first get an `ObjectInputStream` object:

```
var in = new ObjectInputStream(new FileInputStream("e
```

Then, retrieve the objects in the same order in which they were written, using the `readObject` method:

```
var e1 = (Employee) in.readObject();
var e2 = (Employee) in.readObject();
```

There is, however, one change you need to make to any class that you want to save to an output stream and restore from an object input stream. The class must implement the `Serializable` interface:

```
class Employee implements Serializable { . . . }
```

The `Serializable` interface has no methods, so you don't need to change your classes in any way. In this regard, it is similar to the `Cloneable` interface that we discussed in Chapter 6 of Volume I. However, to make a class cloneable, you still had to override the `clone` method of the `Object` class. To make a class serializable, you do not need to do anything else.

Note: You can write and read only *objects* with the `writeObject/readObject` methods. For primitive type values, use methods such as `writeInt/readInt` or `writeDouble/readDouble`. (The object

input/output stream classes implement the `DataInput/DataOutput` interfaces.)

Behind the scenes, an `ObjectOutputStream` looks at all the fields of the objects and saves their contents. For example, when writing an `Employee` object, the name, date, and salary fields are written to the output stream.

However, there is one important situation to consider: What happens when one object is shared by several objects as part of their state?

To illustrate the problem, let us make a slight modification to the `Manager` class. Let's assume that each manager has a secretary:

```
class Manager extends Employee
{
   private Employee secretary;
   . . .
}
```

Each `Manager` object now contains a reference to an `Employee` object that describes the secretary. Of course, two managers can share the same secretary, as is the case in #ch01fig06 and the following code:

```
var harry = new Employee("Harry Hacker", . . .);
var carl = new Manager("Carl Cracker", . . .);
carl.setSecretary(harry);
var tony = new Manager("Tony Tester", . . .);
tony.setSecretary(harry);
```



Figure 1.5: Two managers can share a mutual employee.

Saving such a network of objects is a challenge. Of course, we cannot save and restore the memory addresses for the secretary objects. When an object is reloaded, it will likely occupy a completely different memory address than it originally did.

Instead, each object is saved with a *serial number*—hence the name *object serialization* for this mechanism. Here is the algorithm:

1. Associate a serial number with each object reference that you encounter (as shown in #ch01fig07).



Figure 1.6: An example of object serialization

2. When encountering an object reference for the first time, save the object data to the output stream.
3. If it has been saved previously, just write "same as the previously saved object with serial number x."

When reading the objects back, the procedure is reversed.

1. When an object is specified in an object input stream for the first time, construct it, initialize it with the stream data, and remember the association between the serial number and the object reference.
2. When the tag "same as the previously saved object with serial number x" is encountered, retrieve the object reference for the sequence number.

Note: In this chapter, we will use serialization to save a collection of objects to a disk file and retrieve it exactly as we stored it. Another very important application is the transmittal of a collection of objects across a network connection to another computer. Just as raw memory addresses are meaningless in a file, they are also meaningless when you communicate with a different processor. By replacing memory addresses with serial numbers, serialization permits the transport of object collections from one machine to another.

Note: If the superclass of a serializable class is not serializable, it must have an accessible no-argument constructor. Consider this example:

```
class Person // Not serializable
class Employee extends Person implements S
```

When an `Employee` object is deserialized, its instance fields are read from the object input stream, but the `Person` instance fields are set by the `Person` constructor.

Listing 2.3 is a program that saves and reloads a network of `Employee` and `Manager` objects (some of which share the same employee as a secretary). Note that the secretary object is unique after reloading—when `newStaff[1]` gets a raise, that is reflected in the `secretary` fields of the managers.

Listing 1.3 serial/ObjectStreamTest.java

```
1  package serial;
2
3  import java.io.*;
4
5  /**
6   * @version 1.12 2021-09-10
7   * @author Cay Horstmann
8   */
9  class ObjectStreamTest
```

```
10 {
11    public static void main(String[] args) throw
12    {
13       var harry = new Employee("Harry Hacker",
14       var carl = new Manager("Carl Cracker", 80
15       carl.setSecretary(harry);
16       var tony = new Manager("Tony Tester", 400
17       tony.setSecretary(harry);
18
19       var staff = new Employee[3];
20
21       staff[0] = carl;
22       staff[1] = harry;
23       staff[2] = tony;
24
25       // save all employee records to the file
26       try (var out = new ObjectOutputStream(new
27       {
28          out.writeObject(staff);
29       }
30
31       try (var in = new ObjectInputStream(new F
32       {
33          // retrieve all records into a new arr
34
35          var newStaff = (Employee[]) in.readObj
36
37          // raise secretary's salary
```

```
38          newStaff[1].raiseSalary(10);
39
40          // print the newly read employee recor
41          for (Employee e : newStaff)
42             System.out.println(e);
43       }
44    }
45 }
```

`java.io.ObjectOutputStream` **1.1**

- `ObjectOutputStream(OutputStream out)`
  creates an `ObjectOutputStream` so you can write objects to the specified `OutputStream`.
- `void writeObject(Object obj)`
  writes the specified object to the `ObjectOutputStream`. This method saves the class of the object, the signature of the class, and the values of any nonstatic, nontransient fields of the class and its superclasses.

`java.io.ObjectInputStream` **1.1**

- `ObjectInputStream(InputStream in)`
  creates an `ObjectInputStream` to read back object information from the specified `InputStream`.

- `Object readObject()`
  reads an object from the `ObjectInputStream`. In particular, this method reads back the class of the object, the signature of the class, and the values of the nontransient and nonstatic fields of the class and all its superclasses. It does deserializing so that multiple object references can be recovered.

1.3.2. Understanding the Object Serialization File Format

Object serialization saves object data in a particular file format. Of course, you can use the `writeObject/readObject` methods without having to know the exact sequence of bytes that represents objects in a file. Nonetheless, we found studying the data format extremely helpful for gaining insight into the object serialization process. As the details are somewhat technical, feel free to skip this section if you are not interested in the implementation.

Every file begins with the two-byte "magic number"

```
AC ED
```

followed by the version number of the object serialization format, which is currently

```
00 05
```

(We use hexadecimal numbers throughout this section to denote bytes.) Then, it contains a sequence of objects, in the order in which they were saved.

String objects are saved as

- `74`
- Two-byte length
- Characters in the "modified UTF-8" format

For example, the string "Harry" is saved as

```
74 00 05 Harry
```

When an object is saved, the class of that object must be saved as well. The class descriptor has the following format:

- `72`
- 2-byte length of class name
- Class name
- 8-byte fingerprint
- 1-byte flag
- 2-byte count of instance field descriptors

- Instance field descriptors
- `78` (end marker)
- Superclass descriptor (`70` if none)

The fingerprint is obtained by ordering the descriptions of the class, superclass, interfaces, field types, and method signatures in a canonical way, and then applying the Secure Hash Algorithm version 1 (SHA-1) to that data.

SHA-1 gives a "fingerprint" of a block of information. This fingerprint is always a 20-byte data packet, regardless of the size of the original data. It is created by a clever sequence of bit operations on the data that makes it extremely likely that the fingerprint will change if the information is altered in any way. The serialization mechanism uses only the first eight bytes of the SHA-1 code as a class fingerprint. It is still very likely that the class fingerprint will change if the instance fields or methods change.

When reading an object, its fingerprint is compared against the current fingerprint of the class. If they don't match, it means the class definition has changed after the object was written, and an exception is generated. Of course, in practice, classes do evolve, and it might be necessary for a program to read in older versions of objects. We will discuss this in Section 2.3.7.

The flag byte is composed of the bit masks, defined in `java.io.ObjectStreamConstants`, shown in Table 2.3.

Table 1.3: Bit Masks

Name	Value	Description
`SC_WRITE_METHOD`	1	Class defines `writeObject` method.
`SC_SERIALIZABLE`	2	Class implements `Serializable`.
`SC_EXTERNALIZABLE`	4	Class implements `Externalizable`.
`SC_BLOCK_DATA`	8	Opaque data written as "block data" (default since JDK 1.2).
`SC_ENUM`	16	Class is an enumeration.

The classes that we write implement the `Serializable` interface and will have a flag value of `02`. The serializable `java.util.Date` class has a flag of `03` because it defines its own `writeObject`

method (see Section 2.3.4). We discuss the `Externalizable` interface in Section 2.3.5.

Each instance field descriptor has the format:

- 1-byte type code
- 2-byte length of field name
- Field name
- Class name (if the field is an object)

The type code is one of the following:

`B`	`byte`
`C`	`char`
`D`	`double`
`F`	`float`
`I`	`int`
`J`	`long`

`L`	object
`S`	`short`
`Z`	`boolean`
`[`	array

When the type code is `L`, the field name is followed by the field type. Class and field name strings do not start with the string code `74`, but field types do. Field types use a slightly different encoding of their names—namely, the format used by native methods.

For example, the `salary` field of the `Employee` class is encoded as

```
D 00 06 salary
```

Here is the complete class descriptor of the `Employee` class, contained in the `serial` package in our example program:

```
72 00 0F serial.Employee
```

`74 1E C8 E6 C3 F8 B8 77 02`	Fingerprint and flag
`00 03`	Number of instance fields
`D 00 06 salary`	Instance field type and name
`L 00 07 hireDay`	Instance field type and name
`74 00 10 Ljava/util/Date;`	Instance field class name: `java.util.Date`
`L 00 04 name`	Instance field type and name

`74 00 12 Ljava/lang/String;`	Instance field class name: `java.lang.Strin`
`78`	End marker
`70`	No superclass

These descriptors are fairly long. If the *same* class descriptor is needed again in the file, an abbreviated form is used:

- `71`
- 4-byte serial number

The serial number refers to the previous explicit class descriptor. We discuss the numbering scheme later.

An object is stored as

- `73`
- Class descriptor
- Object data

For example, here is how the instance fields of an `Employee` object are stored:

`40 E8 6A 00 00 00 00 00`	`salary` field value: `double`
`73`	`hireDay` field value: new ob
`71 00 7E 00 08`	Existing class `java.util.D`
`77 08 00 00 00 91 19 97 3D 80 78`	External storag (details later)

```
74 00 0C Harry Hacker
```

`name` field va `String`

As you can see, the data file contains enough information to restore the `Employee` object. (In this example, we store the hireday as a `Date` instead of a `LocalDate`, since the `LocalDate` class has a more complex serialization.)

Caution: As you just saw, the object stream contains the names of the classes, superclasses, and fields of all serialized objects. For inner classes, some of these names are synthesized by the compiler, and the naming convention may change from one Java implementation to another. If that occurs, deserialization fails. Therefore, there is a small risk with serializing inner classes if you intend to have them deserialized with a different implementation.

Static inner classes, including inner enumerations and records, are safe to serialize.

Arrays are saved in the following format:

- `75`
- Class descriptor

- 4-byte number of elements
- Elements

The array class name in the class descriptor is in the same format as that used by native methods (which is slightly different from the format used by class names in other class descriptors). In this format, class names start with an `L` and end with a semicolon.

For example, an array of three `Employee` objects starts out like this:

`75`	Array
`72 00 0B [LEmployee;`	New class, string length, class name `Employee[]`
`40 05 D6 7E 3B BB F2 50 02`	Fingerprint and flags

`00 00`	Number of instance fields
`78`	End marker
`70`	No superclass
`00 00 00 03`	Number of array entries

Note that the fingerprint for an array of `Employee` objects is different from a fingerprint of the `Employee` class itself.

All objects (including arrays and strings) and all class descriptors are given serial numbers as they are saved in the output file. The numbers start at `00 7E 00 00`.

We already saw that a full class descriptor for any given class occurs only once. Subsequent descriptors refer to it. For example, in our previous example, a repeated reference to the `Date` class was coded as

```
71 00 7E 00 08
```

The same mechanism is used for objects. If a reference to a previously saved object is written, it is saved in exactly the same way—that is, `71` followed by the serial number. It is always clear from the context whether a particular serial reference denotes a class descriptor or an object.

Some classes (such as the `Date` class) store object state in an opaque binary block, encoded as

- `77` (short block) or `7A` (long block)
- 1-byte or 4-byte block length
- Block contents
- `78`

Finally, a null reference is stored as

```
70
```

Here is the commented output of the `ObjectStreamTest` program of the preceding section. Run the program, look at a hex dump of its data file `employee.ser`, and compare it with the commented listing. The most important lines are toward the end of the output. They show a reference to a previously saved object.

`AC ED 00 05`	File heade
`75`	Array `sta` (serial #1)
`72 00 12 [Lserial.Employee;`	New class, string leng class name `Employee` (serial #0)
`40 05 D6 7E 3B BB F2 50 02`	Fingerprint and flags

`00 00`	Number of instance fields
`78`	End marke
`70`	No superclass
`00 00 00 03`	Number of array entri
`73`	`staff[0]` new objec (serial #7)
`72 00 0E serial.Manager`	New class, string leng

	class name (serial #2)
`2F FF 1F 1D E8 7A A9 74 02`	Fingerprint and flags
`00 01`	Number of instance fields
`L 00 09 secretary`	Instance fi type and name
`74 00 11 Lserial/Employee;`	Instance fi class name `String` (serial #3)
`78`	End marke

`72 00 0F serial.Employee`	Superclass new class, string leng class name (serial #4)
`74 1E C8 E6 C3 F8 B8 77 02`	Fingerprint and flags
`00 03`	Number of instance fields
`D 00 06 salary`	Instance fi type and name
`L 00 07 hireDay`	Instance fi type and name

`74 00 10 Ljava/util/Date;`	Instance fi class name `String` (serial #5)
`L 00 04 name`	Instance fi type and name
`74 00 12 Ljava/lang/String;`	Instance fi class name `String` (serial #6)
`78`	End marke
`70`	No superclass

`40 F3 88 00 00 00 00 00`	`salary` fi value: `double`
`73`	`hireDay` field value new objec (serial #9)
`72 00 0E java.util.Date`	New class, string leng class name (serial #8)
`68 6A 81 01 4B 59 74 19 03`	Fingerprint and flags
`00 00`	No instanc fields

`78`	End marke
`70`	No superclass
`77 08`	External storage, number of bytes
`00 00 00 83 E7 4B 7D 80`	Opaque bytes
`78`	End marke
`74 00 0C Carl Cracker`	`name` field value:

	`String` (serial #10
`73`	`secretar` field value new object (serial #11
`71 00 7E 00 04`	existing cla (use serial #4)
`40 E8 6A 00 00 00 00 00`	`salary` fi value: `double`
`73`	`hireDay` field value new object (serial #12
`71 00 7E 00 08`	Existing cla (use serial #8)

`77 08`	External storage, number of bytes
`00 00 00 91 19 97 3D 80`	Opaque bytes
`78`	End marke
`74 00 0C Harry Hacker`	`name` field value: `String` (serial #13
`71 00 7E 00 0B`	`staff[1]` existing object (use serial #11)

`73`	`staff[2]` new objec (serial #1
`71 00 7E 00 02`	Existing cl (use serial #2)
`40 E3 88 00 00 00 00 00`	`salary` fi value: `double`
`73`	`hireDay` field value new objec (serial #15
`71 00 7E 00 08`	Existing cl (use serial #8)
`77 08`	External storage,

	number of bytes
`00 00 00 94 6B 50 89 80`	Opaque bytes
`78`	End marke
`74 00 0B Tony Tester`	`name` field value: `String` (serial #16
`71 00 7E 00 0B`	`secretar` field value existing object (use serial #11)

Of course, studying these codes can be about as exciting as reading a phone book. It is not important to know the exact file format (unless you are trying to create an evil effect by modifying the data), but it is still instructive to know that the serialized format has a detailed description of all the objects it contains, with sufficient detail to allow reconstruction of both objects and arrays of objects.

What you should remember is this:

- The serialized format contains the types and instance fields of all objects.
- Each object is assigned a serial number.
- Repeated occurrences of the same object are stored as references to that serial number.

1.3.3. Transient Fields

Certain fields should never be serialized—for example, database connections that are meaningless when an object is reconstituted. Also, when an object keeps a cache of values, it might be better to drop the cache and recompute it instead of storing it.

To prevent a field from being serialized, tag it with the `transient` modifier. Always mark fields as `transient` if they hold instances of nonserializable classes. Transient fields are simply skipped when objects are serialized.

1.3.4. The `readObject` and `writeObject` Methods

In rare cases, you need to tweak the serialization mechanism. A serializable class can add any desired action to the default read and write behavior by defining methods with the signature

```
@Serial private void readObject(ObjectInputStream in)
      throws IOException, ClassNotFoundException;
@Serial private void writeObject(ObjectOutputStream o
      throws IOException;
```

Then, the object headers continue to be written as usual, but the instance variables fields are no longer automatically serialized. Instead, these methods are called.

Note the `@Serial` annotation. The methods for tweaking serialization don't belong to interfaces. Therefore, you can't use the `@Override` annotation to have the compiler check the method declarations. The `@Serial` annotation is meant to enable the same checking for serialization methods. Up to Java 21, the `javac` compiler doesn't do such checking, but that might change in the future. The IntelliJ IDE uses the annotation.

Here is a typical example for customization. A number of classes in the `java.awt.geom` package, such as `Point2D.Double`, are not serializable. Now, suppose you want to serialize a class `LabeledPoint` that stores a `String` and a `Point2D.Double`. First, you need to mark the `Point2D.Double` field as `transient` to avoid a `NotSerializableException`.

```
public class LabeledPoint implements Serializable
{
   private String label;
   private transient Point2D.Double point;
   . . .
}
```

In the `writeObject` method, first write the object descriptor and the `String` field, `label`, by calling the `defaultWriteObject` method. This is a special method of the `ObjectOutputStream` class that can only be called from within a `writeObject` method of a serializable class. Then we write the point coordinates, using the standard `DataOutput` calls.

```
private void writeObject(ObjectOutputStream out) thro
{
   out.defaultWriteObject();
```

```
      out.writeDouble(point.getX());
      out.writeDouble(point.getY());
   }
```

In the `readObject` method, we reverse the process:

```
   private void readObject(ObjectInputStream in)
         throws IOException, ClassNotFoundException
   {
      in.defaultReadObject();
      double x = in.readDouble();
      double y = in.readDouble();
      point = new Point2D.Double(x, y);
   }
```

Another example is the `HashSet` class that supplies its own `readObject` and `writeObject` methods. Instead of saving the internal structure of the hash table, the `writeObject` method simply saves the capacity, load factor, size, and elements. The `readObject` method reads back the capacity and load factor, constructs a new table, and inserts the elements.

The `readObject` and `writeObject` methods only need to save and load their data. They do not concern themselves with superclass data or any other class information.

The `Date` class uses this approach. Its `writeObject` method saves the milliseconds since the "epoch" (January 1, 1970). The data structure that caches calendar data is not saved. For that reason, the serialized `Date` instances in Section 2.3.2 consist of an opaque data block.

Caution: Just like a constructor, the `readObject` method operates on partially initialized objects. If you call a non-final method inside `readObject` that is overridden in a subclass, it may access uninitialized data.

Note: If a serializable class defines a field

```
@Serial private static final ObjectStreamF
```

then serialization uses those field descriptors instead of the non-transient non-static fields. There is also an API for setting the field values before serialization, or reading them after deserialization. This is useful for preserving a legacy layout after a class has evolved. For example, the `BigDecimal` class uses this mechanism to serialize its instances in a format that no longer reflects the instance fields.

1.3.5. The `readExternal` and `writeExternal` Methods

Instead of letting the serialization mechanism save and restore object data, a class can define its own mechanism. For example, you can encrypt the data or use a format that is more efficient than the serialization format.

To do this, a class must implement the `Externalizable` interface. This, in turn, requires it to define two methods:

```
public void readExternal(ObjectInput in)
      throws IOException, ClassNotFoundException;
public void writeExternal(ObjectOutput out) throws IO
```

Unlike the `readObject` and `writeObject` methods, these methods are fully responsible for saving and restoring the entire object, *including the superclass data*. When writing an object, the serialization mechanism merely records the class of the object in the output stream. When reading an externalizable object, the object input stream creates an object with the no-argument constructor and then calls the `readExternal` method.

In this example, the `LabeledPixel` class extends the serializable `Point` class, but it takes over the serialization of the class and

superclass. The fields of the object are not stored in the standard serialization format. Instead, the data are placed in an opaque block.

```
public class LabeledPixel extends Point implements Ex
{
   private String label;

   public LabeledPixel() {} // required for externali

   public void writeExternal(ObjectOutput out)
         throws IOException
   {
      out.writeInt((int) getX());
      out.writeInt((int) getY());
      out.writeUTF(label);
   }

   public void readExternal(ObjectInput in)
         throws IOException, ClassNotFoundException
   {
      int x = in.readInt();
      int y = in.readInt();
      setLocation(x, y);
      label = in.readUTF();
   }
   . . .
}
```

Note: The `readExternal` and `writeExternal` methods should not be annotated with `@Serial`. Since they are defined in the `Externalizable` interface, you can simply annotate them with `@Override`.

Caution: Unlike the `readObject` and `writeObject` methods, which are private and can only be called by the serialization mechanism, the `readExternal` and `writeExternal` methods are public. In particular, `readExternal` potentially permits modification of the state of an existing object.

1.3.6. The `readResolve` and `writeReplace` Methods

We take it for granted that objects can only be constructed with the constructor. However, a deserialized object is *not constructed*. Its instance variables are simply restored from an object stream.

This is a problem if the constructor enforces some condition. For example, a singleton object may be implemented so that the constructor can only be called once. As another example, database entities can be constructed so that they always come from a pool of managed instances.

You shouldn't implement your own mechanism for singletons. If you need a singleton, make an enumerated type with one instance which is, by convention, called `INSTANCE`.

```
public enum PersonDatabase {
   INSTANCE;

   public Person findById(int id) { . . . }
   . . .
}
```

This works because `enum` instances are guaranteed to be deserialized properly.

Now let's suppose that you are in the rare situation where you want to control the identity of each deserialized instance. As an example, suppose a `Person` class wants to restore its instances from a database when deserializing. Then you should not serialize the object itself. Instead, request that a proxy instance is saved. When restored, that proxy locates and constructs the desired object. Your class needs to provide a `writeReplace` method that returns the proxy object:

```
public class Person implements Serializable {
   private int id;
   // Other instance variables
   . . .
   @Serial private Object writeReplace() {
      return new PersonProxy(id);
   }
}
```

When a `Person` object is serialized, none of its instance variables are saved. Instead, the `writeReplace` method is called and *its return value* is serialized and written to the stream.

The proxy class needs to implement a `readResolve` method that yields a `Person` instance:

```
class PersonProxy implements Serializable {
   private int id;

   public PersonProxy(int id) {
      this.id = id;
   }

   @Serial private Object readResolve() {
```

```
        return PersonDatabase.INSTANCE.findById(id);
    }
}
```

When the `readObject` method finds a `PersonProxy` in an `ObjectInputStream`, it deserializes the proxy, calls its `readResolve` method, and returns the result.

Note: Unlike the `readObject` and `writeObject` methods, the `readResolve` and `writeReplace` methods need not be private.

Note: With enumerations and records, `readObject` / `writeObject` or `readExternal` / `writeExternal` methods are not used for serialization. With records, but not with enumerations, the `writeReplace` method will be used.

1.3.7. Versioning

If you use serialization to save objects, you need to consider what happens when your program evolves. Can version 1.1 read the old files? Can the users who still use 1.0 read the files that the new

version is producing? Clearly, it would be desirable if object files could cope with the evolution of classes.

At first glance, it seems that this would not be possible. When a class definition changes in any way, its SHA fingerprint also changes, and you know that object input streams will refuse to read in objects with different fingerprints. However, a class can indicate that it is *compatible* with an earlier version of itself. To do this, you must first obtain the fingerprint of the *earlier* version of the class. Use the standalone `serialver` program that is part of the JDK to obtain this number. For example, running

```
serialver serial.Employee
```

prints

```
serial.Employee: static final long serialVersionUID =
```

All *later* versions of the class must define the `serialVersionUID` constant to the same fingerprint as the original.

```
class Employee implements Serializable // version 1.1
{
   . . .
```

```
    @Serial public static final long serialVersionUID
}
```

When a class has a static data member named `serialVersionUID`, it will not compute the fingerprint manually but will use that value instead.

Once that static data member has been placed inside a class, the serialization system is now willing to read in different versions of objects of that class.

If only the methods of the class change, there is no problem with reading the new object data. However, if the instance fields change, you may have problems. For example, the old file object may have more or fewer instance fields than the one in the program, or the types of the instance fields may be different. In that case, the object input stream makes an effort to convert the serialized object to the current version of the class.

The object input stream compares the instance fields of the current version of the class with those of the version in the serialized object. Of course, the object input stream considers only the nontransient and nonstatic instance fields. If two fields have matching names but different types, the object input stream makes no effort to convert one type to the other—the objects are incompatible. If the serialized

object has instance fields that are not present in the current version, the object input stream ignores the additional data. If the current version has instance fields that are not present in the serialized object, the added fields are set to their default (`null` for objects, zero for numbers, and `false` for `boolean` values).

Here is an example. Suppose we have saved a number of employee records on disk, using the original version (1.0) of the class. Now we change the `Employee` class to version 2.0 by adding a instance field called `department`. #ch01fig09 shows what happens when a 1.0 object is read into a program that uses 2.0 objects. The `department` field is set to `null`. #ch01fig10 shows the opposite scenario: A program using 1.0 objects reads a 2.0 object. The additional `department` field is ignored.



Figure 1.7: Reading an object with fewer instance fields



Figure 1.8: Reading an object with more instance fields

Is this process safe? It depends. Dropping a instance field seems harmless—the recipient still has all the data that it knows how to manipulate. Setting a instance field to `null` might not be so safe. Many classes work hard to initialize all instance fields in all constructors to non-`null` values, so that the methods don't have to be prepared to handle `null` data. It is up to the class designer to implement additional code in the `readObject` method to fix version incompatibilities or to make sure the methods are robust enough to handle `null` data.

Tip: Before you add a `serialVersionUID` field to a class, ask yourself why you made your class serializable. If serialization is used only for short-term persistence, such as distributed method calls in an application server, there is no need to worry about versioning and the `serialVersionUID`. The same applies if you extend a class that happens to be serializable, but you have no intent to ever

persist its instances. If your IDE gives you pesky warnings, change the IDE preferences to turn them off, or add an annotation `@SuppressWarnings("serial")`. This is safer than adding a `serialVersionUID` that you may later forget to change.

Note: Enumerations and records ignore the `serialVersionUID` field. An enumeration always has a `serialVersionUID` of `0L`. You can declare the `serialVersionUID` of a record, but the IDs don't have to match for deserialization.

Note: In this section, you saw what happens when the reader's version of a class has instance fields that aren't present in the object stream. It is also possible during class evolution for a superclass to be added. Then a reader using the new version may read an object stream in which the instance fields of the superclass are not set. By default, those instance fields are set to their zero/`null` default. That may leave the superclass in an unsafe state. The superclass can defend against that problem by defining an initialization method

```
  @Serial private void readObjectNoData() th
```

The method should either set the same state as the no-argument constructor or throw an `InvalidObjectException`. It is only called in the unusual circumstance that an object stream is read which contains an instance of a subclass with missing superclass data.

1.3.8. Using Serialization for Cloning

There is an amusing use for the serialization mechanism: It gives you an easy way to clone an object, provided the class is serializable. Simply serialize it to an output stream and then read it back in. The result is a new object that is a deep copy of the existing object. You don't have to write the object to a file—you can use a `ByteArrayOutputStream` to save the data into a byte array.

As Listing 2.4 shows, to get `clone` for free, simply extend the `SerialCloneable` class, and you are done.

You should be aware that this method, although clever, will usually be much slower than a clone method that explicitly constructs a new object and copies or clones the instance fields.

Listing 1.4 serialClone/SerialCloneTest.java

```
1  package serialClone;
2
3  /**
4   * @version 1.23 2024-01-12
5   * @author Cay Horstmann
6   */
7
8  import java.io.*;
9  import java.time.*;
10
11 public class SerialCloneTest
12 {
13    public static void main(String[] args) throw
14    {
15       var harry = new Employee("Harry Hacker",
16       // clone harry
17       var harry2 = (Employee) harry.clone();
18
19       // mutate harry
20       harry.raiseSalary(10);
21
22       // now harry and the clone are different
23       System.out.println(harry);
24       System.out.println(harry2);
25    }
26 }
```

```
27
28 /**
29  * A class whose clone method uses serializatic
30  */
31 class SerialCloneable implements Cloneable, Ser
32 {
33    public Object clone() throws CloneNotSupport
34    {
35       try
36       {
37          // save the object to a byte array
38          var bout = new ByteArrayOutputStream()
39          try (var out = new ObjectOutputStream(
40          {
41             out.writeObject(this);
42          }
43
44          // read a clone of the object from the
45          var bin = new ByteArrayInputStream(bou
46          try (var in = new ObjectInputStream(bi
47          {
48             return in.readObject();
49          }
50       }
51       catch (IOException | ClassNotFoundExcepti
52       {
53          var e2 = new CloneNotSupportedExceptio
54          e2.initCause(e);
```

```
55            throw e2;
56         }
57      }
58   }
59
60   /**
61    * The familiar Employee class, redefined to ex
62    */
63   class Employee extends SerialCloneable
64   {
65      private String name;
66      private double salary;
67      private LocalDate hireDay;
68
69      public Employee(String n, double s, int year
70      {
71         name = n;
72         salary = s;
73         hireDay = LocalDate.of(year, month, day);
74      }
75
76      public String getName()
77      {
78         return name;
79      }
80
81      public double getSalary()
82      {
```

```
83          return salary;
84       }
85
86       public LocalDate getHireDay()
87       {
88          return hireDay;
89       }
90
91       /**
92        * Raises the salary of this employee.
93        *
94        * @param byPercent the percentage of the ra
95        */
96       public void raiseSalary(double byPercent)
97       {
98          double raise = salary * byPercent / 100;
99          salary += raise;
100      }
101
102      public String toString()
103      {
104         return getClass().getName() + "[name=" +
105      }
106   }
```

1.3.9. Deserialization and Security

During deserialization of a serializable class, objects are created without invoking any constructor of the class. Even if the class has a no-argument constructor, it is not used. The field values are set directly from the values of the object input stream.

Note: For serializable *records*, deserialization calls the canonical constructor, passing it the values of the components from the object input stream. (As a consequence, cyclic references in records are not restored.)

Bypassing constructors is a security risk. An attacker can craft bytes describing an invalid object that could have never been constructed. Suppose, for example, that the `Employee` constructor throws an exception when called with a negative salary. We would like to think that this means that no `Employee` object can have a negative salary. But, as you saw in the preceding section, it is not difficult to inspect the bytes for a serialized object and modify some of them. By doing so, one can craft bytes for an employee with a negative salary and then deserialize them.

A serializable class can optionally implement the `ObjectInputValidation` interface and define a `validateObject` method to check whether its objects are properly deserialized. For

example, the `Employee` class can check that salaries are not negative:

```
public void validateObject() throws InvalidObjectExce
{
   System.out.println("validateObject");
   if (salary < 0)
      throw new InvalidObjectException("salary < 0");
}
```

Unfortunately, the method is not invoked automatically. To invoke it, you must also provide the following method:

```
@Serial private void readObject(ObjectInputStream in)
      throws IOException, ClassNotFoundException
{
   in.registerValidation(this, 0);
   in.defaultReadObject();
}
```

The object is then scheduled for validation, and the `validateObject` method is called when this object and all dependent objects have been loaded. The second parameter lets

you specify a priority. Validation requests with higher priorities are done first.

There are other security risks. Adversaries can create data structures that consume enough resources to crash a virtual machine. More insidiously, any class on the class path can be deserialized. Hackers have been devious about piecing together "gadget chains", sequences of operations in various utility classes that use reflection and culminate in calling methods such as `Runtime.exec` with a string of their choice.

Any application that receives serialized data from untrusted sources over a network connection is vulnerable to such attacks. For example, some servers serialize session data and deserialize whatever data is returned in the HTTP session cookie.

You should avoid situations in which arbitrary data from untrusted sources are deserialized. In the example of session data, the server should sign the data, and only deserialize data with a valid signature.

JEP 290 and 415 provide a *serialization filter* mechanism to harden applications from such attacks. The filters can see the names of deserialized classes and several metrics (stream size, array sizes,

total number of references, longest chain of references). Based on those data, the deserialization can be aborted.

In its simplest form, you provide a pattern describing the valid and invalid classes. For example, if you start our sample serialization demo as

```
java -Djdk.serialFilter='serial.*;java.**;!*' serial.
```

then the objects will be loaded. The filter allows all classes in the `serial` package and all classes whose package name starts with `java`, but no others. If you don't allow `java.**`, or at least `java.util.Date`, deserialization fails.

You can place the filter pattern into a configuration file and specify multiple filters for different purposes. You can also implement your own filters. See https://docs.oracle.com/en/java/javase/21/core/serialization-filtering1.html for details.

1.4. Working with Files

You have learned how to read and write data from a file. However, there is more to file management than reading and writing. The `Path` interface and `Files` class encapsulate the functionality

required to work with the file system on the user's machine. For example, the `Files` class can be used to remove or rename a file, or to find out when a file was last modified. In other words, the input/output stream classes are concerned with the contents of files, whereas the classes that we discuss here are concerned with the storage of files on a disk.

The `Path` interface and `Files` class are much more convenient to use than the `File` class which dates back all the way to JDK 1.0. You should not use the `File` class except to interface with legacy code.

1.4.1. Paths

A `Path` is a sequence of directory names, optionally followed by a file name. The first component of a path may be a *root component* such as `/` or `C:\`. The permissible root components depend on the file system. A path that starts with a root component is *absolute*. Otherwise, it is *relative*. For example, here we construct an absolute and a relative path. For the absolute path, we assume a UNIX-like file system.

```
Path absolute = Path.of("/home", "harry");
Path relative = Path.of("myprog", "conf", "user.prope
```

The static `Path.of` method receives one or more strings, which it joins with the path separator of the default file system (`/` for a UNIX-like file system, `\` for Windows). It then parses the result, throwing an `InvalidPathException` if the result is not a valid path in the given file system. The result is a `Path` object.

The `of` method can get a single string containing multiple components. For example, you can read a path from a configuration file like this:

```
String baseDir = props.getProperty("base.dir");
   // May be a string such as /opt/myprog or c:\Progr
Path basePath = Path.of(baseDir); // OK that baseDir
```

Note: A path does not have to correspond to a file that actually exists. It is merely an abstract sequence of names. As you will see in the next section, when you want to create a file, you first make a path and then call a method to create the corresponding file.

It is very common to combine or *resolve* paths. The call `p.resolve(q)` returns a path according to these rules:

- If `q` is absolute, then the result is `q`.

- if `q` does not have a root, then the result is obtained by joining `p` and `q`.
- Otherwise, the result depends on the rules of the file system.

For example, suppose your application needs to find its working directory relative to a given base directory that is read from a configuration file, as in the preceding example.

```
Path workRelative = Path.of("work");
Path workPath = basePath.resolve(workRelative);
```

There is a shortcut for the `resolve` method that takes a string instead of a path:

```
Path workPath = basePath.resolve("work");
```

Note: The `resolve` method does not simplify the result. For example,

```
Path.of("/usr/bin").resolve("../local")
```

is a path `/usr/bin/../local`.

There is a convenience method `resolveSibling` that resolves against a path's parent, yielding a sibling path. For example, if `workPath` is `/opt/myapp/work`, the call

```
Path tempPath = workPath.resolveSibling("temp");
```

creates `/opt/myapp/temp`.

The opposite of `resolve` is `relativize`. The call `p.relativize(r)` yields the path `q` which, when resolved with `p`, yields `r`. For example, relativizing `/home/harry` against `/home/fred/input.txt` yields `../fred/input.txt`. Here, we assume that `..` denotes the parent directory in the file system.

The `normalize` method removes any redundant `.` and `..` components (or whatever the file system may deem redundant). For example, normalizing the path `/home/harry/../fred/./input.txt` yields `/home/fred/input.txt`.

The `toAbsolutePath` method yields the absolute path of a given path, starting at a root component, such as `/home/fred/input.txt` or `c:\Users\fred\input.txt`.

The `Path` interface has many useful methods for taking paths apart. This code sample shows some of the most useful ones:

```
Path p = Path.of("/home", "fred", "myprog.properties"
Path parent = p.getParent(); // the path /home/fred
Path file = p.getFileName(); // the path myprog.prope
Path root = p.getRoot(); // the path /
```

Caution: The `getFileName` method simply returns the last component of the given path. If the path describes a directory, that's a directory name, not a file name.

As you have already seen in Volume I, you can construct a `Scanner` from a `Path` object:

```
var in = new Scanner(Path.of("/home/fred/input.txt"))
```

Note: Occasionally, you may need to interoperate with legacy APIs that use the `File` class instead of the `Path` interface. The `Path` interface has a `toFile` method, and the `File` class has a `toPath` method.

java.nio.file.Path **7**

- `static Path of(String first, String... more)` **11**
  makes a path by joining the given strings.
- `Path resolve(Path other)`
- `Path resolve(String other)`
  If `other` is absolute, return `other`; otherwise, return the path obtained by joining `this` and `other`.
- `Path resolveSibling(Path other)`
- `Path resolveSibling(String other)`
  If `other` is absolute, return `other`; otherwise, return the path obtained by joining the parent of `this` and `other`.
- `Path relativize(Path other)`
  returns the relative path that, when resolved with `this`, yields `other`.
- `Path normalize()`
  removes redundant path elements such as `.` and `..`
- `Path toAbsolutePath()`
  returns this path if it is absolute; otherwise, this path resolved against the working directory.
- `Path getParent()`
  returns the parent, or `null` if this path has no parent.

- `Path getFileName()`
  returns the last component of this path, or `null` if this path has no components.
- `Path getRoot()`
  returns the root component of this path, or `null` if this path has no root components.
- `toFile()`
  makes a `File` from this path.

`java.io.File` **1.0**

- `Path toPath()` **7**
  makes a `Path` from this file.

1.4.2. Reading and Writing Files

The `Files` class makes quick work of common file operations. For example, you can easily read the entire contents of a file as a byte array, string, list of lines, or stream of lines:

```
byte[] bytes = Files.readAllBytes(path);
String content = Files.readString(path, charset);
List<String> lines = Files.readAllLines(path, charset
Stream<String> lineStream = Files.lines(path, charset
```

Conversely, for writing:

```
Files.write(path, bytes);
Files.writeString(path, content, charset);
Files.write(path, lines, charset);
```

To append to a given file, use

```
Files.write(path, content, charset, StandardOpenOptio
```

The call

```
long pos = Files.mismatch(path1, path2);
```

yields the position of the first byte where the file contents differ.

To get the MIME type of a file (such as `"text/html"` or `"image/png"`), call

```
String mimeType = Files.probeContentType(path);
```

The exact behavior depends on the Java implementation. Each implementation has a collection of `FileTypeDetector` instances that are tried in unspecified order. Each detector may examine the

file extension, OS-specific metadata, or the first few bytes of the contents.

The following methods allow you to interact with an API that uses the classic input/output streams or readers/writers:

```
InputStream in = Files.newInputStream(path);
OutputStream out = Files.newOutputStream(path);
Reader in = Files.newBufferedReader(path, charset);
Writer out = Files.newBufferedWriter(path, charset);
```

These convenience methods save you from dealing with `FileInputStream`, `FileOutputStream`, `BufferedReader`, or `BufferedWriter`.

`java.nio.file.Files` `7`

- `static byte[] readAllBytes(Path path)`
- `static String readString(Path path, Charset charset)`
- `static List<String> readAllLines(Path path, Charset charset)`

  read the contents of a file.

- `static Path write(Path path, byte[] contents, OpenOption... options)`
- `static Path write(Path path, String contents, Charset charset, OpenOption... options)`
- `static Path writeString(Path path, CharSequence contents, Charset cs, OpenOption... options)` 11
- `static Path write(Path path, Iterable<? extends CharSequence> contents, Charset cs, OpenOption options)`
  write the given contents to a file and return `path`.
- `static long mismatch(Path path, Path path2)` 12
  returns the position of the first byte where the file contents differ.
- `static String probeContentType(Path path)` 12
  returns the best guess of the installed file type detectors for the MIME type of the file contents, or `null` if the type could not be determined.
- `static InputStream newInputStream(Path path, OpenOption... options)`
- `static OutputStream newOutputStream(Path path, OpenOption... options)`
- `static BufferedReader newBufferedReader(Path path, Charset charset)`
- `static BufferedWriter newBufferedWriter(Path path,`

`Charset charset, OpenOption... options)`
open a file for reading or writing.

1.4.3. Creating Files and Directories

To create a new directory, call

```
Files.createDirectory(path);
```

All but the last component in the path must already exist. To create intermediate directories as well, use

```
Files.createDirectories(path);
```

You can create an empty file with

```
Files.createFile(path);
```

The call throws an exception if the file already exists. The check for existence and creation are atomic. If the file doesn't exist, it is created before anyone else has a chance to do the same.

There are convenience methods for creating a temporary file or directory in a given or system-specific location.

```
Path newPath = Files.createTempFile(dir, prefix, suff
Path newPath = Files.createTempFile(prefix, suffix);
Path newPath = Files.createTempDirectory(dir, prefix)
Path newPath = Files.createTempDirectory(prefix);
```

Here, `dir` is a `Path`, and `prefix`/`suffix` are strings which may be `null`. For example, the call `Files.createTempFile(null, ".txt")` might return a path such as `/tmp/12344055223648371 94.txt`.

When you create a file or directory, you can specify attributes, such as owners or permissions. However, the details depend on the file system, and we won't cover them here.

`java.nio.file.Files` 7

- `static Path createFile(Path path, FileAttribute<?>... attrs)`
- `static Path createDirectory(Path path, FileAttribute<?>... attrs)`
- `static Path createDirectories(Path path, FileAttribute<?>... attrs)`

  create a file or directory. The `createDirectories` method creates any intermediate directories as well.

- `static Path createTempFile(String prefix, String suffix, FileAttribute<?>... attrs)`
- `static Path createTempFile(Path parentDir, String prefix, String suffix, FileAttribute<?>... attrs)`
- `static Path createTempDirectory(String prefix, FileAttribute<?>... attrs)`
- `static Path createTempDirectory(Path parentDir, String prefix, FileAttribute<?>... attrs)`
  create a temporary file or directory, in a location suitable for temporary files or in the given parent directory. Return the path to the created file or directory.

1.4.4. Copying, Moving, and Deleting Files

To copy a file from one location to another, simply call

```
Files.copy(fromPath, toPath);
```

To move the file instead, call

```
Files.move(fromPath, toPath);
```

The copy or move will fail if the target exists. If you want to overwrite an existing target, use the `REPLACE_EXISTING` option. If

you want to copy all file attributes, use the `COPY_ATTRIBUTES` option. You can supply both like this:

```
Files.copy(fromPath, toPath, StandardCopyOption.REPLA
   StandardCopyOption.COPY_ATTRIBUTES);
```

You can specify that a move should be atomic. Then you are assured that either the move completed successfully, or the source continues to be present. Use the `ATOMIC_MOVE` option:

```
Files.move(fromPath, toPath, StandardCopyOption.ATOMI
```

You can also copy an input stream to a `Path`, which just means saving the input stream to disk. Similarly, you can copy a `Path` to an output stream. Use the following calls:

```
Files.copy(inputStream, toPath);
Files.copy(fromPath, outputStream);
```

As with the other calls to `copy`, you can supply copy options as needed.

Finally, to delete a file, simply call

```
Files.delete(path);
```

This method throws an exception if the file doesn't exist, so instead you may want to use

```
boolean deleted = Files.deleteIfExists(path);
```

The deletion methods can also be used to remove an empty directory.

See Table 2.9 for a summary of the options that are available for file operations.

Table 1.4: Standard Options for File Operations

Option	Description
`StandardOpenOption`; use with `newBufferedWriter`, `newInputStream`, `newOutputStream`, `write`.	
`READ`	Open for reading.
`WRITE`	Open for writing.

Option	Description
`APPEND`	If opened for writing, append to the end of the file.
`TRUNCATE_EXISTING`	If opened for writing, remove existing contents.
`CREATE_NEW`	Create a new file and fail if it exists.
`CREATE`	Atomically create a new file if it doesn't exist.
`DELETE_ON_CLOSE`	Make a “best effort” to delete the file when it is closed.
`SPARSE`	A hint to the file system that this file will be sparse.
`DSYNC` or `SYNC`	Requires that each update to the file data or data and metadata be written synchronously to the storage device.

Option	Description
`StandardCopyOption` ; use with `copy` , `move` .	
`ATOMIC_MOVE`	Move the file atomically.
`COPY_ATTRIBUTES`	Copy the file attributes.
`REPLACE_EXISTING`	Replace the target if it exists.
`LinkOption` ; use with all of the above methods and `exists` , `isDirectory` , `isRegularFile` .	
`NOFOLLOW_LINKS`	Do not follow symbolic links.
`FileVisitOption` ; use with `find` , `walk` , `walkFileTree`	
`FOLLOW_LINKS`	Follow symbolic links.

`java.nio.file.Files` `7`

- `static Path copy(Path from, Path to, CopyOption...`

`options)`

- `static Path move(Path from, Path to, CopyOption... options)`
  copy or move `from` to the given target location and return `to`.
- `static long copy(InputStream from, Path to, CopyOption... options)`
- `static long copy(Path from, OutputStream to, CopyOption... options)`
  copy from an input stream to a file, or from a file to an output stream, returning the number of bytes copied.
- `static void delete(Path path)`
- `static boolean deleteIfExists(Path path)`
  delete the given file or empty directory. The first method throws an exception if the file or directory doesn't exist. The second method returns `false` in that case.

1.4.5. Getting File Information

The following static methods return a `boolean` value to check a property of a path:

- `exists`
- `isHidden`
- `isReadable`, `isWritable`, `isExecutable`
- `isRegularFile`, `isDirectory`, `isSymbolicLink`

The `size` method returns the number of bytes in a file.

```
long fileSize = Files.size(path);
```

The `getOwner` method returns the owner of the file, as an instance of `java.nio.file.attribute.UserPrincipal`.

All file systems report a set of basic attributes, encapsulated by the `BasicFileAttributes` interface, which partially overlaps with that information. The basic file attributes are

- The times at which the file was created, last accessed, and last modified, as instances of the class `java.nio.file.attribute.FileTime`
- Whether the file is a regular file, a directory, a symbolic link, or none of these
- The file size
- The file key—an object of some class, specific to the file system, that may or may not uniquely identify a file

To get these attributes, call

```
BasicFileAttributes attributes = Files.readAttributes
```

If you know that the user's file system is POSIX-compliant, you can instead get an instance of `PosixFileAttributes`:

```
PosixFileAttributes attributes = Files.readAttributes
```

Then you can find out the group owner and the owner, group, and world access permissions of the file. We won't dwell on the details since so much of this information is not portable across operating systems.

`java.nio.file.Files` `7`

- `static boolean exists(Path path)`
- `static boolean isHidden(Path path)`
- `static boolean isReadable(Path path)`
- `static boolean isWritable(Path path)`
- `static boolean isExecutable(Path path)`
- `static boolean isRegularFile(Path path)`
- `static boolean isDirectory(Path path)`
- `static boolean isSymbolicLink(Path path)`
  check for the given property of the file given by the path.
- `static long size(Path path)`
  gets the size of the file in bytes.

- `A readAttributes(Path path, Class<A> type, LinkOption... options)`
  reads the file attributes of type `A`.

java.nio.file.attribute.BasicFileAttributes 7

- `FileTime creationTime()`
- `FileTime lastAccessTime()`
- `FileTime lastModifiedTime()`
- `boolean isRegularFile()`
- `boolean isDirectory()`
- `boolean isSymbolicLink()`
- `long size()`
- `Object fileKey()`
  get the requested attribute.

java.nio.file.attribute.FlleTime 7

- `Instant toInstant()` 8
  yields the `Instant` representing the same time as this `FileTime`.

1.4.6. Visiting Directory Entries

The static `Files.list` method returns a `Stream<Path>` that reads the entries of a directory. The directory is read lazily, making it

possible to efficiently process directories with huge numbers of entries.

Since reading a directory involves a system resource that needs to be closed, you should use a `try` block:

```
try (Stream<Path> entries = Files.list(pathToDirector
{
   . . .
}
```

The `list` method does not enter subdirectories. To process all descendants of a directory, use the `Files.walk` method instead.

```
try (Stream<Path> entries = Files.walk(pathToRoot))
{
   // Contains all descendants, visited in depth-firs
}
```

Here is a sample traversal of the unzipped `src.zip` tree:

```
java
java/nio
java/nio/DirectCharBufferU.java
java/nio/ByteBufferAsShortBufferRL.java
```

```
java/nio/MappedByteBuffer.java
. . .
java/nio/ByteBufferAsDoubleBufferB.java
java/nio/charset
java/nio/charset/CoderMalfunctionError.java
java/nio/charset/CharsetDecoder.java
java/nio/charset/UnsupportedCharsetException.java
java/nio/charset/spi
java/nio/charset/spi/CharsetProvider.java
java/nio/charset/StandardCharsets.java
java/nio/charset/Charset.java
. . .
java/nio/charset/CoderResult.java
java/nio/HeapFloatBufferR.java
. . .
```

As you can see, whenever the traversal yields a directory, it is entered before continuing with its siblings.

You can limit the depth of the tree that you want to visit by calling `Files.walk(pathToRoot, depth)`. Both `walk` methods have a varargs parameter of type `FileVisitOption...`, but there is only one option you can supply: `FOLLOW_LINKS` to follow symbolic links.

Note: If you filter the paths returned by `walk` and your filter criterion involves the file attributes stored

with a directory, such as size, creation time, or type (file, directory, symbolic link), then use the `find` method instead of `walk`. Call that method with a predicate function that accepts a path and a `BasicFileAttributes` object. The only advantage is efficiency. Since the directory is being read anyway, the attributes are readily available.

This code fragment uses the `Files.walk` method to copy one directory to another:

```
Files.walk(source).forEach(p ->
   {
      try
      {
         Path q = target.resolve(source.relativize(p)
         if (Files.isDirectory(p))
            Files.createDirectory(q);
         else
            Files.copy(p, q);
      }
      catch (IOException e)
      {
```

```
            throw new UncheckedIOException(ex);
         }
      });
```

Unfortunately, you cannot easily use the `Files.walk` method to delete a tree of directories since you need to delete the children before deleting the parent. The next section shows you how to overcome that problem.

Caution: The `Files.walk` method throws an exception if any of the subdirectories are not readable. If you only want to visit readable directories, use the `walkFileTree` method described in the next section.

1.4.7. Using Directory Streams

As you saw in the preceding section, the `Files.walk` method produces a `Stream<Path>` that traverses the descendants of a directory. Sometimes, you need more fine-grained control over the traversal process. In that case, use the `Files.newDirectoryStream` object instead. It yields a `DirectoryStream`. Note that this is not a subinterface of `java.util.stream.Stream` but an interface that is specialized for directory traversal. It is a subinterface of `Iterable` so that you can

use directory stream in an enhanced `for` loop. Here is the usage pattern:

```
try (DirectoryStream<Path> entries = Files.newDirecto
{
   for (Path entry : entries)
      Process entries
}
```

The `try` -with-resources block ensures that the directory stream is properly closed.

There is no specific order in which the directory entries are visited.

You can filter the files with a glob pattern:

```
try (DirectoryStream<Path> entries = Files.newDirecto
```

Table 2.10 shows all glob patterns.

Table 1.5: Glob Patterns

Pattern	Description	Example

Pattern	Description	Example
`*`	Matches zero or more characters of a path component.	`*.java` matches all Java files in the current directory.
`**`	Matches zero or more characters, crossing directory boundaries.	`**.java` matches all Java files in any subdirectory.
`?`	Matches one character.	`????.java` matches all four-character (not counting the extension) Java files.
`[. . .]`	Matches a set of characters. You can use hyphens `[0-9]` and negation `[!0-9]`.	`Test[0-9A-F].java` matches `TestX.java`, where x is one hexadecimal digit.
`{. . .}`	Matches alternatives, separated by commas.	`*.{java,class}` matches all Java and class files.

Pattern	Description	Example
`\`	Escapes any of the above as well as `\`.	`*\**` matches all files with a * in their name.

Caution: If you use the glob syntax on Windows, you have to escape backslashes *twice*—once for the glob syntax, and once for the Java string syntax: `Files.newDirectoryStream(dir, "C:\\\\")`.

If you want to visit all descendants of a directory, call the `walkFileTree` method instead and supply an object of type `FileVisitor`. That object gets notified

- When a file is encountered: `FileVisitResult visitFile(T path, BasicFileAttributes attrs)`
- Before a directory is processed: `FileVisitResult preVisitDirectory(T dir, IOException e)`
- After a directory is processed: `FileVisitResult postVisitDirectory(T dir, IOException e)`
- When an error occurred trying to visit a file or directory, such as trying to open a directory without the necessary permissions: `FileVisitResult visitFileFailed(T path, IOException e)`

In each case, you can specify whether you want to

- Continue visiting the next file: `FileVisitResult.CONTINUE`
- Continue the walk, but without visiting the entries in this directory: `FileVisitResult.SKIP_SUBTREE`
- Continue the walk, but without visiting the siblings of this file: `FileVisitResult.SKIP_SIBLINGS`
- Terminate the walk: `FileVisitResult.TERMINATE`

If any of the methods throws an exception, the walk is also terminated, and that exception is thrown from the `walkFileTree` method.

Note: The `FileVisitor` interface is a generic type, but it isn't likely that you'll ever want something other than a `FileVisitor<Path>`. The `walkFileTree` method is willing to accept a `FileVisitor<? super Path>`, but `Path` does not have an abundance of supertypes.

A convenience class `SimpleFileVisitor` implements the `FileVisitor` interface with trivial methods that continue the visit or terminate it in case of an exception. Extend it and override the methods as needed.

For example, here is how to print out all subdirectories of a given directory:

```
Files.walkFileTree(Path.of("/"), new SimpleFileVisito
   {
      public FileVisitResult preVisitDirectory(Path p
            throws IOException
      {
         System.out.println(path);
         return FileVisitResult.CONTINUE;
      }

      public FileVisitResult postVisitDirectory(Path
      {
         return FileVisitResult.CONTINUE;
      }

      public FileVisitResult visitFileFailed(Path pat
      {
         if (e != null) throw e;
         return FileVisitResult.SKIP_SUBTREE;
      }
   });
```

Note that we need to override `postVisitDirectory` and `visitFileFailed`. Otherwise, the visit would fail as soon as it

encounters a directory that it's not allowed to open or a file it's not allowed to access.

Also note that the attributes of the path are passed as an argument to the `preVisitDirectory` and `visitFile` methods. The visitor already had to make an OS call to get the attributes, since it needs to distinguish between files and directories. This way, you don't need to make another call.

The other methods of the `FileVisitor` interface are useful if you need to do some work when entering or leaving a directory. For example, when you delete a directory tree, you need to remove the current directory after you have removed all of its files. Here is the complete code for deleting a directory tree:

```
// Delete the directory tree starting at root
Files.walkFileTree(root, new SimpleFileVisitor<Path>(
   {
      public FileVisitResult visitFile(Path file, Bas
            throws IOException
      {
         Files.delete(file);
         return FileVisitResult.CONTINUE;
      }

      public FileVisitResult postVisitDirectory(Path
```

```
        {
           if (e != null) throw e;
           Files.delete(dir);
           return FileVisitResult.CONTINUE;
        }
     });
```

`java.nio.file.Files` **7**

- `static DirectoryStream<Path> newDirectoryStream(Path path)`
- `static DirectoryStream<Path> newDirectoryStream(Path path, String glob)`
  get an iterator over the files and directories in a given directory. The second method only accepts those entries matching the given glob pattern.
- `static Path walkFileTree(Path start, FileVisitor<? super Path> visitor)`
  walks all descendants of the given path, applying the visitor to all descendants.

`java.nio.file.SimpleFileVisitor<T>` **7**

- `static FileVisitResult visitFile(T path,`

`BasicFileAttributes attrs)`
is called when a file or directory is visited; returns one of `CONTINUE`, `SKIP_SUBTREE`, `SKIP_SIBLINGS`, or `TERMINATE`. The default implementation does nothing and continues.

- `static FileVisitResult preVisitDirectory(T dir, BasicFileAttributes attrs)`
- `static FileVisitResult postVisitDirectory(T dir, IOException exc)`
  are called before and after visiting a directory. The default implementations do nothing and continue. However, if `exc` is non-`null`, it is thrown, causing the visit to terminate with that exception.
- `static FileVisitResult visitFileFailed(T path, IOException exc)`
  is called if an exception was thrown in an attempt to get information about the given file. The default implementation rethrows the exception, which causes the visit to terminate with that exception. Override the method if you want to continue.

1.4.8. ZIP File Systems

The `Paths` class looks up paths in the default file system—the files on the user's local disk. You can have other file systems. One of the more useful ones is a *ZIP file system*. If `zipname` is the name of a ZIP file, then the call

```
FileSystem fs = FileSystems.newFileSystem(Path.of(zip
```

establishes a file system that contains all files in the ZIP archive. It's an easy matter to copy a file out of that archive if you know its name:

```
Files.copy(fs.getPath(sourceName), targetPath);
```

Here, `fs.getPath` is the analog of `Path.of` for an arbitrary file system.

To list all files in a ZIP archive, walk the file tree:

```
FileSystem fs = FileSystems.newFileSystem(Path.of(zip
Files.walkFileTree(fs.getPath("/"), new SimpleFileVis
   {
      public FileVisitResult visitFile(Path file, Bas
            throws IOException
      {
         System.out.println(file);
         return FileVisitResult.CONTINUE;
      }
   });
```

That is nicer than the API described in Section 2.2.3 which required a set of new classes just to deal with ZIP archives.

`java.nio.file.FileSystems` 7

- `static FileSystem newFileSystem(Path path)` 13
returns the file system created by the first file system provider that accepts the given path. By default, there is a provider for ZIP file systems that accepts files whose names end in `.zip` or `.jar`.

`java.nio.file.FileSystem` 7

- `static Path getPath(String first, String... more)`
makes a path by joining the given strings.

1.5. Memory-Mapped Files

Most operating systems can take advantage of a virtual memory implementation to "map" a file, or a region of a file, into memory. Then the file can be accessed as if it were an in-memory array, which is much faster than the traditional file operations.

1.5.1. Memory-Mapped File Performance

At the end of this section, you can find a program that computes the CRC32 checksum of a file using traditional file input and a memory-mapped file. On one machine, we got the timing data shown in Table 2.11 when computing the checksum of the 51MB file `src.zip` in the `lib` directory of the JDK.

Table 1.6: Timing Data for File Operations

Method	Time
Plain input stream	15.1 seconds
Buffered input stream	0.8 seconds
Random access file	11.9 seconds
Memory-mapped file	0.2 seconds

As you can see, on this particular machine, memory mapping is a bit faster than using buffered sequential input and dramatically faster than using a `RandomAccessFile`.

Of course, the exact values will differ greatly from one machine to another, but it is obvious that the performance gain, compared to random access, can be substantial.

Memory mapping uses a slightly less intuitive API than random access files. Here is what you do.

First, get a *channel* for the file. A channel is an abstraction for a disk file that lets you access operating system features such as memory mapping, file locking, and fast data transfers between files.

```
FileChannel channel = FileChannel.open(path, options)
```

Then, get a `ByteBuffer` from the channel by calling the `map` method of the `FileChannel` class. Specify the area of the file that you want to map and a *mapping mode*. Three modes are supported:

- `FileChannel.MapMode.READ_ONLY`: The resulting buffer is read-only. Any attempt to write to the buffer results in a `ReadOnlyBufferException`.
- `FileChannel.MapMode.READ_WRITE`: The resulting buffer is writable, and the changes will be written back to the file at some time. Note that other programs that have mapped the same file might not see those changes immediately. The exact behavior of simultaneous file mapping by multiple programs depends on the operating system.
- `FileChannel.MapMode.PRIVATE`: The resulting buffer is writable, but any changes are private to this buffer and not

propagated to the file.

For example,

```
MappedByteBuffer buffer = channel.map(FileChannel.Map
```

Once you have the buffer, you can read and write data using the methods of the `ByteBuffer` class and the `Buffer` superclass.

Buffers support both sequential and random data access. A buffer has a *position* that is advanced by `get` and `put` operations. For example, you can sequentially traverse all bytes in the buffer as

```
while (buffer.hasRemaining())
{
   byte b = buffer.get();
   . . .
}
```

Alternatively, you can use random access:

```
for (int i = 0; i < buffer.limit(); i++)
{
   byte b = buffer.get(i);
```

```
   . . .
}
```

You can also read and write arrays of bytes with the methods

```
get(byte[] bytes)
get(byte[] bytes, int offset, int length)
```

Finally, there are methods

```
getInt             getChar
getLong            getFloat
getShort           getDouble
```

to read primitive-type values that are stored as *binary* values in the file. As we already mentioned, Java uses big-endian ordering for binary data. However, if you need to process a file containing binary numbers in little-endian order, simply call

```
buffer.order(ByteOrder.LITTLE_ENDIAN);
```

To find out the current byte order of a buffer, call

```
ByteOrder b = buffer.order();
```

To write numbers to a buffer, use one of the methods

```
putInt              putChar
putLong             putFloat
putShort            putDouble
```

At some point, and certainly when the channel is closed, these changes are written back to the file.

Listing 2.5 computes the 32-bit cyclic redundancy checksum (CRC32) of a file. That checksum is often used to determine whether a file has been corrupted. Corruption of a file makes it very likely that the checksum has changed. The `java.util.zip` package contains a class `CRC32` that computes the checksum of a sequence of bytes, using the following loop:

```
var crc = new CRC32();
while (more bytes)
   crc.update(next byte);
long checksum = crc.getValue();
```

The details of the CRC computation are not important. We just use it as an example of a useful file operation. (In practice, you would read

and update data in larger blocks, not a byte at a time. Then the speed differences are not as dramatic.)

Run the program as

```
java memoryMap.MemoryMapTest filename
```

Listing 1.5 memoryMap/MemoryMapTest.java

```
1  package memoryMap;
2
3  import java.io.*;
4  import java.nio.*;
5  import java.nio.channels.*;
6  import java.nio.file.*;
7  import java.util.zip.*;
8
9  /**
10  * This program computes the CRC checksum of a
11  * Usage: java memoryMap.MemoryMapTest filename
12  *
13  * @version 1.03 2018-05-01
14  * @author Cay Horstmann
15  */
16 public class MemoryMapTest
17 {
18    public static long checksumInputStream(Path
```

```
19    {
20       try (InputStream in = Files.newInputStrea
21       {
22          var crc = new CRC32();
23          boolean done = false;
24          while (!done)
25          {
26             int c = in.read();
27             if (c == -1)
28                done = true;
29             else
30                crc.update(c);
31          }
32          return crc.getValue();
33       }
34    }
35
36    public static long checksumBufferedInputStre
37    {
38       try (var in = new BufferedInputStream(Fi
39       {
40          var crc = new CRC32();
41
42          boolean done = false;
43          while (!done)
44          {
45             int c = in.read();
46             if (c == -1)
```

```
47                done = true;
48             else
49                crc.update(c);
50          }
51          return crc.getValue();
52       }
53    }
54
55    public static long checksumRandomAccessFile(
56    {
57       try (var file = new RandomAccessFile(file
58       {
59          long length = file.length();
60          var crc = new CRC32();
61
62          for (long p = 0; p < length; p++)
63          {
64             int c = file.readByte();
65             crc.update(c);
66          }
67          return crc.getValue();
68       }
69    }
70
71    public static long checksumMappedFile(Path f
72    {
73       try (FileChannel channel = FileChannel.op
74       {
```

```
75          var crc = new CRC32();
76          int length = (int) channel.size();
77          MappedByteBuffer buffer = channel.map(
78
79          for (int p = 0; p < length; p++)
80          {
81             int c = buffer.get(p);
82             crc.update(c);
83          }
84          return crc.getValue();
85       }
86    }
87
88    public static void main(String[] args) throw
89    {
90       System.out.println("Input Stream:");
91       long start = System.nanoTime();
92       Path filename = Path.of(args[0]);
93       long crcValue = checksumInputStream(filen
94       long end = System.nanoTime();
95       System.out.println(Long.toHexString(crcVa
96       System.out.printf("%.3f seconds%n", (end
97
98       System.out.println("Buffered Input Strean
99       start = System.nanoTime();
100      crcValue = checksumBufferedInputStream(fi
101      end = System.nanoTime();
102      System.out.println(Long.toHexString(crcVa
```

```
103         System.out.printf("%.3f seconds%n", (end
104
105         System.out.println("Random Access File:")
106         start = System.nanoTime();
107         crcValue = checksumRandomAccessFile(filen
108         end = System.nanoTime();
109         System.out.println(Long.toHexString(crcVa
110         System.out.printf("%.3f seconds%n", (end
111
112         System.out.println("Mapped File:");
113         start = System.nanoTime();
114         crcValue = checksumMappedFile(filename);
115         end = System.nanoTime();
116         System.out.println(Long.toHexString(crcVa
117         System.out.printf("%.3f seconds%n", (end
118      }
119   }
```

`java.io.FileInputStream` **1.0**

- `FileChannel getChannel()` **1.4**
  returns a channel for accessing this input stream.

`java.io.FileOutputStream` **1.0**

- `FileChannel getChannel()` **1.4**
  returns a channel for accessing this output stream.

`java.io.RandomAccessFile` **1.0**

- `FileChannel getChannel()` **1.4**
  returns a channel for accessing this file.

`java.nio.channels.FileChannel` **1.4**

- `static FileChannel open(Path path, OpenOption... options)` **7**
  opens a file channel for the given path. By default, the channel is opened for reading. The parameter `options` is one of the values `WRITE`, `APPEND`, `TRUNCATE_EXISTING`, `CREATE` in the `StandardOpenOption` enumeration.
- `MappedByteBuffer map(FileChannel.MapMode mode, long position, long size)`
  maps a region of the file to memory. The parameter `mode` is one of the constants `READ_ONLY`, `READ_WRITE`, or `PRIVATE` in the `FileChannel.MapMode` class.

`java.nio.Buffer` **1.4**

- `boolean hasRemaining()`
  returns `true` if the current buffer position has not yet reached the buffer's limit position.

- `int limit()`
  returns the limit position of the buffer—that is, the first position at which no more values are available.

`java.nio.ByteBuffer` **1.4**

- `byte get()`
  gets a byte from the current position and advances the current position to the next byte.
- `byte get(int index)`
  gets a byte from the specified index.
- `ByteBuffer put(byte b)`
  puts a byte at the current position and advances the current position to the next byte. Returns a reference to this buffer.
- `ByteBuffer put(int index, byte b)`
  puts a byte at the specified index. Returns a reference to this buffer.
- `ByteBuffer get(byte[] destination)`
- `ByteBuffer get(byte[] destination, int offset, int length)`
  fill a byte array, or a region of a byte array, with bytes from the buffer, and advance the current position by the number of bytes read. If not enough bytes remain in the buffer, then no bytes are read, and a `BufferUnderflowException` is thrown. Return a reference to this buffer.

- `ByteBuffer put(byte[] source)`
- `ByteBuffer put(byte[] source, int offset, int length)`
  put all bytes from a byte array, or the bytes from a region of a byte array, into the buffer, and advance the current position by the number of bytes read. If not enough bytes remain in the buffer, then no bytes are written, and a `BufferOverflowException` is thrown. Return a reference to this buffer.
- `Xxx getXxx()`
- `Xxx getXxx(int index)`
- `ByteBuffer putXxx(Xxx value)`
- `ByteBuffer putXxx(int index, Xxx value)`
  get or put a binary number. Xxx is one of `Int`, `Long`, `Short`, `Char`, `Float`, or `Double`.
- `ByteBuffer order(ByteOrder order)`
- `ByteOrder order()`
  set or get the byte order. The value for `order` is one of the constants `BIG_ENDIAN` or `LITTLE_ENDIAN` of the `ByteOrder` class.
- `static ByteBuffer allocate(int capacity)`
  constructs a buffer with the given capacity.
- `static ByteBuffer wrap(byte[] values)`
  constructs a buffer that is backed by the given array.

- `CharBuffer asCharBuffer()`
  constructs a character buffer that is backed by this buffer. Changes to the character buffer will show up in this buffer, but the character buffer has its own position, limit, and mark.

`java.nio.CharBuffer` **1.4**

- `char get()`
- `CharBuffer get(char[] destination)`
- `CharBuffer get(char[] destination, int offset, int length)`
  get one `char` value, or a range of `char` values, starting at the buffer's position and moving the position past the characters that were read. The last two methods return `this`.
- `CharBuffer put(char c)`
- `CharBuffer put(char[] source)`
- `CharBuffer put(char[] source, int offset, int length)`
- `CharBuffer put(String source)`
- `CharBuffer put(CharBuffer source)`
  put one `char` value, or a range of `char` values, starting at the buffer's position and advancing the position past the characters that were written. When reading from a `CharBuffer`, all remaining characters are read. All methods return `this`.

1.5.2. The Buffer Data Structure

When you use memory mapping, you make a single buffer that spans the entire file or the area of the file that you're interested in. You can also use buffers to read and write more modest chunks of information.

In this section, we briefly describe the basic operations on `Buffer` objects. A buffer is an array of values of the same type. The `Buffer` class is an abstract class with concrete subclasses `ByteBuffer`, `CharBuffer`, `DoubleBuffer`, `FloatBuffer`, `IntBuffer`, `LongBuffer`, and `ShortBuffer`.

Note: The `StringBuffer` class is not related to these buffers.

In practice, you will most commonly use `ByteBuffer` and `CharBuffer`. As shown in #ch01fig11, a buffer has

- A *capacity* that never changes
- A *position* at which the next value is read or written
- A *limit* beyond which reading and writing is meaningless
- Optionally, a *mark* for repeating a read or write operation



Figure 1.9: A buffer

These values fulfill the condition

$0 \leq \text{mark} \leq \text{position} \leq \text{limit} \leq \text{capacity}$

The principal purpose of a buffer is a sequence of "fill, then consume" cycles. At the outset, the buffer's position is 0 and the limit is the capacity. Keep filling the buffer by calling `put` or by reading from a channel.

When you run out of data or reach the capacity, it is time to switch to consuming the contents. Call `flip` to set the limit to the current position and the position to `0`.

Now keep consuming, by calling `get` or writing to a channel, while the `remaining` method (which computes *limit* – *position*) yields a positive value.

When you have consumed all values in the buffer, call `compact` to prepare the buffer for filling it again. Any unconsumed data is copied to the beginning of the buffer. The position is set to follow the copied data, and the limit is set to the capacity.

If you want to reread the buffer, use `rewind` or `mark` / `reset` (see the API notes for details).

To obtain a buffer, call a static method such as `ByteBuffer.allocate` or `ByteBuffer.wrap`.

This loop uses a buffer to transfer data from one channel to another:

```
ByteBuffer buffer = ByteBuffer.allocate(BUFFER_SIZE);
boolean doneReading = false;
boolean doneWriting = false;
while (!(doneReading && doneWriting))
{
   if (sourceChannel.read(buffer) == -1) doneReading
   buffer.flip();
   destinationChannel.write(buffer);
   if (buffer.remaining() == 0) doneWriting = true;
   buffer.compact();
}
```

`java.nio.Buffer` **1.4**

- `Buffer flip()`
  prepares this buffer for reading after writing, by setting the limit to the position and the position to `0`; returns `this`.
- `Buffer rewind()`
  prepares this buffer for rereading the same values by setting the position to `0` and leaving the limit unchanged; returns `this`.
- `Buffer clear()`
  prepares this buffer for writing by setting the position to `0` and the limit to the capacity; returns `this`.
- `Buffer mark()`
  sets the mark of this buffer to the position; returns `this`.
- `Buffer reset()`
  sets the position of this buffer to the mark, thus allowing the marked portion to be read or written again; returns `this`.
- `int remaining()`
  returns the remaining number of readable or writable values—that is, the difference between the limit and position.

`java.nio.ByteBuffer` 1.4

- `Buffer compact()`
  copies any unconsumed bytes to the beginning of the buffer, sets the position to the following byte, and the limit to the capacity; returns `this`.

`java.nio.ReadableByteChannel` 1.4

- `int read(ByteBuffer dst)`
  fills the remaining part of the buffer with available bytes, and returns the number of transferred bytes, or -1 if the channel has reached its end.

`java.nio.WritableByteChannel` 1.4

- `int write(ByteBuffer src)`
  attempts to consume the remaining bytes from the buffer, and returns the number of transferred bytes.

1.6. File Locking

When multiple simultaneously executing programs need to modify the same file, they need to communicate in some way, or the file can

easily become damaged. File locks can solve this problem. A file lock controls access to a file or a range of bytes within a file.

Suppose your application saves a file with system-wide preferences. If a user invokes two instances of the application, it could happen that both of them want to write the file at the same time. In that situation, the first instance should lock the file. When the second instance finds the file locked, it can decide to wait until the file is unlocked or simply skip the writing process.

To lock a file, call either the `lock` or `tryLock` methods of the `FileChannel` class.

```
FileChannel channel = FileChannel.open(path);
FileLock lock = channel.lock();
```

or

```
FileLock lock = channel.tryLock();
```

The first call blocks until the lock becomes available. The second call returns immediately, either with the lock or with `null` if the lock is not available. The file remains locked until the channel is closed or the `release` method is invoked on the lock.

You can also lock a portion of the file with the call

```
FileLock lock(long start, long size, boolean shared)
```

or

```
FileLock tryLock(long start, long size, boolean share
```

The `shared` flag is `false` to lock the file for both reading and writing. It is `true` for a *shared* lock, which allows multiple processes to read from the file, while preventing any process from acquiring an exclusive lock. Not all operating systems support shared locks. You may get an exclusive lock even if you just asked for a shared one. Call the `isShared` method of the `FileLock` class to find out which kind you have.

Note: If you lock the tail portion of a file and the file subsequently grows beyond the locked portion, the additional area is not locked. To lock all bytes, use a size of `Long.MAX_VALUE`.

Be sure to unlock the lock when you are done. As always, this is best done with a `try`-with-resources statement:

```
try (FileLock lock = channel.lock())
{
   access the locked file or segment
}
```

Keep in mind that file locking is system-dependent. Here are some points to watch for:

- On some systems, including Linux, file locking is merely *advisory*. If an application fails to get a lock, it may still write to a file that another application has currently locked.
- On some systems, you cannot simultaneously lock a file and map it into memory.
- File locks are global to the Java virtual machine. Concurrent threads can't each acquire a lock on the same file. The `lock` and `tryLock` methods will throw an `OverlappingFileLockException` if another thread already holds a lock on the same file or an overlapping range.
- On some systems, closing a channel releases all locks on the underlying file. You should therefore avoid multiple channels on the same locked file.
- Locking files on a networked file system is highly system-dependent and should probably be avoided.

- File locking is only guaranteed for Java programs. Programs written in other languages may use different and incompatible locking mechanisms.

The program in Listing 2.6 shows a simple example of file locking. Multiple users want to register their passwords in a common file. The program reads in the file, adds the username and hashed password, and writes the resulting file. It is important that this update is atomic. Otherwise, the password file can be corrupted if two users update it concurrently.

See Chapter 9 for more information about password hashing. It has nothing to do with file locking, but I didn't want to show a sample program that saves unhashed passwords.

The program shows the limitations of the file locking API. It is tied to the `FileChannel` API, which is based on the reading and writing of byte buffers. The program has to turn those byte buffers into readers and writers.

An alternative would be to use a `RandomAccessFile` whose `getChannel` method yields a channel to the file. But it is equally inconvenient. One needs to read the file into a byte array and prepare a byte array to write the modified file.

Listing 1.6 fileLock/FileLockDemo.java

```
1  package fileLock;
2
3  import java.io.*;
4  import java.nio.*;
5  import java.nio.channels.*;
6  import java.nio.file.*;
7  import java.security.*;
8  import java.security.spec.*;
9  import java.util.*;
10
11 import javax.crypto.*;
12 import javax.crypto.spec.*;
13
14 /**
15  * This program writes user names and passwords
16  * The file is atomically updated. With Linux,
17  *    for f in $(seq 1 100) ; do (java fileLock
18  * When all Java processes have finished, then
19  *
20  * @version 1.0 2023-10-27
21  * @author Cay Horstmann
22  */
23
24
25 public class FileLockDemo
26 {
```

```
27    public static void main(String[] args)
28          throws IOException, NoSuchAlgorithmExc
29    {
30       Path path = Path.of("password.properties"
31       FileChannel channel = FileChannel.open(pa
32             StandardOpenOption.WRITE, StandardO
33       try (FileLock lock = channel.lock())
34       {
35          // Read bytes from file
36          ByteBuffer readBuffer = ByteBuffer.all
37          channel.read(readBuffer);
38
39          // Read props from bytes
40          Reader in = new StringReader(new Strin
41          Properties props = new Properties();
42          props.load(in);
43
44          // Get username, password from args or
45          String username;
46          char[] password;
47          if (args.length >= 2)
48          {
49             username = args[0];
50             password = args[1].toCharArray();
51          }
52          else
53          {
54             Console console = System.console();
```

```
55              username = console.readLine("User r
56              password = console.readPassword("Pa
57          }
58
59          // Hash password
60          final int ITERATIONS = 210_000;
61          final int SALT_BYTES = 16;
62          final int HASH_BYTES = 32;
63          SecureRandom random = new SecureRandom
64          byte[] salt = new byte[SALT_BYTES];
65          random.nextBytes(salt);
66
67          var spec = new PBEKeySpec(password, sa
68          SecretKeyFactory skf = SecretKeyFactor
69          byte[] hash = skf.generateSecret(spec)
70          Base64.Encoder encoder = Base64.getEnc
71
72          // Put username and hashed password in
73          props.put(username, ITERATIONS + "|" +
74                + encoder.encodeToString(hash));
75
76          // Write props to bytes
77          StringWriter out = new StringWriter();
78          props.store(out, null);
79          byte[] outBytes = out.toString().getBy
80
81          // Write bytes to file
82          channel.truncate(0);
```

```
83            ByteBuffer writeBuffer = ByteBuffer.wr
84            channel.write(writeBuffer);
85         }
86      }
87   }
```

`java.nio.channels.FileChannel` **1.4**

- `FileLock lock()`
  acquires an exclusive lock on the entire file. This method blocks until the lock is acquired.
- `FileLock tryLock()`
  acquires an exclusive lock on the entire file, or returns `null` if the lock cannot be acquired.
- `FileLock lock(long position, long size, boolean shared)`
- `FileLock tryLock(long position, long size, boolean shared)`
  acquire a lock on a region of the file. The first method blocks until the lock is acquired, and the second method returns `null` if the lock cannot be acquired. The parameter `shared` is `true` for a shared lock, `false` for an exclusive lock.
- `FileChannel truncate(long size)`
  truncates the file to the given size if it is larger.

`java.nio.channels.FileLock` 1.4

- `void close()` 1.7
  releases this lock.

`java.io.RandomAccessFile` 1.0

- `FileChannel getChannel()` 1.4
  yields the channel for this random access file.

1.7. Regular Expressions

Regular expressions are used to specify string patterns. You can use regular expressions whenever you need to locate strings that match a particular pattern. For example, one of our sample programs locates all hyperlinks in an HTML file by looking for strings of the pattern `<a href=". . ."`.

Of course, when specifying a pattern, the `. . .` notation is not precise enough. You need to specify exactly what sequence of characters is a legal match, using a special syntax to describe a pattern.

In the following sections, we cover the regular expression syntax used by the Java API and discuss how to put regular expressions to

work.

1.7.1. The Regular Expression Syntax

Let us start with a simple example. The regular expression

```
[Jj]ava.+
```

matches any string of the following form:

- The first letter is a `J` or `j`.
- The next three letters are `ava`.
- The remainder of the string consists of one or more arbitrary characters.

For example, the string `"javanese"` matches this particular regular expression, but the string `"Core Java"` does not.

As you can see, you need to know a bit of syntax to understand the meaning of a regular expression. Fortunately, for most purposes, a few straightforward constructs are sufficient.

In a regular expression, a character denotes itself unless it is one of the reserved characters

```
. * + ? { | ( ) [ \ ^ $
```

For example, the regular expression `Java` only matches the string `Java`.

The symbol `.` matches any single character. For example, `.a.a` matches `Java` and `data`.

The `*` symbol indicates that the preceding constructs may be repeated 0 or more times; for a `+`, it is 1 or more times. A suffix of `?` indicates that a construct is optional (0 or 1 times). For example, `be+s?` matches `be`, `bee`, and `bees`. You can specify other multiplicities with `{ }`—see Table 2.12.

A `|` denotes an alternative: `.(oo|ee)f` matches `beef` or `woof`. Note the parentheses—without them, `.oo|eef` would be the alternative between `.oo` and `eef`. Parentheses are also used for grouping—see Section 2.7.4.

A *character class* is a set of character alternatives enclosed in brackets, such as `[Jj]`, `[0-9]`, `[A-Za-z]`, or `[^0-9]`. Inside a character class, the `-` denotes a range (all characters whose Unicode values fall between the two bounds). However, a `-` that is the first or last character in a character class denotes itself. A `^` as

the first character in a character class denotes the complement (all characters except those specified).

There are many *predefined character classes* such as `\d` (digits) or `\s` (spaces)— see Table 2.12. More complex character classes can be described with the `\p` syntax in Table 2.13. For example, `\p{Sc}` is the class of Unicode currency symbols.

The characters `^` and `$` match the beginning and end of input.

If you need to have a literal `. * + ? { | ( ) [ \ ^ $`, precede it by a backslash. Inside a character class, you only need to escape `[` and `\`, provided you are careful about the positions of `] - ^`. For example, `[]^-]` is a class containing all three of them.

Caution: If the regular expression is in a string literal, each backslash needs to be escaped with another backslash. If you forget that second backslash, you usually get an error because sequences such as `\$` or `\.` are not valid in string literals. But if you want to match a word boundary and accidentally use `\b` instead of `\\b`, then you have a problem: `\b` is a valid escape sequence, indicating a backspace.

Your IDE can help with that escaping. Paste the regular expression string into an empty string, and the backslashes will be doubled.

Instead of using backslashes, you can surround a string with `\Q` and `\E`. For example, `\(\$0\.99\)` and `\Q($0.99)\E` both match the string `($0.99)`.

Tip: If you have a string that may contain some of the many special characters in the regular expression syntax, you can escape them all by calling `Parse.quote(str)`. This simply surrounds the string with `\Q` and `\E`, but it takes care of the special case where `str` may contain `\E`.

Table 1.7: Regular Expression Syntax

Expression	Description	Example
Characters		
c, not one of `. * + ? { | ( ) [ \ ^ $`	The character c	`J`
`.`	Any character except line terminators, or any character	

Expression	Description	Example
	if the `DOTALL` flag is set	
`\X`	Any Unicode "extended grapheme cluster", which is perceived as a character or symbol	
`\x{` p `}`	The Unicode code point with hex code p	`\x{1D546}`
`\u` hhhh, `\x` hh, `\0` o, `\0` oo, `\0` ooo	The UTF-16 code unit with the given hex or octal value	`\uFEFF`
`\a` , `\e` , `\f` , `\n` , `\r` , `\t`	Alert (`\x{7}`), escape (`\x{1B}`), form feed (`\x{B}`), newline (`\x{A}`), carriage return (`\x{D}`), tab (`\x{9}`)	`\n`

Expression	Description	Example
`\c` c, where c is in `[A-Z]` or one of `@ [ \ ] ^ _ ?`	The control character corresponding to the character c	`\cH` is a backsp (`\x{8}`)
`\` c, where c is not in `[A-Za-z0-9]`	The character c	`\\`
`\Q. . .\E`	Everything between the start and the end of the quotation	`\Q(. . .)\E` r the string `(. .`

Character Classes

`[` C_1C_2 `. . .]`, where C_i are characters, ranges c `-` d,	Any of the characters represented by C_1, C_2, . . .	`[0-9+-]`

Expression	Description	Example
or character classes		
`[^. . .]`	Complement of a character class	`[^\d\s]`
`[. . .&&. . .]`	Intersection of character classes	`[\p{L}&&[^A-Z`
`\p{. . .}`, `\P{. . .}`	A predefined character class (see Table 2.13); its complement	`\p{L}` matches Unicode letter, a does `\pL` —you braces around a letter
`\d`, `\D`	Digits (`[0-9]`, or `\p{Digit}` when the `UNICODE_CHARACTER_CLASS` flag is set); the complement	`\d+` is a sequer digits
`\w`, `\W`	Word characters (`[a-zA-Z0-9_]`, or Unicode word	

Expression	Description	Example
	characters when the `UNICODE_CHARACTER_CLASS` flag is set); the complement	
`\s`, `\S`	Spaces (`[ \n\r\t\f\x{B}]`, or `\p{IsWhite_Space}` when the `UNICODE_CHARACTER_CLASS` flag is set); the complement	`\s*,\s*` is a c surrounded by c white space
`\h`, `\v`, `\H`, `\V`	Horizontal whitespace, vertical whitespace, their complements	
Sequences and Alternatives		
XY	Any string from `X`, followed by any string from `Y`	`[1-9][0-9]*` i positive number leading zero
X | Y	Any string from `X` or `Y`	`http|ftp`

Expression	Description	Example
Grouping		
`(X)`	Captures the match of X	`'([^']*)'` cap the quoted text
`\n`	The nth group	`(['"]).*\1` m `'Fred'` or `"Fr` not `"Fred'`
`(?<name>X)`	Captures the match of X with the given name	`'(?<id>[A-Za-9]+)'` captures match with nam
`\k<name>`	The group with the given name	`\k<id>` matche group with nam
`(?:X)`	Use parentheses without capturing X	In `(?:http|ftp)` the match after `\1`

Expression	Description	Example
`(?` f_1f_2 `. . .: X )`, `(?` f_1 `. . .-` f_k `. . .: X )`, with f_i in `[dimsuUx]`	Matches, but does not capture, X with the given flags on or off (after `-`)	`(?i:jpe?g)` is insensitive matc
Other `(?. .)`	See the `Pattern` API documentation	

Quantifiers

X `?`	Optional X	`\+?` is an optio sign
X `*`, X `+`	0 or more X, 1 or more X	`[1-9][0-9]+` i integer ≥ 10
X `{ n }`, X `{ n ,}`,	n times X, at least n times `X`, between m and n times X	`[0-7]{1,3}` ar three octal digit

Expression	Description	Example
X{m,n}		
Q? , where Q is a quantified expression	Reluctant quantifier, attempting the shortest match before trying longer matches	.*(<.+?>).* c the shortest seq enclosed in angl brackets
Q+ , where Q is a quantified expression	Possessive quantifier, taking the longest match without backtracking	'[^']*+' mat strings enclosed quotes and fails on strings witho closing quote
Boundary Matches		
^ $	Beginning, end of input (or beginning, end of line in multiline mode)	^Java$ matche input or line Ja
\A \Z \z	Beginning of input, end of input, absolute end of input	

Expression	Description	Example
	(unchanged in multiline mode)	
`\b \B`	Word boundary, nonword boundary	`\bJava\b` mat word `Java`
`\b{g}`	Grapheme cluster boundary	Useful with `spl` decompose a st grapheme cluste
`\R`	A Unicode line break	
`\G`	The end of the previous match	

Table 1.8: Predefined Character Classes `\p{. . .}`

Name	Description
posixClass	posixClass is one of `Lower`, `Up` `Alpha`, `Digit`, `Alnum`, `Punc` `Graph`, `Print`, `Cntrl`, `XDig`

Name	Description
	`Space`, `Blank`, `ASCII`, interp as POSIX or Unicode class, depe on the `UNICODE_CHARACTER_CL` flag
`Is` Script, `sc=` Script, `script=` Script	A script accepted by `Character.UnicodeScript.f`
`In` Block, `blk=` Block, `block=` Block	A block accepted by `Character.UnicodeBlock.fo`
Category, `In` Category, `gc=` Category, `general_category=` Category	A one- or two-letter name for a Unicode general category
`Is` Property	Property is one of `Alphabetic` `Ideographic`, `Letter`, `Lowe` `Uppercase`, `Titlecase`, `Punctuation`, `Control`, `White_Space`, `Digit`, `Hex_D` `Join_Control`,

Name	Description
	`Noncharacter_Code_Point`, `Assigned`
`java` Method	Invokes the method `Character.is` Method (must n deprecated)

Unfortunately, the regular expression syntax is not completely standardized between various programs and libraries; there is a consensus on the basic constructs but many maddening differences in the details. The Java regular expression classes use a syntax that is similar to, but not quite the same as, the one used in the Perl language. Table 2.12 shows all constructs of the Java syntax. For more information on the regular expression syntax, consult the API documentation for the `Pattern` class or the book Mastering Regular Expressions by Jeffrey E. F. Friedl (O'Reilly and Associates, 2006).

1.7.2. Testing a Match

Generally, there are two ways to use a regular expression: Either you want to find out whether a string conforms to the expression, or you

want to find all matches of a regular expressions in a string.

In the first case, simply use the static `matches` method:

```
String regex = "-?\\d+";
CharSequence input = . . .;
if (Pattern.matches(regex, input))
{
   . . .
}
```

If you need to use the same regular expression many times, it is more efficient to compile it. Then, create a `Matcher` for each input:

```
Pattern pattern = Pattern.compile(regex);
Matcher matcher = pattern.matcher(input);
if (matcher.matches()) . . .
```

If the match succeeds, you can retrieve the location of matched groups—see the following section.

If you want to test whether the input *contains* a match, use the `find` method instead:

```
if (matcher.find()) . . .
```

The `find` and `match` methods mutate the state of the `Matcher` object. If you just want to find out whether a given `Matcher` has already found a match, call the `hasMatch` method instead.

You can turn the pattern into a predicate:

```
Pattern digits = Pattern.compile("[0-9]+");
List<String> strings = List.of("December", "31st", "1
List<String> matchingStrings = strings.stream().filte
   // ["1999"]
```

The result contains all strings that match the regular expression.

Use the `asPredicate` method to test whether a string contains a match:

```
List<String> sringsContainingMatch = strings.stream()
   // ["31st", "1999"]
```

1.7.3. Finding All Matches in a String

In this section, we consider the other common use case for regular expressions—finding all matches in an input. Use this loop:

```
String input = . . .;
Matcher matcher = pattern.matcher(input);
while (matcher.find())
{
   String match = matcher.group();
   int matchStart = matcher.start();
   int matchEnd = matcher.end();
   . . .
}
```

In this way, you can process each match in turn. As shown in the code fragment, you can get the matched string as well as its position in the input string.

More elegantly, you can call the `results` method to get a `Stream<MatchResult>`. The `MatchResult` interface has methods `group`, `start`, and `end`, just like `Matcher`. (In fact, the `Matcher` class implements this interface.) Here is how you get a list of all matches:

```
List<String> matches = pattern.matcher(input)
   .results()
   .map(MatchResult::group)
   .toList();
```

If you have the data in a file, then you can use the `Scanner.findAll` method to get a `Stream<MatchResult>`, without first having to read the contents into a string. You can pass a `Pattern` or a pattern string:

```
Scanner in = new Scanner(path, "UTF_8");
Stream<String> words = in.findAll("\\pL+")
   .map(MatchResult::group);
```

Listing 2.7 puts this mechanism to work. It locates all hypertext references in a web page and prints them. To run the program, supply a URL on the command line, such as

```
java match.HrefMatch https://horstmann.com
```

Listing 1.7 match/HrefMatch.java

```
1  package match;
2
3  import java.io.*;
4  import java.net.*;
5  import java.util.regex.*;
6
7  /**
8   * This program displays all URLs in a web page
```

```
 * that describes the <a href=...> HTML tag. St
 * java match.HrefMatch URL
 *
 * @version 1.05 2023-08-16
 * @author Cay Horstmann
 */
public class HrefMatch
{
   public static void main(String[] args)
   {
      try
      {
         // get URL string from command line or
         String urlString;
         if (args.length > 0)
            urlString = args[0];
         else
            urlString = "https://openjdk.org/";

         // read contents of URL
         InputStream in = URI.create(urlString)
         var input = new String(in.readAllBytes

         // search for all occurrences of patte
         String patternString = "<a\\s+href\\s*
         Pattern pattern = Pattern.compile(patt
         pattern.matcher(input).results().map(M
      } catch (IOException | PatternSyntaxExcep
```

```
37          {
38             e.printStackTrace();
39          }
40       }
41    }
```

1.7.4. Groups

It is common to use groups for extracting components of a match. For example, suppose you have a line item in the invoice with item name, quantity, and unit price such as

```
Blackwell Toaster    USD29.95
```

Here is a regular expression with groups for each component:

```
(\p{Alnum}+(\s+\p{Alnum}+)*)\s+([A-Z]{3})([0-9.]*)
```

After matching, you can extract the `n` th group from the matcher as

```
String contents = matcher.group(n);
```

Groups are ordered by their opening parenthesis, starting at 1. (Group 0 is the entire input.) In this example, here is how to take the input apart:

```
Matcher matcher = pattern.matcher(input);
if (matcher.matches())
{
   item = matcher.group(1);
   currency = matcher.group(3);
   price = matcher.group(4);
}
```

We aren't interested in group 2; it only arose from the parentheses that were required for the repetition. For greater clarity, you can use a noncapturing group:

```
(\p{Alnum}+(?:\s+\p{Alnum}+)*)\s+([A-Z]{3})([0-9.]*)
```

Or, even better, use named groups:

```
(?<item>\p{Alnum}+(\s+\p{Alnum}+)*)\s+(?<currency>[A-
```

Then, you can retrieve the items by name:

```
item = matcher.group("item");
```

With the `start` and `end` methods, you can get the group positions in the input:

```
int itemStart = matcher.start("item");
int itemEnd = matcher.end("item");
```

As of Java 20, the `MatchResult` class also supports named groups.

The `namedGroups` method yields a `Map<String, Integer>` from group names to numbers.

Note: When you have a group inside a repetition, such as `(\s+\p{Alnum}+)*` in the example above, it is not possible to get all of its matches. The `group` method only yields the last match, which is rarely useful. You need to capture the entire expression with another group.

Tip: You can add comments to regular expressions. A comment starts with `#` and extends until the end of the line. This works particularly well with text blocks:

```
var regex = """
([1-9]|1[0-2]) #hours
:([0-5][0-9]) #minutes
[ap]m""";
```

Listing 2.8 prompts for a pattern, then for strings to match. It prints out whether or not the input matches the pattern. If the input matches and the pattern contains groups, the program prints the group boundaries as parentheses, for example:

```
((11):(59))am
```

Listing 1.8 regex/RegexTest.java

```
1  package regex;
2
3  /**
4   * This program tests regular expression matchi
5   * or hit Enter to exit. If the pattern contair
6   * in the match.
7   * @version 1.03 2018-05-01
8   * @author Cay Horstmann
9   */
10
```

```
11 import java.util.*;
12 import java.util.regex.*;
13
14 public class RegexTest
15 {
16    public static void main(String[] args) throw
17    {
18       var in = new Scanner(System.in);
19       System.out.println("Enter pattern: ");
20       String patternString = in.nextLine();
21
22       Pattern pattern = Pattern.compile(patterr
23
24       while (true)
25       {
26          System.out.println("Enter string to ma
27          String input = in.nextLine();
28          if (input == null || input.equals(""))
29             return;
30          Matcher matcher = pattern.matcher(inpu
31          if (matcher.matches())
32          {
33             System.out.println("Match");
34             int g = matcher.groupCount();
35             if (g > 0)
36             {
37                for (int i = 0; i < input.length
38                {
```

```
39                   // Print any empty groups
40                   for (int j = 1; j <= g; j++)
41                      if (i == matcher.start(j)
42                         System.out.print("()");
43                   // Print ( for non-empty grou
44                   for (int j = 1; j <= g; j++)
45                      if (i == matcher.start(j)
46                         System.out.print("(");
47                   System.out.print(input.charAt
48                   // Print ) for non-empty grou
49                   for (int j = 1; j <= g; j++)
50                      if (i + 1 != matcher.start
51                         System.out.print(")");
52                }
53                System.out.println();
54             }
55          }
56          else
57             System.out.println("No match");
58       }
59    }
60 }
```

1.7.5. Splitting along Delimiters

Sometimes, you want to break an input along matched delimiters and keep everything else. The `Pattern.split` method automates

this task. You obtain an array of strings, with the delimiters removed:

```
String input = "1, 2 , 3,4";
Pattern commas = Pattern.compile("\\s*,\\s*");
String[] tokens = commas.split(input); // ["1", "2",
```

If there are many tokens, you can fetch them lazily:

```
Stream<String> tokens = commas.splitAsStream(input);
```

To also capture the delimiters, use the `splitWithDelimiters` method:

```
tokens = commas.splitWithDelimiters(input, -1); // ["
```

If the second argument is a positive number n, the separator pattern is applied at most n - 1 times, and the last element is the remaining string. Otherwise, the pattern is applied as many times as possible. With a limit of zero, trailing empty strings are discarded.

If you don't care about precompiling the pattern or lazy fetching, you can just use the `split` and `splitWithDelimiter` methods of

the `String` class:

```
tokens = input.split("\\s*,\\s*");
```

Caution: It is easy to forget that the argument of `split` is a regular expression. For example,

```
"com.horstmann.corejava".split(".")
```

does not split along the dots. Instead, every character is a separator, and the result is an empty array!

You need to escape the dot with a backslash in the regular expression, and therefore with two backslashes in the string literal:

```
"com.horstmann.corejava".split("\\.")
```

Alternatively, use the `Pattern.quote` method:

```
"com.horstmann.corejava".split(Pattern.quote("."));
```

If the input is in a file, use a scanner:

```
Scanner in = new Scanner(path, "UTF_8");
in.useDelimiter("\\s*,\\s*");
Stream<String> tokens = in.tokens();
```

1.7.6. Replacing Matches

If you want to replace all matches of a regular expression with a string, call `replaceAll` on the matcher:

```
Matcher matcher = commas.matcher(input);
String result = matcher.replaceAll(",");
   // Normalizes the commas
```

Or, if you don't care about precompiling, use the `replaceAll` method of the `String` class.

```
String result = input.replaceAll("\\s*,\\s*", ",");
```

The replacement string can contain group numbers `$n` or names `${name}`. They are replaced with the contents of the corresponding captured groups.

```
String result = "3:45".replaceAll(
   "(\\d{1,2}):(?<minutes>\\d{2})",
   "$1 hours and ${minutes} minutes");
   // Sets result to "3 hours and 45 minutes"
```

You can use `\` to escape `$` and `\` in the replacement string, or you can call the `Matcher.quoteReplacement` convenience method:

```
matcher.replaceAll(Matcher.quoteReplacement(str))
```

If you want to carry out a more complex operation than splicing in group matches, then you can provide a replacement function instead of a replacement string. The function accepts a `MatchResult` and yields a string. For example, here we replace all words with at least four letters with their uppercase version:

```
String result = Pattern.compile("\\pL{4,}")
   .matcher("Mary had a little lamb")
   .replaceAll(m -> m.group().toUpperCase());
   // Yields "MARY had a LITTLE LAMB"
```

The `replaceFirst` method replaces only the first occurrence of the pattern.

1.7.7. Flags

Several *flags* change the behavior of regular expressions. You can specify them when you compile the pattern:

```
Pattern pattern = Pattern.compile(regex,
   Pattern.CASE_INSENSITIVE | Pattern.UNICODE_CHARACT
```

Or you can specify them inside the pattern:

```
String regex = "(?iU:expression)";
```

Here are the flags:

- `Pattern.CASE_INSENSITIVE` or `i`: Match characters independently of the letter case. By default, this flag takes only US ASCII characters into account.
- `Pattern.UNICODE_CASE` or `u`: When used in combination with `CASE_INSENSITIVE`, use Unicode letter case for matching.
- `Pattern.UNICODE_CHARACTER_CLASS` or `U`: Select Unicode character classes instead of POSIX. Implies `UNICODE_CASE`.
- `Pattern.MULTILINE` or `m`: Make `^` and `$` match the beginning and end of a line, not the entire input.

- `Pattern.UNIX_LINES` or `d`: Only `'\n'` is a line terminator when matching `^` and `$` in multiline mode.
- `Pattern.DOTALL` or `s`: Make the `.` symbol match all characters, including line terminators.
- `Pattern.COMMENTS` or `x`: Whitespace and comments (from `#` to the end of a line) are ignored.
- `Pattern.LITERAL`: The pattern is taken literally and must be matched exactly, except possibly for letter case.
- `Pattern.CANON_EQ`: Take canonical equivalence of Unicode characters into account. For example, u followed by ¨ (diaeresis) matches ü.

The last two flags cannot be specified inside a regular expression.

`java.util.regex.Pattern` **1.4**

- `static Pattern compile(String expression)`
- `static Pattern compile(String expression, int flags)`
  compile the regular expression string into a pattern object for fast processing of matches. The `flags` parameter has one or more of the bits `CASE_INSENSITIVE`, `UNICODE_CASE`, `MULTILINE`, `UNIX_LINES`, `DOTALL`, and `CANON_EQ` set.

- `Matcher matcher(CharSequence input)`
  returns a `matcher` object that you can use to locate the matches of the pattern in the input.
- `String[] split(CharSequence input)`
- `String[] split(CharSequence input, int limit)`
- `String[] splitWithDelimiters(CharSequence input, int limit)`
- `Stream<String> splitAsStream(CharSequence input)` **8**
  split the input string into tokens, with the pattern specifying the form of the delimiters. Return an array or stream of tokens. The delimiters are not part of the tokens. The second form has a parameter `limit` denoting the maximum number of strings to produce. If `limit - 1` matching delimiters have been found, then the last entry of the returned array contains the remaining unsplit input. If `limit` is ≤ `0`, then the entire input is split. If `limit` is `0`, then trailing empty strings are not placed in the returned array.
- `Map<String, Integer> namedGroups()` **20**
  yields an immutable map from group names to group indexes.

`java.util.regex.Matcher` **1.4**

- `boolean matches()`
  returns `true` if the input matches the pattern.

- `boolean lookingAt()`
  returns `true` if the beginning of the input matches the pattern.
- `boolean find()`
- `boolean find(int start)`
  attempt to find the next match and return `true` if another match is found.
- `boolean hasMatch()` **20**
  `true` if this matcher is positioned on a match as a result of calling `matches` or `find`.
- `String replaceAll(String replacement)`
- `String replaceFirst(String replacement)`
  return a string obtained from the matcher input by replacing all matches, or the first match, with the replacement string. The replacement string can contain references to pattern groups as `$n`. Use `\$` to include a `$` symbol.
- `static String quoteReplacement(String str)` **5.0**
  quotes all `\` and `$` in `str`.
- `String replaceAll(Function<MatchResult,String> replacer)` **9**
  replaces every match with the result of the `replacer` function applied to the `MatchResult`.
- `Stream<MatchResult> results()` **9**
  yields a stream of all match results.

java.util.regex.MatchResult **5.0**

- `String group()`
- `String group(int group)`
- `String group(String name)` **20**

  yield the matched string or the string matched by the given group.
- `int start()`
- `int end()`
- `int start(int group)`
- `int start(String nane)` **20**
- `int end(int group)`
- `int end(String name)` **20**

  yield the start and end offsets of the matched string or the string matched by the given group.
- `Map<String, Integer> namedGroups()` **20**

  yields an immutable map from group names to group indexes of the underlying pattern.

`java.util.Scanner` **5.0**

- `Stream<MatchResult> findAll(Pattern pattern)` **9**

  yields a stream of all matches of the given pattern in the input produced by this scanner.

You have now seen how to carry out input and output operations in Java, and had an overview of the regular expression package that was a part of the "new I/O" specification. In the next chapter, we turn to the processing of XML data.

1. XML

The preface of the book *Essential XML* by Don Box et al. (Addison-Wesley, 2000) stated only half-jokingly: "The Extensible Markup Language (XML) has replaced Java, Design Patterns, and Object Technology as the software industry's solution to world hunger." This kind of hype is long gone but, as you will see in this chapter, XML is still a very useful technology for describing structured information. XML tools make it easy to process and transform that information. However, XML is not a silver bullet. You need domain-specific standards and code libraries to use it effectively. Moreover, far from making Java obsolete, XML works very well with Java. Since the late 1990s, IBM, Apache, and others have been instrumental in producing high-quality Java libraries for XML processing. Many of these libraries have now been integrated into the Java platform.

This chapter introduces XML and covers the XML features of the Java API. As always, we'll point out, along the way, when using XML is justified—and when you have to take it with a grain of salt and try solving your problems the old-fashioned way: through good design and code.

1.1. Introducing XML

In Chapter 9 of Volume I, you have seen the use of *property files* to describe the configuration of a program. A property file contains a set of name/value pairs, such as

```
fontname=Times Roman
fontsize=12
windowsize=400 200
color=0 50 100
```

You can use the `Properties` class to read in such a file with a single method call. That's a nice feature, but it doesn't really go far enough. In many cases, the information you want to describe has more structure than the property file format can comfortably handle. Consider the `fontname/fontsize` entries in the example. It would be more object-oriented to have a single entry:

```
font=Times Roman 12
```

But then, parsing the font description gets ugly as you have to figure out when the font name ends and the font size starts.

Property files have a single flat hierarchy. You can often see programmers work around that limitation with key names like

```
title.fontname=Helvetica
title.fontsize=36
body.fontname=Times Roman
body.fontsize=12
```

Another shortcoming of the property file format is the requirement that keys must be unique. To store a sequence of values, you need another workaround, such as

```
menu.item.1=Times Roman
menu.item.2=Helvetica
menu.item.3=Goudy Old Style
```

The XML format solves these problems. It can express hierarchical structures and is thus more flexible than the flat table structure of a property file.

An XML file for describing a program configuration might look like this:

```
<config>
   <entry id="title">
      <font>
         <name>Helvetica</name>
         <size>36</size>
      </font>
```

```
    </entry>
    <entry id="body">
       <font>
          <name>Times Roman</name>
          <size>12</size>
       </font>
    </entry>
    <entry id="background">
       <color>
          <red>0</red>
          <green>50</green>
          <blue>100</blue>
       </color>
    </entry>
 </config>
```

The XML format allows you to express the hierarchy and record repeated elements without contortions.

The format of an XML file is straightforward. It looks similar to an HTML file. There is a good reason for that—both XML and HTML are descendants of the venerable Standard Generalized Markup Language (SGML).

SGML has been around since the 1970s for describing the structure of complex documents. It has been used with success in some industries that require ongoing maintenance of massive

documentation—in particular, the aircraft industry. However, SGML is quite complex, so it has never caught on in a big way. Much of that complexity arises because SGML has two conflicting goals. SGML wants to make sure that documents are formed according to the rules for their document type, but it also wants to make data entry easy by allowing shortcuts that reduce typing. XML was designed as a simplified version of SGML for use on the Internet. As is often true, simpler is better, and XML has enjoyed the immediate and enthusiastic reception that has eluded SGML for so long.

Note: You can find a very nice version of the XML standard, with annotations by Tim Bray, at https://www.xml.com/axml/axml.html.

Even though XML and HTML have common roots, there are important differences between the two.

- Unlike HTML, XML is case-sensitive. For example, `<H1>` and `<h1>` are different XML tags.
- In HTML, you can omit end tags, such as `</p>` or `</li>`, if it is clear from the context where a paragraph or list item ends. In XML, you can never omit an end tag.
- In XML, elements that have a single tag without a matching end tag must end in a `/`, as in `<img src="coffeecup.png"/>`. That way, the parser knows not to look for a `</img>` tag.

- In XML, attribute values must be enclosed in quotation marks. In HTML, quotation marks are optional. For example, `<img src="my hamster.png" width=300>` is legal HTML but not legal XML. In XML, you have to use quotation marks: `width="300"`.
- In HTML, you can have attribute names without values, such as `<input type="radio" name="language" value="Java" checked>`. In XML, all attributes must have values, such as `checked="true"` or (ugh) `checked="checked"`.
- There are XML formulations for HTML versions 4 and 5 that are known as XHTML.

1.2. The Structure of an XML Document

An XML document should start with a header such as

```
<?xml version="1.0"?>
```

or

```
<?xml version="1.0" encoding="UTF-8"?>
```

Strictly speaking, a header is optional, but it is highly recommended.

Note: Since SGML was created for processing of real documents, XML files are called *documents* even

though many of them describe data sets that one would not normally call documents.

The header can be followed by a *document type definition* (DTD), such as

```
<!DOCTYPE web-app PUBLIC
   "-//Sun Microsystems, Inc.//DTD Web Application 2.
   "http://java.sun.com/j2ee/dtds/web-app_2_2.dtd">
```

DTDs are an important mechanism to ensure the correctness of a document, but they are not required. We will discuss them later in this chapter.

Finally, the body of the XML document contains the *root element*, which can contain other elements. For example,

```
<?xml version="1.0"?>
<!DOCTYPE config . . .>
<config>
   <entry id="title">
      <font>
         <name>Helvetica</name>
         <size>36</size>
      </font>
```

```
    </entry>
    . . .
</config>
```

An element can contain *child elements*, text, or both. In the preceding example, the `font` element has two child elements, `name` and `size`. The `name` element contains the text `"Helvetica"`.

Tip: It is best to structure your XML documents so that an element contains *either* child elements *or* text. Here's an example of what you should avoid:

```
<font>
   Helvetica
   <size>36</size>
</font>
```

This is called *mixed content* in the XML specification. As you will see later in this chapter, you can simplify parsing if you avoid mixed content.

XML elements can contain attributes, such as

```
<size unit="pt">36</size>
```

There is some disagreement among XML designers about when to use elements and when to use attributes. For example, it would seem easier to describe a font as

```
<font name="Helvetica" size="36"/>
```

compared to

```
<font>
   <name>Helvetica</name>
   <size>36</size>
</font>
```

However, attributes are much less flexible. Suppose you want to add units to the size value. If you use attributes, you will have to add the unit to the attribute value:

```
<font name="Helvetica" size="36 pt"/>
```

Ugh! Now you have to parse the string `"36 pt"`, just the kind of hassle that XML was designed to avoid. Adding an attribute to the `size` element is much cleaner:

```
<font>
   <name>Helvetica</name>
   <size unit="pt">36</size>
</font>
```

A commonly used rule of thumb is that attributes should be used only to modify the interpretation of a value, not to specify values. If you find yourself engaged in a metaphysical discussion about whether a particular setting is a modification of the interpretation of a value or not, just say "no" to attributes and use elements throughout. Many useful XML documents don't use attributes at all.

Note: In HTML, the rule for attribute usage is simple: If it isn't displayed on the web page, it's an attribute. For example, consider the hyperlink

```
<a href="http://java.sun.com">Java Technol
```

The string `Java Technology` is displayed on the web page, but the URL of the link is not a part of the displayed page. However, the rule isn't all that helpful for most XML files because the data in an XML file aren't normally meant to be viewed by humans.

Elements and text are the "bread and butter" of XML documents. Here are a few other markup instructions that you might encounter:

- *Character references* have the form `&#decimalValue;` or `&#xhexValue;`. For example, the é character can be denoted with either of the following:

  ```
  &#233; &#xE9;
  ```

- *Entity references* have the form `&name;`. The entity references

  ```
  &lt; &gt; &amp; &quot; &apos;
  ```

  have predefined meanings: the less-than, greater-than, ampersand, quotation mark, and apostrophe characters. You can define other entity references in a DTD.
- *CDATA sections* are delimited by `<![CDATA[` and `]]>`. They are a special form of character data. You can use them to include strings that contain characters such as `< > &` without having them interpreted as markup, for example:

  ```
  <![CDATA[< & > are my favorite delimiters]]>
  ```

CDATA sections cannot contain the string `]]>`. Use this feature with caution! It is too often used as a back door for smuggling legacy data into XML documents.

- *Processing instructions* are instructions for applications that process XML documents. They are delimited by `<?` and `?>`, for example

```
<?xml-stylesheet href="mystyle.css" type="text/css"
```

Every XML document starts with a processing instruction

```
<?xml version="1.0"?>
```

- *Comments* are delimited by `<!--` and `-->`, for example

```
<!-- This is a comment. -->
```

Comments should not contain the string `--`. Comments should only be information for human readers. They should never contain hidden commands; use processing instructions for commands.

1.3. Parsing an XML Document

To process an XML document, you need to *parse* it. A parser is a program that reads a file, confirms that the file has the correct format, breaks it up into the constituent elements, and lets a programmer access those elements. The Java API supplies two kinds of XML parsers:

- Tree parsers, such as a Document Object Model (DOM) parser, that read an XML document into a tree structure.
- Streaming parsers, such as a Simple API for XML (SAX) parser, that generate events as they read an XML document.

DOM parsers are easier to use for most purposes, so we explain them first. You may consider a streaming parser if you process very long documents whose tree structures would use up a lot of memory, or if you are only interested in a few elements and don't care about their context. For more information, see Section 3.7.

The DOM parser interface is standardized by the World Wide Web Consortium (W3C). The `org.w3c.dom` package contains the definitions of interface types such as `Document` and `Element`. Different suppliers, such as the Apache Organization and IBM, have written DOM parsers whose classes implement these interfaces. The Java API for XML Processing (JAXP) actually makes it possible to plug in any of these parsers. But the JDK also comes with a DOM parser that is derived from the Apache parser.

To read an XML document, you need a `DocumentBuilder` object that you get from a `DocumentBuilderFactory` like this:

```
DocumentBuilderFactory factory = DocumentBuilderFacto
DocumentBuilder builder = factory.newDocumentBuilder(
```

You can now read a document from a file:

```
File f = . . .;
Document doc = builder.parse(f);
```

Alternatively, you can use a URL:

```
URL u = . . .;
Document doc = builder.parse(u.toString());
```

You can even specify an arbitrary input stream:

```
InputStream in = . . .;
Document doc = builder.parse(in);
```

Note: If you use an input stream as an input source, the parser will not be able to locate other files that are referenced relative to the location of the document,

such as a DTD in the same directory. You can install an "entity resolver" to overcome that problem. See https://www.xml.com/pub/a/2004/03/03/catalogs.html and https://https://openjdk.org/jeps/268 for more information.

A `Document` object is an in-memory representation of the tree structure of an XML document. It is composed of objects whose classes implement the `Node` interface and its various subinterfaces. Figure 3.1 shows the inheritance hierarchy of the subinterfaces.



Figure 1.1: The `Node` interface and its subinterfaces

Start analyzing the contents of a document by calling the `getDocumentElement` method. It returns the root element.

```
Element root = doc.getDocumentElement();
```

For example, if you are processing a document

```
<?xml version="1.0"?>
<font>
   . . .
</font>
```

then calling `getDocumentElement` returns the `font` element.

The `getTagName` method returns the tag name of an element. In the preceding example, `root.getTagName()` returns the string `"font"`.

To get an element's children (which may be subelements, text, comments, or other nodes), use the `getChildNodes` method. That method returns a collection of type `NodeList`. That type was standardized before the standard Java collections, so it has a different access protocol. The `item` method gets the item with a given index, and the `getLength` method gives the total count of the items. You can enumerate all children like this:

```
NodeList children = root.getChildNodes();
for (int i = 0; i < children.getLength(); i++)
{
   Node child = children.item(i);
   . . .
}
```

Be careful when analyzing children. Suppose, for example, that you are processing the document

```
<font>
   <name>Helvetica</name>
   <size>36</size>
</font>
```

You would expect the `font` element to have two children, but the parser reports five:

- The whitespace between `<font>` and `<name>`
- The `name` element
- The whitespace between `</name>` and `<size>`
- The `size` element
- The whitespace between `</size>` and `</font>`

Figure 3.2 shows the DOM tree.



Figure 1.2: A simple DOM tree

If you expect only subelements, you can ignore the whitespace:

```
for (int i = 0; i < children.getLength(); i++)
{
   Node child = children.item(i);
   if (child instanceof Element childElement)
   {
      . . .
   }
}
```

Now you look at only two elements, with tag names `name` and `size`.

As you will see in the next section, you can do even better if your document has a DTD. Then the parser knows which elements don't have text nodes as children, and it can suppress the whitespace for you.

When analyzing the `name` and `size` elements, you want to retrieve the text strings that they contain. Those text strings are themselves contained in child nodes of type `Text`. You know that these `Text` nodes are the only children, so you can use the `getFirstChild` method without having to traverse another `NodeList`. Then, use the `getData` method to retrieve the string stored in a `Text` node:

```
for (int i = 0; i < children.getLength(); i++)
{
   Node child = children.item(i);
   if (child instanceof Element childElement)
   {
      var textNode = (Text) childElement.getFirstChil
      String text = textNode.getData().strip();
      if (childElement.getTagName().equals("name"))
         name = text;
      else if (childElement.getTagName().equals("size
         size = Integer.parseInt(text);
   }
}
```

Tip: It is a good idea to call `strip` on the return value of the `getData` method. If the author of an XML file puts the beginning and the ending tags on separate lines, such as

```
<size>
   36
</size>
```

then the parser will include all line breaks and spaces in the text node data. Calling the `strip` method removes the whitespace surrounding the actual data.

You can also get the last child with the `getLastChild` method, and the next sibling of a node with `getNextSibling`. Therefore, another way of traversing a node's children is

```
for (Node childNode = element.getFirstChild();
      childNode != null;
      childNode = childNode.getNextSibling())
{
   . . .
}
```

To enumerate the attributes of a node, call the `getAttributes` method. It returns a `NamedNodeMap` object that contains `Node` objects describing the attributes. You can traverse the nodes in a `NamedNodeMap` the same way as in a `NodeList`. Then, call the `getNodeName` and `getNodeValue` methods to get the attribute names and values.

```
NamedNodeMap attributes = element.getAttributes();
for (int i = 0; i < attributes.getLength(); i++)
{
   Node attribute = attributes.item(i);
   String name = attribute.getNodeName();
   String value = attribute.getNodeValue();
   . . .
}
```

Alternatively, if you know the name of an attribute, you can retrieve the corresponding value directly:

```
String unit = element.getAttribute("unit");
```

You have now seen how to analyze a DOM tree. The program in Listing 3.1 puts these techniques to work by converting an XML document to JSON format.

The tree display clearly shows how child elements are surrounded by text containing whitespace and comments. You can clearly see the newline and return characters as `\n`.

You don't have to be familiar with JSON to understand how the program works with the DOM tree. Simply observe the following:

- We use a `DocumentBuilder` to read a `Document` from a file.
- For each element, we print the tag name, attributes, and elements.
- For character data, we produce a string with the data. If the data comes from a comment, we add a `"Comment: "` prefix.

Listing 1.1 dom/JSONConverter.java

```
1  package dom;
2
3  import java.io.*;
4  import java.util.*;
5
6  import javax.xml.parsers.*;
7
8  import org.w3c.dom.*;
9  import org.xml.sax.*;
10
11 /**
12  * This program displays an XML document as a t
```

```
 * @version 1.21 2021-05-30
 * @author Cay Horstmann
 */
public class JSONConverter
{
   public static void main(String[] args)
         throws SAXException, IOException, Pars
   {
      String filename;
      if (args.length == 0)
      {
         try (var in = new Scanner(System.in))
         {
            System.out.print("Input file: ");
            filename = in.nextLine();
         }
      }
      else
         filename = args[0];
      DocumentBuilderFactory factory = Document
      DocumentBuilder builder = factory.newDocu

      Document doc = builder.parse(filename);
      Element root = doc.getDocumentElement();
      System.out.println(convert(root, 0));
   }

   public static StringBuilder convert(Node nod
```

```
41    {
42       if (node instanceof Element elem)
43       {
44          return elementObject(elem, level);
45       }
46       else if (node instanceof CharacterData cd
47       {
48          return characterString(cd, level);
49       }
50       else
51       {
52          return pad(new StringBuilder(), level)
53             jsonEscape(node.getClass().getName(
54       }
55    }
56
57    private static Map<Character, String> replac
58       '\n', "\\n", '\r', "\\r", '\t', "\\t", '"
59
60    private static StringBuilder jsonEscape(Stri
61    {
62       var result = new StringBuilder("\"");
63       for (int i = 0; i < str.length(); i++)
64       {
65          char ch = str.charAt(i);
66          String replacement = replacements.get(
67          if (replacement == null) result.append
68          else result.append(replacement);
```

```
69          }
70          result.append("\"");
71          return result;
72       }
73
74       private static StringBuilder characterString
75       {
76          var result = new StringBuilder();
77          StringBuilder data = jsonEscape(node.getD
78          if (node instanceof Comment) data.insert(
79          pad(result, level).append(data);
80          return result;
81       }
82
83       private static StringBuilder elementObject(E
84       {
85          var result = new StringBuilder();
86          pad(result, level).append("{\n");
87          pad(result, level + 1).append("\"name\":
88          result.append(jsonEscape(elem.getTagName(
89          NamedNodeMap attrs = elem.getAttributes()
90          if (attrs.getLength() > 0)
91          {
92             pad(result.append(",\n"), level + 1).a
93             result.append(attributeObject(attrs));
94          }
95          NodeList children = elem.getChildNodes();
96          if (children.getLength() > 0)
```

```
97          {
98             pad(result.append(",\n"), level + 1).a
99             for (int i = 0; i < children.getLength
100            {
101               if (i > 0) result.append(",\n");
102               result.append(convert(children.item
103            }
104            result.append("\n");
105            pad(result, level + 1).append("]\n");
106         }
107         pad(result, level).append("}");
108         return result;
109      }
110
111      private static StringBuilder pad(StringBuild
112      {
113         for (int i = 0; i < level; i++) builder.a
114         return builder;
115      }
116
117      private static StringBuilder attributeObject
118      {
119         var result = new StringBuilder("{");
120         for (int i = 0; i < attrs.getLength(); i+
121         {
122            if (i > 0) result.append(", ");
123            result.append(jsonEscape(attrs.item(i)
124            result.append(": ");
```

```
125             result.append(jsonEscape(attrs.item(i)
126          }
127          result.append("}");
128          return result;
129       }
130    }
```

`javax.xml.parsers.DocumentBuilderFactory` **1.4**

- `static DocumentBuilderFactory newInstance()`
  returns an instance of the `DocumentBuilderFactory` class.
- `DocumentBuilder newDocumentBuilder()`
  returns an instance of the `DocumentBuilder` class.

`javax.xml.parsers.DocumentBuilder` **1.4**

- `Document parse(File f)`
- `Document parse(String url)`
- `Document parse(InputStream in)`
  parse an XML document from the given file, URL, or input stream and return the parsed document.

org.w3c.dom.Document **1.4**

- `Element getDocumentElement()`
  returns the root element of the document.

org.w3c.dom.Element **1.4**

- `String getTagName()`
  returns the name of the element.
- `String getAttribute(String name)`
  returns the value of the attribute with the given name, or an empty string if there is no such attribute.

org.w3c.dom.Node **1.4**

- `NodeList getChildNodes()`
  returns a node list that contains all children of this node.
- `Node getFirstChild()`
- `Node getLastChild()`
  get the first or last child node of this node, or `null` if this node has no children.
- `Node getNextSibling()`
- `Node getPreviousSibling()`
  get the next or previous sibling of this node, or `null` if this node has no siblings.
- `Node getParentNode()`
  gets the parent of this node, or `null` if this node is the document node.

- `NamedNodeMap getAttributes()`
  returns a node map that contains `Attr` nodes that describe all attributes of this node.
- `String getNodeName()`
  returns the name of this node. If the node is an `Attr` node, the name is the attribute name.
- `String getNodeValue()`
  returns the value of this node. If the node is an `Attr` node, the value is the attribute value.

org.w3c.dom.CharacterData **1.4**

- `String getData()`
  returns the text stored in this node.

org.w3c.dom.NodeList **1.4**

- `int getLength()`
  returns the number of nodes in this list.
- `Node item(int index)`
  returns the node with the given index. The index is between `0` and `getLength()` – 1.

org.w3c.dom.NamedNodeMap **1.4**

- `int getLength()`
  returns the number of nodes in this map.
- `Node item(int index)`
  returns the node with the given index. The index is between `0` and `getLength()` – 1.

1.4. Validating XML Documents

In the previous section, you saw how to traverse the tree structure of a DOM document. However, with that approach, you'll have to do quite a bit of tedious programming and error checking. It's not just having to deal with whitespace between elements; you will also need to check whether the document contains the nodes that you expect. For example, suppose you are reading this element:

```
<font>
   <name>Helvetica</name>
   <size>36</size>
</font>
```

You get the first child. Oops . . . it is a text node containing whitespace `"\n "`. You skip text nodes and find the first element node. Then, you need to check that its tag name is `"name"` and that

it has one child node of type `Text`. You move on to the next nonwhitespace child and make the same check. What if the author of the document switched the order of the children or added another child element? It is tedious to code all this error checking—but reckless to skip the checks.

Fortunately, one of the major benefits of an XML parser is that it can automatically verify that a document has the correct structure. That makes parsing much simpler. For example, if you know that the `font` fragment has passed validation, you can simply get the two grandchildren, cast them as `Text` nodes, and get the text data, without any further checking.

To specify the document structure, you can supply a DTD or an XML Schema definition. A DTD or schema contains rules that explain how a document should be formed, by specifying the legal child elements and attributes for each element. For example, a DTD might contain a rule:

```
<!ELEMENT font (name,size)>
```

This rule expresses that a `font` element must always have two children, which are `name` and `size` elements. The XML Schema language expresses the same constraint as

```
<xsd:element name="font">
   <xsd:sequence>
      <xsd:element name="name" type="xsd:string"/>
      <xsd:element name="size" type="xsd:int"/>
   </xsd:sequence>
</xsd:element>
```

XML Schema can express more sophisticated validation conditions (such as the fact that the `size` element must contain an integer) than can DTDs. Unlike the DTD syntax, the XML Schema syntax itself uses XML, which is a benefit if you need to process schema files.

In the next section, we will discuss DTDs in detail, then briefly cover the basics of XML Schema support. Finally, we will present a complete application that demonstrates how validation simplifies XML programming.

1.4.1. Document Type Definitions

There are several methods for supplying a DTD. You can include a DTD in an XML document like this:

```
<?xml version="1.0"?>
<!DOCTYPE config [
   <!ELEMENT config . . .>
   more rules
```

```
   . . .
]>
<config>
   . . .
</config>
```

As you can see, the rules are included inside a `DOCTYPE` declaration, in a block delimited by `[. . .]`. The document type must match the name of the root element, such as `config` in our example.

Supplying a DTD inside an XML document is somewhat uncommon because DTDs can grow lengthy. It makes more sense to store the DTD externally. The `SYSTEM` declaration can be used for that purpose. Specify a URL that contains the DTD, for example:

```
<!DOCTYPE config SYSTEM "config.dtd">
```

or

```
<!DOCTYPE config SYSTEM "http://myserver.com/config.d
```

Caution: If you use a relative URL for the DTD (such as `"config.dtd"`), give the parser a `File` or `URL` object, not an

`InputStream`. If you must parse from an input stream, supply an entity resolver (see the following note).

The mechanism for identifying well-known DTDs has its origin in SGML. Here is an example:

```
<!DOCTYPE web-app
   PUBLIC "-//Sun Microsystems, Inc.//DTD Web Applicat
   "http://java.sun.com/j2ee/dtds/web-app_2_2.dtd">
```

If an XML processor knows how to locate the DTD with the public identifier, it need not go to the URL.

Note: The system identifier URL of a DTD may not actually be working, or be purposefully slowed down. An example for the latter is the system identifier of the XHTML 1.0 Strict DTD, `http://www.w3.org/TR/xhtml1/DTD/xhtml1-strict.dtd`. If you parse an XHTML file, it may take a minute or two for the DTD to be served.

The remedy is to use an *entity resolver* that maps public identifiers to local files. You provide an object of a class that implements the `EntityResolver` interface and provides a `resolveEntity` method.

XML catalogs are a convenient mechanism for resolving entities. Provide one or more *catalog files* of the form

```
<?xml version="1.0"?>
<!DOCTYPE catalog PUBLIC "-//OASIS//DTD XMI
      "http://www.oasis-open.org/committees
<catalog xmlns="urn:oasis:names:tc:entity:x
   <public publicId=". . ." uri=". . ."/>
   . . .
</catalog>
```

Then construct and install a resolver like this:

```
builder.setEntityResolver(CatalogManager.ca
   CatalogFeatures.defaults(),
   Path.of("catalog.xml").toAbsolutePath()
```

See Listing 3.6 for a complete example.

Instead of setting the catalog file locations in your program, you can specify them on the command line with the `javax.xml.catalog.files` system property. Provide absolute `file` URLs separated by semicolons.

Now that you have seen how the parser locates the DTD, let us consider the various kinds of rules.

The `ELEMENT` rule specifies what children an element can have. Use a regular expression, made up of the components shown in #ch02table01.

Table 1.1: Rules for Element Content

Rule	Meaning
$E*$	0 or more occurrences of E
$E+$	1 or more occurrences of E
$E?$	0 or 1 occurrences of E
$E_1 \mid E_2 \mid \ldots \mid E_n$	One of E_1, E_2, . . ., E_n
E_1, E_2, . . ., E_n	E_1 followed by E_2, . . ., E_n
`#PCDATA`	Text
$(\#PCDATA \mid E_1 \mid E_2 \mid \ldots \mid E_n)*$	0 or more occurrences of text and E_1, E_2, . . ., E_n in any order (mixed

Rule	Meaning
	content)
`ANY`	Any children allowed
`EMPTY`	No children allowed

Here are several simple but typical examples. The following rule states that a `menu` element contains 0 or more `item` elements:

```
<!ELEMENT menu (item)*>
```

This set of rules states that a font is described by a `name` followed by a `size`, each of which contain text:

```
<!ELEMENT font (name,size)>
<!ELEMENT name (#PCDATA)>
<!ELEMENT size (#PCDATA)>
```

The abbreviation `PCDATA` denotes *parsed character data*. It is "parsed" because the parser interprets the text string, looking for `<` characters that denote the start of a new tag, or `&` characters that denote the start of an entity.

An element specification can contain regular expressions that are nested and complex. For example, here is a rule that describes the makeup of a chapter in a book:

```
<!ELEMENT chapter (intro,(heading,(para|image|table|n
```

Each chapter starts with an introduction, which is followed by one or more sections consisting of a heading and one or more paragraphs, images, tables, or notes.

However, in one common case you can't define the rules to be as flexible as you might like. Whenever an element can contain text, there are only two valid cases. Either the element contains nothing but text, such as

```
<!ELEMENT name (#PCDATA)>
```

or the element contains *any combination of text and tags in any order*, such as

```
<!ELEMENT para (#PCDATA|em|strong|code)*>
```

It is not legal to specify any other types of rules that contain `#PCDATA`. For example, the following is illegal:

```
<!ELEMENT captionedImage (image,#PCDATA)>
```

You have to rewrite such a rule, either by introducing another `caption` element or by allowing any combination of `image` elements and text.

This restriction simplifies the job of the XML parser when parsing *mixed content* (a mixture of tags and text). Since you lose some control by allowing mixed content, it is best to design DTDs so that all elements contain either other elements or nothing but text.

Note: Actually, it isn't quite true that you can specify arbitrary regular expressions of elements in a DTD rule. An XML parser may reject certain complex rule sets that lead to nondeterministic parsing. For example, a regular expression `((x,y)|(x,z))` is nondeterministic. When the parser sees `x`, it doesn't know which of the two alternatives to take. This expression can be rewritten in a deterministic form as `(x,(y|z))`. However, some expressions can't be reformulated, such as `((x,y)*|x?)`. The parser in the Java XML API gives no warnings when presented with an ambiguous DTD; it simply picks the first matching alternative when parsing, which causes it to reject some correct inputs. The parser is well within its rights

to do so because the XML standard allows a parser to assume that the DTD is unambiguous.

You can also specify rules to describe the legal attributes of elements. The general syntax is

```
<!ATTLIST element attribute type default>
```

#ch02table02 shows the legal attribute types, and #ch02table03 shows the syntax for the defaults.

Table 1.2: Attribute Types

Type	Meaning
`CDATA`	Any character string
$(A_1\|A_2\| \ldots \|A_n)$	One of the string attributes A_1, A_2, . . ., A_n
`NMTOKEN`, `NMTOKENS`	One or more name tokens
`ID`	A unique ID

Type	Meaning
`IDREF`, `IDREFS`	One or more references to a unique ID
`ENTITY`, `ENTITIES`	One or more unparsed entities

Table 1.3: Attribute Defaults

Default	Meaning
`#REQUIRED`	Attribute is required.
`#IMPLIED`	Attribute is optional.
A	Attribute is optional; the parser reports it to be *A* if it is not specified.
`#FIXED` *A*	The attribute must either be unspecified or *A*; in either case, the parser reports it to be *A.*

Here are two typical attribute specifications:

```
<!ATTLIST font style (plain|bold|italic|bold-italic)
```

```
<!ATTLIST size unit CDATA #IMPLIED>
```

The first specification describes the `style` attribute of a `font` element. There are four legal attribute values, and the default value is `plain`. The second specification expresses that the `unit` attribute of the `size` element can contain any character data sequence.

Note: It is generally recommended to use elements, not attributes, to describe data. Thus, the font style should be a separate element, such as `<font><style>plain</style>. . .</font>`. However, attributes have an undeniable advantage for enumerated types because the parser can verify that the values are legal. For example, if the font style is an attribute, the parser checks that it is one of the four allowed values, and supplies a default if no value was given.

The handling of a `CDATA` attribute value is subtly different from the processing of `#PCDATA` that you have seen before, and quite unrelated to the `<![CDATA[. . .]]>` sections. The attribute value is first *normalized*—that is, the parser processes character and entity

references (such as `é` or `<`) and replaces whitespace with spaces.

An `NMTOKEN` (or name token) is similar to `CDATA`, but most nonalphanumeric characters and internal whitespace are disallowed, and the parser removes leading and trailing whitespace. `NMTOKENS` is a whitespace-separated list of name tokens.

The `ID` construct is quite useful. An `ID` is a name token that must be unique in the document—the parser checks the uniqueness. You will see an application in the next sample program. An `IDREF` is a reference to an ID that exists in the same document, which the parser also checks. `IDREFS` is a whitespace-separated list of ID references.

An `ENTITY` attribute value refers to an "unparsed external entity." That is a holdover from SGML that is rarely used in practice. The annotated XML specification at https://www.xml.com/axml/axml.html has an example.

A DTD can also define *entities*, or abbreviations that are replaced during parsing. You can find a good example for the use of entities in the user interface descriptions of the Firefox browser. Those descriptions are formatted in XML and contain entity definitions such as

```
<!ENTITY back.label "Back">
```

Elsewhere, text can contain an entity reference, for example:

```
<menuitem label="&back.label;"/>
```

The parser replaces the entity reference with the replacement string. To internationalize the application, only the string in the entity definition needs to be changed. Other uses of entities are more complex and less common; look at the XML specification for details.

This concludes the introduction to DTDs. Now that you have seen how to use DTDs, you can configure your parser to take advantage of them.

First, tell the document builder factory to turn on validation:

```
factory.setValidating(true);
```

All builders produced by this factory validate their input against a DTD. The most useful benefit of validation is ignoring whitespace in element content. For example, consider the XML fragment

```
<font>
   <name>Helvetica</name>
   <size>36</size>
</font>
```

A nonvalidating parser reports the whitespace between the `font`, `name`, and `size` elements because it has no way of knowing if the children of `font` are

```
(name,size)
(#PCDATA,name,size)*
```

or perhaps

```
ANY
```

Once the DTD specifies that the children are `(name,size)`, the parser knows that the whitespace between them is not text. Call

```
factory.setIgnoringElementContentWhitespace(true);
```

and the builder will stop reporting the whitespace in text nodes. That means you can now *rely on* the fact that a `font` node has two children. You no longer need to program a tedious loop:

```
for (int i = 0; i < children.getLength(); i++)
{
   Node child = children.item(i);
   if (child instanceof Element childElement)
   {
      if (childElement.getTagName().equals("name")) .
      else if (childElement.getTagName().equals("size
   }
}
```

Instead, you can simply access the first and second child:

```
var nameElement = (Element) children.item(0);
var sizeElement = (Element) children.item(1);
```

That is why DTDs are so useful. You don't overload your program with rule-checking code—the parser has already done that work by the time you get the document.

When the parser reports an error, your application will want to do something about it—log it, show it to the user, or throw an exception to abandon the parsing. Therefore, you should install an error handler whenever you use validation. Supply an object that implements the `ErrorHandler` interface. That interface has three methods:

```
void warning(SAXParseException e)
void error(SAXParseException e)
void fatalError(SAXParseException e)
```

Install the error handler with the `setErrorHandler` method of the `DocumentBuilder` class:

```
builder.setErrorHandler(handler);
```

`javax.xml.parsers.DocumentBuilder` **1.4**

- `void setEntityResolver(EntityResolver resolver)`
  sets the resolver to locate entities that are referenced in the XML documents being parsed.
- `void setErrorHandler(ErrorHandler handler)`
  sets the handler to report errors and warnings that occur during parsing.

org.xml.sax.EntityResolver **1.4**

- `public InputSource resolveEntity(String publicID, String systemID)`
  returns an input source that contains the data referenced by the given ID(s), or `null` to indicate that this resolver doesn't know

how to resolve the particular name. The `publicID` parameter may be `null` if no public ID was supplied.

`org.xml.sax.InputSource` **1.4**

- `InputSource(InputStream in)`
- `InputSource(Reader in)`
- `InputSource(String systemID)`

  construct an input source from a stream, reader, or system ID (usually a relative or absolute URL).

org.xml.sax.ErrorHandler **1.4**

- `void fatalError(SAXParseException e)`
- `void error(SAXParseException e)`
- `void warning(SAXParseException e)`

  Override these methods to provide handlers for fatal errors, nonfatal errors, and warnings.

`org.xml.sax.SAXParseException` **1.4**

- `int getLineNumber()`
- `int getColumnNumber()`

  return the line and column numbers of the end of the processed input that caused the exception.

`javax.xml.catalog.CatalogManager` 9

- `static CatalogResolver catalogResolver(CatalogFeatures features, URI... uris)`
  produces a resolver that uses the catalog files located at the provided URIs. This class implements `EntityResolver` as well as the resolver classes used by StAX, schema validation, and XSL transforms.

`javax.xml.catalog.CatalogFeatures` 9

- `static CatalogFeatures defaults()`
  yields an instance with default settings.

`javax.xml.parsers.DocumentBuilderFactory` 1.4

- `boolean isValidating()`
- `void setValidating(boolean value)`
  get or set the `validating` property of the factory. If set to `true`, the parsers that this factory generates validate their input.

- `boolean isIgnoringElementContentWhitespace()`
- `void setIgnoringElementContentWhitespace(boolean value)`
  get or set the `ignoringElementContentWhitespace` property of the factory. If set to `true`, the parsers that this factory generates ignore whitespace between element nodes that don't have mixed content (i.e., a mixture of elements and `#PCDATA`).

1.4.2. XML Schema

XML Schema is quite a bit more complex than the DTD syntax, so we will only cover the basics. For more information, we recommend the tutorial at https://www.w3.org/TR/xmlschema-0.

To reference a schema file in a document, add attributes to the root element, for example:

```
<?xml version="1.0"?>
<config xmlns:xsi="http://www.w3.org/2001/XMLSchema-i
      xsi:noNamespaceSchemaLocation="config.xsd">
   . . .
</config>
```

This declaration states that the schema file `config.xsd` should be used to validate the document. If your document uses namespaces, the syntax is a bit more complex—see the XML Schema tutorial for

details. (The prefix `xsi` is a *namespace alias*; see Section 3.6 for more information.)

A schema defines a *type* for each element and attribute. A *simple type* is a string, perhaps with restrictions on its contents. Everything else is a *complex* type. An element with a simple type can have no attributes and no child elements. Otherwise, it must have a complex type. Conversely, attributes always have a simple type.

Some simple types are built into XML Schema, including

```
xsd:string
xsd:int
xsd:boolean
```

Note: We use the prefix `xsd:` to denote the XML Schema Definition namespace. Some authors use the prefix `xs:` instead.

You can define your own simple types. For example, here is an enumerated type:

```
<xsd:simpleType name="StyleType">
   <xsd:restriction base="xsd:string">
      <xsd:enumeration value="PLAIN" />
```

```
      <xsd:enumeration value="BOLD" />
      <xsd:enumeration value="ITALIC" />
      <xsd:enumeration value="BOLD_ITALIC" />
   </xsd:restriction>
</xsd:simpleType>
```

When you define an element, you specify its type:

```
<xsd:element name="name" type="xsd:string"/>
<xsd:element name="size" type="xsd:int"/>
<xsd:element name="style" type="StyleType"/>
```

The type constrains the element content. For example, the elements

```
<size>10</size>
<style>PLAIN</style>
```

will validate correctly, but the elements

```
<size>default</size>
<style>SLANTED</style>
```

will be rejected by the parser.

You can compose types into complex types, for example:

```
<xsd:complexType name="FontType">
   <xsd:sequence>
      <xsd:element ref="name"/>
      <xsd:element ref="size"/>
      <xsd:element ref="style"/>
   </xsd:sequence>
</xsd:complexType>
```

A `FontType` is a sequence of `name`, `size`, and `style` elements. In this type definition, we use the `ref` attribute and refer to definitions that are located elsewhere in the schema. You can also nest definitions, like this:

```
<xsd:complexType name="FontType">
   <xsd:sequence>
      <xsd:element name="name" type="xsd:string"/>
      <xsd:element name="size" type="xsd:int"/>
      <xsd:element name="style">
         <xsd:simpleType>
            <xsd:restriction base="xsd:string">
               <xsd:enumeration value="PLAIN" />
               <xsd:enumeration value="BOLD" />
               <xsd:enumeration value="ITALIC" />
               <xsd:enumeration value="BOLD_ITALIC" /
            </xsd:restriction>
         </xsd:simpleType>
```

```
        </xsd:element>
     </xsd:sequence>
  </xsd:complexType>
```

Note the *anonymous type definition* of the `style` element.

The `xsd:sequence` construct is the equivalent of the concatenation notation in DTDs. The `xsd:choice` construct is the equivalent of the `|` operator. For example,

```
  <xsd:complexType name="contactinfo">
     <xsd:choice>
        <xsd:element ref="email"/>
        <xsd:element ref="phone"/>
     </xsd:choice>
  </xsd:complexType>
```

This is the equivalent of the DTD type `email|phone`.

To allow repeated elements, use the `minoccurs` and `maxoccurs` attributes. For example, the equivalent of the DTD type `item*` is

```
  <xsd:element name="item" type=". . ." minoccurs="0" ma
```

To specify attributes, add `xsd:attribute` elements to `complexType` definitions:

```
<xsd:element name="size">
   <xsd:complexType>
      . . .
      <xsd:attribute name="unit" type="xsd:string" us
   </xsd:complexType>
</xsd:element>
```

This is the equivalent of the DTD statement

```
<!ATTLIST size unit CDATA #IMPLIED "cm">
```

Enclose element and type definitions of your schema inside an `xsd:schema` element:

```
<xsd:schema xmlns:xsd="http://www.w3.org/2001/XMLSche
   . . .
</xsd:schema>
```

Parsing an XML file with a schema is similar to parsing a file with a DTD, but with two differences:

1. You need to turn on support for namespaces, even if you don't use them in your XML files.

```
factory.setNamespaceAware(true);
```

2. You need to prepare the factory for handling schemas, with the following magic incantation:

```
final String JAXP_SCHEMA_LANGUAGE =
      "http://java.sun.com/xml/jaxp/properties/sche
final String W3C_XML_SCHEMA = "http://www.w3.org/20
factory.setAttribute(JAXP_SCHEMA_LANGUAGE, W3C_XML_
```

1.4.3. A Practical Example

In this section, we work through a practical example that shows the use of XML in a realistic setting.

Suppose an application needs configuration data that specifies arbitrary objects, not just text strings. We provide two mechanisms for instantiating the object: with a constructor, and with a factory method. Here is how to make a `Color` object using a constructor:

```
<construct class="java.awt.Color">
   <int>55</int>
   <int>200</int>
   <int>100</int>
</construct>
```

Here is an example with a factory method:

```
<factory class="java.nio.file.Path" method="of">
   <string>logging.properties</string>
</factory>
```

If the factory method name is omitted, it defaults to `getInstance`.

As you can see, there are elements for describing strings and integers. We also support the `boolean` type, and other primitive types can be added in the same way.

Just to show off the syntax, there is a second mechanism for primitive types:

```
<value type="int">30</value>
```

A configuration is a sequence of entries. Each entry has an ID and an object:

```
<config>
   <entry id="background">
      <construct class="java.awt.Color">
         <value type="int">55</value>
         <value type="int">200</value>
         <value type="int">100</value>
      </construct>
   </entry>
   . . .
</config>
```

The parser checks that IDs are unique.

The program in Listing 3.2 shows how to parse a configuration file. A sample configuration is defined in Listing 3.3.

The program uses the schema instead of the DTD if you choose a file that contains the string `-schema`.

The DTD, shown in Listing 3.4, is straightforward.

Listing 3.5 contains the equivalent schema. In the schema, we can provide additional checking: an `int` or `boolean` element can only contain integer or boolean content. Note the use of the `xsd:group` construct to define parts of complex types that are used repeatedly.

This example is a typical use of XML. The XML format is robust enough to express complex relationships. The XML parser adds value by taking over the routine job of validity checking and supplying defaults.

Listing 1.2 read/XMLReadTest.java

```
1  package read;
2
3  import java.io.*;
4  import java.lang.reflect.*;
5  import java.util.*;
6
7  import javax.xml.parsers.*;
8
9  import org.w3c.dom.*;
10 import org.xml.sax.*;
11
12 /**
13  * This program shows how to use an XML file to
14  * @version 1.0 2018-04-03
15  * @author Cay Horstmann
16  */
17 public class XMLReadTest
18 {
19    public static void main(String[] args) throw
20          SAXException, IOException, ReflectiveO
```

```
21    {
22       String filename;
23       if (args.length == 0)
24       {
25          try (var in = new Scanner(System.in))
26          {
27             System.out.print("Input file: ");
28             filename = in.nextLine();
29          }
30       }
31       else
32          filename = args[0];
33
34       DocumentBuilderFactory factory = Document
35       factory.setValidating(true);
36
37       if (filename.contains("-schema"))
38       {
39          factory.setNamespaceAware(true);
40          final String JAXP_SCHEMA_LANGUAGE =
41                "http://java.sun.com/xml/jaxp/pr
42          final String W3C_XML_SCHEMA = "http://
43          factory.setAttribute(JAXP_SCHEMA_LANGU
44       }
45
46       factory.setIgnoringElementContentWhitespa
47
48       DocumentBuilder builder = factory.newDocu
```

```
49
50          builder.setErrorHandler(new ErrorHandler(
51             {
52                public void warning(SAXParseExcepti
53                {
54                   System.err.println("Warning: " +
55                }
56
57                public void error(SAXParseException
58                {
59                   System.err.println("Error: " + e
60                   System.exit(0);
61                }
62
63                public void fatalError(SAXParseExce
64                {
65                   System.err.println("Fatal error:
66                   System.exit(0);
67                }
68             });
69
70          Document doc = builder.parse(filename);
71          Map<String, Object> config = parseConfig(
72          System.out.println(config);
73       }
74
75       private static Map<String, Object> parseConf
76             throws ReflectiveOperationException
```

```
77      {
78         var result = new HashMap<String, Object>(
79         NodeList children = e.getChildNodes();
80         for (int i = 0; i < children.getLength();
81         {
82            var child = (Element) children.item(i)
83            String name = child.getAttribute("id")
84            Object value = parseObject((Element) c
85            result.put(name, value);
86         }
87         return result;
88      }
89
90      private static Object parseObject(Element e)
91            throws ReflectiveOperationException
92      {
93         String tagName = e.getTagName();
94         if (tagName.equals("factory")) return par
95         else if (tagName.equals("construct")) ret
96         else
97         {
98            String childData = ((CharacterData) e.
99            if (tagName.equals("int"))
100               return Integer.valueOf(childData);
101           else if (tagName.equals("boolean"))
102              return Boolean.valueOf(childData);
103           else
104              return childData;
```

```
105         }
106     }
107
108     private static Object parseFactory(Element e
109             throws ReflectiveOperationException
110     {
111         String className = e.getAttribute("class"
112         String methodName = e.getAttribute("metho
113         Object[] args = parseArgs(e.getChildNodes
114         Class<?>[] parameterTypes = getParameterT
115         Method method = Class.forName(className).
116         return method.invoke(null, args);
117     }
118
119     private static Object parseConstruct(Element
120             throws ReflectiveOperationException
121     {
122         String className = e.getAttribute("class"
123         Object[] args = parseArgs(e.getChildNodes
124         Class<?>[] parameterTypes = getParameterT
125         Constructor<?> constructor = Class.forNam
126         return constructor.newInstance(args);
127     }
128
129     private static Object[] parseArgs(NodeList e
130             throws ReflectiveOperationException
131     {
132         var result = new Object[elements.getLengt
```

```
133         for (int i = 0; i < result.length; i++)
134            result[i] = parseObject((Element) elem
135         return result;
136      }
137
138      private static Map<Class<?>, Class<?>> toPri
139            Integer.class, int.class,
140            Boolean.class, boolean.class);
141
142      private static Class<?>[] getParameterTypes(
143      {
144         var result = new Class<?>[args.length];
145         for (int i = 0; i < result.length; i++)
146         {
147            Class<?> cl = args[i].getClass();
148            result[i] = toPrimitive.get(cl);
149            if (result[i] == null) result[i] = cl;
150         }
151         return result;
152      }
153   }
```

Listing 1.3 read/config.xml

```
1  <?xml version="1.0"?>
2  <!DOCTYPE config SYSTEM "config.dtd">
3  <config>
4    <entry id="background">
```

```
    <construct class="java.awt.Color">
      <int>55</int>
      <int>200</int>
      <int>100</int>
    </construct>
  </entry>
  <entry id="currency">
    <factory class="java.util.Currency">
      <string>USD</string>
    </factory>
  </entry>
</config>
```

Listing 1.4 read/config.dtd

```
<!ELEMENT config (entry)*>

<!ELEMENT entry (string|int|boolean|construct|f
<!ATTLIST entry id ID #IMPLIED>

<!ELEMENT construct (string|int|boolean|constru
<!ATTLIST construct class CDATA #IMPLIED>

<!ELEMENT factory (string|int|boolean|construct
<!ATTLIST factory class CDATA #IMPLIED>
<!ATTLIST factory method CDATA "getInstance">

```

```
<!ELEMENT string (#PCDATA)>
<!ELEMENT int (#PCDATA)>
<!ELEMENT boolean (#PCDATA)>
```

Listing 1.5 read/config.xsd

```
<xsd:schema xmlns:xsd="http://www.w3.org/2001/X
   <xsd:element name="config">
      <xsd:complexType>
         <xsd:sequence>
            <xsd:element name="entry" minOccurs
               <xsd:complexType>
                  <xsd:group ref="Object"/>
                  <xsd:attribute name="id" type
               </xsd:complexType>
            </xsd:element>
         </xsd:sequence>
      </xsd:complexType>
   </xsd:element>

   <xsd:element name="construct">
      <xsd:complexType>
         <xsd:group ref="Arguments"/>
         <xsd:attribute name="class" type="xsd:
      </xsd:complexType>
   </xsd:element>

   <xsd:element name="factory">
```

```
23        <xsd:complexType>
24           <xsd:group ref="Arguments"/>
25           <xsd:attribute name="class" type="xsd:
26           <xsd:attribute name="method" type="xsd
27        </xsd:complexType>
28     </xsd:element>
29
30     <xsd:group name="Object">
31        <xsd:choice>
32           <xsd:element ref="construct"/>
33           <xsd:element ref="factory"/>
34           <xsd:element name="string" type="xsd:s
35           <xsd:element name="int" type="xsd:int"
36           <xsd:element name="boolean" type="xsd:
37        </xsd:choice>
38     </xsd:group>
39
40     <xsd:group name="Arguments">
41        <xsd:sequence>
42           <xsd:group ref="Object" minOccurs="0"
43        </xsd:sequence>
44     </xsd:group>
45  </xsd:schema>
```

1.5. Locating Information with XPath

If you want to locate a specific piece of information in an XML document, it can be a bit of a hassle to navigate the nodes of the

DOM tree. The XPath language makes it simple to access tree nodes. For example, suppose you have this XHTML document:

```
<html>
   <head>
      . . .
      <title>. . .</title>
      . . .
   </head>
   . . .
</html>
```

You can get the title text by evaluating the XPath expression

```
/html/head/title/text()
```

That's a lot simpler than the plain DOM approach:

1. Get the document root.
2. Get the first child and cast is as an `Element`.
3. Locate the `title` element among its children.
4. Get its first child and cast it as a `CharacterData` node.
5. Get its data.

An XPath can describe *a set of nodes* in an XML document. For example, the XPath

```
/html/body/form
```

describes the set of all `form` elements that are children of the `body` element in an XHTML file. You can select a particular element with the `[]` operator:

```
/html/body/form[1]
```

is the first form. (The index values start at 1.)

Use the `@` operator to get attribute values. The XPath expression

```
/html/body/form[1]/@action
```

describes the `action` attribute of the first form. The XPath expression

```
/html/body/form/@action
```

describes all `action` attribute nodes of all `form` elements that are children of the `body` element.

There are a number of useful XPath functions. For example,

```
count(/html/body/form)
```

returns the number of `form` children of the `body` element. There are many more elaborate XPath expressions; see the specification at https://www.w3c.org/TR/xpath or the online tutorial at https://www.zvon.org/xxl/XPathTutorial/General/examples.html.

To evaluate XPath expressions, first create an `XPath` object from an `XPathFactory`:

```
XPathFactory xpfactory = XPathFactory.newInstance();
path = xpfactory.newXPath();
```

Then, call the `evaluate` method to evaluate XPath expressions:

```
String username = path.evaluate("/html/head/title/tex
```

You can use the same `XPath` object to evaluate multiple expressions.

This form of the `evaluate` method returns a string result. It is suitable for retrieving text, such as the text child of the `title` element in the preceding example. If an XPath expression yields multiple nodes, make a call such as the following:

```
XPathNodes result = path.evaluateExpression("/html/bo
```

The `XPathNodes` class is similar to a `NodeList`, but it extends the `Iterable` interface, allowing you to use an enhanced `for` loop.

If the result is a single node, use one of the following calls:

```
Node node = path.evaluateExpression("/html/body/form[
node = (Node) path.evaluate("/html/body/form[1]", doc
```

If the result is a number, use:

```
int count = path.evaluateExpression("count(/html/body/
count = ((Number) path.evaluate("count(/html/body/for
      doc, XPathConstants.NUMBER)).intValue();
```

You don't have to start the search at the document root; you can start at any node or node list. For example, if you have a node from a previous evaluation, you can call

```
String result = path.evaluate(expression, node);
```

If you do not know the result of evaluating an XPath expression (perhaps because it comes from a user), then call

```
XPathEvaluationResult<?> result = path.evaluateExpres
```

The expression `result.type()` is one of the constants

```
STRING
NODESET
NODE
NUMBER
BOOLEAN
```

of the `XPathEvaluationResult.XPathResultType` enumeration. Call `result.value()` to get the value.

The program in Listing 3.6 demonstrates evaluation of arbitrary XPath expressions. Load an XML file and type an expression. The result of the expression is displayed.

Listing 1.6 xpath/XPathTest.java

```
1 package xpath;
2
3 import java.nio.file.*;
```

```
4  import java.util.*;
5
6  import javax.xml.catalog.*;
7  import javax.xml.parsers.*;
8  import javax.xml.xpath.*;
9
10 import org.w3c.dom.*;
11
12 /**
13  * This program evaluates XPath expressions.
14  * @version 1.1 2018-04-06
15  * @author Cay Horstmann
16  */
17 public class XPathTest
18 {
19    public static void main(String[] args) throw
20    {
21       DocumentBuilderFactory factory = Document
22       DocumentBuilder builder = factory.newDocu
23
24       // Avoid a delay in parsing an XHTML file
25       // Section 3.4.1
26       builder.setEntityResolver(CatalogManager.
27             CatalogFeatures.defaults(),
28             Path.of("xpath/catalog.xml").toAbso
29
30       XPathFactory xpfactory = XPathFactory.new
31       XPath path = xpfactory.newXPath();
```

```
32        try (var in = new Scanner(System.in))
33        {
34           String filename;
35           if (args.length == 0)
36           {
37              System.out.print("Input file: ");
38              filename = in.nextLine();
39           }
40           else
41              filename = args[0];
42
43           Document doc = builder.parse(filename)
44           boolean done = false;
45           while (!done)
46           {
47              System.out.print("XPath expression
48              String expression = in.nextLine();
49              if (expression.strip().isEmpty()) d
50              else
51              {
52                 try
53                 {
54                    XPathEvaluationResult<?> resu
55                          = path.evaluateExpressi
56                    if (result.type() == XPathEva
57                    {
58                       for (Node n : (XPathNodes)
59                          System.out.println(desc
```

```
60                   }
61                   else if (result.type() == XPa
62                      System.out.println((Node)
63                   else
64                      System.out.println(result.
65                }
66                catch (XPathExpressionException
67                {
68                   System.out.println(e.getMessa
69                }
70             }
71          }
72       }
73    }
74
75    public static String description(Node n)
76    {
77       if (n instanceof Element) return "Element
78       else if (n instanceof Attr) return "Attri
79       else return n.toString();
80    }
81 }
```

`javax.xml.xpath.XPathFactory` **5.0**

- `static XPathFactory newInstance()`
  returns an `XPathFactory` instance for creating `XPath` objects.

- `XPath newXpath()`
  constructs an `XPath` object for evaluating XPath expressions.

javax.xml.xpath.XPath **5.0**

- `String evaluate(String expression, Object startingPoint)`
  evaluates an expression, beginning at the given starting point. The starting point can be a node or node list. If the result is a node or node set, the returned string consists of the data of all text node children.
- `Object evaluate(String expression, Object startingPoint, QName resultType)`
  evaluates an expression, beginning at the given starting point. The starting point can be a node or node list. The `resultType` is one of the constants `STRING`, `NODE`, `NODESET`, `NUMBER`, or `BOOLEAN` in the `XPathConstants` class. The return value is a `String`, `Node`, `NodeList`, `Number`, or `Boolean`.
- `<T> T evaluateExpression(String expression, Object item, Class<T> type)` **9**
  evaluates the given expression and yields the result as a value of the given type.
- `XPathEvaluationResult<?> evaluateExpression(String expression, InputSource source)` **9**
  evaluates the given expression.

javax.xml.xpath.XPathEvaluationResult<T> 9

- `XPathEvaluationResult.XPathResultType type()`
  returns one of the enumeration constants `STRING`, `NODESET`, `NODE`, `NUMBER`, `BOOLEAN`.
- `T value()`
  returns the result value.

1.6. Using Namespaces

The Java language uses packages to avoid name clashes. Programmers can use the same name for different classes as long as they aren't in the same package. XML has a similar *namespace* mechanism for element and attribute names.

A namespace is identified by a Uniform Resource Identifier (URI). Here are three examples:

```
http://www.w3.org/2001/XMLSchema
uuid:1c759aed-b748-475c-ab68-10679700c4f2
urn:com:books-r-us
```

The HTTP URL form is the most common. Note that the URL is just used as an identifier string, not as a locator for a document. For example, the namespace identifiers

```
http://www.horstmann.com/corejava
http://www.horstmann.com/corejava/index.html
```

denote *different* namespaces, even though a web server would serve the same document for both URLs.

There need not be any document at a namespace URL—the XML parser doesn't attempt to find anything at that location. However, as a help to programmers who encounter a possibly unfamiliar namespace, it is customary to place a document explaining the purpose of the namespace at the URL location. For example, if you point your browser to the namespace URL for the XML Schema namespace (`http://www.w3.org/2001/XMLSchema`), you will find a document describing the XML Schema standard.

Why use HTTP URLs for namespace identifiers? It is easy to ensure that they are unique. If you choose a real URL, the host part's uniqueness is guaranteed by the domain name system. Your organization can then arrange for the uniqueness of the remainder of the URL. This is the same rationale that underlies the use of reversed domain names in Java package names.

Of course, although long namespace identifiers are good for uniqueness, you don't want to deal with long identifiers any more than you have to. In the Java programming language, you use the

`import` mechanism to specify the long names of packages, and then use just the short class names. In XML, there is a similar mechanism:

```
<element xmlns="namespaceURI">
   children
</element>
```

The element and its children are now part of the given namespace.

A child can provide its own namespace, for example:

```
<element xmlns="namespaceURI1">
   <child xmlns="namespaceURI2">
      grandchildren
   </child>
   more children
</element>
```

Then the first child and the grandchildren are part of the second namespace.

This simple mechanism works well if you need only a single namespace or if the namespaces are naturally nested. Otherwise, you will want to use a second mechanism that has no analog in Java. You can have a *prefix* for a namespace—a short identifier that you

choose for a particular document. Here is a typical example—the `xsd` prefix in an XML Schema file:

```
<xsd:schema xmlns:xsd="http://www.w3.org/2001/XMLSchem
   <xsd:element name="config"/>
   . . .
</xsd:schema>
```

The attribute

```
xmlns:prefix="namespaceURI"
```

defines a namespace and a prefix. In our example, the prefix is the string `xsd`. Thus, `xsd:schema` really means `schema` in the namespace `http://www.w3.org/2001/XMLSchema`.

Note: Only child elements inherit the namespace of their parent. Attributes without an explicit prefix are never part of a namespace. Consider this contrived example:

```
<configuration xmlns="http://www.horstmann
   xmlns:si="http://www.bipm.fr/enus/3_SI/
   <size value="210" si:unit="mm"/>
```

```
    . . .
</configuration>
```

In this example, the elements `configuration` and `size` are part of the namespace with URI `http://www.horstmann.com/corejava`. The attribute `si:unit` is part of the namespace with URI `http://www.bipm.fr/enus/3_SI/si.html`. However, the attribute `value` is not part of any namespace.

You can control how the parser deals with namespaces. By default, the DOM parser of the Java XML API is not namespace-aware.

To turn on namespace handling, call the `setNamespaceAware` method of the `DocumentBuilderFactory`:

```
DocumentBuilderFactory factory = DocumentBuilderFacto
factory.setNamespaceAware(true);
```

Now, all builders the factory produces support namespaces.

Alternatively, since Java 13, call

```
DocumentBuilderFactory factory = DocumentBuilderFacto
```

Each node created by a builder has three properties:

- The *qualified name*, with a prefix, returned by `getNodeName`, `getTagName`, and so on
- The namespace URI, returned by the `getNamespaceURI` method
- The *local name*, without a prefix or a namespace, returned by the `getLocalName` method

Here is an example. Suppose the parser sees the following element:

```
<xsd:schema xmlns:xsd="http://www.w3.org/2001/XMLSche
```

It then reports the following:

- Qualified name = `xsd:schema`
- Namespace URI = `http://www.w3.org/2001/XMLSchema`
- Local name = `schema`

Note: If namespace awareness is turned off, `getNamespaceURI` and `getLocalName` return `null`.

---

org.w3c.dom.Node 1.4

- `String getLocalName()`
  returns the local name (without prefix), or `null` if the parser is not namespace-aware.
- `String getNamespaceURI()`
  returns the namespace URI, or `null` if the node is not part of a namespace or if the parser is not namespace-aware.

`javax.xml.parsers.DocumentBuilderFactory` 1.4

- `static DocumentBuilderFactory newNSInstance()` 13
  yields a factory whose builders are namespace-aware.
- `boolean isNamespaceAware()`
- `void setNamespaceAware(boolean value)`
  get or set the `namespaceAware` property of the factory. If set to `true`, the parsers that this factory generates are namespace-aware.

1.7. Streaming Parsers

The DOM parser reads an XML document in its entirety into a tree data structure. For most practical applications, DOM works fine. However, it can be inefficient if the document is large and if your processing algorithm is simple enough that you can analyze nodes on

the fly, without having to see all of the tree structure. In these cases, you should use a streaming parser.

In the following sections, we discuss two streaming parsers supplied by the Java API. The SAX parser uses event callbacks, and the StAX parser provides an iterator through the parsing events. The latter is usually a bit more convenient.

1.7.1. Using the SAX Parser

The SAX parser reports events as it parses the components of the XML input, but it does not store the document in any way—it is up to the event handlers to build a data structure. In fact, the DOM parser is built on top of the SAX parser. It builds the DOM tree as it receives the parser events.

Whenever you use a SAX parser, you need a handler that defines the event actions for the various parse events. The `ContentHandler` interface defines several callback methods that the parser executes as it parses the document. Here are the most important ones:

- `startElement` and `endElement` are called each time a start tag or end tag is encountered.
- `characters` is called whenever character data are encountered.
- `startDocument` and `endDocument` are called once each, at the start and the end of the document.

For example, when parsing the fragment

```
<font>
   <name>Helvetica</name>
   <size units="pt">36</size>
</font>
```

the parser makes the following callbacks:

1. `startElement`, element name: `font`
2. `startElement`, element name: `name`
3. `characters`, content: `Helvetica`
4. `endElement`, element name: `name`
5. `startElement`, element name: `size`, attributes: `units="pt"`
6. `characters`, content: `36`
7. `endElement`, element name: `size`
8. `endElement`, element name: `font`

Your handler needs to override these methods and have them carry out whatever action you want to carry out as you parse the file. The program at the end of this section prints all links of the form `<a href=". . .">` in an HTML file. It simply overrides the `startElement` method of the handler to check for elements with name `a` and an attribute with name `href`. This is potentially useful

for implementing a "web crawler"—a program that reaches more and more web pages by following links.

Note: HTML doesn't have to be valid XML, and most web pages deviate so much from proper XML that the example programs will not be able to parse them. However, the pages on my web site `https://horstmann.com` are written in XHTML (an HTML dialect that is proper XML). You can use those pages to test the example program. For example, if you run

```
java sax.SAXTest https://horstmann.com/core
```

you will see a list of the URLs of all links on that page.

The sample program is a good example for the use of SAX. We don't care at all in which context the `a` elements occur, and there is no need to store a tree structure.

Here is how you get a SAX parser:

```
SAXParserFactory factory = SAXParserFactory.newInstan
```

```
SAXParser parser = factory.newSAXParser();
```

You can now process a document:

```
parser.parse(source, handler);
```

Here, `source` can be a file, URL string, or input stream. The `handler` belongs to a subclass of `DefaultHandler`. The `DefaultHandler` class defines do-nothing methods for the four interfaces:

```
ContentHandler
DTDHandler
EntityResolver
ErrorHandler
```

The example program defines a handler that overrides the `startElement` method of the `ContentHandler` interface to watch out for `a` elements with an `href` attribute:

```
var handler = new DefaultHandler()
   {
      public void startElement(String namespaceURI, S
            Attributes attrs) throws SAXException
      {
```

```
            if (lname.equalsIgnoreCase("a") && attrs !=
            {
               String href = attrs.getValue("href");
               if (href != null) System.out.println(href
            }
         }
      };
```

The `startElement` method has three parameters that describe the element name. The `qname` parameter reports the qualified name of the form `prefix:localname`. If namespace processing is turned on, then the `namespaceURI` and `lname` parameters provide the namespace and local (unqualified) name.

As with the DOM parser, namespace processing is turned off by default. To activate namespace processing, call the `setNamespaceAware` method of the factory class. Alternatively, as of Java 13, make a namespace-aware factory with `newNSInstance`:

```
   SAXParserFactory factory = SAXParserFactory.newNSInst
   SAXParser saxParser = factory.newSAXParser();
```

In this program, we cope with another common issue. An XHTML file starts with a tag that contains a DTD reference, and the parser will want to load it. Understandably, the W3C isn't too happy to serve

billions of copies of files such as `www.w3.org/TR/xhtml1/DTD/xhtml1-strict.dtd`. At one point, they refused altogether, but at the time of this writing, they serve the DTD at a glacial pace. If you don't need to validate the document, just call

```
factory.setFeature("http://apache.org/xml/features/no
```

Listing 3.7 contains the code for the web crawler program. Later in this chapter, you will see another interesting use of SAX. An easy way of turning a non-XML data source into XML is to report the SAX events that an XML parser would report. See Section 3.9 for details.

Listing 1.7 sax/SAXTest.java

```
1  package sax;
2
3  import java.io.*;
4  import java.net.*;
5  import javax.xml.parsers.*;
6  import org.xml.sax.*;
7  import org.xml.sax.helpers.*;
8
9  /**
10  * This program demonstrates how to use a SAX p
```

```
 * hyperlinks of an XHTML web page. <br>
 * Usage: java sax.SAXTest URL
 * @version 1.02 2023-10-24
 * @author Cay Horstmann
 */
public class SAXTest
{
   public static void main(String[] args) throw
   {
      String url;
      if (args.length == 0)
      {
         url = "https://www.w3.org/2010/04/xhtm
         System.out.println("Using " + url);
      }
      else url = args[0];

      var handler = new DefaultHandler()
         {
            public void startElement(String nam
                  String qname, Attributes attr
            {
               if (lname.equals("a") && attrs !
               {
                  String href = attrs.getValue(
                  if (href != null) System.out.
               }
            }
```

```
39            };
40
41         SAXParserFactory factory = SAXParserFacto
42         factory.setNamespaceAware(true);
43         factory.setFeature(
44            "http://apache.org/xml/features/nonval
45            false);
46         SAXParser saxParser = factory.newSAXParse
47         InputStream in = new URI(url).toURL().ope
48         saxParser.parse(in, handler);
49      }
50   }
```

`javax.xml.parsers.SAXParserFactory` **1.4**

- `static SAXParserFactory newInstance()`
- `static SAXParserFactory newNSInstance()` **13**

  return an instance of the `SAXParserFactory` class. The second method yields a namespace-aware instance.
- `SAXParser newSAXParser()`

  returns an instance of the `SAXParser` class.
- `boolean isNamespaceAware()`
- `void setNamespaceAware(boolean value)`

  get or set the `namespaceAware` property of the factory. If set to `true`, the parsers that this factory generates are namespace-aware.

- `boolean isValidating()`
- `void setValidating(boolean value)`

  get or set the `validating` property of the factory. If set to `true`, the parsers that this factory generates validate their input.

`javax.xml.parsers.SAXParser` **1.4**

- `void parse(File f, DefaultHandler handler)`
- `void parse(String url, DefaultHandler handler)`
- `void parse(InputStream in, DefaultHandler handler)`

  parse an XML document from the given file, URL, or input stream and report parse events to the given handler.

org.xml.sax.ContentHandler **1.4**

- `void startDocument()`
- `void endDocument()`

  are called at the start or the end of the document.
- `void startElement(String uri, String lname, String qname, Attributes attr)`
- `void endElement(String uri, String lname, String qname)`

  are called at the start or the end of an element. If the parser is namespace-aware, they report the URI of the namespace, the local name without prefix, and the qualified name with prefix.

- `void characters(char[] data, int start, int length)`
  is called when the parser reports character data.

org.xml.sax.Attributes **1.4**

- `int getLength()`
  returns the number of attributes stored in this attribute collection.
- `String getLocalName(int index)`
  returns the local name (without prefix) of the attribute with the given index, or the empty string if the parser is not namespace-aware.
- `String getURI(int index)`
  returns the namespace URI of the attribute with the given index, or the empty string if the node is not part of a namespace or if the parser is not namespace-aware.
- `String getQName(int index)`
  returns the qualified name (with prefix) of the attribute with the given index, or the empty string if the qualified name is not reported by the parser.
- `String getValue(int index)`
- `String getValue(String qname)`
- `String getValue(String uri, String lname)`
  return the attribute value from a given index, qualified name, or namespace URI + local name. Return `null` if the value doesn't exist.

1.7.2. Using the StAX Parser

The StAX parser is a "pull parser." Instead of installing an event handler, you simply iterate through the events, using this basic loop:

```
InputStream in = url.openStream();
XMLInputFactory factory = XMLInputFactory.newInstance
XMLStreamReader parser = factory.createXMLStreamReade
while (parser.hasNext())
{
   int event = parser.next();
   Call parser methods to obtain event details
}
```

For example, when parsing the fragment

```
<font>
   <name>Helvetica</name>
   <size units="pt">36</size>
</font>
```

the parser yields the following events:

1. `START_ELEMENT`, element name: `font`
2. `CHARACTERS`, content: white space
3. `START_ELEMENT`, element name: `name`

4. `CHARACTERS`, content: `Helvetica`
5. `END_ELEMENT`, element name: `name`
6. `CHARACTERS`, content: white space
7. `START_ELEMENT`, element name: `size`
8. `CHARACTERS`, content: `36`
9. `END_ELEMENT`, element name: `size`
10. `CHARACTERS`, content: white space
11. `END_ELEMENT`, element name: `font`

To analyze the attribute values, call the appropriate methods of the `XMLStreamReader` class. For example,

```
String units = parser.getAttributeValue(null, "units"
```

gets the `units` attribute of the current element.

By default, namespace processing is enabled. You can deactivate it by modifying the factory:

```
XMLInputFactory factory = XMLInputFactory.newInstance
factory.setProperty(XMLInputFactory.IS_NAMESPACE_AWAR
```

Listing 3.8 contains the code for the web crawler program implemented with the StAX parser. As you can see, the code is

simpler than the equivalent SAX code because you don't have to worry about event handling.

Listing 1.8 stax/StAXTest.java

```
1  package stax;
2
3  import java.io.*;
4  import java.net.*;
5  import javax.xml.stream.*;
6
7  /**
8   * This program demonstrates how to use a StAX
9   * hyperlinks of an XHTML web page. <br>
10  * Usage: java stax.StAXTest URL
11  * @author Cay Horstmann
12  * @version 1.11 2023-10-24
13  */
14 public class StAXTest
15 {
16    public static void main(String[] args) throw
17    {
18       String urlString;
19       if (args.length == 0)
20       {
21          urlString = "http://www.w3c.org";
22          System.out.println("Using " + urlStrin
23       }
```

```
24          else urlString = args[0];
25          InputStream in = new URI(urlString).toURL
26          XMLInputFactory factory = XMLInputFactory
27          XMLStreamReader parser = factory.createXM
28          while (parser.hasNext())
29          {
30             int event = parser.next();
31             if (event == XMLStreamConstants.START_
32             {
33                if (parser.getLocalName().equals("a
34                {
35                   String href = parser.getAttribut
36                   if (href != null)
37                      System.out.println(href);
38                }
39             }
40          }
41       }
42    }
```

`javax.xml.stream.XMLInputFactory` **6**

- `static XMLInputFactory newInstance()`
  returns an instance of the `XMLInputFactory` class.
- `void setProperty(String name, Object value)`
  sets a property for this factory, or throws an `IllegalArgumentException` if the property is not supported or

cannot be set to the given value. The JDK implementation supports the following Boolean-valued properties:

`"javax.xml.stream.isValidating"`	V c c r V M b s
`"javax.xml.stream.isNamespaceAware"`	V (c r a p M b s
`"javax.xml.stream.isCoalescing"`	V

`"javax.xml.stream.isReplacingEntityReferences"`	V (c e r a a a c
`"javax.xml.stream.isSupportingExternalEntities"`	V (c e e r T s

`"javax.xml.stream.supportDTD"`	`V` `(` `c` `D` `r` `e`

- `XMLStreamReader createXMLStreamReader(InputStream in)`
- `XMLStreamReader createXMLStreamReader(InputStream in, String characterEncoding)`
- `XMLStreamReader createXMLStreamReader(Reader in)`
- `XMLStreamReader createXMLStreamReader(Source in)`

  create a parser that reads from the given stream, reader, or JAXP source.

javax.xml.stream.XMLStreamReader **6**

- `boolean hasNext()`

  returns `true` if there is another parse event.

- `int next()`
  sets the parser state to the next parse event and returns one of the following constants: `START_ELEMENT`, `END_ELEMENT`, `CHARACTERS`, `START_DOCUMENT`, `END_DOCUMENT`, `CDATA`, `COMMENT`, `SPACE` (ignorable whitespace), `PROCESSING_INSTRUCTION`, `ENTITY_REFERENCE`, `DTD`.
- `boolean isStartElement()`
- `boolean isEndElement()`
- `boolean isCharacters()`
- `boolean isWhiteSpace()`
  return `true` if the current event is a start element, end element, character data, or whitespace.
- `QName getName()`
- `String getLocalName()`
  get the name of the element in a `START_ELEMENT` or `END_ELEMENT` event.
- `String getText()`
  returns the characters of a `CHARACTERS`, `COMMENT`, or `CDATA` event, the replacement value for an `ENTITY_REFERENCE`, or the internal subset of a `DTD`.

- `int getAttributeCount()`
- `QName getAttributeName(int index)`
- `String getAttributeLocalName(int index)`
- `String getAttributeValue(int index)`
  get the attribute count and the names and values of the attributes, provided the current event is `START_ELEMENT`.
- `String getAttributeValue(String namespaceURI, String name)`
  gets the value of the attribute with the given name, provided the current event is `START_ELEMENT`. If `namespaceURI` is `null`, the namespace is not checked.

1.8. Generating XML Documents

You now know how to write Java programs that read XML. Let us now turn to the opposite process: producing XML output. Of course, you could write an XML file simply by making a sequence of `print` calls, printing the elements, attributes, and text content, but that would not be a good idea. The code is rather tedious, and you can easily make mistakes if you don't pay attention to special symbols (such as `"` or `<`) in the attribute values and text content.

A better approach is to build up a DOM tree with the contents of the document and then write out the tree contents. The following sections discuss the details.

1.8.1. Documents without Namespaces

To build a DOM tree, you start out with an empty document. You can get an empty document by calling the `newDocument` method of the `DocumentBuilder` class:

```
Document doc = builder.newDocument();
```

Use the `createElement` method of the `Document` class to construct the elements of your document:

```
Element rootElement = doc.createElement(rootName);
Element childElement = doc.createElement(childName);
```

Use the `createTextNode` method to construct text nodes:

```
Text textNode = doc.createTextNode(textContents);
```

Add the root element to the document, and add the child nodes to their parents:

```
doc.appendChild(rootElement);
rootElement.appendChild(childElement);
childElement.appendChild(textNode);
```

As you build up the DOM tree, you may also need to set element attributes. Simply call the `setAttribute` method of the `Element` class:

```
rootElement.setAttribute(name, value);
```

1.8.2. Documents with Namespaces

If you use namespaces, the procedure for creating a document is slightly different.

First, set the builder factory to be namespace-aware, then create the builder:

```
DocumentBuilderFactory factory = DocumentBuilderFacto
factory.setNamespaceAware(true);
builder = factory.newDocumentBuilder();
```

Then use `createElementNS` instead of `createElement` to create any nodes:

```
String namespace = "http://www.w3.org/2000/svg";
Element rootElement = doc.createElementNS(namespace,
```

If your node has a qualified name with a namespace prefix, then any necessary `xmlns`-prefixed attributes are created automatically. For example, if you need SVG inside XHTML, you can construct an element like this:

```
Element svgElement = doc.createElement(namespace, "svg
```

When the element is written, it turns into

```
<svg:svg xmlns:svg="http://www.w3.org/2000/svg">
```

If you need to set element attributes whose names are in a namespace, use the `setAttributeNS` method of the `Element` class:

```
rootElement.setAttributeNS(namespace, qualifiedName, v
```

1.8.3. Writing Documents

Somewhat curiously, it is not so easy to write a DOM tree to an output stream. The easiest approach is to use the Extensible Stylesheet Language Transformations (XSLT) API. For more

information about XSLT, turn to Section 3.9. Right now, consider the code that follows a magic incantation to produce XML output.

We apply the do-nothing transformation to the document and capture its output. To include a `DOCTYPE` node in the output, we also need to set the `SYSTEM` and `PUBLIC` identifiers as output properties.

```
// construct the do-nothing transformation
Transformer t = TransformerFactory.newInstance().newT
// set output properties to get a DOCTYPE node
t.setOutputProperty(OutputKeys.DOCTYPE_SYSTEM, system
t.setOutputProperty(OutputKeys.DOCTYPE_PUBLIC, public
// set indentation
t.setOutputProperty(OutputKeys.INDENT, "yes");
t.setOutputProperty(OutputKeys.METHOD, "xml");
t.setOutputProperty("{http://xml.apache.org/xslt}inde
// apply the do-nothing transformation and send the o
t.transform(new DOMSource(doc), new StreamResult(new
```

Another approach is to use the `LSSerializer` interface. To get an instance, you have to use the following magic incantation:

```
DOMImplementation impl = doc.getImplementation();
var implLS = (DOMImplementationLS) impl.getFeature("LS
```

```
LSSerializer ser = implLS.createLSSerializer();
```

If you want spaces and line breaks, set this flag:

```
ser.getDomConfig().setParameter("format-pretty-print"
```

Then it's simple enough to convert a document to a string:

```
String str = ser.writeToString(doc);
```

If you want to write the output directly to a file, you need an `LSOutput`:

```
LSOutput out = implLS.createLSOutput();
out.setEncoding("UTF-8");
out.setByteStream(Files.newOutputStream(path));
ser.write(doc, out);
```

`javax.xml.parsers.DocumentBuilder` **1.4**

- `Document newDocument()`
  returns an empty document.

org.w3c.dom.Document **1.4**

- `Element createElement(String name)`
- `Element createElementNS(String uri, String qname)`
  create an element with the given name.
- `Text createTextNode(String data)`
  creates a text node with the given data.

org.w3c.dom.Node **1.4**

- `Node appendChild(Node child)`
  appends a node to the list of children of this node. Returns the appended node.

org.w3c.dom.Element **1.4**

- `void setAttribute(String name, String value)`
- `void setAttributeNS(String uri, String qname, String value)`
  set the attribute with the given name to the given value. If the qualified name has an alias prefix, then `uri` must not be `null`.

`javax.xml.transform.TransformerFactory` 1.4

- `static TransformerFactory newInstance()`
  returns an instance of the `TransformerFactory` class.
- `Transformer newTransformer()`
  returns an instance of the `Transformer` class that carries out an identity (do-nothing) transformation.

`javax.xml.transform.Transformer` 1.4

- `void setOutputProperty(String name, String value)`
  sets an output property. See https://www.w3.org/TR/xslt#output for a listing of the standard output properties. The most useful ones are shown here:

`doctype-public`	The public ID to be used in the `DOCTYPE` declaration
`doctype-system`	The system ID to be used in the `DOCTYPE` declaration
`indent`	`"yes"` or `"no"`
`method`	`"xml"`, `"html"`, `"text"`, or a custom string

- `void transform(Source from, Result to)`
  transforms an XML document.

`javax.xml.transform.dom.DOMSource` **1.4**

- `DOMSource(Node n)`
  constructs a source from the given node. Usually, `n` is a document node.

`javax.xml.transform.stream.StreamResult` **1.4**

- `StreamResult(File f)`
- `StreamResult(OutputStream out)`
- `StreamResult(Writer out)`
- `StreamResult(String systemID)`
  construct a stream result from a file, stream, writer, or system ID (usually a relative or absolute URL).

1.8.4. Writing an XML Document with StAX

In the preceding section, you saw how to produce an XML document by writing a DOM tree. If you have no other use for the DOM tree, that approach is not very efficient.

The StAX API lets you write an XML tree directly. Construct an `XMLStreamWriter` from an `OutputStream`:

```
XMLOutputFactory factory = XMLOutputFactory.newInstan
XMLStreamWriter writer = factory.createXMLStreamWrite
```

To produce the XML header, call

```
writer.writeStartDocument();
```

Then call

```
writer.writeStartElement(name);
```

Add attributes by calling

```
writer.writeAttribute(name, value);
```

Now you can add child elements by calling `writeStartElement` again, or write characters with

```
writer.writeCharacters(text);
```

When you have written all child nodes, call

```
writer.writeEndElement();
```

This causes the current element to be closed.

To write an element without children (such as `<img . . ./>`), use the call

```
writer.writeEmptyElement(name);
```

Finally, at the end of the document, call

```
writer.writeEndDocument();
```

This call closes any open elements.

You still need to close the `XMLStreamWriter`, and you need to do it manually since the `XMLStreamWriter` interface does not extend the `AutoCloseable` interface.

As with the DOM/XSLT approach, you don't have to worry about escaping characters in attribute values and character data. However, it is possible to produce malformed XML, such as a document with multiple root nodes. Also, the current version of StAX has no support for producing indented output.

Listing 3.9 demonstrates two ways of producing XML: by constructing and saving a DOM tree, and by directly writing the XML with the StAX

API.

The program draws a modernist painting—a random set of colored rectangles (see Figure 3.3). To save our masterpiece, we use the Scalable Vector Graphics (SVG) format. SVG is an XML format to describe complex graphics in a device-independent fashion. You can find more information about SVG at https://www.w3.org/Graphics/SVG. To view SVG files, simply use any modern browser.

Figure 1.3: Generating modern art

We don't need to go into details about SVG; for our purposes, we just need to know how to express a set of colored rectangles. Here is a sample:

```
<?xml version="1.0" encoding="UTF-8"?>
<!DOCTYPE svg PUBLIC "-//W3C//DTD SVG 20000802//EN"
   "http://www.w3.org/TR/2000/CR-SVG-20000802/DTD/svg
<svg xmlns="http://www.w3.org/2000/svg" width="300" h
```

```
    <rect x="231" y="61" width="9" height="12" fill="#
    <rect x="107" y="106" width="56" height="5" fill="
    . . .
</svg>
```

As you can see, each rectangle is described as a `rect` node. The position, width, height, and fill color are attributes. The fill color is an RGB value in hexadecimal.

Note: SVG uses attributes heavily. In fact, some attributes are quite complex. For example, here is a path element:

```
<path d="M 100 100 L 300 100 L 200 300 z">
```

The `M` denotes a "moveto" command, `L` is "lineto," and `z` is "closepath" (!). Apparently, the designers of this data format didn't have much confidence in using XML for structured data. In your own XML formats, you might want to use elements instead of complex attributes. Or, if you find that XML is too verbose for your purpose, choose a different format.

Listing 1.9 write/XMLWriteTest.java

```
1  package write;
2
3  import java.io.*;
4  import java.nio.file.*;
5  import java.util.random.*;
6
7  import javax.xml.parsers.*;
8  import javax.xml.stream.*;
9  import javax.xml.transform.*;
10 import javax.xml.transform.dom.*;
11 import javax.xml.transform.stream.*;
12
13 import org.w3c.dom.*;
14
15 /**
16  * This program shows how to write an XML file.
17  * format.
18  * @version 1.14 2023-08-27
19  * @author Cay Horstmann
20  */
21 public class XMLWriteTest
22 {
23    public static void main(String[] args) throw
24    {
25       Document doc = newDrawing(600, 400);
26       writeDocument(doc, "drawing1.svg");
```

```
27          writeNewDrawing(600, 400, "drawing2.svg")
28       }
29
30       private static RandomGenerator generator = R
31
32       /**
33        * Creates a new random drawing.
34        * @param drawingWidth the width of the draw
35        * @param drawingHeight the height of the dr
36        * @return the DOM tree of the SVG document
37        */
38       public static Document newDrawing(int drawin
39             throws ParserConfigurationException
40       {
41          DocumentBuilderFactory factory = Document
42          factory.setNamespaceAware(true);
43          DocumentBuilder builder = factory.newDocu
44          String namespace = "http://www.w3.org/200
45          Document doc = builder.newDocument();
46          Element svgElement = doc.createElementNS(
47          doc.appendChild(svgElement);
48          svgElement.setAttribute("width", "" + dra
49          svgElement.setAttribute("height", "" + dr
50          int n = 10 + generator.nextInt(20);
51          for (int i = 1; i <= n; i++)
52          {
53             int x = generator.nextInt(drawingWidth
54             int y = generator.nextInt(drawingHeigh
```

```
55          int width = generator.nextInt(drawingW
56          int height = generator.nextInt(drawing
57          int r = generator.nextInt(256);
58          int g = generator.nextInt(256);
59          int b = generator.nextInt(256);
60
61          Element rectElement = doc.createElemen
62          rectElement.setAttribute("x", "" + x);
63          rectElement.setAttribute("y", "" + y);
64          rectElement.setAttribute("width", "" +
65          rectElement.setAttribute("height", ""
66          rectElement.setAttribute("fill",
67             "#%02x%02x%02x".formatted(r, g, b))
68          svgElement.appendChild(rectElement);
69       }
70       return doc;
71    }
72
73    /**
74     * Saves a document using DOM/XSLT.
75     * @param doc the document to be written
76     * @param filename the name of the destinati
77     */
78    public static void writeDocument(Document do
79          throws TransformerException, IOExcepti
80    {
81       Transformer t = TransformerFactory.newIns
82       t.setOutputProperty(OutputKeys.DOCTYPE_SY
```

```
83                "http://www.w3.org/TR/2000/CR-SVG-2
84          t.setOutputProperty(OutputKeys.DOCTYPE_PU
85                "-//W3C//DTD SVG 20000802//EN");
86          t.setOutputProperty(OutputKeys.INDENT, "y
87          t.setOutputProperty(OutputKeys.METHOD, "x
88          t.setOutputProperty("{http://xml.apache.o
89          t.transform(new DOMSource(doc), new Strea
90                Files.newOutputStream(Path.of(filen
91       }
92
93       /**
94        * Uses StAX to write an SVG document with a
95        * @param drawingWidth the width of the draw
96        * @param drawingHeight the width of the dra
97        * @param filename the name of the destinati
98        */
99       public static void writeNewDrawing(int drawi
100            String filename) throws XMLStreamExcep
101      {
102         XMLOutputFactory factory = XMLOutputFacto
103         XMLStreamWriter writer = factory.createXM
104               Files.newOutputStream(Path.of(filen
105         writer.writeStartDocument();
106         writer.writeDTD("""
107   <!DOCTYPE svg PUBLIC "-//W3C//DTD SVG 20000802/
108     "http://www.w3.org/TR/2000/CR-SVG-20000802/DT
109   """);
110         writer.writeStartElement("svg");
```

```
111         writer.writeDefaultNamespace("http://www.
112         writer.writeAttribute("width", "" + drawi
113         writer.writeAttribute("height", "" + draw
114         int n = 10 + generator.nextInt(20);
115         for (int i = 1; i <= n; i++)
116         {
117            int x = generator.nextInt(drawingWidth
118            int y = generator.nextInt(drawingHeigh
119            int width = generator.nextInt(drawingW
120            int height = generator.nextInt(drawing
121            int r = generator.nextInt(256);
122            int g = generator.nextInt(256);
123            int b = generator.nextInt(256);
124            writer.writeEmptyElement("rect");
125            writer.writeAttribute("x", "" + x);
126            writer.writeAttribute("y", "" + y);
127            writer.writeAttribute("width", "" + wi
128            writer.writeAttribute("height", "" + h
129            writer.writeAttribute("fill", "#%02x%0
130         }
131         writer.writeEndDocument(); // closes svg
132      }
133   }
```

`javax.xml.stream.XMLOutputFactory` **6**

- `static XMLOutputFactory newInstance()`
  returns an instance of the `XMLOutputFactory` class.

- `XMLStreamWriter createXMLStreamWriter(OutputStream stream)`
- `XMLStreamWriter createXMLStreamWriter(OutputStream stream, String encoding)`
- `XMLStreamWriter createXMLStreamWriter(Writer writer)`
- `XMLStreamWriter createXMLStreamWriter(Result result)`

  create a writer that writes to the given stream, writer, or JAXP result.

javax.xml.stream.XMLStreamWriter **6**

- `void writeStartDocument()`
- `void writeStartDocument(String xmlVersion)`
- `void writeStartDocument(String encoding, String xmlVersion)`

  write the XML processing instruction at the top of the document. Note that the `encoding` parameter is only used to write the attribute. It does not set the character encoding of the output.
- `void setDefaultNamespace(String namespaceURI)`
- `void setPrefix(String prefix, String namespaceURI)`

  set the default namespace or the namespace associated with a prefix. The declaration is scoped to the current element or, if no element has been written, to the document root.

- `void writeStartElement(String localName)`
- `void writeStartElement(String namespaceURI, String localName)`
  write a start tag, replacing the `namespaceURI` with the associated prefix.
- `void writeEndElement()`
  closes the current element.
- `void writeEndDocument()`
  closes all open elements.
- `void writeEmptyElement(String localName)`
- `void writeEmptyElement(String namespaceURI, String localName)`
  write a self-closing tag, replacing the `namespaceURI` with the associated prefix.
- `void writeAttribute(String localName, String value)`
- `void writeAttribute(String namespaceURI, String localName, String value)`
  write an attribute for the current element, replacing the `namespaceURI` with the associated prefix.
- `void writeCharacters(String text)`
  writes character data.
- `void writeCData(String text)`
  writes a `CDATA` block.

- `void writeDTD(String dtd)`
  writes the `dtd` string, which is assumed to contain a `DOCTYPE` declaration.
- `void writeComment(String comment)`
  writes a comment.
- `void close()`
  closes this writer.

1.9. XSL Transformations

The XSL Transformations (XSLT) mechanism allows you to specify rules for transforming XML documents into other formats, such as plain text, XHTML, or any other XML format. XSLT is commonly used to translate from one machine-readable XML format to another, or to translate XML into a presentation format for human consumption.

You need to provide an XSLT stylesheet that describes the conversion of XML documents into some other format. An XSLT processor reads an XML document and the stylesheet and produces the desired output (see Figure 3.4).



Figure 1.4: Applying XSL transformations

The XSLT specification is quite complex, and entire books have been written on the subject. We can't possibly discuss all the features of XSLT, so we will just work through a representative example. You can find more information in the book *Essential XML* by Don Box et al. The XSLT specification is available at https://www.w3.org/TR/xslt.

Suppose we want to transform XML files with employee records into HTML documents. Consider this input file:

```
<staff>
   <employee>
      <name>Carl Cracker</name>
      <salary>75000.0</salary>
      <hiredate year="1987" month="12" day="15"/>
   </employee>
   <employee>
```

```
      <name>Harry Hacker</name>
      <salary>50000.0</salary>
      <hiredate year="1989" month="10" day="1"/>
   </employee>
   <employee>
      <name>Tony Tester</name>
      <salary>40000.0</salary>
      <hiredate year="1990" month="3" day="15"/>
   </employee>
</staff>
```

The desired output is an HTML table:

```
<table border="1">
<tr>
<td>Carl Cracker</td><td>$75000.0</td><td>1987-12-15</
</tr>
<tr>
<td>Harry Hacker</td><td>$50000.0</td><td>1989-10-1</
</tr>
<tr>
<td>Tony Tester</td><td>$40000.0</td><td>1990-3-15</td
</tr>
</table>
```

A stylesheet with transformation templates has this form:

```
<?xml version="1.0" encoding="ISO-8859-1"?>
<xsl:stylesheet
      xmlns:xsl="http://www.w3.org/1999/XSL/Transform
      version="1.0">
   <xsl:output method="html"/>
   template1

   template2
   . . .
</xsl:stylesheet>
```

In our example, the `xsl:output` element specifies the method as HTML. Other valid method settings are `xml` and `text`.

Here is a typical template:

```
<xsl:template match="/staff/employee">
   <tr><xsl:apply-templates/></tr>
</xsl:template>
```

The value of the `match` attribute is an XPath expression. The template states: Whenever you see a node in the XPath set `/staff/employee`, do the following:

1. Emit the string `<tr>.`
2. Keep applying templates as you process its children.

3. Emit the string `</tr>` after you are done with all children.

In other words, this template generates the HTML table row markers around every employee record.

The XSLT processor starts processing by examining the root element. Whenever a node matches one of the templates, it applies the template. (If multiple templates match, the best matching one is used; see the specification at https://www.w3.org/TR/xslt for the gory details.) If no template matches, the processor carries out a default action. For text nodes, the default is to include the contents in the output. For elements, the default action is to create no output but to keep processing the children.

Here is a template for transforming `name` nodes in an employee file:

```
<xsl:template match="/staff/employee/name">
   <td><xsl:apply-templates/></td>
</xsl:template>
```

As you can see, the template produces the `<td>. . .</td>` delimiters, and it asks the processor to recursively visit the children of the `name` element. There is just one child—the text node. When the processor visits that node, it emits the text contents (provided, of course, that there is no other matching template).

You have to work a little harder if you want to copy attribute values into the output. Here is an example:

```
<xsl:template match="/staff/employee/hiredate">
   <td><xsl:value-of select="@year"/>-<xsl:value-of
   select="@month"/>-<xsl:value-of select="@day"/></t
</xsl:template>
```

When processing a `hiredate` node, this template emits

1. The string `<td>`
2. The value of the `year` attribute
3. A hyphen
4. The value of the `month` attribute
5. A hyphen
6. The value of the `day` attribute
7. The string `</td>`

The `xsl:value-of` statement computes the string value of a node set. The node set is specified by the XPath value of the `select` attribute. In this case, the path is relative to the currently processed node. The node set is converted to a string by concatenation of the string values of all nodes. The string value of an attribute node is its value. The string value of a text node is its contents. The string value

of an element node is the concatenation of the string values of its child nodes (but not its attributes).

Listing 3.10 contains the stylesheet for turning an XML file with employee records into an HTML table.

Listing 3.11 shows a different set of transformations. The input is the same XML file, and the output is plain text in the familiar property file format:

```
employee.1.name=Carl Cracker
employee.1.salary=75000.0
employee.1.hiredate=1987-12-15
employee.2.name=Harry Hacker
employee.2.salary=50000.0
employee.2.hiredate=1989-10-1
employee.3.name=Tony Tester
employee.3.salary=40000.0
employee.3.hiredate=1990-3-15
```

That example uses the `position()` function which yields the position of the current node as seen from its parent. We thus get an entirely different output simply by switching the stylesheet. This means you can safely use XML to describe your data; if some applications need the data in another format, just use XSLT to generate the alternative format.

It is simple to generate XSL transformations on the Java platform. Set up a transformer factory for each stylesheet. Then, get a transformer object and tell it to transform a source to a result:

```
var styleSheet = new File(filename);
var styleSource = new StreamSource(styleSheet);
Transformer t = TransformerFactory.newInstance().newT
t.transform(source, result);
```

The arguments of the `transform` method are objects of classes that implement the `Source` and `Result` interfaces. Several classes implement the `Source` interface:

```
DOMSource
SAXSource
StAXSource
StreamSource
```

You can construct a `StreamSource` from a file, stream, reader, or URL, and a `DOMSource` from the node of a DOM tree. For example, in the preceding section, we invoked the identity transformation as

```
t.transform(new DOMSource(doc), result);
```

In our example program, we do something slightly more interesting. Instead of starting out with an existing XML file, we produce a SAX XML reader that gives the illusion of parsing an XML file by emitting appropriate SAX events. Actually, our XML reader reads a flat file, as described in Chapter 1. The input file looks like this:

```
Carl Cracker|75000.0|1987|12|15
Harry Hacker|50000.0|1989|10|1
Tony Tester|40000.0|1990|3|15
```

Our XML reader generates SAX events as it processes the input. Here is a part of the `parse` method of the `EmployeeReader` class that implements the `XMLReader` interface:

```
var attributes = new AttributesImpl();
handler.startDocument();
handler.startElement("", "staff", "staff", attributes
boolean done = false;
while (!done)
{
   String line = in.readLine();
   if (line == null) done = true;
   else
   {
      handler.startElement("", "employee", "employee"
      var tokenizer = new StringTokenizer(line, "|");
```

```
        handler.startElement("", "name", "name", attrib
        String s = tokenizer.nextToken();
        handler.characters(s.toCharArray(), 0, s.length
        handler.endElement("", "name", "name");
        . . .
        handler.endElement("", "employee", "employee");
     }
  }
  handler.endElement("", rootElement, rootElement);
  handler.endDocument();
```

The `SAXSource` for the transformer is constructed from the XML reader:

```
  t.transform(new SAXSource(new EmployeeReader(),
     new InputSource(new FileInputStream(filename))), r
```

This is an ingenious trick to convert non-XML legacy data into XML. Of course, most XSLT applications will already have XML input data, and you can simply invoke the `transform` method on a `StreamSource`:

```
  t.transform(new StreamSource(file), result);
```

The transformation result is an object of a class that implements the `Result` interface. The Java API supplies three classes:

```
DOMResult
SAXResult
StreamResult
```

To store the result in a DOM tree, use a `DocumentBuilder` to generate a new document node and wrap it into a `DOMResult`:

```
Document doc = builder.newDocument();
t.transform(source, new DOMResult(doc));
```

To save the output in a file, use a `StreamResult`:

```
t.transform(source, new StreamResult(file));
```

Listing 3.12 contains the complete source code.

Listing 1.10 transform/makehtml.xsl

```
1 <?xml version="1.0" encoding="ISO-8859-1"?>
2
3 <xsl:stylesheet
4    xmlns:xsl="http://www.w3.org/1999/XSL/Transf
```

```
   version="1.0">

   <xsl:output method="html"/>

   <xsl:template match="/staff">
      <table border="1"><xsl:apply-templates/><
   </xsl:template>

   <xsl:template match="/staff/employee">
      <tr><xsl:apply-templates/></tr>
   </xsl:template>

   <xsl:template match="/staff/employee/name">
      <td><xsl:apply-templates/></td>
   </xsl:template>

   <xsl:template match="/staff/employee/salary"
      <td>$<xsl:apply-templates/></td>
   </xsl:template>

   <xsl:template match="/staff/employee/hiredat
      <td><xsl:value-of select="@year"/>-<xsl:v
      select="@month"/>-<xsl:value-of select="@
   </xsl:template>

</xsl:stylesheet>
```

Listing 1.11 transform/makeprop.xsl

```
<?xml version="1.0"?>

<xsl:stylesheet
   xmlns:xsl="http://www.w3.org/1999/XSL/Transf
   version="1.0">

   <xsl:output method="text" omit-xml-declarati

   <xsl:template match="/staff/employee">
employee.<xsl:value-of select="position()"
/>.name=<xsl:value-of select="name/text()"/>
employee.<xsl:value-of select="position()"
/>.salary=<xsl:value-of select="salary/text()"/
employee.<xsl:value-of select="position()"
/>.hiredate=<xsl:value-of select="hiredate/@yea
/>-<xsl:value-of select="hiredate/@month"
/>-<xsl:value-of select="hiredate/@day"/>
   </xsl:template>

</xsl:stylesheet>
```

Listing 1.12 transform/TransformTest.java

```
1  package transform;
2
3  import java.io.*;
4  import java.nio.file.*;
5  import java.util.*;
6  import javax.xml.transform.*;
7  import javax.xml.transform.sax.*;
8  import javax.xml.transform.stream.*;
9  import org.xml.sax.*;
10 import org.xml.sax.helpers.*;
11
12 /**
13  * This program demonstrates XSL transformation
14  * employee records. The records are stored in
15  * format. Specify the stylesheet on the comman
16  *    java transform.TransformTest transform/ma
17  * @version 1.05 2021-09-21
18  * @author Cay Horstmann
19  */
20 public class TransformTest
21 {
22    public static void main(String[] args) throw
23    {
24       Path path;
25       if (args.length > 0) path = Path.of(args[
26       else path = Path.of("transform", "makehtm
```

```
27          try (InputStream styleIn = Files.newInput
28          {
29             var styleSource = new StreamSource(sty
30
31             Transformer t = TransformerFactory.new
32             t.setOutputProperty(OutputKeys.INDENT,
33             t.setOutputProperty(OutputKeys.METHOD,
34             t.setOutputProperty("{http://xml.apach
35
36             try (InputStream docIn = Files.newInpu
37             {
38                t.transform(new SAXSource(new Emplo
39                   new StreamResult(System.out));
40             }
41          }
42       }
43    }
44
45    /**
46     * This class reads the flat file employee.dat
47     * was parsing an XML file.
48     */
49    class EmployeeReader implements XMLReader
50    {
51       private ContentHandler handler;
52
53       public void parse(InputSource source) throws
54       {
```

```
55        InputStream stream = source.getByteStream
56        var in = new BufferedReader(new InputStre
57        var atts = new AttributesImpl();
58
59        if (handler == null) throw new SAXExcepti
60
61        handler.startDocument();
62        handler.startElement("", "staff", "staff"
63        boolean done = false;
64        while (!done)
65        {
66           String line = in.readLine();
67           if (line == null) done = true;
68           else
69           {
70              handler.startElement("", "employee"
71              var t = new StringTokenizer(line, "
72
73              handler.startElement("", "name", "n
74              String s = t.nextToken();
75              handler.characters(s.toCharArray(),
76              handler.endElement("", "name", "nam
77
78              handler.startElement("", "salary",
79              s = t.nextToken();
80              handler.characters(s.toCharArray(),
81              handler.endElement("", "salary", "s
82
```

```
83              atts.addAttribute("", "year", "year
84              atts.addAttribute("", "month", "mon
85              atts.addAttribute("", "day", "day",
86              handler.startElement("", "hiredate"
87              handler.endElement("", "hiredate",
88              atts.clear();
89
90              handler.endElement("", "employee",
91           }
92        }
93
94        handler.endElement("", "staff", "staff");
95        handler.endDocument();
96     }
97
98     public void setContentHandler(ContentHandler
99     {
100       handler = newValue;
101    }
102
103    public ContentHandler getContentHandler()
104    {
105       return handler;
106    }
107
108    // the following methods are just do-nothing
109    public void parse(String systemId) throws IO
110    public void setErrorHandler(ErrorHandler han
```

```
111     public ErrorHandler getErrorHandler() { retu
112     public void setDTDHandler(DTDHandler handler
113     public DTDHandler getDTDHandler() { return n
114     public void setEntityResolver(EntityResolver
115     public EntityResolver getEntityResolver() {
116     public void setProperty(String name, Object
117     public Object getProperty(String name) { ret
118     public void setFeature(String name, boolean
119     public boolean getFeature(String name) { ret
120 }
```

`javax.xml.transform.TransformerFactory` **1.4**

- `Transformer newTransformer(Source styleSheet)`
  returns an instance of the `Transformer` class that reads a stylesheet from the given source.

`javax.xml.transform.stream.StreamSource` **1.4**

- `StreamSource(File f)`
- `StreamSource(InputStream in)`
- `StreamSource(Reader in)`
- `StreamSource(String systemID)`
  construct a stream source from a file, stream, reader, or system ID (usually a relative or absolute URL).

`javax.xml.transform.sax.SAXSource` **1.4**

- `SAXSource(XMLReader reader, InputSource source)`
  constructs a SAX source that obtains data from the given input source and uses the given reader to parse the input.

org.xml.sax.XMLReader **1.4**

- `void setContentHandler(ContentHandler handler)`
  sets the handler that is notified of parse events as the input is parsed.
- `void parse(InputSource source)`
  parses the input from the given input source and sends parse events to the content handler.

`javax.xml.transform.dom.DOMResult` **1.4**

- `DOMResult(Node n)`
  constructs a source from the given node. Usually, `n` is a new document node.

`org.xml.sax.helpers.AttributesImpl` **1.4**

- `void addAttribute(String uri, String lname, String`

`qname, String type, String value)`
adds an attribute to this attribute collection. The `lname` parameter is the local name without prefix, and `qname` is the qualified name with prefix. The `type` parameter is one of `"CDATA"`, `"ID"`, `"IDREF"`, `"IDREFS"`, `"NMTOKEN"`, `"NMTOKENS"`, `"ENTITY"`, `"ENTITIES"`, or `"NOTATION"`.

- `void clear()`
  removes all attributes from this attribute collection.

This example concludes our discussion of XML support in the Java API. You should now have a good perspective on the major strengths of XML—in particular, its automated parsing and validation as well as its powerful transformation mechanism. Of course, all this technology is only going to work for you if you design your XML formats well. You need to make sure that the formats are rich enough to express all your business needs, that they are stable over time, and that your business partners are willing to accept your XML documents. Those issues can be far more challenging than dealing with parsers, DTDs, or transformations.

In the next chapter, we will discuss network programming on the Java platform, starting with the basics of network sockets and moving on to higher-level protocols for e-mail and the World Wide Web.

1. Networking

We begin this chapter by reviewing basic networking concepts, then move on to writing Java programs that connect to network services. We will show you how network clients and servers are implemented. Finally, you will see how to send e-mail from a Java program and how to harvest information from a web server.

1.1. Connecting to a Server

In the following sections, you will connect to a server, first by hand and with telnet, and then with a Java program.

1.1.1. Using Telnet

The telnet program is a great debugging tool for network programming. You should be able to launch it by typing `telnet` from a command shell.

Note: In Windows, you need to activate telnet. Go to the Control Panel, select Programs, click Turn Windows Features On or Off, and select the Telnet client checkbox. The Windows firewall also blocks quite a few

network ports that we use in this chapter; you might need an administrator account to unblock them.

You may have used telnet to connect to a remote computer, but you can use it to communicate with other services provided by Internet hosts as well. Here is an example of what you can do. Type

```
telnet time-a.nist.gov 13
```

As Figure 4.1 shows, you should get back a line like this:

```
57488 16-04-10 04:23:00 50 0 0 610.5 UTC(NIST) *
```



Figure 1.1: Output of the "time of day" service

What is going on? You have connected to the "time of day" service that most UNIX machines constantly run. The particular server that you connected to is operated by the National Institute of Standards and Technology and gives the measurement of a Cesium atomic clock. (Of course, the reported time is not completely accurate due to network delays.)

By convention, the "time of day" service is always attached to "port" number 13.

Note: In network parlance, a port is not a physical device, but an abstraction facilitating communication between a server and a client (see Figure 4.2).



Figure 1.2: A client connecting to a server port

The server software is continuously running on the remote machine, waiting for any network traffic that wants to chat with port 13. When the operating system on the remote computer receives a network package that contains a request to connect to port number 13, it wakes up the listening server process and establishes the connection. The connection stays up until it is terminated by one of the parties.

When you began the telnet session with `time-a.nist.gov` at port 13, a piece of network software knew enough to convert the string `"time-a.nist.gov"` to its correct Internet Protocol (IP) address, 129.6.15.28. The telnet software then sent a connection request to that address, asking for a connection to port 13. Once the connection was established, the remote program sent back a line of data and closed the connection. In general, of course, clients and servers engage in a more extensive dialog before one or the other closes the connection.

Here is another experiment along the same lines—but a bit more interesting. Type

```
telnet horstmann.com 80
```

Then type very carefully the following:

```
GET /index.html HTTP/1.1
Host: horstmann.com
blank line
```

That is, hit the Enter key twice at the end.

Figure 4.3 shows the response. It should look eerily familiar—you got a page of HTML-formatted text, namely Cay Horstmann's home

page.

Figure 1.3: Using telnet to access an HTTP port

This is exactly the same process that your web browser goes through to get a web page. It uses HTTP to request web pages from servers. Of course, the browser displays the HTML code more nicely.

Note: The `Host` key/value pair is required when you connect to a web server that hosts multiple domains at the same IP address. You can omit it if the server hosts a single domain.

1.1.2. Connecting to a Server with Java

Our first network program in Listing 4.1 will do the same thing we did using telnet—connect to a port and print out what it finds.

Listing 1.1 `socket/SocketTest.java`

```
1  package socket;
2
3  import java.io.*;
4  import java.net.*;
5  import java.util.*;
6
7  /**
8   * This program makes a socket connection to th
9   * the time that the server sends.
10  * @version 1.23 2023-08-16
11  * @author Cay Horstmann
12  */
13 public class SocketTest
14 {
```

```
15    public static void main(String[] args) throw
16    {
17       try (var s = new Socket("time-a.nist.gov"
18             var in = new Scanner(s.getInputStre
19       {
20          while (in.hasNextLine())
21          {
22             String line = in.nextLine();
23             System.out.println(line);
24          }
25       }
26    }
27 }
```

The key statements of this simple program are these:

```
var s = new Socket("time-a.nist.gov", 13);
InputStream inStream = s.getInputStream();
```

The first line opens a *socket*, which is a network software abstraction that enables communication out of and into this program. We pass the remote address and the port number to the socket constructor. If the connection fails, an `UnknownHostException` is thrown, which is a subclass of `IOException`.

The `getInputStream` method in `java.net.Socket` returns an `InputStream` object that you can use just like any other stream.

The method throws an `IOException` if it is not possible to read from the socket. Once you have grabbed the stream, this program simply prints each input line to standard output. This process continues until the stream is finished and the server disconnects.

This program works only with very simple servers, such as a "time of day" service. In more complex networking programs, the client sends request data to the server, and the server might not immediately disconnect at the end of a response. You will see how to implement that behavior in several examples throughout this chapter.

The `Socket` class is pleasant and easy to use because the Java library hides the complexities of establishing a networking connection and sending data across it. The `java.net` package essentially gives you the same programming interface you would use to work with a file.

Note: In this book, we cover only the Transmission Control Protocol (TCP). The Java platform also supports the User Datagram Protocol (UDP), which can be used to send packets (also called *datagrams*) with much less overhead than TCP. The drawback is that packets need not be delivered in sequential order to the receiving application and can even be dropped

altogether. It is up to the recipient to put the packets in order and to request retransmission of missing packets. UDP is well suited for applications in which missing packets can be tolerated—for example, for audio or video streams or continuous measurements.

`java.net.Socket` **1.0**

- `Socket(String host, int port)`
  constructs a socket to connect to the given host and port.
- `InputStream getInputStream()`
- `OutputStream getOutputStream()`
  get the stream to read data from the socket or write data to the socket.

1.1.3. Socket Timeouts

Reading from a socket blocks until data are available. If the host is unreachable, your application waits for a long time and you are at the mercy of the underlying operating system to eventually time out.

You can decide what timeout value is reasonable for your particular application. Then, call the `setSoTimeout` method to set a timeout value (in milliseconds).

```
var s = new Socket(. . .);
s.setSoTimeout(10000); // time out after 10 seconds
```

If the timeout value has been set for a socket, all subsequent read operations throw a `SocketTimeoutException` when the timeout has been reached before the operation has completed its work. You can catch that exception and react to the timeout.

```
try
{
   InputStream in = s.getInputStream(); // read from
   . . .
}
catch (SocketTimeoutException e)
{
   react to timeout
}
```

There is no timeout for write operations.

There is one additional timeout issue that you need to address. The constructor

```
Socket(String host, int port)
```

can block indefinitely until an initial connection to the host is established.

You can overcome this problem by first constructing an unconnected socket and then connecting it with a timeout:

```
var s = new Socket();
s.connect(new InetSocketAddress(host, port), timeout)
```

See Section 4.2.4 for how to allow users to interrupt a socket connection at any time.

`java.net.Socket` **1.0**

- `Socket()` **1.1**
  creates a socket that has not yet been connected.
- `void connect(SocketAddress address)` **1.4**
  connects this socket to the given address.
- `void connect(SocketAddress address, int timeoutInMilliseconds)` **1.4**
  connects this socket to the given address, or throws a `SocketTimeoutException` if the time interval expired.

- `void setSoTimeout(int timeoutInMilliseconds)` 1.1
  sets the blocking time for read requests on this socket. If the timeout is reached when reading, a `SocketTimeoutException` is thrown.
- `boolean isConnected()` 1.4
- `boolean isClosed()` 1.4
  returns `true` if the socket is connected or closed.

1.1.4. Internet Addresses

Usually, you don't have to worry too much about Internet addresses—the numerical host addresses that consist of 4 bytes (or, with IPv6, 16 bytes) such as 129.6.15.28. However, you can use the `InetAddress` class if you need to convert between host names and Internet addresses.

The `java.net` package supports IPv6 Internet addresses, provided the host operating system does.

The static `getByName` method returns an `InetAddress` object of a host. For example,

```
InetAddress address = InetAddress.getByName("time-a.n
```

returns an `InetAddress` object that encapsulates the sequence of four bytes 129.6.15.28. You can access the bytes with the `getAddress` method.

```
byte[] addressBytes = address.getAddress();
```

Some host names with a lot of traffic correspond to multiple Internet addresses, to facilitate load balancing. For example, at the time of this writing, the host name `google.com` corresponds to twelve different Internet addresses. One of them is picked at random when the host is accessed. You can get all hosts with the `getAllByName` method.

```
InetAddress[] addresses = InetAddress.getAllByName(ho
```

Finally, you sometimes need the address of the local host. If you simply ask for the address of `localhost`, you always get the local loopback address 127.0.0.1, which cannot be used by others to connect to your computer. Instead, use the static `getLocalHost` method to get the address of your local host.

```
InetAddress address = InetAddress.getLocalHost();
```

Listing 4.2 is a simple program that prints the Internet address of your local host if you do not specify any command-line arguments, or all Internet addresses of another host if you specify the host name on the command line, such as

```
java inetAddress.InetAddressTest www.horstmann.com
```

Listing 1.2 inetAddress/InetAddressTest.java

```
1  package inetAddress;
2
3  import java.io.*;
4  import java.net.*;
5
6  /**
7   * This program demonstrates the InetAddress cl
8   * argument, or run without command-line argume
9   * @version 1.02 2012-06-05
10  * @author Cay Horstmann
11  */
12 public class InetAddressTest
13 {
14    public static void main(String[] args) throw
15    {
16       if (args.length > 0)
17       {
```

```
18            String host = args[0];
19            InetAddress[] addresses = InetAddress
20            for (InetAddress a : addresses)
21               System.out.println(a);
22         }
23         else
24         {
25            InetAddress localHostAddress = InetAdd
26            System.out.println(localHostAddress);
27         }
28      }
29   }
```

`java.net.InetAddress` **1.0**

- `static InetAddress getByName(String host)`
- `static InetAddress[] getAllByName(String host)`
  construct an `InetAddress`, or an array of all Internet addresses, for the given host name.
- `static InetAddress getLocalHost()`
  constructs an `InetAddress` for the local host.
- `byte[] getAddress()`
  returns an array of bytes that contains the numerical address.
- `String getHostAddress()`
  returns a string with decimal numbers, separated by periods, for example `"129.6.15.28"`.

- `String getHostName()`
  returns the host name.

1.2. Implementing Servers

Now that we have implemented a basic network client that receives data from the Internet, let's program a simple server that can send information to clients.

1.2.1. Server Sockets

A server program, when started, waits for a client to attach to its port. For our example program, we chose port number 8189, which is not used by any of the standard services. The `ServerSocket` class establishes a socket. In our case, the command

```
var s = new ServerSocket(8189);
```

establishes a server that monitors port 8189. The command

```
Socket incoming = s.accept();
```

tells the program to wait indefinitely until a client connects to that port. Once someone connects to this port by sending the correct request over the network, this method returns a `Socket` object that

represents the connection that was made. You can use this object to get input and output streams, as is shown in the following code:

```
InputStream inStream = incoming.getInputStream();
OutputStream outStream = incoming.getOutputStream();
```

Everything that the server sends to the server output stream becomes the input of the client program, and all the output from the client program ends up in the server input stream.

In all the examples in this chapter, we transmit text through sockets. We therefore turn the streams into scanners and writers.

```
var in = new Scanner(inStream);
var out = new PrintWriter(new OutputStreamWriter(outS
```

Let’s send the client a greeting:

```
out.println("Hello! Enter BYE to exit.");
```

When you use telnet to connect to this server program at port 8189, you will see this greeting on the terminal screen.

In this simple server, we just read the client's input, a line at a time, and echo it. This demonstrates that the program receives the input. An actual server would obviously compute and return an answer depending on the input.

```
String line = in.nextLine();
out.println("Echo: " + line);
if (line.strip().equals("BYE")) done = true;
```

In the end, we close the incoming socket.

```
incoming.close();
```

That is all there is to it. Every server program, such as an HTTP web server, continues performing this loop:

1. It receives a command from the client ("get me this information") through an incoming data stream.
2. It decodes the client command.
3. It gathers the information that the client requested.
4. It sends the information to the client through the outgoing data stream.

Listing 4.3 is the complete program.

Listing 1.3 server/EchoServer.java

```
1  package server;
2
3  import java.io.*;
4  import java.net.*;
5  import java.util.*;
6
7  /**
8   * This program implements a simple server that
9   * or a port given as argument, and echoes back
10  * @version 1.23 2023-08-16
11  * @author Cay Horstmann
12  */
13 public class EchoServer
14 {
15    public static void main(String[] args) throw
16    {
17       int port = args.length >= 1 ? Integer.par
18
19       try (var s = new ServerSocket(port); // e
20             Socket incoming = s.accept()) // wa
21       {
22          serve(incoming);
23       }
24    }
25
26    public static void serve(Socket incoming) th
```

```
27      {
28         try (var in = new Scanner(incoming.getInp
29            var out = new PrintWriter(incoming.get
30               true /* autoFlush */))
31         {
32            out.println( "Hello! Enter BYE to exit
33
34            // echo client input
35            boolean done = false;
36            while (!done && in.hasNextLine())
37            {
38               String line = in.nextLine();
39               out.println("Echo: " + line);
40               if (line.strip().equals("BYE"))
41                  done = true;
42            }
43         }
44      }
45   }
```

To try it out, compile and run the program. Then use telnet to connect to the server `localhost` (or IP address 127.0.0.1) and port 8189.

If you are connected directly to the Internet, anyone in the world can access your echo server, provided they know your IP address and the magic port number.

When you connect to the port, you will see the message shown in Figure 4.4:

```
Hello! Enter BYE to exit.
```



Figure 1.4: Accessing an echo server

Type anything and watch the input echo on your screen. Type `BYE` (all uppercase letters) to disconnect. The server program will terminate as well.

`java.net.ServerSocket` **1.0**

- `ServerSocket(int port)`
  creates a server socket that monitors a port.

- `Socket accept()`
  waits for a connection. This method blocks (i.e., idles) the current thread until the connection is made. The method returns a `Socket` object through which the program can communicate with the connecting client.
- `void close()`
  closes the server socket.

1.2.2. Serving Multiple Clients

There is one problem with the simple server in the preceding example. Suppose we want to allow multiple clients to connect to our server at the same time. Typically, a server runs constantly on a server computer, and clients from all over the Internet might want to use it at the same time. Without support for multiple connections, any one client can monopolize the service by connecting to it for a long time. We can do much better through the magic of threads.

Every time we know the program has established a new socket connection—that is, every time the call to `accept()` returns a socket—we will launch a new thread to take care of the connection between the server and *that* client. The main program will just go back and wait for the next connection. For this to happen, the main loop of the server must look like this:

```
ExecutorService service = Executors.newVirtualThreadP
while (true)
{
   Socket incoming = s.accept();
   service.submit(() -> serve(incoming));
}
```

The `serve` method contains the communication loop with the client:

```
public void serve(Socket incoming)
{
   try (var in = new Scanner(incoming.getInputStream(
      var out = new PrintWriter(incoming.getOutputStr
         true /* autoFlush */))
   {
      Process input and send response
   }
   catch (IOException e)
   {
      Handle exception
   }
}
```

When each connection starts a new thread, multiple clients can connect to the server at the same time. You can easily check this out.

1. Compile and run the server program (Listing 4.4).
2. Open several telnet windows as we have in Figure 4.5.
3. Switch between windows and type commands. Note that you can communicate through all of them simultaneously.
4. When done, switch to the window from which you launched the server program and press Ctrl+C to kill it.



Figure 1.5: Several telnet windows communicating simultaneously

Listing 1.4 threaded/EchoServer.java

```
1  package threaded;
2
3  import java.io.*;
4  import java.net.*;
5  import java.util.*;
6  import java.util.concurrent.*;
7
8  /**
9   * This program implements a multithreaded serv
10  * all client input.
11  * @author Cay Horstmann
12  * @version 1.24 2023-08-16
13  */
14 public class EchoServer
15 {
16    public static void main(String[] args) throw
17    {
18       try (var s = new ServerSocket(8189))
19       {
20          int i = 1;
21          ExecutorService service = Executors.ne
22
23          while (true)
24          {
25             Socket incoming = s.accept();
26             System.out.println("Spawning " + i)
```

```
27              service.submit(() -> serve(incoming
28              i++;
29           }
30        }
31     }
32
33     public static void serve(Socket incoming)
34     {
35        try (var in = new Scanner(incoming.getInp
36           var out = new PrintWriter(incoming.get
37              true /* autoFlush */))
38        {
39           out.println( "Hello! Enter BYE to exit
40
41           // echo client input
42           boolean done = false;
43           while (!done && in.hasNextLine())
44           {
45              String line = in.nextLine();
46              out.println("Echo: " + line);
47              if (line.strip().equals("BYE"))
48                 done = true;
49           }
50        }
51        catch (IOException e)
52        {
53           e.printStackTrace();
```

```
54          }
55       }
56    }
```

1.2.3. Half-Close

The *half-close* allows one end of a socket connection to terminate its output while still receiving data from the other end.

Here is a typical situation. Suppose you transmit data to the server but you don't know at the outset how much data you have. With a file, you'd just close the file at the end of the data. However, if you close a socket, you immediately disconnect from the server and cannot read the response.

The half-close solves this problem. You can close the output stream of a socket, thereby indicating to the server the end of the requested data, but keep the input stream open.

The client side looks like this:

```
try (var socket = new Socket(host, port))
{
   var in = new Scanner(socket.getInputStream());
   var writer = new PrintWriter(socket.getOutputStrea
   // send request data
   writer.print(. . .);
```

```
      writer.flush();
      socket.shutdownOutput();
      // now socket is half-closed
      // read response data
      while (in.hasNextLine())
      {
         String line = in.nextLine();
         . . .
      }
   }
```

The server side simply reads input until the end of the input stream is reached. Then it sends the response.

Of course, this protocol is only useful for one-shot services such as HTTP where the client connects, issues a request, catches the response, and then disconnects.

`java.net.Socket` **1.0**

- `void shutdownInput()` **1.3**
- `void shutdownOutput()` **1.3**

  sets the input or output stream to "end of stream."

- `boolean isInputShutdown()` 1.4
- `boolean isOutputShutdown()` 1.4

returns `true` if input or output has been shut down.

1.2.4. Interruptible Sockets

When you connect to a socket, the current thread blocks until the connection has been established or a timeout has elapsed. Similarly, when you read data through a socket, the current thread blocks until the operation is successful or has timed out. (There is no timeout for writing data.)

In interactive applications, you would like to give users an option to simply cancel a socket connection that does not appear to produce results. However, if a platform thread blocks on an unresponsive socket, you cannot unblock it by calling `interrupt`.

Note: When using virtual threads, socket operations are interruptible, and you do not need the technique discussed in this section.

To interrupt a socket operation, use a `SocketChannel`, a feature of the `java.nio` package. Open the `SocketChannel` like this:

```
SocketChannel channel = SocketChannel.open(new InetSo
```

A channel does not have associated streams. Instead, it has `read` and `write` methods that make use of `Buffer` objects. (See Chapter 2 for more information about NIO buffers.) These methods are declared in the interfaces `ReadableByteChannel` and `WritableByteChannel`.

If you don't want to deal with buffers, you can use the `Scanner` class to read from a `SocketChannel` because `Scanner` has a constructor with a `ReadableByteChannel` parameter:

```
var in = new Scanner(channel);
```

To turn a channel into an output stream, use the static `Channels.newOutputStream` method.

```
OutputStream outStream = Channels.newOutputStream(cha
```

That's all you need to do. Whenever a thread is interrupted during an open, read, or write operation, the operation does not block, but is terminated with an exception.

The program in Listing 4.5 contrasts interruptible and blocking sockets. A server sends numbers and pretends to be stuck after the tenth number. You are asked whether you want to use a socket or a

channel. You can also choose between platform and virtual threads. A client thread is started that connects to the server and prints the output. Hit Enter to interrupt the client thread. If you do so within the first ten numbers, you can interrupt the thread.

However, if you use a socket and a platform thread, interruption after the first ten numbers does not work. The blocking thread keeps blocking until the server finally closes the connection. The remedy is to use a channel or virtual threads.

Listing 1.5 interruptible/InterruptibleSocketTest.java

```
1  package interruptible;
2
3  import java.util.*;
4  import java.net.*;
5  import java.io.*;
6  import java.nio.channels.*;
7
8  /**
9   * This program shows how to interrupt a socket
10  * @author Cay Horstmann
11  * @version 1.1 2023-08-16
12  */
13 public class InterruptibleSocketTest
14 {
```

```
15    public static void main(String[] args)
16    {
17       Thread.ofPlatform().start(new TestServer(
18       Scanner console = new Scanner(System.in);
19       System.out.print("Socket or channel? (S/C
20       boolean socket = console.nextLine().equal
21       System.out.print("Platform or virtual? (P
22       boolean platform = console.nextLine().equ
23       Runnable client = socket ? InterruptibleS
24             : InterruptibleSocketTest::useChann
25       Thread clientThread = platform ? Thread.o
26             : Thread.ofVirtual().start(client);
27
28       System.out.print("Hit Enter to interrupt
29       console.nextLine();
30       clientThread.interrupt();
31    }
32
33    /**
34     * Connects to the test server, using a chan
35     */
36    public static void useChannel()
37    {
38       System.out.println("Channel:\n");
39       try (SocketChannel channel
40             = SocketChannel.open(new InetSocket
41       {
42          Scanner in = new Scanner(channel);
```

```
43          while (!Thread.currentThread().isInter
44          {
45             System.out.print("Reading ");
46             if (in.hasNextLine())
47             {
48                String line = in.nextLine();
49                System.out.println(line);
50             }
51          }
52       }
53       catch (IOException e)
54       {
55          e.printStackTrace();
56       }
57       finally
58       {
59          System.out.println("Channel closed\n")
60       }
61    }
62
63    /**
64     * Connects to the test server, using a sock
65     */
66    public static void useSocket()
67    {
68       System.out.println("Socket:\n");
69       try (var sock = new Socket("localhost", 8
70       {
```

```
71          Scanner in = new Scanner(sock.getInput
72          while (!Thread.currentThread().isInter
73          {
74             System.out.print("Reading ");
75             if (in.hasNextLine())
76             {
77                String line = in.nextLine();
78                System.out.println(line);
79             }
80          }
81       }
82       catch (IOException e)
83       {
84          e.printStackTrace();
85       }
86       finally
87       {
88          System.out.println("Socket closed\n");
89       }
90    }
91
92    /**
93     * A server that listens to port 8189 and se
94     * simulating a hanging server after 10 numb
95     */
96    static class TestServer implements Runnable
97    {
98       public void run()
```

```
99        {
100          try (var s = new ServerSocket(8189);
101             Socket incoming = s.accept())
102          {
103             serve(incoming);
104          }
105          catch (Exception e)
106          {
107             e.printStackTrace();;
108          }
109          finally
110          {
111             System.out.println("Closing connect
112          }
113       }
114
115       private void serve(Socket incoming) throw
116       {
117          int counter = 0;
118          try (var out = new PrintWriter(incomi
119                true /* autoFlush */))
120          {
121             while (counter < 100)
122             {
123                counter++;
124                if (counter <= 10) out.println(c
125                Thread.sleep(100);
126             }
```

```
127             }
128          }
129       }
130    }
```

`java.net.InetSocketAddress` **1.4**

- `InetSocketAddress(String hostname, int port)`
  constructs an address object with the given host and port, resolving the host name during construction. If the host name cannot be resolved, the address object's `unresolved` property is set to `true`.
- `boolean isUnresolved()`
  returns `true` if this address object could not be resolved.

`java.nio.channels.SocketChannel` **1.4**

- `static SocketChannel open(SocketAddress address)`
  opens a socket channel and connects it to a remote address.

`java.nio.channels.Channels` **1.4**

- `static InputStream newInputStream(ReadableByteChannel channel)`
  constructs an input stream that reads from the given channel.

- `static OutputStream newOutputStream(WritableByteChannel channel)` constructs an output stream that writes to the given channel.

1.2.5. Secure Socket Communication

When you implement clients and servers across the Internet and you exchange confidential information, you do not want to use plain text traffic. Instead, you should use a secure communication mechanism. There are three aspects to secure communication:

- The communication is encrypted, so it cannot be read by third parties.
- The identity of the server is authenticated with a digital signature that the client verifies. Optionally, the client can also provide a digital signature, but this is not common for web applications.
- Transmitted data are digitally signed by the sender and verified by the receiver, guaranteeing that no third party modified or substituted the data.

The TLS (Transport Layer Security) protocol is the most common mechanism for secure communication. It is a successor to the SSL (Secure Socket Layer) protocol.

In Java, you use classes from the `javax.net.ssl` package to establish secure connections. Here is how to construct a socket for a

secure connection:

```
SocketFactory factory = SSLSocketFactory.getDefault()
Socket s = factory.createSocket(host, port);
```

For secure server sockets, you also use a factory:

```
ServerSocketFactory factory = SSLServerSocketFactory.
ServerSocket s = factory.createServerSocket(port);
```

If you need to configure the secure connection parameters of the client or server socket, cast the object returned by the factory to a `SSLSocket` or `SSLServerSocket`:

```
((SSLServerSocket) s).setNeedClientAuth(true);
```

The client and server encrypt the traffic, using a shared encryption key. However, they need to know that they are really talking to each other and not to a "man in the middle". The server presents a certificate to vouch for its authenticity. The certificate needs to be signed by a certificate authority known to the client. The JDK has a built-in list of known certificate authorities. You would normally

obtain a server certificate from one of them and install it in the server. However, for testing, we will generate our own certificates.

See Chapter 9 for a detailed description of certificates and the `keytool` program used to manage them. Here are the commands to generate the certificates and place them in a "key store" for the server and client.

First, generate the server certificate:

```
keytool -genkeypair -alias servercert -keyalg RSA -ke
```

You will be asked a number of questions about the organization in charge of the server. For this demonstration, you can leave them all to the default value of "unknown".

Next, export the certificate and import it into the client store.

```
keytool -exportcert -keystore server.jks -storepass s
keytool -import -trustcacerts -file servercert.pem -k
```

When importing the certificate, which is not signed by one of the known certificate authorities, you will be asked whether you trust it. Answer with `yes`.

Now start the server. You need to specify the keystore containing the server certificate.

```
java -Djavax.net.ssl.keyStore=server.jks -Djavax.net.
```

Then run the client, specifying the keystore containing the certificate that the client trusts. This would not be necessary if the certificate was signed by a certificate authority that is known to the JDK.

```
java -Djavax.net.ssl.trustStore=client.jks -Djavax.ne
```

Tip: If there are connection problems, try running the client with the `-Djavax.net.debug=ssl` command-line option.

Listing 1.6 ssl/EchoClient.java

```
1 package ssl;
2
3 import java.io.*;
4 import java.util.*;
5
6 import java.net.*;
```

```
 7 import javax.net.*;
 8 import javax.net.ssl.*;
 9
10 /**
11  * This program makes a socket connection to th
12  * the time that the server sends.
13  * @version 1.23 2023-08-16
14  * @author Cay Horstmann
15  */
16 public class EchoClient
17 {
18    public static void main(String[] args) throw
19    {
20       int port = args.length >= 1 ? Integer.par
21       SocketFactory factory = SSLSocketFactory
22       String message = """
23 Hello
24 World
25 BYE
26 """;
27       try (Socket s = factory.createSocket(Inet
28          OutputStream os = s.getOutputStream();
29          var in = new Scanner(s.getInputStream(
30       {
31          os.write(message.getBytes());
32          os.flush();
33          boolean done = false;
34          while (!done)
```

```
35          {
36             String line = in.nextLine();
37             System.out.println(line);
38             if (line.equals("Echo: BYE")) done
39          }
40       }
41    }
42 }
```

Listing 1.7 ssl/EchoServer.java

```
1  package ssl;
2
3  import java.io.*;
4  import java.net.*;
5  import java.util.*;
6  import java.util.concurrent.*;
7  import javax.net.*;
8  import javax.net.ssl.*;
9
10 /**
11  * This program implements a simple server that
12  * or a port given as argument, and echoes back
13  * @version 1.0 2023-08-16
14  * @author Cay Horstmann
15  */
16 public class EchoServer
17 {
```

```
18    public static void main(String[] args) throw
19    {
20       int port = args.length >= 1 ? Integer.par
21       // establish server socket
22       ServerSocketFactory factory = SSLServerSo
23       try (ServerSocket s = factory.createServe
24       {
25          ExecutorService service = Executors.ne
26
27          while (true)
28          {
29             // wait for client connection
30             Socket incoming = s.accept();
31             service.submit(() -> serve(incoming
32          }
33       }
34    }
35
36    public static void serve(Socket incoming)
37    {
38       try (var in = new Scanner(incoming.getInp
39          var out = new PrintWriter(incoming.get
40             true /* autoFlush */))
41       {
42          out.println( "Hello! Enter BYE to exit
43
44          // echo client input
45          boolean done = false;
```

```
46            while (!done && in.hasNextLine())
47            {
48               String line = in.nextLine();
49               out.println("Echo: " + line);
50               if (line.strip().equals("BYE"))
51                  done = true;
52            }
53         }
54         catch (IOException e)
55         {
56            e.printStackTrace();
57         }
58      }
59   }
```

`javax.net.ServerSocketFactory` **1.4**

- `static ServerSocket createServerSocket(int port)`
  yields a server socket for the given port.

`javax.net.ssl.SSLServerSocketFactory` **1.4**

- `static ServerSocketFactory getDefault()`
  returns a factory that produces `SSLServerSocket` instances.

`javax.net.ssl.SSLSocketFactory` `1.4`

- `static SocketFactory getDefault()`
  returns a factory that produces `SSLSocket` instances.

`javax.net.SocketFactory` `1.4`

- `static Socket createSocket(InetAddress host, int port)`
  `static Socket createSocket(String host, int port)`
  yields a socket for connecting to the given host and port.

1.3. Getting Web Data

To access web servers in a Java program, you will want to work at a higher level than socket connections and HTTP requests. In the following sections, we discuss the classes that the Java library provides for this purpose.

1.3.1. URLs and URIs

The `java.net` package makes a useful distinction between URLs (uniform resource *locators*) and URIs (uniform resource *identifiers*).

A URI is a purely syntactical construct that contains the various parts of the string specifying a web resource. A URL is a special kind of

URI, namely one with sufficient information to *locate* a resource. Other URIs, such as

```
mailto:cay@horstmann.com
```

are not locators—there is no data to locate from this identifier. Such a URI is called a URN (uniform resource *name*).

In the Java library, the `URI` class has no methods for accessing the resource that the identifier specifies—its sole purpose is parsing. In contrast, the `URL` class can open a stream to the resource. For that reason, the `URL` class only works with schemes that the Java library knows how to handle, such as `http:`, `https:`, `ftp:`, the local file system (`file:`), and JAR files (`jar:`).

You can construct a `URL` object from a `URI`:

```
var url = new URI(urlString).toURL();
```

Caution: The `URL` class has constructors that were deprecated in Java 20. They have various technical issues that make it possible to construct invalid URLs. Instead, first construct a URI, and then obtain the URL, as shown above.

If you simply want to fetch the contents of the resource, use the `openStream` method of the `URL` class. This method yields an `InputStream` object. Use it in the usual way—for example, to construct a `Scanner`:

```
InputStream inStream = url.openStream();
var in = new Scanner(inStream);
```

In the next section, you will see how to use the `URLConnection` class for more control over the connection.

Let us return to URIs. To see why parsing is not trivial, consider how complex URIs can be. For example,

```
https://google.com?q=Beach+Chalet
ftp://username:password@ftp.yourserver.com/pub/file.t
```

The URI specification gives the rules for the makeup of these identifiers. A URI has the syntax

```
[scheme:]schemeSpecificPart[#fragment]
```

Here, the brackets [ ] enclose optional parts, and the `:` and `#` are included literally in the identifier.

If the `scheme:` part is present, the URI is called *absolute*. Otherwise, it is called *relative*.

An absolute URI is *opaque* if the `schemeSpecificPart` does not begin with a `/` such as

```
mailto:cay@horstmann.com
```

All absolute nonopaque URIs and all relative URIs are *hierarchical*. Examples are

```
http://horstmann.com/index.html
../../java/net/Socket.html#Socket()
```

The `schemeSpecificPart` of a hierarchical URI has the structure

```
[//authority][path][?query]
```

where, again, the brackets [ ] enclose optional parts.

For server-based URIs, the authority part has the form

```
[user-info@]host[:port]
```

The `port` must be an integer.

RFC 2396, which standardizes URIs, also supports a registry-based mechanism in which the authority has a different format, but this is not in common use.

One of the purposes of the `URI` class is to parse an identifier and break it up into its components. You can retrieve them with the methods

```
getScheme
getSchemeSpecificPart
getAuthority
getUserInfo
getHost
getPort
getPath
getQuery
getFragment
```

The other purpose of the `URI` class is the handling of absolute and relative identifiers. If you have an absolute URI such as

```
https://docs.mycompany.com/api/java/net/ServerSocket.
```

and a relative URI such as

```
../../java/net/Socket.html#Socket()
```

then you can combine the two into an absolute URI.

```
https://docs.mycompany.com/api/java/net/Socket.html#S
```

This process is called *resolving* a relative URL.

The opposite process is called *relativization*. For example, suppose you have a *base* URI

```
https://docs.mycompany.com/api
```

and a URI

```
https://docs.mycompany.com/api/java/lang/String.html
```

Then the relativized URI is

```
java/lang/String.html
```

The URI class supports both of these operations:

```
relative = base.relativize(combined);
combined = base.resolve(relative);
```

1.3.2. Using a `URLConnection` to Retrieve Information

If you want additional information about a web resource, you should use the `URLConnection` class, which gives you much more control than the basic `URL` class.

When working with a `URLConnection` object, you must carefully schedule your steps.

1. Call the `openConnection` method of the `URL` class to obtain the `URLConnection` object:

```
URLConnection connection = url.openConnection();
```

2. Set any request properties, using the methods

```
setDoInput
setDoOutput
setIfModifiedSince
setUseCaches
setAllowUserInteraction
```

```
setRequestProperty
setConnectTimeout
setReadTimeout
```

We discuss these methods later in this section and in the API notes.

3. Connect to the remote resource by calling the `connect` method:

```
connection.connect();
```

Besides making a socket connection to the server, this method also queries the server for *header information.*

4. After connecting to the server, you can query the header information. Two methods, `getHeaderFieldKey` and `getHeaderField`, enumerate all fields of the header. The method `getHeaderFields` gets a standard `Map` object containing the header fields. For your convenience, the following methods query standard fields:

```
getContentType
getContentLength
getContentEncoding
```

```
getDate
getExpiration
getLastModified
```

5. Finally, you can access the resource data. Use the `getInputStream` method to obtain an input stream for reading the information. (This is the same input stream that the `openStream` method of the `URL` class returns.) The other method, `getContent`, isn't very useful in practice. The objects that are returned by standard content types such as `text/plain` and `image/gif` require classes in the `com.sun` hierarchy for processing. You could register your own content handlers, but we do not discuss this technique in our book.

Caution: Some programmers form a wrong mental image when using the `URLConnection` class, thinking that the `getInputStream` and `getOutputStream` methods are similar to those of the `Socket` class. But that isn't quite true. The `URLConnection` class does quite a bit of magic behind the scenes—in particular, the handling of request and response headers. For that reason, it is important that you follow the setup steps for the connection.

Let us now look at some of the `URLConnection` methods in detail. Several methods set properties of the connection before connecting

to the server. The most important ones are `setDoInput` and `setDoOutput`. By default, the connection yields an input stream for reading from the server but no output stream for writing. If you want an output stream (for example, for posting data to a web server), you need to call

```
connection.setDoOutput(true);
```

Next, you may want to set some of the request headers. The request headers are sent together with the request command to the server. Here is an example:

```
GET www.server.com/index.html HTTP/1.0
Referer: https://www.somewhere.com/links.html
Proxy-Connection: Keep-Alive
User-Agent: Mozilla/5.0 (X11; U; Linux i686; en-US; r
Host: www.server.com
Accept: text/html, image/gif, image/jpeg, image/png,
Accept-Language: en
Accept-Charset: iso-8859-1,*,utf-8
Cookie: orangemilano=192218887821987
```

The `setIfModifiedSince` method tells the connection that you are only interested in data modified since a certain date.

Finally, you can use the catch-all `setRequestProperty` method to set any name/value pair that is meaningful for the particular protocol. For the format of the HTTP request headers, see RFC 2616. Some of these properties are not well documented and are passed around by word of mouth from one programmer to the next. For example, if you want to access a password-protected web page, you must do the following:

1. Concatenate the username, a colon, and the password.

```
String input = username + ":" + password;
```

2. Compute the Base64 encoding of the resulting string. (The Base64 encoding encodes a sequence of bytes into a sequence of printable ASCII characters.)

```
Base64.Encoder encoder = Base64.getEncoder();
String encoding = encoder.encodeToString(input.getB
```

3. Call the `setRequestProperty` method with a name of `"Authorization"` and the value `"Basic " + encoding`.

```
connection.setRequestProperty("Authorization", "Bas
```



Tip: You just saw how to access a password-protected web page. To access a password-protected file by FTP, use an entirely different method: Construct a URL of the form

```
ftp://username:password@ftp.yourserver.com/pub/file.t
```

Once you call the `connect` method, you can query the response header information. First, let's see how to enumerate all response header fields. The implementors of this class felt a need to express their individuality by introducing yet another iteration protocol. The call

```
String key = connection.getHeaderFieldKey(n);
```

gets the `n` th key from the response header, where `n` starts from `1` ! It returns `null` if `n` is less than 1 or greater than the total number of header fields. There is no method to return the number of fields; you simply keep calling `getHeaderFieldKey` until you get `null` . Similarly, the call

```
String value = connection.getHeaderField(n);
```

returns the `n` th value.

The method `getHeaderFields` returns a `Map` of response header fields.

```
Map<String,List<String>> headerFields = connection.ge
```

Here is a set of response header fields from a typical HTTP request:

```
Date: Wed, 27 Aug 2008 00:15:48 GMT
Server: Apache/2.2.2 (Unix)
Last-Modified: Sun, 22 Jun 2008 20:53:38 GMT
Accept-Ranges: bytes
Content-Length: 4813
Connection: close
Content-Type: text/html
```

Note: Even though `connection.getHeaderFieldKey(0)` returns `null`, you can call `connection.getHeaderField(0)` to get the response status line (such as `"HTTP/1.1 200 OK"`). You also get it when you call `headerFields.get(null)`.

As a convenience, six methods query the values of the most common header types and convert them to numeric types when appropriate. Table 4.1 shows these convenience methods. The methods with return type `long` return the number of seconds since January 1, 1970 GMT.

Table 1.1: Convenience Methods for Response Header Values

Key Name	Method Name	Return Type
`Date`	`getDate`	`long`
`Expires`	`getExpiration`	`long`
`Last-Modified`	`getLastModified`	`long`
`Content-Length`	`getContentLength`	`int`
`Content-Type`	`getContentType`	`String`
`Content-Encoding`	`getContentEncoding`	`String`

The program in Listing 4.8 lets you experiment with URL connections. Supply a URL and an optional username and password on the command line when running the program, for example:

```
java urlConnection.URLConnectionTest https://horstman
```

The program prints

- All keys and values of the header
- The return values of the six convenience methods in Table 4.1
- The first ten lines of the requested resource

Listing 1.8 urlConnection/URLConnectionTest.java

```
1  package urlConnection;
2
3  import java.io.*;
4  import java.net.*;
5  import java.util.*;
6
7  /**
8   * This program connects to an URL and displays
9   * 10 lines of the requested data.
10  *
11  * Supply the URL and an optional username and
12  * command line.
13  * @version 1.13 2023-08-16
14  * @author Cay Horstmann
15  */
```

```
16 public class URLConnectionTest
17 {
18    public static void main(String[] args)
19    {
20       try
21       {
22          String urlName;
23          if (args.length > 0) urlName = args[0]
24          else urlName = "http://horstmann.com";
25
26          var url = new URI(urlName).toURL();
27          URLConnection connection = url.openCon
28
29          // set username, password if specified
30
31          if (args.length > 2)
32          {
33             String username = args[1];
34             String password = args[2];
35             String input = username + ":" + pas
36             Base64.Encoder encoder = Base64.get
37             String encoding = encoder.encodeToS
38             connection.setRequestProperty("Auth
39          }
40
41          connection.connect();
42
43          // print header fields
```

```
44
45          Map<String, List<String>> headers = co
46          for (Map.Entry<String, List<String>> e
47          {
48             String key = entry.getKey();
49             for (String value : entry.getValue(
50                System.out.println(key + ": " +
51          }
52
53          // print convenience functions
54
55          System.out.println("----------");
56          System.out.println("getContentType: "
57          System.out.println("getContentLength:
58          System.out.println("getContentEncoding
59          System.out.println("getDate: " + conne
60          System.out.println("getExpiration: " +
61          System.out.println("getLastModifed: "
62          System.out.println("----------");
63
64          String encoding = connection.getConter
65          if (encoding == null) encoding = "UTF-
66          try (var in = new Scanner(connection.g
67          {
68             // print first ten lines of content
69
70             for (int n = 1; in.hasNextLine() &&
71                System.out.println(in.nextLine()
```

```
72                if (in.hasNextLine()) System.out.pr
73             }
74          }
75          catch (IOException | URISyntaxException e
76          {
77             e.printStackTrace();
78          }
79       }
80    }
```

`java.net.URL` **1.0**

- `InputStream openStream()`
  opens an input stream for reading the resource data.
- `URLConnection openConnection()`
  returns a `URLConnection` object that manages the connection to the resource.

`java.net.URLConnection` **1.0**

- `void setDoInput(boolean doInput)`
- `boolean getDoInput()`
  If `doInput` is `true`, the user can receive input from this `URLConnection`.

- `void setDoOutput(boolean doOutput)`
- `boolean getDoOutput()`
  If `doOutput` is `true`, the user can send output to this `URLConnection`.
- `void setIfModifiedSince(long time)`
- `long getIfModifiedSince()`
  The `ifModifiedSince` property configures this `URLConnection` to fetch only data modified since a given time. The time is given in seconds since midnight, GMT, January 1, 1970.
- `void setConnectTimeout(int timeout)` **5.0**
- `int getConnectTimeout()` **5.0**
  set or get the timeout for the connection (in milliseconds). If the timeout has elapsed before a connection was established, the `connect` method of the associated input stream throws a `SocketTimeoutException`.
- `void setReadTimeout(int timeout)` **5.0**
- `int getReadTimeout()` **5.0**
  set or get the timeout for reading data (in milliseconds). If the timeout has elapsed before a read operation was successful, the `read` method throws a `SocketTimeoutException`.
- `void setRequestProperty(String key, String value)`
  sets a request header field.

- `Map<String,List<String>> getRequestProperties()` **1.4**
  returns a map of request properties. All values for the same key are placed in a list.
- `void connect()`
  connects to the remote resource and retrieves the response header information.
- `Map<String,List<String>> getHeaderFields()` **1.4**
  returns a map of response headers. All values for the same key are placed in a list.
- `String getHeaderFieldKey(int n)`
  gets the key for the `n` th response header field, or `null` if `n` is ≤ `0` or greater than the number of response header fields.
- `String getHeaderField(int n)`
  gets value of the `n` th response header field, or the response status line if `n` is 0 or `null` if `n` is < `0` or greater than the number of response header fields.
- `int getContentLength()`
  gets the content length if available, or `-1` if unknown.
- `String getContentType()`
  gets the content type, such as `text/plain` or `image/gif`.
- `String getContentEncoding()`
  gets the content encoding, such as `gzip`. This value is not commonly used, because the default `identity` encoding is not supposed to be specified with a `Content-Encoding` header.

- `long getDate()`
- `long getExpiration()`
- `long getLastModifed()`
  get the date of creation, expiration, and last modification of the resource. The dates are specified as seconds since midnight, GMT, January 1, 1970.
- `InputStream getInputStream()`
- `OutputStream getOutputStream()`
  return a stream for reading from the resource or writing to the resource.
- `Object getContent()`
  selects the appropriate content handler to read the resource data and convert it into an object. This method is not useful for reading standard types such as `text/plain` or `image/gif` unless you install your own content handler.

1.3.3. Posting Form Data

In the preceding section, you saw how to read data from a web server. Now we will show you how your programs can send data back to a web server and to programs that the web server invokes.

To send information from a web browser to the web server, a user fills out a *form*, like the one in Figure 4.6.


ZIP Code™ Lookup | USPS - Mozilla Firefox
https://tools.usps.com/zip-code-lookup.htm?byaddress
English
Locations
Support
Informed Delivery
Register / Sign In
USPS.COM
Quick Tools
Mail & Ship
Track & Manage
Postal Store
Business
International
Help
Look Up a ZIP Code™
ZIP Code™ by Address
ZIP Code™ by City and State
Cities by ZIP Code™
FAQs
ZIP Code™ by Address
Enter a street address along with city and state OR enter a street address and ZIP Code™.
*indicate a required field
Company
*Street Address
1 Main Street
Apt/Suite/Other
City
San Francisco
State
CA - California
ZIP Code™
Enter ZIP Code™
Find
USPS.COM

Figure 1.6: An HTML form

When the user clicks the Submit button, the text in the text fields and the settings of any checkboxes, radio buttons, and other input elements are sent back to the web server. The web server invokes a program that processes the user input.

Many technologies enable web servers to invoke programs. Among the best known ones are Java servlets, JavaServer Faces, Microsoft Active Server Pages (ASP), and Common Gateway Interface (CGI) scripts.

The server-side program processes the form data and produces another HTML page that the web server sends back to the browser. This sequence is illustrated in Figure 4.7. The response page can contain new information (for example, in an information-search program) or just an acknowledgment. The web browser then displays the response page.



Figure 1.7: Data flow during execution of a server-side program

We do not discuss the implementation of server-side programs in this book. Our interest is merely in writing client programs that interact with existing server-side programs.

When form data are sent to a web server, it does not matter whether the data are interpreted by a servlet, a CGI script, or some other server-side technology. The client sends the data to the web server in a standard format, and the web server takes care of passing it on to the program that generates the response.

Two commands, called `GET` and `POST`, are commonly used to send information to a web server.

In the `GET` command, you simply attach query parameters to the end of the URL. The URL has the form

```
https://host/path?query
```

Each parameter has the form `name=value`. Parameters are separated by `&` characters. Parameter values are encoded using the *URL encoding* scheme, following these rules:

- Leave the characters `A` through `Z`, `a` through `z`, `0` through `9`, and `. - ~ _` unchanged.
- Replace all spaces with `+` characters.
- Encode all other characters into UTF-8 and encode each byte by a `%`, followed by a two-digit hexadecimal number.

For example, to transmit *San Francisco, CA*, you use `San+Francisco%2c+CA`, as the hexadecimal number `2c` is the UTF-8 code of the `','` character.

This encoding keeps any intermediate programs from messing with spaces and other special characters.

At the time of this writing, the Google Maps site (https://www.google.com/maps) accepts query parameters with names `q` and `hl` whose values are the location query and the

human language of the response. To get a map of 1 Market Street in San Francisco, with a response in German, use the following URL:

```
https://www.google.com/maps?q=1+Market+Street+San+Fra
```

Very long query strings can look unattractive in browsers, and older browsers and proxies have a limit on the number of characters that you can include in a `GET` request. For that reason, a `POST` request is often used for forms with a lot of data. In a `POST` request, you do not attach parameters to a URL; instead, you get an output stream from the `URLConnection` and write name/value pairs to the output stream. You still have to URL-encode the values and separate them with `&` characters.

Let us look at this process in detail. To post data to a server-side program, first establish a `URLConnection`:

```
URL url = new URI("https://host/path").toURL();
URLConnection connection = url.openConnection();
```

Then, call the `setDoOutput` method to set up the connection for output:

```
connection.setDoOutput(true);
```

Next, call `getOutputStream` to get a stream through which you can send data to the server. If you are sending text to the server, it is convenient to wrap that stream into a `PrintWriter`.

```
var out = new PrintWriter(connection.getOutputStream(
```

Now you are ready to send data to the server:

```
out.print(name1 + "=" + URLEncoder.encode(value1, Sta
out.print(name2 + "=" + URLEncoder.encode(value2, Sta
```

Close the output stream:

```
out.close();
```

Finally, call `getInputStream` and read the server response.

Caution: The static methods `URLEncoder.encode` and `URLDecoder.decode` have a version that uses the default charset, but they have been deprecated in Java 6 because they should

always be used with UTF-8. Sadly, they are still deprecated even though Java 18 changed the default character encoding to UTF-8.

Let's run through a practical example. The web site at https://tools.usps.com/zip-code-lookup.htm?byaddress contains a form to find the zip code for a street address (see Figure 4.6). To use this form in a Java program, you need to know the URL and the parameters of the `POST` request.

You could get that information by looking at the HTML code of the form, but it is usually easier to "spy" on a request with a network monitor. Most browsers have a network monitor as part of their development toolkit. For example, Figure 4.8 shows a screen capture of the Firefox network monitor when submitting data to our example web site. You can find out the submission URL as well as the parameter names and values.



Figure 1.8: Monitoring the submission of a form

When posting form data, the HTTP header includes the content type:

```
Content-Type: application/x-www-form-urlencoded
```

You can also post data in other formats. For example, when sending data in JavaScript Object Notation (JSON), set the content type to `application/json`.

The header for a `POST` must also include the content length, for example

```
Content-Length: 124
```

The program in Listing 4.9 sends `POST` form data to any server-side program. Place the data into a `.properties` file such as the following:

```
url=https://tools.usps.com/tools/app/ziplookup/zipByA
User-Agent=HTTPie/0.9.2
address1=1 Market Street
address2=
city=San Francisco
state=CA
companyName=
. . .
```

The program removes the `url` and `User-Agent` entries and sends all others to the `doPost` method.

In the `doPost` method, we first open the connection and set the user agent. (The zip code service does not work with the default `User-Agent` request parameter which contains the string `Java`, perhaps because the postal service doesn't want to serve programmatic requests.)

Then we call `setDoOutput(true)`, and open the output stream. We then enumerate all keys and values. For each of them, we send the `key`, `=` character, `value`, and `&` separator character:

```
out.print(key);
out.print("=");
out.print(URLEncoder.encode(value, StandardCharsets.U
if (more pairs) out.print("&");
```

When switching from writing to reading any part of the response, the actual interaction with the server happens. The `Content-Length` header is set to the size of the output. The `Content-Type` header is set to `application/x-www-form-urlencoded` unless a different content type was specified. The headers and data are sent to the server. Then the response headers and server response are read and can be queried. In our example program, this switch happens in the call to `connection.getContentEncoding()`.

There is one twist with reading the response. If a server-side error occurs, the call to `connection.getInputStream()` throws a `FileNotFoundException`. However, the server still sends an error page back to the browser (such as the ubiquitous "Error 404—page not found"). To capture this error page, call the `getErrorStream` method:

```
InputStream err = connection.getErrorStream();
```

Note: The `getErrorStream` method, as well as several other methods in this program, belong to the `HttpURLConnection` subclass of `URLConnection`. If you make a request to an URL that starts with `http://` or `https://`, you can cast the resulting connection object to `HttpURLConnection`.

When you send `POST` data to a server, it can happen that the server-side program responds with a *redirect*: a different URL that should be called to get the actual information. The server could do that because the information is available elsewhere, or to provide a bookmarkable URL. The `HttpURLConnection` class can handle redirects in most cases.

Note: If cookies need to be sent from one site to another in a redirect, you can configure the global cookie handler like this:

```
CookieHandler.setDefault(new CookieManager
```

Then cookies will be properly included in the redirect.

Even though redirects are usually automatically handled, there are some situations where you need to do them yourself. Automatic redirects between HTTP and HTTPS are not supported for security reasons. Redirects can also fail for more subtle reasons. For example, an earlier version of the zip code service used a redirect. Recall that we set the `User-Agent` request parameter so that the post office didn't think we made a request via the Java API. While it is possible to set the user agent to a different string in the initial request, that setting is not used in automatic redirects. Instead, automatic redirects always send a generic user agent string that contains the word `Java`.

In such situations, you can manually carry out the redirects. Before connecting the server, turn off automatic redirects:

```
connection.setInstanceFollowRedirects(false);
```

After making the request, get the response code:

```
int responseCode = connection.getResponseCode();
```

Check if it is one of

```
HttpURLConnection.HTTP_MOVED_PERM
HttpURLConnection.HTTP_MOVED_TEMP
HttpURLConnection.HTTP_SEE_OTHER
```

In that case, get the `Location` response header to obtain the URL for the redirect. Then disconnect and make another connection to the new URL:

```
String location = connection.getHeaderField("Location
if (location != null)
{
   URL base = connection.getURL();
   connection.disconnect();
   URL url = base.toURI().resolve(location).toURL();
```

```
    connection = (HttpURLConnection) url.openConnectio
    . . .
}
```

The techniques that this program illustrates can be useful whenever you need to query information from an existing web site. Simply find out the parameters that you need to send, and then strip out the HTML tags and other unnecessary information from the reply.

Listing 1.9 post/PostTest.java

```
1  package post;
2
3  import java.io.*;
4  import java.net.*;
5  import java.nio.charset.*;
6  import java.nio.file.*;
7  import java.util.*;
8
9  /**
10  * This program demonstrates how to use the URL
11  * @version 1.44 2023-08-16
12  * @author Cay Horstmann
13  */
14 public class PostTest
15 {
```

```
16    public static void main(String[] args) throw
17    {
18       String propsFilename = args.length > 0 ?
19       var props = new Properties();
20       try (Reader in = Files.newBufferedReader(
21             Path.of(propsFilename)))
22       {
23          props.load(in);
24       }
25       String urlString = props.remove("url").to
26       Object userAgent = props.remove("User-Age
27       Object redirects = props.remove("redirect
28       CookieHandler.setDefault(new CookieManage
29       String result = doPost(new URI(urlString)
30          userAgent == null ? null : userAgent.t
31          redirects == null ? -1 : Integer.parse
32       System.out.println(result);
33    }
34
35    /**
36     * Do an HTTP POST.
37     * @param url the URL to post to
38     * @param nameValuePairs the query parameter
39     * @param userAgent the user agent to use, c
40     * @param redirects the number of redirects
41     * redirects
42     * @return the data returned from the server
43     * @throws URISyntaxException
```

```
44      */
45     public static String doPost(URL url, Map<Obj
46           int redirects) throws IOException, URI
47     {
48        var connection = (HttpURLConnection) url
49        if (userAgent != null)
50           connection.setRequestProperty("User-Ag
51
52        if (redirects >= 0)
53           connection.setInstanceFollowRedirects(
54
55        connection.setDoOutput(true);
56
57        try (var out = new PrintWriter(connection
58        {
59           boolean first = true;
60           for (Map.Entry<Object, Object> pair :
61           {
62              if (first) first = false;
63              else out.print("&");
64              String name = pair.getKey().toStrin
65              String value = pair.getValue().toSt
66              out.print(name);
67              out.print("=");
68              out.print(URLEncoder.encode(value,
69           }
70        }
71        String encoding = connection.getContentEn
```

```
72        if (encoding == null) encoding = "UTF-8";
73
74        if (redirects > 0)
75        {
76           int responseCode = connection.getRespo
77           if (responseCode == HttpURLConnection
78                 || responseCode == HttpURLConnec
79                 || responseCode == HttpURLConnec
80           {
81              String location = connection.getHea
82              if (location != null)
83              {
84                 URL base = connection.getURL();
85                 connection.disconnect();
86                 return doPost(base.toURI().resol
87                       redirects - 1);
88              }
89           }
90        }
91        else if (redirects == 0)
92        {
93           throw new IOException("Too many redire
94        }
95
96        var response = new StringBuilder();
97        try (var in = new Scanner(connection.getI
98        {
99           while (in.hasNextLine())
```

```
100             {
101                response.append(in.nextLine());
102                response.append("\n");
103             }
104          }
105          catch (IOException e)
106          {
107             InputStream err = connection.getErrorS
108             if (err == null) throw e;
109             try (var in = new Scanner(err))
110             {
111                response.append(in.nextLine());
112                response.append("\n");
113             }
114          }
115
116          return response.toString();
117       }
118    }
```

`java.net.HttpURLConnection` **1.0**

- `InputStream getErrorStream()`
  returns a stream from which you can read web server error messages.

`java.net.URLEncoder` 1.0

- `static String encode(String s, String encoding)` 1.4
  returns the URL-encoded form of the string `s`, using the given character encoding scheme. (The recommended scheme is `"UTF-8"`.) In URL encoding, the characters `A`–`Z`, `a`–`z`, `0`–`9`, `- _ . ~` are left unchanged. Space is encoded into `+`, and all other characters are encoded into sequences of encoded bytes of the form `%XY`, where `0xXY` is the hexadecimal value of the byte.

`java.net.URLDecoder` 1.2

- `static string decode(String s, String encoding)` 1.4
  returns the decoding of the URL encoded string `s` under the given character encoding scheme.

1.4. The HTTP Client

The `URLConnection` class was designed before HTTP was the universal protocol of the Web. It provides support for a number of protocols, but its HTTP support is somewhat cumbersome. When the decision was made to support HTTP/2, it became clear that it would be best to provide a modern client interface instead of reworking the existing API. The `HttpClient` provides HTTP/2 support and a more

convenient API than the `URLConnection` class with its rather fussy set of stages.

1.4.1. The `HttpClient` Class

An `HttpClient` can issue requests and receive responses. You get a client by calling

```
HttpClient client = HttpClient.newHttpClient()
```

Alternatively, if you need to configure the client, you use a builder API, like this:

```
HttpClient client = HttpClient.newBuilder()
   .followRedirects(HttpClient.Redirect.ALWAYS)
   .build();
```

That is, you get a builder, call methods to customize the item that is going to be built, and then call the `build` method to finalize the building process. This is a common pattern for constructing immutable objects.

There are a number of advanced options for selecting HTTP 2 and for controlling cookies, SSL, proxy settings, and authentication.

The `HttpClient` is autocloseable, so you can declare it in a `try`-with-resources statement. Its `close` method waits for the completion of submitted requests and then closes its connection pool.

1.4.2. The `HttpRequest` class and Body Publishers

You also follow the builder pattern for formulating requests. Here is a `GET` request:

```
HttpRequest request = HttpRequest.newBuilder()
    .uri(new URI(urlString))
    .GET()
    .build();
```

The URI is the "uniform resource identifier" which is, when using HTTP, the same as a URL. However, in Java, the `URL` class has methods for actually opening a connection to a URL, whereas the `URI` class is only concerned with the syntax (scheme, host, port, path, query, fragment, and so on).

With a `POST` request, you need a "body publisher" that turns the request data into the data that is being posted. There are body publishers for strings, byte arrays, and files. For example, if your

request is in JSON, you just provide the JSON string to a string body publisher.

```
HttpRequest request = HttpRequest.newBuilder()
    .uri(new URI(urlString))
    .header("Content-Type", "application/json")
    .POST(HttpRequest.BodyPublishers.ofString(jsonStri
    .build();
```

It is unfortunate that the API does not support the required formatting for common content types. The sample program in Listing 4.10 provides body publishers for form data and file uploads.

In that program, you can see how body publishers are used to send strings and files. The file upload requires both, employing the `BodyPublishers.concat` method to concatenate multiple body publishers to produce the request body.

The `HttpRequest.Builder` class also has build methods for the less common `PUT`, `DELETE`, and `HEAD` requests.

Java 16 adds a builder for filtering the headers of an existing `HttpRequest`. You provide the request and a function that receives the header names and values, returning `true` for those that should be retained. For example, here we modify the content type:

```
HttpRequest request2 = HttpRequest.newBuilder(request
      (name, value) -> !name.equalsIgnoreCase("Conten
   .header("Content-Type", "application/xml") // Add
   .build();
```

1.4.3. The `HttpResponse` Interface and Body Handlers

When sending the request, you have to tell the client how to handle the response. If you just want the body as a string, send the request with a `HttpResponse.BodyHandlers.ofString()`, like this:

```
HttpResponse<String> response = client.send(request,
```

`HttpResponse` is a generic interface whose type parameter denotes the type of the response body. You get the response body string simply as

```
String bodyString = response.body();
```

There are other response body handlers that get the response as a byte array or input stream. `BodyHandlers.ofFile(filePath)` yields a handler that saves the response to the given file, and

`BodyHandlers.ofFileDownload(directoryPath)` saves the response in the given directory, using the file name from the `Content-Disposition` header. Finally, the handler obtained from `BodyHandlers.discarding()` simply discards the response.

Processing the contents of the response is not considered part of the API. For example, if you receive JSON data, you need a JSON library to parse the contents.

The `HttpResponse` object also yields the status code and the response headers.

```
int status = response.statusCode();
HttpHeaders responseHeaders = response.headers();
```

You can turn the `HttpHeaders` object into a map:

```
Map<String, List<String>> headerMap = responseHeaders
```

The map values are lists since in HTTP, each key can have multiple values.

If you just want the value of a particular key, and you know that there won't be multiple values, call the `firstValue` method:

```
Optional<String> lastModified = responseHeaders.first
```

You get the response value or an empty optional if none was supplied.

Note: The `HttpHeaders` class is aware that keys for HTTP parameters are case-insensitive. If you call `responseHeaders.firstValue("Last-Modified")`, you get the desired header value even if it was sent as `last-modified`.

1.4.4. Asynchronous Processing

You can process the response asynchronously. When building the client, provide an executor:

```
ExecutorService executor = Executors.newCachedThreadP
HttpClient client = HttpClient.newBuilder().executor(
```

Build a request and then invoke the `sendAsync` method on the client. You receive a `CompletableFuture<HttpResponse<T>>`, where `T` is the type of the body handler. Use the `CompletableFuture` API as described in Chapter 10 of Volume I:

```
HttpRequest request = HttpRequest.newBuilder().uri(ur
client.sendAsync(request, HttpResponse.BodyHandlers.o
   thenAccept(response -> . . .);
```

Tip: To enable logging for the `HttpClient`, add this line to `net.properties` in your JDK:

```
jdk.httpclient.HttpClient.log=all
```

Instead of `all`, you can specify a comma-separated list of the following event types:

- `channel`
- `content`
- `errors`
- `frames`, optionally followed by one or more of `:control`, `:data`, `:window`, or `:all`
- `headers`
- `requests`
- `ssl`
- `trace`

Don't use any spaces:

```
jdk.httpclient.HttpClient.log=headers,requests,frames
```

Then, set the logging level for the logger with name `jdk.httpclient.HttpClient` to `INFO`, for example by adding this line to the `logging.properties` file in your JDK:

```
jdk.httpclient.HttpClient.level=INFO
```

The program in Listing 4.10 shows how to make synchronous requests to different services. Run it as:

```
java httpClient.HttpClientTest form.properties
java httpClient.HttpClientTest fileupload.properties
java httpClient.HttpClientTest json.properties
```

With each run, a "Hello, World" program is sent to the CodeCheck service, and the result of running it is displayed. That service can accept form posts, file uploads, and JSON posts. Note the logging output from the `HttpClient`.

Listing 1.10 httpClient/HttpClientTest.java

```
1  package httpClient;
2
3  import java.io.*;
4  import java.net.*;
5  import java.nio.charset.*;
6  import java.nio.file.*;
7  import java.util.*;
8  import java.util.stream.Stream;
9  import java.net.http.*;
10 import java.net.http.HttpRequest.*;
11
12 /**
13  * This program demonstrates the HTTP client
14  * @version 1.02 2023-08-16
15  * @author Cay Horstmann
16  */
17 class MoreBodyPublishers
18 {
19    public static BodyPublisher ofFormData(Map<O
20    {
21       boolean first = true;
22       var builder = new StringBuilder();
23       for (Map.Entry<Object, Object> entry : da
24       {
25          if (first) first = false;
26          else builder.append("&");
```

```
27          builder.append(URLEncoder.encode(entry
28             StandardCharsets.UTF_8));
29          builder.append("=");
30          builder.append(URLEncoder.encode(entry
31             StandardCharsets.UTF_8));
32       }
33       return BodyPublishers.ofString(builder.to
34    }
35
36    public static BodyPublisher ofMimeMultipartD
37          throws IOException
38    {
39       var bps = new ArrayList<BodyPublisher>();
40       var header = new StringBuilder();
41       for (Map.Entry<String, List<?>> entry : d
42       {
43          for (Object value : entry.getValue())
44          {
45             header.append("--%s\r\nContent-Disp
46                   boundary, entry.getKey()));
47
48             if (value instanceof Path path)
49             {
50                header.append("; filename=\"%s\"
51                String mimeType = Files.probeCon
52                if (mimeType != null) header.app
53                header.append("\r\n");
54                bps.add(BodyPublishers.ofString(
```

```
55                  bps.add(BodyPublishers.ofFile(pa
56              }
57              else
58              {
59                  header.append("\r\n\r\n%s\r\n".f
60                  header.append("\r\n");
61                  bps.add(BodyPublishers.ofString(
62              }
63              header = new StringBuilder("\r\n");
64          }
65      }
66      bps.add(BodyPublishers.ofString("\r\n--%s
67      return BodyPublishers.concat(bps.toArray(
68  }
69
70  public static BodyPublisher ofSimpleJSON(Map
71  {
72      var builder = new StringBuilder();
73      builder.append("{");
74      var first = true;
75      for (Map.Entry<Object, Object> entry : da
76      {
77          if (first) first = false;
78          else
79              builder.append(",");
80          builder.append(jsonEscape(entry.getKey
81              .append(jsonEscape(entry.getValue()
82      }
```

```
83          builder.append("}");
84          return BodyPublishers.ofString(builder.to
85       }
86
87       private static Map<Character, String> replac
88          '\n', "\\n", '\r', "\\r", '\t', "\\t", ''
89
90       private static StringBuilder jsonEscape(Stri
91       {
92          var result = new StringBuilder("\"");
93          for (int i = 0; i < str.length(); i++)
94          {
95             char ch = str.charAt(i);
96             String replacement = replacements.get(
97             if (replacement == null) result.append
98             else result.append(replacement);
99          }
100         result.append("\"");
101         return result;
102      }
103   }
104
105   public class HttpClientTest
106   {
107      public static void main(String[] args)
108            throws IOException, URISyntaxExceptior
109      {
110         System.setProperty("jdk.httpclient.HttpCl
```

```
111         String propsFilename = args.length > 0 ?
112         Path propsPath = Path.of(propsFilename);
113         var props = new Properties();
114         try (Reader in = Files.newBufferedReader(
115         {
116            props.load(in);
117         }
118         String urlString = "" + props.remove("url
119         String contentType = "" + props.remove("C
120         BodyPublisher publisher = null;
121         if (contentType.equals("application/x-www
122            publisher = MoreBodyPublishers.ofFormD
123         else if (contentType.equals("multipart/fo
124         {
125            // Split each value along commas, repl
126            // file:// with Path objects
127            var data = new HashMap<String, List<?>
128            for (Map.Entry<Object, Object> entry
129            {
130               data.put(entry.getKey().toString(),
131                     Stream.of(entry.getValue().to
132                        .map(s -> s.startsWith("fi
133                           ? propsPath.getParent()
134                           : s)
135                        .toList());
136            }
137            String boundary = UUID.randomUUID().to
138            contentType += "; boundary=" + boundar
```

```
139             publisher = MoreBodyPublishers.ofMimeM
140          }
141          else
142          {
143             contentType = "application/json";
144             publisher = MoreBodyPublishers.ofSimpl
145          }
146
147          String result = doPost(urlString, content
148          System.out.println(result);
149       }
150
151       public static String doPost(String url, Stri
152             throws IOException, URISyntaxExceptior
153       {
154          try (HttpClient client = HttpClient.newBu
155             .followRedirects(HttpClient.Redirect.A
156          {
157
158             HttpRequest request  = HttpRequest.new
159                .uri(new URI(url))
160                .header("Content-Type", contentType
161                .POST(publisher)
162                .build();
163
164             HttpResponse<String> response
165                = client.send(request, HttpResponse
166             return response.body();
```

```
167         }
168     }
169 }
```

`java.net.http.HttpClient` **11**

- `static HttpClient newHttpClient()`
  yields an `HttpClient` with a default configuration.
- `static HttpClient.Builder newBuilder()`
  yields a builder for building an `HttpClient`.
- `<T> HttpResponse<T> send(HttpRequest request, HttpResponse.BodyHandler<T> responseBodyHandler)`
- `<T> CompletableFuture<HttpResponse<T>> sendAsync(HttpRequest request, HttpResponse.BodyHandler<T> responseBodyHandler)`
  make a synchronous or asynchronous request and process the response body with the given handler.

`java.net.http.HttpClient.Builder` **11**

- `HttpClient build()`
  yields an `HttpClient` with the properties configured by this builder.
- `HttpClient.Builder`

`followRedirects(HttpClient.Redirect policy)`
sets the redirect policy to one of the values `ALWAYS`, `NEVER`, or `NORMAL` (only refuse redirects from HTTPS to HTTP) of the `HttpClient.Redirect` enumeration.

- `HttpClient.Builder executor(Executor executor)`
sets the executor for asynchronous requests.

`java.net.http.HttpRequest` **11**

- `HttpRequest.Builder newBuilder()`
returns a builder for building an `HttpRequest`.
- `HttpRequest.Builder newBuilder(HttpRequest request, BiPredicate<String,String> filter)` **16**
returns a builder for building a request with the same properties as the provided one, with only the headers that are accepted by the filter.

`java.net.http.HttpRequest.Builder` **11**

- `HttpRequest build()`
yields an `HttpRequest` with the properties configured by this builder.
- `HttpRequest.Builder uri(URI uri)`
sets the URI for this request.

- `HttpRequest.Builder header(String name, String value)`
  sets a request header for this request.
- `HttpRequest.Builder GET()`
- `HttpRequest.Builder DELETE()`
- `HttpRequest.Builder POST(HttpRequest.BodyPublisher bodyPublisher)`
- `HttpRequest.Builder PUT(HttpRequest.BodyPublisher bodyPublisher)`
  set the request method and body for this request.

`java.net.http.HttpResponse<T>` **11**

- `T body()`
  yields the body of this response.
- `int statusCode()`
  yields the status code for this response.
- `HttpHeaders headers()`
  yields the response headers.

`java.net.http.HttpHeaders` **11**

- `Map<String,List<String>> map()`
  yields a `Map` of these headers.

- `Optional<String> firstValue(String name)`
  yields the first value with the given name in these headers, if present.

1.5. The Simple HTTP Server

Since Java 6, the JDK provided a simple web server in the `com.sun.net.httpserver` package. In Java 18, a command-line tool was added to the JDK that invokes a static file server based upon that package. At that time, a few convenience classes were added, and JEP 408 affirms that the package is "officially supported". The web server is intended for testing, development, and debugging.

1.5.1. The Command-Line Tool

To start the simple file server, use the command

```
jwebserver
```

It serves all files in the current directory and its subdirectories on port 8000. When a file is served, a message is printed. You can change the directory and port with the `-d` and `-p` options:

```
jwebserver -d /tmp -p 8189
```

You can also set the message output level with the `-o` command-line option. Choices are `info` (the default), `verbose`, and `none`.

To kill the server, press Ctrl+C or use the `kill` / `pkill` command.

This server is only useful for serving files. It is similar to the `python -m http.server` command. In fact, you can also invoke the simple Java file server as `java -m jdk.httpserver`.

1.5.2. The HTTP Server API

You can start the simple file server programmatically as:

```
import com.sun.net.httpserver.*;
. . .
HttpServer server = SimpleFileServer.createFileServer
   Path.of("/tmp"), OutputLevel.VERBOSE);
server.start();
```

Now you can customize it in various ways. Alternatively, if you don't want to serve files, you can get a do-nothing server as

```
HttpServer server = HttpServer.create(new InetSocketA
```

The second argument is the "backlog" of the server socket—that is, the maximum number of queued connection requests. With a zero argument, a default value is used.

You can set the executor for processing requests:

```
server.setExecutor(Executors.newVirtualThreadPerTaskE
```

For the server to do anything interesting, you need to create *contexts*.

A context has

- A *path* that must be a prefix of the request path
- A *handler* that computes the response
- A list of *filters* that can transform the request or response (see Section 4.5.4)

If a request matches multiple contexts, the one with the longest path is executed. For example, here we install two handlers for paths `/static/` and `/`:

```
server.createContext("/static/", SimpleFileHandler.cr
server.createContext("/", HttpHandlers.of(301, Header
```

Note that you can leverage existing handlers, such as the handler of the simple file server.

The static `HttpHandlers.of` method produces a simple handler that returns a fixed response. You pass the status code, response headers, and response body.

The static `HttpHandlers.handleOrElse` uses a `Predicate<Request>` to select among two handlers:

```
HttpHandler handler = HttpHanders.handleOrElse(reques
   SimpleFileHandler.createFileHandler(staticRoot).
   HttpHandlers.of(500, Headers.of(), "Bad request me
```

For more complex handlers, you need to provide an instance of a subclass of `HttpHandler`. See the next section for details.

1.5.3. Handlers

A handler produces the response to an HTTP request in its method

```
public void handle(HttpExchange exchange)
```

The `HttpExchange` instance holds both the request and response data. The handler must use the object in this specific order:

1. Read the request method, URI, and headers:

```
String method = exchange.getRequestMethod();
URI uri = exchange.getRequestURI();
Headers requestHeaders = exchange.getRequestHeaders
String userAgent = requestHeaders.getFirst("user-ag
```

2. Read the request body for `POST`, `PUT`, and `PATCH` requests:

```
InputStream in = exchange.getRequestBody();
String body = new String(in.readAllBytes());
in.close();
```

3. Set the response headers:

```
Headers responseHeaders = exchange.getResponseHeade
responseHeaders.add("Content-type", "text/plain");
. . .
```

4. Set the status code and the length of the response body:

```
exchange.sendResponseHeaders(200, responseBytes.len
```

5. Write the response body, if there is one:

```
OutputStream responseBody = exchange.getResponseBod
responseBody.write(responseBytes);
responseBody.close();
```

The request and response headers are instances of the `Headers` class, which implements `Map<String, List<String>>`. Recall that there can be multiple values for each header.

The `Headers` class is similar to the `HttpHeaders` that you saw in Section 4.4, but it directly implements the `Map<String, List<String>>` interface. As with `HttpHeaders`, the keys are case-insensitive.

If you know that there is at most one value for a given key, call `getFirst` to retrieve it. To add a key/value pair to a response map, use the `add` method, as in the code snippet above.

The sample program in Listing 4.11 has an example of a handler that produces a text response with all details of the request.

1.5.4. Filters

In addition to a handler, a context can have a chain of filters. A filter can modify the request or response, or carry out additional work such as logging or authentication. For example, the simple web server uses a filter for displaying the requests.

To implement a filter, extend the abstract `Filter` class and implement two methods. The `description` method should return some descriptive string. Typically, the `doFilter` method looks like this:

```
public void doFilter(HttpExchange exchange, Filter.Ch
{
    Request processing
    chain.doFilter(exchange);
    Response processing
}
```

By calling `chain.doFilter(exchange)`, the remaining filters and the handler are invoked.

A filter can abort further filtering and handling—for example, if authentication fails. Then it should not call `chain.doFilter(exchange)`, and instead produce a response in the `exchange` object.

You add a filter like this:

```
  context.getFilters().add(filter);
```

Caution: As you can see, the HTTP server API is a bit rough and old-fashioned. In your own code, do not provide methods that yield references to internal mutable data structures, as the `Context.getFilters` method does.

The `Filter` class has three static factory methods for filters:

```
  public Filter beforeHandler(String description, Consu
  public Filter afterHandler(String description, Consum
  public Filter adaptRequest(String description, UnaryO
```

The first two pass the `exchange` object (either before or after the request) to the consumer that can inspect or modify it.

The third method makes it a bit more convenient to add a header to a request:

```
  Filter f = Filter.adaptRequest("Adding header", reque
```

Of course, compared with mature web servers, such as Tomcat or Jetty, this server is rather basic. But it is a part of the JDK and can be sufficient for prototyping and testing.

The program in Listing 4.11 shows a simple server that echoes all request data in a plain-text response. Start it and point your browser to `http://localhost:8189` to see the request headers of your browser. The server is also useful for observing the form post and the file upload requests of the program in Listing 4.10.

Listing 1.11 httpServer/EchoServer.java

```
1  package httpServer;
2
3  import java.io.IOException;
4  import java.io.OutputStream;
5  import java.net.InetSocketAddress;
6  import java.util.concurrent.Executors;
7
8  import com.sun.net.httpserver.*;
9
10 /**
11  * This program implements an HTTP server that
12  * or a port given as argument, and echoes back
13  * @version 1.0 2023-11-01
14  * @author Cay Horstmann
15  */
```

```
16 public class EchoServer
17 {
18    public static void main(String[] args) throw
19    {
20       int port = args.length >= 1 ? Integer.par
21       HttpServer server = HttpServer.create(new
22       server.setExecutor(Executors.newVirtualTh
23       server.createContext("/", HttpHandlers.of
24       server.createContext("/echo", (HttpExchan
25             {
26                var headers = new StringBuilder(
27                exchange.getRequestHeaders().for
28                   vs.forEach(v ->
29                      headers.append("%s: %s\n"
30
31                String requestBody = new String(
32                String response = "%s %s\n%s\n%s
33                      exchange.getRequestMethod(
34                      headers,
35                      requestBody);
36                byte[] responseBytes = response
37
38                exchange.sendResponseHeaders(200
39                OutputStream responseBody = exch
40                responseBody.write(responseBytes
41                responseBody.close();
42             }
43          );
```

```
44          server.start();
45       }
46    }
```

1.6. Sending E-Mail

In the past, it was simple to write a program that sends e-mail by making a socket connection to port 25, the SMTP port, of a mail server. The Simple Mail Transport Protocol (SMTP) describes the format for e-mail messages. Once you are connected to the server, send a mail header (in the SMTP format, which is easy to generate), followed by the mail message.

Here are the details:

1. Open a socket to your host.

```
var s = new Socket("mail.yourserver.com", 25); // 2
var out = new PrintWriter(s.getOutputStream());
```

2. Send the following information to the print stream:

```
HELO sending host
MAIL FROM: sender e-mail address
RCPT TO: recipient e-mail address
```

```
DATA
Subject: subject
(blank line)
mail message (any number of lines)
.
QUIT
```

The SMTP specification (RFC 821) states that lines must be terminated with `\r` followed by `\n`.

It used to be that SMTP servers were often willing to route e-mail from anyone. However, in these days of spam floods, most servers have built-in checks and only accept requests from users or IP address ranges that they trust. Authentication usually happens over secure socket connections.

Implementing these authentication schemes manually would be very tedious. Instead, we will show you how to use the Jakarta Mail API to send e-mail from a Java program.

To use Jakarta Mail, you need to set up some properties that depend on your mail server. For example, with GMail, you use

```
mail.transport.protocol=smtps
mail.smtps.auth=true
mail.smtps.host=smtp.gmail.com
```

```
mail.smtps.user=accountname@gmail.com
```

Our sample program reads these from a property file.

For security reasons, we don't put the password into the property file but instead prompt for it.

Caution: With most mail providers, you need to generate and use a special application password instead of using your normal mail password.

Read in the property file, then get a mail session like this:

```
Session mailSession = Session.getDefaultInstance(prop
```

Make a message with the desired sender, recipient, subject, and message text:

```
var message = new MimeMessage(mailSession);
message.setFrom(new InternetAddress(from));
message.addRecipient(RecipientType.TO, new InternetAd
message.setSubject(subject);
message.setText(builder.toString());
```

Then send it off:

```
Transport tr = mailSession.getTransport();
tr.connect(null, password);
tr.sendMessage(message, message.getAllRecipients());
tr.close();
```

The program in Listing 4.12 reads the message from a text file of the format

```
Sender
Recipient
Subject
Message text (any number of lines)
```

To run the program, download the Angus Jakarta Mail implementation from https://eclipse-ee4j.github.io/angus-mail. You need four JAR files: `angus-mail.jar`, `jakarta-mail-api.jar`, `angus-activation.jar`, and `jakarta-activation-api.jar`. Place them inside a directory `jakarta-mail`. Then edit the `mail/mail.properties` file and run

```
javac -classpath .:jakarta-mail/\* mail/MailTest.java
```

```
java -classpath .:jakarta-mail/\* mail.MailTest path/
```

At the time of this writing, GMail does not check the veracity of the information—you can supply any sender you like. (Keep this in mind the next time you get an e-mail message from `president@whitehouse.gov` inviting you to a black-tie affair on the front lawn.)

Tip: If you can't figure out why your mail connection isn't working, an

```
mailSession.setDebug(true);
```

and check out the messages. Also, the Jakarta Mail API FAQ at https://eclipse-ee4j.github.io/angus-mail/FAQ has some useful debugging hints.

Listing 1.12 mail/MailTest.java

```
1  package mail;
2
3  import java.io.*;
4  import java.nio.file.*;
```

```
5  import java.util.*;
6  import jakarta.mail.*;
7  import jakarta.mail.internet.*;
8  import jakarta.mail.internet.MimeMessage.Recipi
9
10 /**
11  * This program shows how to use JavaMail to se
12  * @author Cay Horstmann
13  * @version 1.03 2023-08-16
14  */
15 public class MailTest
16 {
17    public static void main(String[] args) throw
18    {
19       var props = new Properties();
20       try (Reader in = Files.newBufferedReader(
21             Path.of("mail", "mail.properties"))
22       {
23          props.load(in);
24       }
25       List<String> lines = Files.readAllLines(P
26
27       String from = lines.get(0);
28       String to = lines.get(1);
29       String subject = lines.get(2);
30
31       var builder = new StringBuilder();
32       for (int i = 3; i < lines.size(); i++)
```

```
33          {
34             builder.append(lines.get(i));
35             builder.append("\n");
36          }
37
38          Console console = System.console();
39          var password = new String(console.readPas
40
41          Session mailSession = Session.getDefaultI
42          // mailSession.setDebug(true);
43          var message = new MimeMessage(mailSessior
44          message.setFrom(new InternetAddress(from)
45          message.addRecipient(RecipientType.TO, ne
46          message.setSubject(subject);
47          message.setText(builder.toString());
48          Transport tr = mailSession.getTransport()
49          try
50          {
51             tr.connect(null, password);
52             tr.sendMessage(message, message.getAll
53          }
54          finally
55          {
56             tr.close();
57          }
58       }
59    }
```

In this chapter, you have seen how to write network clients and servers in Java and how to harvest information from web servers. The next chapter covers database connectivity. You will learn how to work with relational databases in Java, using the JDBC API.

1. Database Programming

In 1996, Sun released the first version of the JDBC API. This API lets programmers connect to a database to query or update it using the Structured Query Language (SQL). (SQL, usually pronounced "sequel," is an industry standard for relational database access.) JDBC has since become one of the most commonly used APIs in the Java library.

JDBC has been updated several times. As this book is published, JDBC 4.3, the version included with Java 9, is the most current version.

In this chapter, I will explain the key ideas behind JDBC. I will introduce you to (or refresh your memory of) SQL, the industry-standard Structured Query Language for relational databases. The chapter has enough details and examples to let you start using JDBC for common programming situations.

Note: According to Oracle, JDBC is a trademarked term and not an acronym for Java Database Connectivity. It was named to be reminiscent of ODBC, a standard database API pioneered by Microsoft and since incorporated into the SQL standard.

1.1. The Design of JDBC

From the start, the developers of the Java technology were aware of the potential that Java showed for working with databases. In 1995, they began work on extending the standard Java library to deal with SQL access to databases. What they first hoped to do was to extend Java so that a program could talk to any random database using only "pure" Java. It didn't take them long to realize that this is an impossible task: There are simply too many databases out there, using too many protocols. Moreover, although database vendors were all in favor of Java providing a standard network protocol for database access, they were only in favor of it if Java used *their* network protocol.

What all the database vendors and tool vendors *did* agree on was that it would be useful for Java to provide a pure Java API for SQL access along with a driver manager to allow third-party drivers to connect to specific databases. Database vendors could provide their own drivers to plug into the driver manager. There would then be a simple mechanism for registering third-party drivers with the driver manager.

This organization follows the very successful model of Microsoft's ODBC which provided a C programming language interface for database access. Both JDBC and ODBC are based on the same idea:

Programs written according to the API talk to the driver manager, which, in turn, uses a driver to talk to the actual database.

This means the JDBC API is all that most programmers will ever have to deal with.

1.1.1. JDBC Driver Types

The JDBC specification classifies drivers into the following *types*:

- A *type 1 driver* translates JDBC to ODBC and relies on an ODBC driver to communicate with the database. Early versions of Java included one such driver, the *JDBC/ODBC bridge*. However, the bridge requires deployment and proper configuration of an ODBC driver. When JDBC was first released, the bridge was handy for testing, but it was never intended for production use. At this point, many better drivers are available, and the JDK no longer provides the JDBC/ODBC bridge.
- A *type 2 driver* is written partly in Java and partly in native code; it communicates with the client API of a database. To use such a driver, you must install some platform-specific code onto the client in addition to a Java library.
- A *type 3 driver* is a pure Java client library that uses a database-independent protocol to communicate database requests to a server component, which then translates the requests into a

database-specific protocol. This simplifies deployment because the platform-specific code is located only on the server.

- A *type 4 driver* is a pure Java library that translates JDBC requests directly to a database-specific protocol.

Note: The JDBC specification is available at https://jcp.org/aboutJava/communityprocess/mrel/jsr221/index3.html.

Most database vendors supply either a type 3 or type 4 driver with their database. Furthermore, a number of third-party companies specialize in producing drivers with better standards conformance, support for more platforms, better performance, or, in some cases, simply better reliability than the drivers provided by the database vendors.

In summary, the ultimate goal of JDBC is to make possible the following:

- Programmers can write applications in the Java programming language to access any database using standard SQL statements (or even specialized extensions of SQL) while still following Java language conventions.
- Database vendors and database tool vendors can supply the low-level drivers. Thus, they can optimize their drivers for their

specific products.

Note: If you are curious as to why Java just didn't adopt the ODBC model, the reason, as given at the JavaOne conference in 1996, was this:

- ODBC is hard to learn.
- ODBC has a few commands with lots of complex options. The preferred style in the Java programming language is to have simple and intuitive methods, but to have lots of them.
- ODBC relies on the use of `void*` pointers and other C features that are not natural in the Java programming language.
- An ODBC-based solution is inherently less safe and harder to deploy than a pure Java solution.

1.1.2. Typical Uses of JDBC

The traditional client/server model has a rich GUI on the client and a database on the server (see Figure 5.1). In this model, a JDBC driver is deployed on the client.



Figure 1.1: A traditional client/server application

However, nowadays it is far more common to have a three-tier model where the client application does not make database calls. Instead, it calls on a middleware layer on the server that in turn makes the database queries. The three-tier model has a couple of advantages. It separates *visual presentation* (on the client) from the *business logic* (in the middle tier) and the raw data (in the database). Therefore, it becomes possible to access the same data and the same business rules from multiple clients, such as a Java desktop application, a web browser, or a mobile app.

Communication between the client and the middle tier typically occurs through HTTP. JDBC manages the communication between the middle tier and the back-end database. Figure 5.2 shows the basic architecture.



Figure 1.2: A three-tier application

1.2. The Structured Query Language

JDBC lets you communicate with databases using SQL, which is the command language for essentially all relational database servers. Desktop databases such as Microsoft Access have a GUI for queries and updates, but JDBC is focused on server-based databases such as Oracle, PostgreSQL, MySQL, Microsoft SQL Server, and so on.

The JDBC package can be thought of as nothing more than an API for communicating SQL statements to databases. We will briefly introduce SQL in this section. If you have never seen SQL before, you might not find this material sufficient. If so, turn to one of the many learning resources on the topic; I recommend *Learning SQL* by Alan Beaulieu (O'Reilly, 2009) or the online book *Learn SQL The Hard Way* at https://sql.learncodethehardway.org.

You can think of a database as a bunch of named tables with rows and columns. Each column has a *column name*. Each row contains a

set of related data.

As an example database for this book, we use a set of database tables that describe a collection of classic computer science books.

Table 1.1: The `Authors` Table

Author_Id	Name	Fname
ALEX	Alexander	Christopher
BROO	Brooks	Frederick P.
. . .	. . .	. . .

Table 1.2: The `Books` Table

Title	ISBN	Publisher_Id	Price
A Guide to the SQL Standard	0-201-96426-0	0201	47.95
A Pattern Language: Towns,	0-19-501919-9	019	65.00

Title	ISBN	Publisher_Id	Price
Buildings, Construction			
. . .	. . .	. . .	. . .

Table 1.3: The `BooksAuthors` Table

ISBN	Author_Id	Seq_No
0-201-96426-0	DATE	1
0-201-96426-0	DARW	2
0-19-501919-9	ALEX	1
. . .	. . .	. . .

Table 1.4: The `Publishers` Table

Publisher_Id	Name	URL
0201	Addison-Wesley	www.aw-bc.com

Publisher_Id	Name	URL
0407	John Wiley & Sons	www.wiley.com
. . .	. . .	. . .

Figure 5.3 shows a view of the `Books` table. Figure 5.4 shows the result of *joining* this table with the `Publishers` table. The `Books` and the `Publishers` tables each contain an identifier for the publisher. When we join both tables on the publisher code, we obtain a *query result* made up of values from the joined tables. Each row in the result contains the information about a book, together with the publisher name and web page URL. Note that the publisher names and URLs are duplicated across several rows because we have several books with the same publisher.



Figure 1.3: Sample table containing books



Figure 1.4: Two tables joined together

The benefit of joining tables is avoiding unnecessary duplication of data in the database tables. For example, a naive database design might have had columns for the publisher name and URL right in the `Books` table. But then the database itself, and not just the query result, would have many duplicates of these entries. If a publisher's web address changed, *all* entries would need to be updated. Clearly, this is somewhat error-prone. In the relational model, we distribute data into multiple tables so that no information is unnecessarily duplicated. For example, each publisher's URL is contained only once in the publisher table. If the information needs to be combined, the tables are joined.

In the figures, you can see a graphical tool to inspect and link the tables. Many vendors have tools to express queries in a simple form by connecting column names and filling information into forms. Such tools are often called *query by example* (QBE) tools. In contrast, a query that uses SQL is written out in text, using SQL syntax, for example:

```
SELECT Books.Title, Books.Publisher_Id, Books.Price,
FROM Books, Publishers
WHERE Books.Publisher_Id = Publishers.Publisher_Id
```

In the remainder of this section, you will learn how to write such queries. If you are already familiar with SQL, just skip this section.

By convention, SQL keywords are written in capital letters, although this is not necessary.

The `SELECT` statement is quite flexible. You can simply select all rows in the `Books` table with the following query:

```
SELECT * FROM Books
```

The `FROM` clause is required in every SQL `SELECT` statement. It tells the database which tables to examine to find the data.

You can choose the columns that you want:

```
SELECT ISBN, Price, Title
FROM Books
```

You can restrict the rows in the answer with the `WHERE` clause:

```
SELECT ISBN, Price, Title
FROM Books
WHERE Price <= 29.95
```

Be careful with the "equals" comparison. SQL uses `=` and `<>`, rather than `==` or `!=` as in the Java programming language, for equality testing.

Note: Some database vendors support the use of `!=` for inequality testing. This is not standard SQL, so I recommend against such use.

The `WHERE` clause can also use pattern matching by means of the `LIKE` operator. The wildcard characters are not the usual `*` and `?`, however. Use a `%` for zero or more characters and an underscore for a single character. For example,

```
SELECT ISBN, Price, Title
FROM Books
WHERE Title NOT LIKE '%n_x%'
```

excludes books with titles that contain words such as Unix or Linux.

Note that strings are enclosed in single quotes, not double quotes. A single quote inside a string is represented by a pair of single quotes. For example,

```
SELECT Title
FROM Books
WHERE Title LIKE '%''%'
```

reports all titles that contain a single quote.

You can select data from multiple tables:

```
SELECT * FROM Books, Publishers
```

Without a `WHERE` clause, this query is not very interesting. It lists *all combinations* of rows from both tables. In our case, where `Books` has 20 rows and `Publishers` has 8 rows, the result is a set of rows with 20 × 8 entries and lots of duplications. We really want to constrain the query to say that we are only interested in *matching* books with their publishers:

```
SELECT * FROM Books, Publishers
WHERE Books.Publisher_Id = Publishers.Publisher_Id
```

This query result has 20 rows, one for each book, because each book has one publisher in the `Publisher` table.

Whenever you have multiple tables in a query, the same column name can occur in two different places. That happened in our

example. There is a column called `Publisher_Id` in both the `Books` and the `Publishers` tables. When an ambiguity would otherwise result, you must prefix each column name with the name of the table to which it belongs, such as `Books.Publisher_Id`.

You can use SQL to change the data inside a database as well. For example, suppose you want to reduce by $5.00 the current price of all books that have "C++" in their title:

```
UPDATE Books
SET Price = Price - 5.00
WHERE Title LIKE '%C++%'
```

Similarly, to delete all C++ books, use a `DELETE` query:

```
DELETE FROM Books
WHERE Title LIKE '%C++%'
```

SQL comes with built-in functions for taking averages, finding maximums and minimums in a column, and so on, which we do not discuss here.

Typically, to insert values into a table, you can use the `INSERT` statement:

```
INSERT INTO Books
VALUES ('A Guide to the SQL Standard', '0-201-96426-0
```

You need a separate `INSERT` statement for every row being inserted in the table.

Of course, before you can query, modify, and insert data, you must have a place to store data. Use the `CREATE TABLE` statement to make a new table. Specify the name and data type for each column. For example,

```
CREATE TABLE Books
(
   Title VARCHAR(60),
   ISBN CHAR(13),
   Publisher_Id VARCHAR(6),
   Price DECIMAL(10,2)
)
```

Table 5.5 shows the most common SQL data types.

Table 1.5: Common SQL Data Types

Data Types	Description

Data Types	Description
`INTEGER` or `INT`	Typically, a 32-bit integer
`SMALLINT`	Typically, a 16-bit integer
`NUMERIC(m,n)`, `DECIMAL(m,n)` or `DEC(m,n)`	Fixed-point decimal number with `m` total digits and `n` digits after the decimal point
`FLOAT(n)`	A floating-point number with `n` binary digits of precision
`REAL`	Typically, a 32-bit floating-point number
`DOUBLE`	Typically, a 64-bit floating-point number
`CHARACTER(n)` or `CHAR(n)`	Fixed-length string of length `n`
`VARCHAR(n)`	Variable-length strings of maximum

Data Types	Description
	length `n`
`BOOLEAN`	A Boolean value
`DATE`	Calendar date, implementation-dependent
`TIME`	Time of day, implementation-dependent
`TIMESTAMP`	Date and time of day, implementation-dependent
`BLOB`	A binary large object
`CLOB`	A character large object

In this book, we do not discuss the additional clauses, such as keys and constraints, that you can use with the `CREATE TABLE` statement.

1.3. JDBC Configuration

Of course, you need a database program for which a JDBC driver is available. There are many excellent choices, such as IBM DB2, Microsoft SQL Server, MySQL, Oracle, and PostgreSQL.

You must also create a database for your experimental use. We assume you name it `COREJAVA`. Create a new database, or have your database administrator create one with the appropriate permissions. You need to be able to create, update, and drop tables in the database.

If this is your first experience with databases, I recommend that you use the Apache Derby database, which is available from https://db.apache.org/derby.

Alternatively, if you are familiar with Docker, it is easy to run PostgreSQL in a docker image:

```
docker pull postgres
docker run -e POSTGRES_PASSWORD=secret -e POSTGRES_DB
```

You need to gather a number of items before you can write your first database program. The following sections cover these items.

1.3.1. Database URLs

When connecting to a database, you must use various database-specific parameters such as host names, port numbers, and database names.

JDBC uses a syntax similar to that of ordinary URLs to describe data sources. Here are examples of the syntax:

```
jdbc:derby://localhost:1527/COREJAVA;create=true
jdbc:postgresql:COREJAVA
```

These JDBC URLs specify a Derby database and a PostgreSQL database named `COREJAVA`.

The general syntax is

```
jdbc:subprotocol:other stuff
```

where a subprotocol selects the specific driver for connecting to the database.

The format for the other stuff depends on the subprotocol used. You will need to look up your vendor's documentation for the specific format.

1.3.2. Driver JAR Files

You need to obtain the JAR file in which the driver for your database is located. If you use Derby, you need the file `derbyclient.jar`. With another database, you need to locate the appropriate driver. For example, the PostgreSQL drivers are available at https://jdbc.postgresql.org.

Include the driver JAR file on the class path when running a program that accesses the database. (You don't need the JAR file for compiling.)

When you launch programs from the command line, simply use the command

```
java -classpath driverJarPath:. ProgramName
```

On Windows, use a semicolon to separate the current directory (denoted by the `.` character) from the driver JAR path.

1.3.3. Starting the Database

The database server needs to be started before you can connect to it. The details depend on your database.

With the Derby database, follow these steps:

1. Open a command shell and change to a directory that will hold the database files.
2. Locate the file `derbyrun.jar` in the Derby installation directory. We will denote the directory containing `lib/derbyrun.jar` with `derby`.
3. Run the command

```
java -jar derby/lib/derbyrun.jar server start
```

4. Double-check that the database is working correctly. Create a file `ij.properties` that contains these lines:

```
ij.driver=org.apache.derby.jdbc.ClientDriver
ij.protocol=jdbc:derby://localhost:1527/
ij.database=COREJAVA;create=true
```

   From another command shell, run Derby's interactive scripting tool (called `ij`) by executing

```
java -jar derby/lib/derbyrun.jar ij -p ij.propertie
```

   Now you can issue SQL commands such as

```
CREATE TABLE Greetings (Message VARCHAR(20));
INSERT INTO Greetings VALUES ('Hello, World!');
SELECT * FROM Greetings;
DROP TABLE Greetings;
```

Note that each command must be terminated by a semicolon. To exit, type

```
EXIT;
```

5. When you are done using the database, stop the server with the command

```
java -jar derby/lib/derbyrun.jar server shutdown
```

If you use another database, you need to consult the documentation to find out how to start and stop your database server, and how to connect to it and issue SQL commands.

1.3.4. Connecting to the Database

In your Java program, open a database connection like this:

```
String url = "jdbc:postgresql:COREJAVA";
String username = "dbuser";
String password = "secret";
```

```
  Connection conn = DriverManager.getConnection(url, us
```

The driver manager iterates through the registered drivers to find a driver that can use the subprotocol specified in the database URL.

The `getConnection` method returns a `Connection` object. In the following sections, you will see how to use the `Connection` object to execute SQL statements.

To connect to the database, you will need a username and password for your database.

Note: By default, Derby lets you connect with any username, and it does not check passwords. A separate set of tables is generated for each user. The default username is `app`.

The test program in Listing 5.1 puts these steps to work. It loads connection parameters from a file named `database.properties` and connects to the database. The `database.properties` file supplied with the sample code contains connection information for the Derby database. If you use a different database, put your database-specific connection information into that file. Here is an example for connecting to a PostgreSQL database:

```
jdbc.drivers=org.postgresql.Driver
jdbc.url=jdbc:postgresql:COREJAVA
jdbc.username=dbuser
jdbc.password=secret
```

After connecting to the database, the test program executes the following SQL statements:

```
CREATE TABLE Greetings (Message VARCHAR(20))
INSERT INTO Greetings VALUES ('Hello, World!')
SELECT * FROM Greetings
```

The result of the `SELECT` statement is printed, and you should see an output of

```
Hello, World!
```

Then the table is removed by executing the statement

```
DROP TABLE Greetings
```

To run this test, start your database as described previously, and launch the program as

```
java -classpath driverJarPath:. test.TestDB
```

Tip: One way to debug JDBC-related problems is to enable JDBC tracing. Call the `DriverManager.setLogWriter` method to send trace messages to a `PrintWriter`. The trace output contains a detailed listing of the JDBC activity. Most JDBC driver implementations provide additional mechanisms for tracing. For example, with Derby, you can add a `traceFile` option to the JDBC URL: `jdbc:derby://localhost:1527/COREJAVA;create=true;traceFile=trace.out`.

Note: Since JDBC 4, driver JAR files contain a file `META-INF/services/java.sql.Driver` which contains the name of the driver class.

In the unlikely case that you use an older driver JAR, you need to find out the name of the JDBC driver class used by your vendor. Then set the `jdbc.drivers` property on the command line:

```
java -Djdbc.drivers=driverClassName ProgramN
```

Listing 1.1 test/TestDB.java

```
1  package test;
2
3  import java.nio.file.*;
4  import java.sql.*;
5  import java.io.*;
6  import java.util.*;
7
8  /**
9   * This program tests that the database and the
10  * @version 1.05 2023-08-16
11  * @author Cay Horstmann
12  */
13 public class TestDB
14 {
15    public static void main(String[] args) throw
16    {
17       try
18       {
19          runTest();
20       }
21       catch (SQLException e)
22       {
```

```
23            for (Throwable t : e)
24               t.printStackTrace();
25         }
26      }
27
28      /**
29       * Runs a test by creating a table, adding a
30       * removing the table.
31       */
32      public static void runTest() throws SQLExcep
33      {
34         try (Connection conn = getConnection();
35               Statement stat = conn.createStateme
36         {
37            stat.executeUpdate("CREATE TABLE Greet
38            stat.executeUpdate("INSERT INTO Greeti
39
40            try (ResultSet result = stat.executeQu
41            {
42               if (result.next())
43                  System.out.println(result.getStr
44            }
45            stat.executeUpdate("DROP TABLE Greetin
46         }
47      }
48
49      /**
50       * Gets a connection from the properties spe
```

```
51      * @return the database connection
52      */
53     public static Connection getConnection() thr
54     {
55        var props = new Properties();
56        try (Reader in = Files.newBufferedReader(
57        {
58           props.load(in);
59        }
60        String drivers = props.getProperty("jdbc
61        if (drivers != null) System.setProperty("
62        String url = props.getProperty("jdbc.url"
63        String username = props.getProperty("jdbc
64        String password = props.getProperty("jdbc
65
66        return DriverManager.getConnection(url, u
67     }
68  }
```

`java.sql.DriverManager` **1.1**

- `static Connection getConnection(String url, String user, String password)`
  establishes a connection to the given database and returns a `Connection` object.

1.4. Working with JDBC Statements

In the following sections, you will see how to use the JDBC `Statement` to execute SQL statements, obtain results, and deal with errors. Then we show you a simple program for populating a database.

1.4.1. Executing SQL Statements

To execute a SQL statement, you first create a `Statement` object. To create statement objects, use the `Connection` object that you obtained from the call to `DriverManager.getConnection`.

```
Statement stat = conn.createStatement();
```

Next, place the statement that you want to execute into a string, for example:

```
String command = """
UPDATE Books
   SET Price = Price - 5.00
   WHERE Title NOT LIKE '%Introduction%'
""";
```

Then, call the `executeUpdate` method of the `Statement` interface:

```
stat.executeUpdate(command);
```

The `executeUpdate` method returns a count of the rows that were affected by the SQL statement, or zero for statements that do not return a row count. For example, the call to `executeUpdate` in the preceding example returns the number of rows where the price was lowered by $5.00.

The `executeUpdate` method can execute actions such as `INSERT`, `UPDATE`, and `DELETE`, as well as data definition statements such as `CREATE TABLE` and `DROP TABLE`. However, you need to use the `executeQuery` method to execute `SELECT` queries. There is also a catch-all `execute` statement to execute arbitrary SQL statements. It's commonly used only for queries that a user supplies interactively.

When you execute a query, you are interested in the result. The `executeQuery` method returns an object of type `ResultSet` that you can use to walk through the result one row at a time.

```
ResultSet rs = stat.executeQuery("SELECT * FROM Books
```

The basic loop for analyzing a result set looks like this:

```
while (rs.next())
{
    look at a row of the result set
}
```

Caution: The iteration protocol of the `ResultSet` interface is different from that of the `java.util.Iterator` interface. Here, the iterator is initialized to a position *before* the first row. You must call the `next` method once to move the iterator to the first row. Also, there is no `hasNext` method; keep calling `next` until it returns `false`.

The order of the rows in a result set is completely arbitrary. Unless you specifically ordered the result with an `ORDER BY` clause, you should not attach any significance to the row order.

When inspecting an individual row, you will want to know the contents of the fields. A large number of accessor methods give you this information.

```
String isbn = rs.getString(1);
double price = rs.getDouble("Price");
```

There are accessors for various *types*, such as `getString` and `getDouble`. Each accessor has two forms, one taking a numeric

argument, and the other, a string argument. When you supply a numeric argument, you refer to the column with that number. For example, `rs.getString(1)` returns the value of the first column in the current row.

Caution: Unlike array indexes, database column numbers start at `1`

When you supply a string argument, you refer to the column in the result set with that name. For example, `rs.getDouble("Price")` returns the value of the column with label `Price`. Using the numeric argument is a bit more efficient, but string arguments make the code easier to read and maintain.

Each `get` method makes reasonable type conversions when the type of the method doesn't match the type of the column. For example, the call `rs.getString("Price")` converts the floating-point value of the `Price` column to a string.

java.sql.Connection **1.1**

- `Statement createStatement()`
  creates a `Statement` object that can be used to execute SQL queries and updates without parameters.

- `void close()`
  immediately closes the current connection and the JDBC resources that it created.

java.sql.Statement **1.1**

- `ResultSet executeQuery(String sqlQuery)`
  executes the SQL statement given in the string and returns a `ResultSet` object to view the query result.
- `int executeUpdate(String sqlStatement)`
- `long executeLargeUpdate(String sqlStatement)` **8**
  execute the SQL `INSERT`, `UPDATE`, or `DELETE` statement specified by the string. Also execute Data Definition Language (DDL) statements such as `CREATE TABLE`. Return the number of rows affected, or `0` for a statement without an update count.
- `boolean execute(String sqlStatement)`
  executes the SQL statement specified by the string. Multiple result sets and update counts may be produced. Returns `true` if the first result is a result set, `false` if the result is an update count. Call `getResultSet` or `getUpdateCount` to retrieve the first result. See Section 5.5.4 for details on processing multiple results.
- `ResultSet getResultSet()`
  returns the result set of the preceding query statement, or `null` if the preceding statement did not have a result set. Call this

method only once per executed statement.

- `int getUpdateCount()`
- `long getLargeUpdateCount()` 8
  return the number of rows affected by the preceding update statement, or `-1` if the preceding statement was a statement without an update count. Call this method only once per executed statement.
- `void close()`
  closes this statement object and its associated result set.
- `boolean isClosed()` 6
  returns `true` if this statement is closed.
- `void closeOnCompletion()` 7
  causes this statement to be closed once all of its result sets have been closed.

java.sql.ResultSet 1.1

- `boolean next()`
  makes the current row in the result set move forward by one. Returns `false` after the last row. Note that you must call this method to advance to the first row.
- `Xxx getXxx(int columnNumber)`
- `Xxx getXxx(String columnLabel)`
  (Xxx is a type such as `int`, `double`, `String`, `Date`, etc.)

- `<T> T getObject(int columnIndex, Class<T> type)` 7
- `<T> T getObject(String columnLabel, Class<T> type)` 7
- `void updateObject(int columnIndex, Object x, SQLType targetSqlType)` 8
- `void updateObject(String columnLabel, Object x, SQLType targetSqlType)` 8
  return or update the value of the column with the given column index or label, converted to the specified type. The column label is the label specified in the SQL `AS` clause or the column name if `AS` is not used.
- `int findColumn(String columnName)`
  gives the column index associated with a column name.
- `void close()`
  immediately closes the current result set.
- `boolean isClosed()` 6
  returns `true` if this statement is closed.

1.4.2. Managing Connections, Statements, and Result Sets

Every `Connection` object can create one or more `Statement` objects. You can use the same `Statement` object for multiple unrelated commands and queries. However, a statement has *at most*

one open result set. If you issue multiple queries whose results you analyze concurrently, you need multiple `Statement` objects.

Be forewarned, though, that there is a limit to the number of statements per connection. Use the `getMaxStatements` method of the `DatabaseMetaData` interface to find out the number of concurrently open statements that your JDBC driver supports.

In practice, you should probably not fuss with multiple concurrent result sets. If the result sets are related, you should be able to issue a combined query and analyze a single result. It is much more efficient to let the database combine queries than it is for a Java program to iterate through multiple result sets.

Be sure to finish processing of any result set before you issue a new query or update on a `Statement` object. The result sets of prior queries are automatically closed.

When you are done using a `ResultSet`, `Statement`, or `Connection`, it is a good idea to call the `close` method immediately. These objects use large data structures that draw on the finite resources of the database server.

The `close` method of a `Statement` object closes any associated result sets. Similarly, the `close` method of the `Connection` class closes all statements of the connection.

Conversely, you can call the `closeOnCompletion` method on a `Statement`, and it will close automatically as soon as all its result sets have closed.

If your connections are short-lived, don't worry about closing statements and result sets. To make sure a connection object cannot possibly remain open, use a `try`-with-resources statement:

```
try (Connection conn = . . .)
{
   Statement stat = conn.createStatement();
   ResultSet result = stat.executeQuery(queryString);
   process query result
}
```

1.4.3. Analyzing SQL Exceptions

Each `SQLException` has a chain of `SQLException` objects that are retrieved with the `getNextException` method. This exception chain is in addition to the "cause" chain of `Throwable` objects that every exception has. (See Chapter 7 of Volume I for details about Java exceptions.) One would need two nested loops to fully enumerate all these exceptions. Fortunately, the `SQLException` class has been enhanced to implement the `Iterable<Throwable>` interface. The `iterator()` method yields an

`Iterator<Throwable>` that iterates through both chains: It starts by going through the cause chain of the first `SQLException`, then moves on to the next `SQLException`, and so on. You can simply use an enhanced `for` loop:

```
for (Throwable t : sqlException)
{
   do something with t
}
```

You can call `getSQLState` and `getErrorCode` on a `SQLException` to analyze it further. The first method yields a string that is standardized by either X/Open or SQL:2003. (Call the `getSQLStateType` method of the `DatabaseMetaData` interface to find out which standard is used by your driver.) The error code is vendor-specific.

The SQL exceptions are organized into an inheritance tree (shown in Figure 5.5). This allows you to catch specific error types in a vendor-independent way.



Figure 1.5: SQL exception types

In addition, the database driver can report nonfatal conditions as warnings. You can retrieve warnings from connections, statements, and result sets. The `SQLWarning` class is a subclass of `SQLException` (even though a `SQLWarning` is not thrown as an exception). Call `getSQLState` and `getErrorCode` to get further information about the warnings. Similar to SQL exceptions, warnings are chained. To retrieve all warnings, use this loop:

```
SQLWarning w = stat.getWarning();
while (w != null)
{
```

```
    do something with w
    w = w.nextWarning();
}
```

The `DataTruncation` subclass of `SQLWarning` is used when data being read from the database are unexpectedly truncated. If data truncation happens in an update statement, a `DataTruncation` is thrown as an exception.

`java.sql.SQLException` **1.1**

- `SQLException getNextException()`
  gets the next SQL exception chained to this one, or `null` at the end of the chain.
- `Iterator<Throwable> iterator()` **6**
  gets an iterator that yields the chained SQL exceptions and their causes.
- `String getSQLState()`
  gets the "SQL state"—a standardized error code.
- `int getErrorCode()`
  gets the vendor-specific error code.

`java.sql.SQLWarning` 1.1

- `SQLWarning getNextWarning()`
  returns the next warning chained to this one, or `null` at the end of the chain.

java.sql.Connection 1.1
java.sql.Statement 1.1
java.sql.ResultSet 1.1

- `SQLWarning getWarnings()`
  returns the first of the pending warnings, or `null` if no warnings are pending.

`java.sql.DataTruncation` 1.1

- `boolean getParameter()`
  returns `true` if the data truncation applies to a parameter, `false` if it applies to a column.
- `int getIndex()`
  returns the index of the truncated parameter or column.
- `int getDataSize()`
  returns the number of bytes that should have been transferred, or `-1` if the value is unknown.

- `int getTransferSize()`
  returns the number of bytes that were actually transferred, or `-1` if the value is unknown.

1.4.4. Populating a Database

We are now ready to write our first real JDBC program. Sure, it would be nice to try some of the fancy queries discussed earlier, but we have a problem: Right now, there are no data in the database. We need to populate the database, and a simple way of doing that is with a set of SQL instructions to create tables and insert data into them. Most database programs can process a set of SQL instructions from a text file, but there are pesky differences about statement terminators and other syntactical issues.

For that reason, we will use JDBC in a simple program that reads a file with SQL instructions, one instruction per line, and executes them.

Specifically, the program reads data from a text file in a format such as

```
CREATE TABLE Publishers (Publisher_Id VARCHAR(6), Nam
INSERT INTO Publishers VALUES ('0201', 'Addison-Wesle
INSERT INTO Publishers VALUES ('0471', 'John Wiley &
```

```
. . .
```

Listing 5.2 contains the code for the program that reads a file with SQL statements and executes them. You don't have to read through the code; simply use the program so you can populate your database and run the examples in the remainder of this chapter.

Make sure that your database server is running, and run the program as follows:

```
java -classpath driverJarPath:. exec.ExecSQL Books.sql
java -classpath driverJarPath:. exec.ExecSQL Authors.sql
java -classpath driverJarPath:. exec.ExecSQL Publishers
java -classpath driverJarPath:. exec.ExecSQL BooksAuthor
```

Before running the program, check that the file `database.properties` is set up properly for your environment (see Section 5.3.4).

Note: Your database may also have a utility to read SQL files directly. For example, with Derby, you can run

```
java -jar derby/lib/derbyrun.jar ij -p ij.p
```

(The `ij.properties` file is described in Section 5.3.3.)

In the data format for the `ExecSQL` command, we allow an optional semicolon at the end of each line because most database utilities expect this format.

The following steps briefly describe the `ExecSQL` program:

1. Connect to the database. The `getConnection` method reads the properties in the file `database.properties` and adds the `jdbc.drivers` property to the system properties. The driver manager uses the `jdbc.drivers` property to load the appropriate database driver. The `getConnection` method uses the `jdbc.url`, `jdbc.username`, and `jdbc.password` properties to open the database connection.
2. Open the file with the SQL statements. If no file name was supplied, prompt the user to enter the statements on the console.
3. Execute each statement with the generic `execute` method. If it returns `true`, the statement had a result set. The four SQL files provided for the book database all end in a `SELECT *` statement so that you can see that the data were successfully inserted.
4. If there was a result set, print out the result. Since this is a generic result set, we need to use metadata to find out how many columns the result has. For more information, see Section 5.8.

5. If there is any SQL exception, print the exception and any chained exceptions that may be contained in it.
6. Close the connection to the database.

Listing 5.2 shows the code for the program.

Listing 1.2 exec/ExecSQL.java

```
1  package exec;
2
3  import java.io.*;
4  import java.nio.file.*;
5  import java.util.*;
6  import java.sql.*;
7
8  /**
9   * Executes all SQL statements in a file. Call
10  * java -classpath driverPath:. ExecSQL commanc
11  *
12  * @version 1.35 2023-08-16
13  * @author Cay Horstmann
14  */
15 class ExecSQL
16 {
17    public static void main(String[] args) throw
18    {
19       try (Scanner in = args.length == 0 ? new
```

```
20              : new Scanner(Path.of(args[0]));
21           Connection conn = getConnection();
22           Statement stat = conn.createStatement(
23        {
24           while (true)
25           {
26              if (args.length == 0) System.out.pr
27
28              if (!in.hasNextLine()) return;
29
30              String line = in.nextLine().strip()
31              if (line.equalsIgnoreCase("EXIT"))
32              if (line.endsWith(";")) // remove t
33                 line = line.substring(0, line.le
34              try
35              {
36                 boolean isResult = stat.execute(
37                 if (isResult)
38                 {
39                    try (ResultSet rs = stat.getR
40                    {
41                       showResultSet(rs);
42                    }
43                 }
44                 else
45                 {
46                    int updateCount = stat.getUpd
47                    System.out.println(updateCour
```

```
48                }
49             }
50             catch (SQLException e)
51             {
52                for (Throwable t : e)
53                   t.printStackTrace();
54             }
55          }
56       }
57       catch (SQLException e)
58       {
59          for (Throwable t : e)
60             t.printStackTrace();
61       }
62    }
63
64    /**
65     * Gets a connection from the properties spe
66     * @return the database connection
67     */
68    public static Connection getConnection() thr
69    {
70       var props = new Properties();
71       try (Reader in = Files.newBufferedReader(
72             Path.of("database.properties")))
73       {
74          props.load(in);
75       }
```

```
76          String drivers = props.getProperty("jdbc
77          if (drivers != null) System.setProperty("
78
79          String url = props.getProperty("jdbc.url"
80          String username = props.getProperty("jdbc
81          String password = props.getProperty("jdbc
82
83          return DriverManager.getConnection(url, u
84       }
85
86       /**
87        * Prints a result set.
88        * @param result the result set to be printe
89        */
90       public static void showResultSet(ResultSet r
91       {
92          ResultSetMetaData metaData = result.getMe
93          int columnCount = metaData.getColumnCount
94
95          for (int i = 1; i <= columnCount; i++)
96          {
97             if (i > 1) System.out.print(", ");
98             System.out.print(metaData.getColumnLab
99          }
100         System.out.println();
101
102         while (result.next())
103         {
```

```
104             for (int i = 1; i <= columnCount; i++)
105             {
106                if (i > 1) System.out.print(", ");
107                System.out.print(result.getString(i
108             }
109             System.out.println();
110          }
111       }
112    }
```

1.5. Query Execution

In this section, we write a program that executes queries against the `COREJAVA` database. For this program to work, you must have a `COREJAVA` database populated with tables as described in the preceding section.

When querying the database, you can select the author and the publisher or leave either of them as `Any`.

You can also change the data in the database. Select a publisher and type an amount. All prices of that publisher are adjusted by the amount you entered, and the program displays how many rows were changed. After a price change, you might want to run a query to verify the new prices.

1.5.1. Prepared Statements

In this program, we use one new feature, *prepared statements.* Consider the SQL query for all books by a particular publisher, regardless of the author:

```
SELECT Books.Price, Books.Title
FROM Books, Publishers
WHERE Books.Publisher_Id = Publishers.Publisher_Id
AND Publishers.Name = the name from the list box
```

Instead of building a separate query statement every time the user launches such a query, we can *prepare* a query with a host variable and use it many times, each time filling in a different string for the variable. That technique improves performance. Whenever the database executes a query, it first computes a strategy of how to do it efficiently. By preparing the query and reusing it, you ensure that the planning step is done only once.

Each host variable in a prepared query is indicated with a `?`. If there is more than one variable, you must keep track of the positions of the `?` when setting the values. For example, our prepared query becomes

```
String publisherQuery = """
SELECT Books.Price, Books.Title
FROM Books, Publishers
```

```
  WHERE Books.Publisher_Id = Publishers.Publisher_Id AN
  """;
  PreparedStatement pstat = conn.prepareStatement(publi
```

Before executing the prepared statement, you must bind the host variables to actual values with a `set` method. As with the `get` methods of the `ResultSet` interface, there are different `set` methods for the various types. Here, we want to set a string to a publisher name:

```
  pstat.setString(1, publisher);
```

The first argument is the position number of the host variable that we want to set. The position 1 denotes the first `?`. The second argument is the value that we want to assign to the host variable.

If you reuse a prepared query that you have already executed, all host variables stay bound unless you change them with a `set` method or call the `clearParameters` method. That means you only need to call a `setXxx` method on those host variables that change from one query to the next.

Once all variables have been bound to values, you can execute the prepared statement:

```
ResultSet rs = pstat.executeQuery();
```

Tip: Building a query manually, by concatenating strings, is tedious and potentially dangerous. You have to worry about special characters such as quotes—and, if your query involves user input, you have to guard against injection attacks. Therefore, use prepared statements whenever your query involves variables.

The price update feature is implemented as an `UPDATE` statement. Note that we call `executeUpdate`, not `executeQuery`, because the `UPDATE` statement does not return a result set. The return value of `executeUpdate` is the count of changed rows.

```
int r = stat.executeUpdate();
System.out.println(r + " rows updated");
```

Note: A `PreparedStatement` object becomes invalid after the associated `Connection` object is closed. However, many databases automatically *cache* prepared statements. If the same query is prepared twice, the database simply reuses the query strategy.

Therefore, don't worry about the overhead of calling `prepareStatement`.

The following list briefly describes the structure of the example program:

- The author and publisher array lists are populated by running two queries that return all author and publisher names in the database.
- The queries involving authors are complex. A book can have multiple authors, so the `BooksAuthors` table stores the correspondence between authors and books. For example, the book with ISBN 0-201-96426-0 has two authors with codes `DATE` and `DARW`. The `BooksAuthors` table has the rows

  ```
  0-201-96426-0, DATE, 1
  0-201-96426-0, DARW, 2
  ```

  to indicate this fact. The third column lists the order of the authors. (We can't just use the position of the rows in the table. There is no fixed row ordering in a relational table.) Thus, the query has to join the `Books`, `BooksAuthors`, and `Authors` tables to compare the author name with the one selected by the user.

```
SELECT Books.Price, Books.Title FROM Books, BooksAu
WHERE Authors.Author_Id = BooksAuthors.Author_Id AN
AND Books.Publisher_Id = Publishers.Publisher_Id AN
AND Publishers.Name = ?
```

Tip: Some Java programmers avoid complex SQL statements such as this one. A surprisingly common, but very inefficient, workaround is to write lots of Java code that iterates through multiple result sets. But the database is *a lot* better at executing query code than a Java program can be—that's the core competency of a database. A rule of thumb: If you can do it in SQL, don't do it in Java.

- The `changePrices` method executes an `UPDATE` statement. Note that the `WHERE` clause of the `UPDATE` statement needs the publisher *code* and we only know the publisher *name*. This problem is solved with a nested subquery:

```
UPDATE Books
SET Price = Price + ?
WHERE Books.Publisher_Id = (SELECT Publisher_Id FRO
```

Listing 5.3 is the complete program code.

Listing 1.3 query/QueryTest.java

```
1  package query;
2
3  import java.io.*;
4  import java.nio.file.*;
5  import java.sql.*;
6  import java.util.*;
7
8  /**
9   * This program demonstrates several complex da
10  * @version 1.33 2023-08-16
11  * @author Cay Horstmann
12  */
13 public class QueryTest
14 {
15    private static final String allQuery = "SELE
16
17    private static final String authorPublisherQ
18 SELECT Books.Price, Books.Title
19 FROM Books, BooksAuthors, Authors, Publishers
20 WHERE Authors.Author_Id = BooksAuthors.Author_I
21    AND BooksAuthors.ISBN = Books.ISBN
22    AND Books.Publisher_Id = Publishers.Publishe
23    AND Authors.Name = ?
24    AND Publishers.Name = ?
25 """;
26
```

```
   private static final String authorQuery = "'
SELECT Books.Price, Books.Title FROM Books, Boo
WHERE Authors.Author_Id = BooksAuthors.Author_I
   AND BooksAuthors.ISBN = Books.ISBN"
   AND Authors.Name = ?
""";

   private static final String publisherQuery =
SELECT Books.Price, Books.Title FROM Books, Pub
WHERE Books.Publisher_Id = Publishers.Publisher
   AND Publishers.Name = ?
""";

   private static final String priceUpdate = "'
UPDATE Books SET Price = Price + ? "
WHERE Books.Publisher_Id =
   (SELECT Publisher_Id FROM Publishers WHERE N
""";

   private static Scanner in;
   private static ArrayList<String> authors = n
   private static ArrayList<String> publishers

   public static void main(String[] args) throw
   {
      try (Connection conn = getConnection())
      {
         in = new Scanner(System.in);
```

```
55          authors.add("Any");
56          publishers.add("Any");
57          try (Statement stat = conn.createState
58          {
59             // Fill the authors array list
60             String query = "SELECT Name FROM Au
61             try (ResultSet rs = stat.executeQue
62             {
63                while (rs.next())
64                   authors.add(rs.getString(1));
65             }
66
67             // Fill the publishers array list
68             query = "SELECT Name FROM Publisher
69             try (ResultSet rs = stat.executeQue
70             {
71                while (rs.next())
72                   publishers.add(rs.getString(1
73             }
74          }
75          boolean done = false;
76          while (!done)
77          {
78             System.out.print("Q)uery C)hange pr
79             String input = in.next().toUpperCas
80             if (input.equals("Q"))
81                executeQuery(conn);
82             else if (input.equals("C"))
```

```
83                changePrices(conn);
84             else
85                done = true;
86          }
87       }
88       catch (SQLException e)
89       {
90          for (Throwable t : e)
91             System.out.println(t.getMessage());
92       }
93    }
94
95    /**
96     * Executes the selected query.
97     * @param conn the database connection
98     */
99    private static void executeQuery(Connection
100   {
101      String author = select("Authors:", author
102      String publisher = select("Publishers:",
103      PreparedStatement stat;
104      if (!author.equals("Any") && !publisher.e
105      {
106         stat = conn.prepareStatement(authorPub
107         stat.setString(1, author);
108         stat.setString(2, publisher);
109      }
110      else if (!author.equals("Any") && publish
```

```
111         {
112             stat = conn.prepareStatement(authorQu
113             stat.setString(1, author);
114         }
115         else if (author.equals("Any") && !publish
116         {
117             stat = conn.prepareStatement(publishe
118             stat.setString(1, publisher);
119         }
120         else
121            stat = conn.prepareStatement(allQuery)
122
123         try (ResultSet rs = stat.executeQuery())
124         {
125            while (rs.next())
126               System.out.println(rs.getString(1)
127         }
128      }
129
130      /**
131       * Executes an update statement to change pr
132       * @param conn the database connection
133       */
134      public static void changePrices(Connection c
135      {
136         String publisher = select("Publishers:",
137         System.out.print("Change prices by: ");
138         double priceChange = in.nextDouble();
```

```
139         PreparedStatement stat = conn.prepareStat
140         stat.setDouble(1, priceChange);
141         stat.setString(2, publisher);
142         int r = stat.executeUpdate();
143         System.out.println(r + " records updated
144      }
145
146      /**
147       * Asks the user to select a string.
148       * @param prompt the prompt to display
149       * @param options the options from which the
150       * @return the option that the user chose
151       */
152      public static String select(String prompt, L
153      {
154         while (true)
155         {
156            System.out.println(prompt);
157            for (int i = 0; i < options.size(); i+
158               System.out.printf("%2d) %s%n", i +
159            int sel = in.nextInt();
160            if (sel > 0 && sel <= options.size())
161               return options.get(sel - 1);
162         }
163      }
164
165      /**
166       * Gets a connection from the properties spe
```

```
167      * @return the database connection
168      */
169     public static Connection getConnection() thr
170     {
171        var props = new Properties();
172        try (Reader in = Files.newBufferedReader(
173        {
174           props.load(in);
175        }
176
177        String drivers = props.getProperty("jdbc
178        if (drivers != null) System.setProperty("
179
180        String url = props.getProperty("jdbc.url"
181        String username = props.getProperty("jdbc
182        String password = props.getProperty("jdbc
183
184        return DriverManager.getConnection(url, u
185     }
186 }
```

java.sql.Connection **1.1**

- `PreparedStatement prepareStatement(String sql)` returns a `PreparedStatement` object containing the precompiled statement. The string `sql` contains a SQL

statement with one or more parameter placeholders denoted by `?` characters.

java.sql.PreparedStatement **1.1**

- `void setXxx(int n, Xxx x)`
  (Xxx is a type such as `int`, `double`, `String`, `Date`, etc.)
  sets the value of the `n`th parameter to `x`.
- `void clearParameters()`
  clears all current parameters in the prepared statement.
- `ResultSet executeQuery()`
  executes a prepared SQL query and returns a `ResultSet` object.
- `int executeUpdate()`
  executes the prepared SQL `INSERT`, `UPDATE`, or `DELETE` statement represented by the `PreparedStatement` object. Returns the number of rows affected, or `0` for DDL statements such as `CREATE TABLE`.

1.5.2. Reading and Writing LOBs

In addition to numbers, strings, and dates, many databases can store *large objects* (LOBs) such as images or other data. In SQL, binary large objects are called BLOBs, and character large objects are called CLOBs.

Note: It depends on the application whether it is better to store large objects in the database or a file system. This section tells you what to do once you have decided to use a database for that purpose.

To read a LOB, execute a `SELECT` statement and call the `getBlob` or `getClob` method on the `ResultSet`. You will get an object of type `Blob` or `Clob`. To get the binary data from a `Blob`, call the `getBytes` or `getBinaryStream`. For example, if you have a table with book cover images, you can retrieve an image like this:

```
PreparedStatement pstat = conn.prepareStatement("SELE
. . .
pstat.set(1, isbn);
try (ResultSet result = pstat.executeQuery())
{
   if (result.next())
   {
      Blob coverBlob = result.getBlob(1);
      Image coverImage = ImageIO.read(coverBlob.getBi
   }
}
```

Similarly, if you retrieve a `Clob` object, you can get character data by calling the `getSubString` or `getCharacterStream` method.

To place a LOB into a database, call `createBlob` or `createClob` on your `Connection` object, get an output stream or writer to the LOB, write the data, and store the object in the database. For example, here is how you store an image:

```
Blob coverBlob = connection.createBlob();
int offset = 0;
OutputStream out = coverBlob.setBinaryStream(offset);
ImageIO.write(coverImage, "PNG", out);
PreparedStatement pstat = conn.prepareStatement("INSE
pstat.set(1, isbn);
pstat.set(2, coverBlob);
pstat.executeUpdate();
```

java.sql.ResultSet **1.1**

- `Blob getBlob(int columnIndex)` **1.2**
- `Blob getBlob(String columnLabel)` **1.2**
- `Clob getClob(int columnIndex)` **1.2**
- `Clob getClob(String columnLabel)` **1.2**

get the BLOB or CLOB at the given column.

java.sql.Blob **1.2**

- `long length()`
  gets the length of this BLOB.
- `byte[] getBytes(long startPosition, long length)`
  gets the data in the given range from this BLOB.
- `InputStream getBinaryStream()`
- `InputStream getBinaryStream(long startPosition, long length)`
  return a stream to read the data from this BLOB or from the given range.
- `OutputStream setBinaryStream(long startPosition)` **1.4**
  returns an output stream for writing into this BLOB, starting at the given position.

java.sql.Clob **1.4**

- `long length()`
  gets the number of characters of this CLOB.
- `String getSubString(long startPosition, long length)`
  gets the characters in the given range from this CLOB.

- `Reader getCharacterStream()`
- `Reader getCharacterStream(long startPosition, long length)`
  return a reader (not a stream) to read the characters from this CLOB or from the given range.
- `Writer setCharacterStream(long startPosition)` **1.4**
  returns a writer (not a stream) for writing into this CLOB, starting at the given position.

java.sql.Connection **1.1**

- `Blob createBlob()` **6**
- `Clob createClob()` **6**
  create an empty BLOB or CLOB.

1.5.3. SQL Escapes

The "escape" syntax features are commonly supported by databases but use database-specific syntax variations. It is the job of the JDBC driver to translate the escape syntax to the syntax of a particular database.

Escapes are provided for the following features:

- Date and time literals
- Calling scalar functions

- Calling stored procedures
- Outer joins
- The escape character in `LIKE` clauses

Date and time literals vary widely among databases. To embed a date or time literal, specify the value in one of the ISO 8601/RFC 3339 formats shown below, where the milliseconds are optional. The driver will then translate it into the native format. Use `d`, `t`, `ts` for `DATE`, `TIME`, or `TIMESTAMP` values:

```
{d '2024-01-24'}
{t '23:59:59'}
{ts '2024-01-24 23:59:59.999'}
```

A *scalar function* is a function that returns a single value. Many functions are widely available in databases, but with varying names. The JDBC specification provides standard names and translates them into the database-specific names. To call a function, embed the standard function name and arguments like this:

```
{fn left(?, 20)}
{fn user()}
```

You can find a complete list of supported function names in the JDBC specification.

An *outer join* of two tables does not require that the rows of each table match according to the join condition. For example, the query

```
SELECT * FROM {oj Books LEFT OUTER JOIN Publishers
ON Books.Publisher_Id = Publisher.Publisher_Id}
```

contains books for which `Publisher_Id` has no match in the `Publishers` table, with `NULL` values to indicate that no match exists. You would need a `RIGHT OUTER JOIN` to include publishers without matching books, or a `FULL OUTER JOIN` to return both. Most databases support all forms of outer joins, but some do not. The `oj` escape allows a JDBC driver to locate and rewrite any unsupported outer join operations. If your databases support all forms of outer joins, you need not worry about this escape.

Finally, the `_` and `%` characters have special meanings in a `LIKE` clause—to match a single character or a sequence of characters. There is no standard way to use them literally. If you want to match all strings containing a `_`, use this construct:

```
. . . WHERE ? LIKE %!_% {escape '!'}
```

Here we define `!` as the escape character. The combination `!_` denotes a literal underscore.

A *stored procedure* is a procedure that executes in the database, written in a database-specific language. To invoke a stored procedure, use the `call` escape. You need not supply parentheses if the procedure has no parameters. Use `=` to capture a return value:

```
{call PROC1(?, ?)}
{call PROC2}
{call ? = PROC3(?)}
```

You need to use the `CallableStatement` interface to execute a stored procedure. Set all input parameters and specify the types of any outputs.

```
CallableStatement cstat = conn.prepareCall("{call PRO
cstat.setInt(1, id);
cstat.registerOutParameter(2, java.sql.Types.VARCHAR)
cstat.execute();
String name = cstat.getString(2);
```

1.5.4. Multiple Results

It is possible for a query to return multiple result sets or update counts. This can happen when executing a stored procedure, or with

databases that also allow submission of multiple `SELECT` statements in a single query. Here is how you retrieve all result sets:

1. Use the `execute` method to execute the SQL statement.
2. Retrieve the first result set or update count.
3. Repeatedly call the `getMoreResults` method to move on to the next result set or update count.
4. Finish when there are no more result sets or update counts.

The `execute` and `getMoreResults` methods return `true` if the next item in the chain is a result set. The `getUpdateCount` method returns `-1` if the next item in the chain is not an update count.

The following loop traverses all results:

```
boolean isResult = stat.execute(command);
boolean done = false;
while (!done)
{
   if (isResult)
   {
      ResultSet result = stat.getResultSet();
      do something with result
   }
   else
   {
      int updateCount = stat.getUpdateCount();
```

```
         if (updateCount >= 0)
            do something with updateCount
         else
            done = true;
      }
      if (!done) isResult = stat.getMoreResults();
   }
```

java.sql.Statement **1.1**

- `boolean getMoreResults()`
- `boolean getMoreResults(int current)` **6**
  get the next result for this statement. The `current` parameter is one of `CLOSE_CURRENT_RESULT` (default), `KEEP_CURRENT_RESULT`, or `CLOSE_ALL_RESULTS`. Return `true` if the next result exists and is a result set.

1.5.5. Retrieving Autogenerated Keys

Most databases support some mechanism for autonumbering rows in a table. Unfortunately, the mechanisms differ widely among vendors. These automatic numbers are often used as primary keys. Although JDBC doesn't offer a vendor-independent solution for generating keys, it does provide an efficient way of retrieving them. When you

insert a new row into a table and a key is automatically generated, you can retrieve it with the following code:

```
stat.executeUpdate(insertStatement, Statement.RETURN_
ResultSet rs = stat.getGeneratedKeys();
if (rs.next())
{
   int key = rs.getInt(1);
   . . .
}
```

java.sql.Statement 1.1

- `boolean execute(String statement, int autogenerated)` 1.4
- `int executeUpdate(String statement, int autogenerated)` 1.4
  execute the given SQL statement, as previously described. If `autogenerated` is set to `Statement.RETURN_GENERATED_KEYS` and the statement is an `INSERT` statement, the first column contains the autogenerated key.

1.6. Scrollable and Updatable Result Sets

As you have seen, the `next` method of the `ResultSet` interface iterates over the rows in a result set. That is certainly adequate for a program that needs to analyze the data. However, consider a visual data display that shows a table or query results (such as Figure 5.4). You usually want the user to be able to move both forward and backward in the result set. In a *scrollable* result, you can move forward and backward through a result set and even jump to any position.

Furthermore, once users see the contents of a result set displayed, they may be tempted to edit it. In an *updatable* result set, you can programmatically update entries so that the database is automatically updated. We discuss these capabilities in the following sections.

1.6.1. Scrollable Result Sets

By default, result sets are not scrollable or updatable. To obtain scrollable result sets from your queries, you must obtain a different `Statement` object with the method

```
Statement stat = conn.createStatement(type, concurren
```

For a prepared statement, use the call

```
PreparedStatement pstat = conn.prepareStatement(comma
```

The possible values of `type` and `concurrency` are listed in Table 5.6. You have the following choices:

- Do you want the result set to be scrollable? If not, use `ResultSet.TYPE_FORWARD_ONLY`.
- If the result set is scrollable, do you want it to reflect changes in the database that occurred after the query that yielded it? (In our discussion, we assume the `ResultSet.TYPE_SCROLL_INSENSITIVE` setting for scrollable result sets. This assumes that the result set does not "sense" database changes that occurred after execution of the query.)
- Do you want to be able to update the database by editing the result set? (See the next section for details.)

Table 1.6: `ResultSet` Type and Concurrency Values

Value	Explanation
`TYPE_FORWARD_ONLY`	The result set is not scrollable (default).

Value	Explanation
`TYPE_SCROLL_INSENSITIVE`	The result set is scrollable but not sensitive to database changes.
`TYPE_SCROLL_SENSITIVE`	The result set is scrollable and sensitive to database changes.
`CONCUR_READ_ONLY`	The result set cannot be used to update the database (default).
`CONCUR_UPDATABLE`	The result set can be used to update the database.

For example, if you simply want to be able to scroll through a result set but don’t want to edit its data, use

```
Statement stat = conn.createStatement(
   ResultSet.TYPE_SCROLL_INSENSITIVE, ResultSet.CONCU
```

All result sets that are returned by calls

```
ResultSet rs = stat.executeQuery(query);
```

are now scrollable. A scrollable result set has a *cursor* that indicates the current position.

Note: Not all database drivers support scrollable or updatable result sets. (The `supportsResultSetType` and `supportsResultSetConcurrency` methods of the `DatabaseMetaData` interface will tell you which types and concurrency modes are supported by a particular database using a particular driver.) Even if a database supports all result set modes, a particular query might not be able to yield a result set with all the properties that you requested. (For example, the result set of a complex query might not be updatable.) In that case, the `executeQuery` method returns a `ResultSet` of lesser capabilities and adds a `SQLWarning` to the connection object. (Section 5.4.3 shows how to retrieve the warning.) Alternatively, you can use the `getType` and `getConcurrency` methods of the `ResultSet` interface to find out what mode a result set actually has. If you do not check the result set capabilities and issue an unsupported operation,

such as `previous` on a result set that is not scrollable, the operation will throw a `SQLException`.

Scrolling is very simple. Use

```
if (rs.previous()) . . .;
```

to scroll backward. The method returns `true` if the cursor is positioned on an actual row, or `false` if it is now positioned before the first row.

You can move the cursor backward or forward by any number of rows with the call

```
rs.relative(n);
```

If `n` is positive, the cursor moves forward. If `n` is negative, it moves backward. If `n` is zero, the call has no effect. If you attempt to move the cursor outside the current set of rows, it is set to point either after the last row or before the first row, depending on the sign of `n`. Then, the method returns `false` and the cursor does not move. The method returns `true` if the cursor is positioned on an actual row.

Alternatively, you can set the cursor to a particular row number:

```
rs.absolute(n);
```

To get the current row number, call

```
int currentRow = rs.getRow();
```

The first row in the result set has number `1`. If the return value is `0`, the cursor is not currently on a row—it is either before the first row or after the last row.

The convenience methods `first`, `last`, `beforeFirst`, and `afterLast` move the cursor to the first, to the last, before the first, or after the last position.

Finally, the methods `isFirst`, `isLast`, `isBeforeFirst`, and `isAfterLast` test whether the cursor is at one of these special positions.

Using a scrollable result set is very simple. The hard work of caching the query data is carried out behind the scenes by the database driver.

1.6.2. Updatable Result Sets

If you want to edit the data in the result set and have the changes automatically reflected in the database, create an updatable result set. Updatable result sets don't have to be scrollable, but if you present data to a user for editing, you usually want to allow scrolling as well.

To obtain updatable result sets, create a statement as follows:

```
Statement stat = conn.createStatement(
   ResultSet.TYPE_SCROLL_INSENSITIVE, ResultSet.CONCU
```

The result sets returned by a call to `executeQuery` are then updatable.

Note: Not all queries return updatable result sets. If your query is a join that involves multiple tables, the result might not be updatable. However, if your query involves only a single table or if it joins multiple tables by their primary keys, you should expect the result set to be updatable. Call the `getConcurrency` method of the `ResultSet` interface to find out for sure.

For example, suppose you want to raise the prices of some books, but you don't have a simple criterion for issuing an `UPDATE`

statement. Then, you can iterate through all books and update prices based on arbitrary conditions.

```
String query = "SELECT * FROM Books";
ResultSet rs = stat.executeQuery(query);
while (rs.next())
{
   if (. . .)
   {
      double increase = . . .;
      double price = rs.getDouble("Price");
      rs.updateDouble("Price", price + increase);
      rs.updateRow(); // make sure to call updateRow
   }
}
```

There are `updateXxx` methods for all data types that correspond to SQL types, such as `updateDouble`, `updateString`, and so on; specify the name or the number of the column (as with the `getXxx` methods), then the new value for the field.

Note: If you use the `updateXxx` method whose first parameter is the column number, be aware that this is the column number in the *result set*. It could well be different from the column number in the database.

The `updateXxx` method changes only the row values, not the database. When you are done with the field updates in a row, you must call the `updateRow` method. That method sends all updates in the current row to the database. If you move the cursor to another row without calling `updateRow`, this row's updates are discarded from the row set and never communicated to the database. You can also call the `cancelRowUpdates` method to cancel the updates to the current row.

The preceding example shows how to modify an existing row. If you want to add a new row to the database, first use the `moveToInsertRow` method to move the cursor to a special position, called the *insert row.* Then, build up a new row in the insert row position by issuing `updateXxx` instructions. When you are done, call the `insertRow` method to deliver the new row to the database. When you are done inserting, call `moveToCurrentRow` to move the cursor back to the position before the call to `moveToInsertRow`. Here is an example:

```
rs.moveToInsertRow();
rs.updateString("Title", title);
rs.updateString("ISBN", isbn);
rs.updateString("Publisher_Id", pubid);
```

```
rs.updateDouble("Price", price);
rs.insertRow();
rs.moveToCurrentRow();
```

Note that you cannot influence *where* the new data is added in the result set or the database.

If you don’t specify a column value in the insert row, it is set to a SQL `NULL`. However, if the column has a `NOT NULL` constraint, an exception is thrown and the row is not inserted.

Finally, you can delete the row under the cursor:

```
rs.deleteRow();
```

The `deleteRow` method immediately removes the row from both the result set and the database.

The `updateRow`, `insertRow`, and `deleteRow` methods of the `ResultSet` interface give you the same power as executing `UPDATE`, `INSERT`, and `DELETE` SQL statements. However, Java programmers might find it more natural to manipulate the database contents through result sets than by constructing SQL statements.

Caution: If you are not careful, you can write staggeringly inefficient code with updatable result sets. It is *much* more efficient to execute an `UPDATE` statement than to make a query and iterate through the result, changing data along the way. Updatable result sets make sense for interactive programs in which a user can make arbitrary changes, but for most programmatic changes, a SQL `UPDATE` is more appropriate.

Note: JDBC 2 delivered further enhancements to result sets, such as the capability to update a result set with the most recent data if the data have been modified by another concurrent database connection. JDBC 3 added yet another refinement, specifying the behavior of result sets when a transaction is committed. However, these advanced features are outside the scope of this introductory chapter. We refer you to the *JDBC™ API Tutorial and Reference, Third Edition*, by Maydene Fisher, Jon Ellis, and Jonathan Bruce (Addison-Wesley, 2003) and the JDBC specification for more information.

java.sql.Connection 1.1

- `Statement createStatement(int type, int concurrency)` 1.2
- `PreparedStatement prepareStatement(String command, int type, int concurrency)` 1.2
  create a statement or prepared statement that yields result sets with the given type and concurrency. The `type` parameter is of the constants `TYPE_FORWARD_ONLY`, `TYPE_SCROLL_INSENSITIVE`, or `TYPE_SCROLL_SENSITIVE`, and `concurrency` is one of the constants `CONCUR_READ_ONLY` or `CONCUR_UPDATABLE`, all defined in the `ResultSet` interface.

java.sql.ResultSet 1.1

- `int getType()` 1.2
  returns the type of this result set—one of `TYPE_FORWARD_ONLY`, `TYPE_SCROLL_INSENSITIVE`, or `TYPE_SCROLL_SENSITIVE`.
- `int getConcurrency()` 1.2
  returns the concurrency setting of this result set—one of `CONCUR_READ_ONLY` or `CONCUR_UPDATABLE`.
- `boolean previous()` 1.2
  moves the cursor to the preceding row. Returns `true` if the cursor is positioned on a row, or `false` if the cursor is

positioned before the first row.

- `int getRow()` **1.2**
  gets the number of the current row. Rows are numbered starting with `1`.
- `boolean absolute(int r)` **1.2**
  moves the cursor to row `r`. Returns `true` if the cursor is positioned on a row.
- `boolean relative(int d)` **1.2**
  moves the cursor by `d` rows. If `d` is negative, the cursor is moved backward. Returns `true` if the cursor is positioned on a row.
- `boolean first()` **1.2**
- `boolean last()` **1.2**
  move the cursor to the first or last row. Return `true` if the cursor is positioned on a row.
- `void beforeFirst()` **1.2**
- `void afterLast()` **1.2**
  move the cursor before the first or after the last row.
- `boolean isFirst()` **1.2**
- `boolean isLast()` **1.2**
  test whether the cursor is at the first or last row.
- `boolean isBeforeFirst()` **1.2**
- `boolean isAfterLast()` **1.2**
  test whether the cursor is before the first or after the last row.

- `void moveToInsertRow()` **1.2**
  moves the cursor to the insert row. The insert row is a special row for inserting new data with the `updateXxx` and `insertRow` methods.
- `void moveToCurrentRow()` **1.2**
  moves the cursor back from the insert row to the row that it occupied when the `moveToInsertRow` method was called.
- `void insertRow()` **1.2**
  inserts the contents of the insert row into the database and the result set.
- `void deleteRow()` **1.2**
  deletes the current row from the database and the result set.
- `void updateXxx(int column, Xxx data)` **1.2**
- `void updateXxx(String columnName, Xxx data)` **1.2**
  (Xxx is a type such as `int`, `double`, `String`, `Date`, etc.)
  update a field in the current row of the result set.
- `void updateRow()` **1.2**
  sends the current row updates to the database.
- `void cancelRowUpdates()` **1.2**
  cancels the current row updates.

java.sql.DatabaseMetaData **1.1**

- `boolean supportsResultSetType(int type)` **1.2**
  returns `true` if the database can support result sets of the given type; `type` is one of the constants `TYPE_FORWARD_ONLY`, `TYPE_SCROLL_INSENSITIVE`, or `TYPE_SCROLL_SENSITIVE` of the `ResultSet` interface.
- `boolean supportsResultSetConcurrency(int type, int concurrency)` **1.2**
  returns `true` if the database can support result sets of the given combination of type and concurrency. The `type` parameter is one of the constants `TYPE_FORWARD_ONLY`, `TYPE_SCROLL_INSENSITIVE`, or `TYPE_SCROLL_SENSITIVE`, and `concurrency` is one of the constants `CONCUR_READ_ONLY` or `CONCUR_UPDATABLE`, all defined in the `ResultSet` interface.

1.7. Row Sets

Scrollable result sets are powerful, but they have a major drawback. You need to keep the database connection open during the entire user interaction. However, a user can walk away from the computer for a long time, leaving the connection occupied. That is not good—database connections are scarce resources. In this situation, use a *row set*. The `RowSet` interface extends the `ResultSet` interface, but row sets don't have to be tied to a database connection.

Row sets are also suitable if you need to move a query result to a different tier of a complex application, or to another device such as a cell phone. You would never want to move a result set—its data structures can be huge, and it is tethered to the database connection.

1.7.1. Constructing Row Sets

The `javax.sql.rowset` package provides the following interfaces that extend the `RowSet` interface:

- A `CachedRowSet` allows disconnected operation. We will discuss cached row sets in the following section.
- A `WebRowSet` is a cached row set that can be saved to an XML file. The XML file can be moved to another tier of a web application where it is opened by another `WebRowSet` object.
- The `FilteredRowSet` and `JoinRowSet` interfaces support lightweight operations on row sets that are equivalent to SQL `SELECT` and `JOIN` operations. These operations are carried out on the data stored in row sets, without having to make a database connection.
- A `JdbcRowSet` is a thin wrapper around a `ResultSet`. It adds useful methods from the `RowSet` interface.

To obtain a cached row set, call:

```
RowSetFactory factory = RowSetProvider.newFactory();
CachedRowSet crs = factory.createCachedRowSet();
```

There are similar methods for obtaining the other row set types.

1.7.2. Cached Row Sets

A cached row set contains all data from a result set. Since `CachedRowSet` is a subinterface of the `ResultSet` interface, you can use a cached row set exactly as you would use a result set. Cached row sets confer an important benefit: You can close the connection and still use the row set. As you will see in our sample program in Listing 5.4, this greatly simplifies the implementation of interactive applications. Each user command simply opens the database connection, issues a query, puts the result in a cached row set, and then closes the database connection.

It is even possible to modify the data in a cached row set. Of course, the modifications are not immediately reflected in the database; you need to make an explicit request to accept the accumulated changes. The `CachedRowSet` then reconnects to the database and issues SQL statements to write the accumulated changes.

You can populate a `CachedRowSet` from a result set:

```
ResultSet result = . . .;
RowSetFactory factory = RowSetProvider.newFactory();
CachedRowSet crs = factory.createCachedRowSet();
crs.populate(result);
conn.close(); // now OK to close the database connect
```

Alternatively, you can let the `CachedRowSet` object establish a connection automatically. Set up the database parameters:

```
crs.setURL("jdbc:derby://localhost:1527/COREJAVA");
crs.setUsername("dbuser");
crs.setPassword("secret");
```

Then set the query statement and any parameters:

```
crs.setCommand("SELECT * FROM Books WHERE Publisher_I
crs.setString(1, publisherId);
```

Finally, populate the row set with the query result:

```
crs.execute();
```

This call establishes a database connection, issues the query, populates the row set, and disconnects.

If your query result is very large, you would not want to put it into the row set in its entirety. After all, your users will probably only look at a few rows. In that case, specify a page size:

```
CachedRowSet crs = . . .;
crs.setCommand(command);
crs.setPageSize(20);
. . .
crs.execute();
```

Now you will only get 20 rows. To get the next batch of rows, call

```
crs.nextPage();
```

You can inspect and modify the row set with the same methods you use for result sets. If you modified the row set contents, you must write it back to the database by calling

```
crs.acceptChanges(conn);
```

or

```
crs.acceptChanges();
```

The second call works only if you configured the row set with the information required to connect to a database (such as the URL, username, and password).

In Section 5.6.2, you saw that not all result sets are updatable. Similarly, a row set that contains the result of a complex query will not be able to write its changes back to the database. You should be safe if your row set contains data from a single table.

Caution: If you populated the row set from a result set, the row set does not know the name of the table to update. You need to call `setTableName` to set the table name.

Another complexity arises if the data in the database have changed after you populated the row set. This is clearly a sign of trouble that could lead to inconsistent data. The reference implementation checks whether the original row set values (that is, the values before editing) are identical to the current values in the database. If so, they are replaced with the edited values; otherwise, a `SyncProviderException` is thrown and none of the changes are written. Other implementations may use other strategies for synchronization.

javax.sql.RowSet **1.4**

- `String getURL()`
- `void setURL(String url)`
  get or set the database URL.
- `String getUsername()`
- `void setUsername(String username)`
  get or set the username for connecting to the database.
- `String getPassword()`
- `void setPassword(String password)`
  get or set the password for connecting to the database.
- `String getCommand()`
- `void setCommand(String command)`
  get or set the command that is executed to populate this row set.
- `void execute()`
  populates this row set by issuing the statement set with `setCommand`. For the driver manager to obtain a connection, the URL, username, and password must be set.

javax.sql.rowset.CachedRowSet **5.0**

- `void execute(Connection conn)`
  populates this row set by issuing the statement set with `setCommand`. This method uses the given connection *and closes*

it.

- `void populate(ResultSet result)`
  populates this cached row set with the data from the given result set.
- `String getTableName()`
- `void setTableName(String tableName)`
  get or set the name of the table from which this cached row set was populated.
- `int getPageSize()`
- `void setPageSize(int size)`
  get or set the page size.
- `boolean nextPage()`
- `boolean previousPage()`
  load the next or previous page of rows. Return `true` if there is a next or previous page.
- `void acceptChanges()`
- `void acceptChanges(Connection conn)`
  reconnect to the database and write the changes that are the result of editing the row set. May throw a `SyncProviderException` if the data cannot be written back because the database data have changed.

`javax.sql.rowset.RowSetProvider` 7

- `static RowSetFactory newFactory()`
  creates a row set factory.

javax.sql.rowset.RowSetFactory 7

- `CachedRowSet createCachedRowSet()`
- `FilteredRowSet createFilteredRowSet()`
- `JdbcRowSet createJdbcRowSet()`
- `JoinRowSet createJoinRowSet()`
- `WebRowSet createWebRowSet()`
  create a row set of the specified type.

1.8. Metadata

In the preceding sections, you saw how to populate, query, and update database tables. However, JDBC can give you additional information about the *structure* of a database and its tables. For example, you can get a list of the tables in a particular database or the column names and types of a table. This information is not useful when you are implementing a business application with a predefined database. After all, if you design the tables, you know their structure. Structural information is, however, extremely useful for programmers who write tools that work with any database.

In SQL, data that describe the database or one of its parts are called *metadata* (to distinguish them from the actual data stored in the database). You can get three kinds of metadata: about a database, about a result set, and about parameters of prepared statements.

To find out more about the database, request an object of type `DatabaseMetaData` from the database connection.

```
DatabaseMetaData meta = conn.getMetaData();
```

Use this object to get information about the database. For example, the call

```
ResultSet mrs = meta.getTables(null, null, null, new
```

returns a result set that contains information about all tables in the database. (See the API note at the end of this section for other parameters to this method.)

Each row in the result set contains information about a table in the database. The third column is the name of the table. (Again, see the API note for the other columns.) The following loop gathers all table names:

```
while (mrs.next())
   tableNames.add(mrs.getString(3));
```

There is a second important use for database metadata. Databases are complex, and the SQL standard leaves plenty of room for variability. Well over a hundred methods in the `DatabaseMetaData` interface can inquire about the database, including calls with such exotic names as

```
meta.supportsCatalogsInPrivilegeDefinitions()
```

and

```
meta.nullPlusNonNullIsNull()
```

Clearly, these are geared toward advanced users with special needs—in particular, those who need to write highly portable code that works with multiple databases.

The `DatabaseMetaData` interface gives data about the database. A second metadata interface, `ResultSetMetaData`, reports information about a result set. Whenever you have a result set from a query, you can inquire about the number of columns and each column's name, type, and field width. Here is a typical loop:

```
ResultSet rs = stat.executeQuery("SELECT * FROM " + t
ResultSetMetaData rsmd = rs.getMetaData();
for (int i = 1; i <= rsmd.getColumnCount(); i++)
{
   String columnName = rsmd.getColumnLabel(i);
   int columnWidth = rsmd.getColumnDisplaySize(i);
   . . .
}
```

If you have a prepared statement, you can get the metadata of the result set that is returned when the statement is executed:

```
PreparedStatement pstat = conn.prepareStatement(. . .
ResultSetMetaData rsmd = pstat.getMetaData();
```

A third kind of metadata describes the parameters of a prepared statement:

```
ParameterMetaData pmd = pstat.getParameterMetaData();
for (int i = 1; i <= pmd.getParameterCount())
{
   System.out.println(pmd.getParameterTypeName(i));
}
```

The program in Listing 5.4 uses metadata to let you browse all tables in a database and carry out simple edits. The program also illustrates the use of a cached row set.

The companion code has a prettier GUI version. The combo box on top displays all tables in the database. Select one of them, and the center of the frame is filled with the field names of that table and the values of the first row, as shown in Figure 5.6. Click Next and Previous to scroll through the rows in the table. You can also delete a row and edit values of type `String`. Click the Save button to save the changes to the database.



Figure 1.6: The `ViewDB` GUI application

Note: The example program shows you how to implement tools for working with arbitrary tables. Many databases and IDEs come with much more sophisticated tools for viewing and editing tables. If

you prefer a standalone program, check out DBeaver (https://dbeaver.io) or SQuirreL (https://https://squirrelsql.org). These programs can be used with any JDBC database.

Listing 1.4 view/ViewDB2.java

```
1  package view;
2
3  import java.io.*;
4  import java.nio.file.*;
5  import java.sql.*;
6  import java.util.*;
7
8  import javax.sql.rowset.*;
9
10 import util.*;
11
12 /**
13  * This program uses metadata to display arbitr
14  * @version 1.0 2023-08-16
15  * @author Cay Horstmann
16  */
17 public class ViewDB2
18 {
19    private CachedRowSet crs;
20    private Scanner console;
```

```
21
22    record Column(String label, int width, Strin
23    private List<Column> columns = new ArrayList
24
25    public static void main(String[] args)
26    {
27       new ViewDB2().run();
28    }
29
30    public void run()
31    {
32       try (Connection conn = getConnection(reac
33       {
34          console = new Scanner(System.in);
35          DatabaseMetaData meta = conn.getMetaDa
36          var tableNames = new ArrayList<String>
37
38          try (ResultSet mrs = meta.getTables(nu
39          {
40             while (mrs.next())
41                tableNames.add(mrs.getString(3))
42          }
43          System.out.println("Choose a table");
44          String selected = Choices.choose(consc
45          showTable(selected, conn);
46          executeCommands();
47          crs.acceptChanges(conn);
48       }
```

```
49          catch (SQLException e)
50          {
51             for (Throwable t : e)
52                t.printStackTrace();
53          }
54          catch (IOException e)
55          {
56             e.printStackTrace();
57          }
58       }
59
60       /**
61        * Prepares the columns list for showing a r
62        * @param tableName the name of the table to
63        * @param conn the database connection
64        */
65       public void showTable(String tableName, Conn
66       {
67          try (Statement stat = conn.createStatemen
68                ResultSet result = stat.executeQuer
69          {
70             // copy into cached row set
71             RowSetFactory factory = RowSetProvider
72             crs = factory.createCachedRowSet();
73             crs.setTableName(tableName);
74             crs.populate(result);
75
76             ResultSetMetaData rsmd = result.getMet
```

```
77          for (int i = 1; i <= rsmd.getColumnCou
78          {
79             columns.add(new Column(rsmd.getColu
80                   rsmd.getColumnDisplaySize(i),
81                   rsmd.getColumnClassName(i)));
82          }
83
84          showNextRow();
85       }
86    }
87
88    public void executeCommands() throws SQLExce
89    {
90       while (true)
91       {
92          String selection = Choices.choose(cons
93          switch (selection)
94          {
95             case "Next" -> showNextRow();
96             case "Previous" -> showPreviousRow(
97             case "Edit" -> editRow();
98             case "Delete" -> deleteRow();
99             default -> { return; }
100         }
101      }
102   }
103
104   /**
```

```
105      * Shows a database row by populating all te
106      */
107     public void showRow(ResultSet rs) throws SQL
108     {
109        for (int i = 1; i <= columns.size(); i++)
110        {
111           String format = "%%s [%%%ds]%%n".forma
112           System.out.printf(format, columns.get(
113        }
114     }
115
116     /**
117      * Moves to the previous table row.
118      */
119     public void showPreviousRow() throws SQLExce
120     {
121        if (crs == null || crs.isFirst()) return;
122        crs.previous();
123        showRow(crs);
124     }
125
126     /**
127      * Moves to the next table row.
128      */
129     public void showNextRow() throws SQLExceptio
130     {
131        if (crs == null || crs.isLast()) return;
132        crs.next();
```

```
133         showRow(crs);
134      }
135
136      /**
137       * Deletes current table row.
138       */
139      public void deleteRow() throws SQLException
140      {
141         if (crs == null) return;
142         crs.deleteRow();
143         if (crs.isAfterLast())
144         {
145            if (!crs.last()) crs = null;
146         }
147         showRow(crs);
148      }
149
150      /**
151       * Updates changed data into the current row
152       */
153      public void editRow() throws SQLException
154      {
155         List<String> editableColumns = columns.st
156               .filter(c -> c.columnClass.equals("
157               .map(Column::label)
158               .toList();
159         System.out.println("Choose column");
160         String label = Choices.choose(console, ed
```

```
161         System.out.print("New value:  ");
162         String newValue = console.nextLine();
163         crs.updateString(label, newValue);
164         crs.updateRow();
165      }
166
167      private Properties readDatabaseProperties()
168      {
169         var props = new Properties();
170         try (Reader in = Files.newBufferedReader(
171         {
172            props.load(in);
173         }
174         String drivers = props.getProperty("jdbc
175         if (drivers != null) System.setProperty("
176         return props;
177      }
178
179      /**
180       * Gets a connection from the properties spe
181       * @return the database connection
182       */
183      private Connection getConnection(Properties
184      {
185         String url = props.getProperty("jdbc.url"
186         String username = props.getProperty("jdbc
187         String password = props.getProperty("jdbc
188
```

```
189         return DriverManager.getConnection(url, u
190      }
191   }
```

java.sql.Connection **1.1**

- `DatabaseMetaData getMetaData()`
  returns the metadata for the connection as a `DatabaseMetaData` object.

java.sql.DatabaseMetaData **1.1**

- `ResultSet getTables(String catalog, String schemaPattern, String tableNamePattern, String types[])`
  returns a description of all tables in a catalog that match the schema and table name patterns and the type criteria. (A *schema* describes a group of related tables and access permissions. A *catalog* describes a related group of schemas. These concepts are important for structuring large databases.)
  The `catalog` and `schemaPattern` parameters can be `""` to retrieve those tables without a catalog or schema, or `null` to return tables regardless of catalog or schema.
  The `types` array contains the names of the table types to include. Typical types are `TABLE`, `VIEW`, `SYSTEM TABLE`,

`GLOBAL TEMPORARY`, `LOCAL TEMPORARY`, `ALIAS`, and `SYNONYM`. If `types` is `null`, tables of all types are returned. The result set has five columns, all of which are of type `String`.

Column	Name	Explanation
1	`TABLE_CAT`	Table catalog (may be `null`)
2	`TABLE_SCHEM`	Table schema (may be `null`)
3	`TABLE_NAME`	Table name
4	`TABLE_TYPE`	Table type
5	`REMARKS`	Comment on the table

- `int getJDBCMajorVersion()` **1.4**
- `int getJDBCMinorVersion()` **1.4**

  return the major or minor JDBC version numbers of the driver that established the database connection. For example, a JDBC 4.3 driver has major version number 4 and minor version number 3.
- `int getMaxConnections()`

  returns the maximum number of concurrent connections allowed to this database.

- `int getMaxStatements()`
  returns the maximum number of concurrently open statements allowed per database connection, or `0` if the number is unlimited or unknown.

java.sql.ResultSet **1.1**

- `ResultSetMetaData getMetaData()`
  returns the metadata associated with the current `ResultSet` columns.

java.sql.PreparedStatement **1.1**

- `ResultSetMetaData getMetaData()` **1.2**
  returns the metadata associated with the result set that is returned when this statement is executed.
- `ParameterMetaData getMetaData()` **1.4**
  returns metadata describing the parameters of this statement.

java.sql.ResultSetMetaData **1.1**

- `int getColumnCount()`
  returns the number of columns in the current `ResultSet` object.

- `String getColumnName(int column)`
- `String getColumnLabel(int column)`
- `int getColumnDisplaySize(int column)`
  returns the name, suggested title, and display size of the column with the given one-based index.

java.sql.ParameterMetaData **1.4**

- `int getParameterCount()`
  returns the number of parameters of the prepared statement.
- `int getParameterType(int param)`
- `String getParameterTypeName(int param)`
- `String getParameterClassName(int param)`
  returns the type of the parameter with the given one-based index, as a constant defined in `java.sql.Types`, or as a database-specific type name, or as a fully-qualified Java class name.
- `int getParameterMode(int param)`
  returns the mode of the parameter with the given one-based index, as one of the static constants `parameterModeIn`, `parameterModeOut`, `parameterModeInOut`, or `parameterModeUnknown`.
- `int isNullable(int param)`
  returns the nullability mode of the parameter with the given one-based index, as one of the static constants `parameterNoNulls`,

`parameterNullable`, or `parameterNullableUnknown`.

- `int getPrecision(int param)`
  returns the maximum column size of the parameter with the given one-based index. For non-numeric data types, this is the length of the string or string representation, or the number of bytes for binary data.
- `int getScale(int param)`
  returns the number of digits after the decimal point of the parameter with the given one-based index, or 0 for non-numeric data.

1.9. Transactions

You can group a set of statements to form a *transaction*. The transaction can be *committed* when all has gone well—or, if an error has occurred in one of them, it can be *rolled back* as if none of the statements had been issued.

The major reason for grouping statements into transactions is *database integrity*. For example, suppose we want to transfer money from one bank account to another. Then, it is important that we simultaneously debit one account and credit another. If the system fails after debiting the first account but before crediting the other account, the debit needs to be undone.

If you group update statements into a transaction, the transaction either succeeds in its entirety and can be *committed,* or it fails somewhere in the middle. In that case, you can carry out a *rollback* and the database automatically undoes the effect of all updates that occurred since the last committed transaction.

1.9.1. Programming Transactions with JDBC

By default, a database connection is in *autocommit mode*, and each SQL statement is committed to the database as soon as it is executed. Once a statement is committed, you cannot roll it back. Turn off this default so you can use transactions:

```
conn.setAutoCommit(false);
```

Create a statement object in the normal way:

```
Statement stat = conn.createStatement();
```

Call `executeUpdate` any number of times:

```
stat.executeUpdate(command1);
stat.executeUpdate(command2);
stat.executeUpdate(command3);
```

```
. . .
```

If all statements have been executed without error, call the `commit` method:

```
conn.commit();
```

However, if an error occurred, call

```
conn.rollback();
```

Then, all statements since the last commit are automatically reversed. You typically issue a rollback when your transaction was interrupted by a `SQLException`.

1.9.2. Save Points

With some databases and drivers, you can gain finer-grained control over the rollback process by using *save points*. Creating a save point marks a point to which you can later return without having to abandon the entire transaction. For example,

```
Statement stat = conn.createStatement(); // start tra
stat.executeUpdate(command1);
Savepoint svpt = conn.setSavepoint(); // set savepoin
stat.executeUpdate(command2);

if (. . .) conn.rollback(svpt); // undo effect of com
. . .
conn.commit();
```

When you no longer need a save point, you should release it:

```
conn.releaseSavepoint(svpt);
```

1.9.3. Batch Updates

Suppose a program needs to execute many `INSERT` statements to populate a database table. You can improve the performance of the program by using a *batch update.* In a batch update, a sequence of statements is collected and submitted as a batch.

Note: Use the `supportsBatchUpdates` method of the `DatabaseMetaData` interface to find out if your database supports this feature.

The statements in a batch can be actions such as `INSERT`, `UPDATE`, or `DELETE` as well as data definition statements such as `CREATE TABLE` or `DROP TABLE`. An exception is thrown if you add a `SELECT` statement to a batch. (Conceptually, a `SELECT` statement makes no sense in a batch because it returns a result set without updating the database.)

To execute a batch, first create a `Statement` object in the usual way:

```
Statement stat = conn.createStatement();
```

Now, instead of calling `executeUpdate`, call the `addBatch` method:

```
String command = "CREATE TABLE . . ."
stat.addBatch(command);

while (. . .)
{
   command = "INSERT INTO . . . VALUES (" + . . . + "
   stat.addBatch(command);
}
```

Finally, submit the entire batch:

```
int[] counts = stat.executeBatch();
```

The call to `executeBatch` returns an array of the row counts for all submitted statements.

For proper error handling in batch mode, treat the batch execution as a single transaction. If a batch fails in the middle, you want to roll back to the state before the beginning of the batch.

First, turn the autocommit mode off, then collect the batch, execute it, commit it, and finally restore the original autocommit mode:

```
boolean autoCommit = conn.getAutoCommit();
conn.setAutoCommit(false);
Statement stat = conn.getStatement();
. . .
// keep calling stat.addBatch(. . .);
. . .
stat.executeBatch();
conn.commit(); conn.setAutoCommit(autoCommit);
```

java.sql.Connection **1.1**

- `boolean getAutoCommit()`
- `void setAutoCommit(boolean b)`
  get or set the autocommit mode of this connection to `b`. If autocommit is `true`, all statements are committed as soon as their execution is completed.
- `void commit()`
  commits all statements that were issued since the last commit.
- `void rollback()`
  undoes the effect of all statements that were issued since the last commit.
- `Savepoint setSavepoint()` **1.4**
- `Savepoint setSavepoint(String name)` **1.4**
  set an unnamed or named save point.
- `void rollback(Savepoint svpt)` **1.4**
  rolls back until the given save point.
- `void releaseSavepoint(Savepoint svpt)` **1.4**
  releases the given save point.

java.sql.Savepoint **1.4**

- `int getSavepointId()`
  gets the ID of this unnamed save point, or throws a `SQLException` if this is a named save point.
- `String getSavepointName()`
  gets the name of this save point, or throws a `SQLException` if this is an unnamed save point.

java.sql.Statement **1.1**

- `void addBatch(String command)` **1.2**
  adds the command to the current batch of commands for this statement.
- `int[] executeBatch()` **1.2**
- `long[] executeLargeBatch()` **8**
  execute all commands in the current batch. Each value in the returned array corresponds to one of the batch statements. If it is non-negative, it is a row count. If it is the value `SUCCESS_NO_INFO`, the statement succeeded, but no row count is available. If it is `EXECUTE_FAILED`, the statement failed.

java.sql.DatabaseMetaData 1.1

- `boolean supportsBatchUpdates()` 1.2
  returns `true` if the driver supports batch updates.

1.9.4. Advanced SQL Types

Table 5.8 lists the SQL data types supported by JDBC and their equivalents in the Java programming language.

Table 1.8: SQL Data Types and Their Corresponding Java Types

SQL Data Type	Java Data Type
`INTEGER` or `INT`	`int`
`SMALLINT`	`short`
`NUMERIC(m,n)`, `DECIMAL(m,n)` or `DEC(m,n)`	`java.math.BigDecimal`
`FLOAT(n)`	`double`
`REAL`	`float`

SQL Data Type	Java Data Type
`DOUBLE`	`double`
`CHARACTER(n)` or `CHAR(n)`	`String`
`VARCHAR(n)`, `LONG VARCHAR`	`String`
`BOOLEAN`	`boolean`
`DATE`	`java.sql.Date`
`TIME`	`java.sql.Time`
`TIMESTAMP`	`java.sql.Timestamp`
`BLOB`	`java.sql.Blob`
`CLOB`	`java.sql.Clob`
`ARRAY`	`java.sql.Array`
`ROWID`	`java.sql.RowId`

SQL Data Type	Java Data Type
`NCHAR(n)`, `NVARCHAR(n)`, `LONG NVARCHAR`	`String`
`NCLOB`	`java.sql.NClob`
`SQLXML`	`java.sql.SQLXML`

A SQL `ARRAY` is a sequence of values. For example, in a `Student` table, you can have a `Scores` column that is an `ARRAY OF INTEGER`. The `getArray` method returns an object of the interface type `java.sql.Array`. That interface has methods to fetch the array values.

When you get a LOB or an array from a database, the actual contents are fetched from the database only when you request individual values. This is a useful performance enhancement, as the data can be quite voluminous.

Some databases support `ROWID` values that describe the location of a row so that it can be retrieved very rapidly. JDBC 4 introduced an interface `java.sql.RowId` and the methods to supply the row ID in queries and retrieve it from results.

A *national character string* (`NCHAR` and its variants) stores strings in a local character encoding and sorts them using a local sorting convention. JDBC 4 provided methods for converting between Java `String` objects and national character strings in queries and results.

Some databases can store user-defined structured types. JDBC 3 provides a mechanism for automatically mapping structured SQL types to Java objects.

Some databases provide native storage for XML data. JDBC 4 introduced a `SQLXML` interface that can mediate between the internal XML representation and the DOM `Source/Result` interfaces, as well as binary streams. See the API documentation for the `SQLXML` class for details.

We do not discuss these advanced SQL types any further. You can find more information on these topics in the *JDBC API Tutorial and Reference* and the JDBC specification.

1.10. Connection Management in Web and Enterprise Applications

The simplistic database connection setup with a `database.properties` file, as described in the preceding sections,

is suitable for small test programs but won't scale for larger applications.

When a JDBC application is deployed in a web or enterprise environment, the management of database connections is integrated with a directory service called JNDI (Java Naming and Directory Interface). The properties of data sources across the enterprise can be stored in a directory. Using a directory allows for centralized management of usernames, passwords, database names, and JDBC URLs.

In such an environment, you can use the following code to establish a database connection:

```
var jndiContext = new InitialContext();
var source = (DataSource) jndiContext.lookup("java:co
Connection conn = source.getConnection();
```

Note that the `DriverManager` is no longer involved. Instead, the JNDI service locates a *data source.* A data source is an interface that allows for simple JDBC connections as well as more advanced services, such as executing distributed transactions that involve multiple databases. The `DataSource` interface is defined in the `javax.sql` standard extension package.

Note: In a Java EE container, you don't even have to program the JNDI lookup. Simply use the `Resource` annotation on a `DataSource` field, and the data source reference will be set when your application is loaded:

```
@Resource(name="jdbc/corejava")
private DataSource source;
```

Of course, the data source needs to be configured somewhere. If you write database programs that execute in a servlet container such as Apache Tomcat or in an application server such as GlassFish, place the database configuration (including the JNDI name, JDBC URL, username, and password) in a configuration file, or set it in an admin GUI.

Management of usernames and logins is just one of the issues that require special attention. Another issue involves the cost of establishing database connections. Our sample database programs used two strategies for obtaining a database connection. The `QueryDB` program in Listing 5.3 established a single database connection at the start of the program and closed it at the end of the program. The `ViewDB` program in Listing 5.4 opened a new connection whenever one was needed.

However, neither of these approaches is satisfactory. Database connections are a finite resource. If a user walks away from an application for some time, the connection should not be left open. Conversely, obtaining a connection for each query and closing it afterward is very costly.

The solution is to *pool* connections. This means that database connections are not physically closed but are kept in a queue and reused. Connection pooling is an important service, and the JDBC specification provides hooks for implementors to supply it. However, the JDK itself does not provide any implementation, and database vendors don't usually include one with their JDBC drivers either. Instead, vendors of web containers and application servers supply connection pool implementations.

Using a connection pool is completely transparent to the programmer. Acquire a connection from a source of pooled connections by obtaining a data source and calling `getConnection`. When you are done using the connection, call `close`. That doesn't close the physical connection but tells the pool that you are done using it. The connection pool typically makes an effort to pool prepared statements as well.

You have now learned about the JDBC fundamentals and know enough to implement simple database applications. However, as we

mentioned at the beginning of this chapter, databases are complex and quite a few advanced topics are beyond the scope of this introductory chapter. For an overview of advanced JDBC capabilities, refer to the *JDBC API Tutorial and Reference* or the JDBC specification.

In this chapter, you have learned how to work with relational databases in Java. The next chapter covers the date and time library.

1. The Date and Time API

Time flies like an arrow, and we can easily set a starting point and count forward and backward in seconds. So why is it so hard to deal with time? The problem is humans. All would be easy if we could just tell each other: “Meet me at 1523793600, and don’t be late!” But we want time to relate to daylight and the seasons. That’s where things get complicated. Java 1.0 had a `Date` class that was, in hindsight, naïve, and had most of its methods deprecated in Java 1.1 when a `Calendar` class was introduced. Its API wasn’t stellar, its instances were mutable, and it didn’t deal with issues such as leap seconds. The third time is a charm, and the `java.time` API introduced in Java 8 has remedied the flaws of the past and should serve us for quite some time. In this chapter, you will learn what makes time computations so vexing, and how the Date and Time API solves these issues.

1.1. The Time Line

Historically, the fundamental time unit—the second—was derived from Earth's rotation around its axis. There are 24 hours or 24 × 60 × 60 = 86400 seconds in a full revolution, so it seems just a question of astronomical measurements to precisely define a second. Unfortunately, Earth wobbles slightly, and a more precise definition

was needed. In 1967, a new precise definition of a second, matching the historical definition, was derived from an intrinsic property of atoms of caesium-133. Since then, a network of atomic clocks keeps the official time.

Ever so often, the official time keepers synchronize the absolute time with the rotation of Earth. At first, the official seconds were slightly adjusted, but starting in 1972, "leap seconds" were occasionally inserted. (In theory, a second might need to be removed once in a while, but that has not yet happened.) There is talk of changing the system again. Clearly, leap seconds are a pain, and many computer systems instead use "smoothing" where time is artificially slowed down or sped up just before the leap second, keeping 86,400 seconds per day. This works because the local time on a computer isn't all that precise, and computers are used to synchronizing themselves with an external time service.

The Java Date and Time API specification requires that Java uses a time scale that

- Has 86,400 seconds per day
- Exactly matches the official time at noon each day
- Closely matches it elsewhere, in a precisely defined way

That gives Java the flexibility to adjust to future changes in the official time.

In Java, an `Instant` represents a point on the time line. An origin, called the *epoch*, is arbitrarily set at midnight of January 1, 1970 at the prime meridian that passes through the Greenwich Royal Observatory in London. This is the same convention used in the UNIX/POSIX time. Starting from that origin, time is measured in 86,400 seconds per day, forward and backward, to nanosecond precision. The `Instant` values go back as far as a billion years (`Instant.MIN`). That's not quite enough to express the age of the universe (around 13.5 billion years) but it should be enough for all practical purposes. After all, a billion years ago, the earth was covered in ice and populated by microscopic ancestors of today's plants and animals. The largest value, `Instant.MAX`, is December 31 of the year 1,000,000,000.

The static method call `Instant.now()` gives the current instant. You can compare two instants with the `equals` and `compareTo` methods in the usual way, so you can use instants as timestamps.

To find out the difference between two instants, use the static method `Duration.between`. For example, here is how you can measure the running time of an algorithm:

```
Instant start = Instant.now();
runAlgorithm();
Instant end = Instant.now();
Duration timeElapsed = Duration.between(start, end);
long millis = timeElapsed.toMillis();
```

A `Duration` is the amount of time between two instants. You can get the length of a `Duration` in conventional units by calling `toNanos`, `toMillis`, `toSeconds`, `toMinutes`, `toHours`, or `toDays`.

Note: In Java 8, you had to call `getSeconds` instead of `toSeconds`.

If you need nanosecond precision, be aware of overflow. A `long` value can hold almost 300 years of nanoseconds. If your durations are shorter than that, simply convert them to nanoseconds. You can use longer durations—a `Duration` object stores the number of seconds in a `long`, and the number of nanoseconds in an additional `int`. The `Duration` API has a number of methods, shown at the end of this section, for carrying out arithmetic.

For example, if you want to check whether an algorithm is at least ten times faster than another, you can compute

```
Duration timeElapsed2 = Duration.between(start2, end2
boolean overTenTimesFaster
   = timeElapsed.multipliedBy(10).minus(timeElapsed2)
```

This is just to show the syntax. Since the algorithms aren't going to run for hundreds of years, you can simply use

```
boolean overTenTimesFaster = timeElapsed.toNanos() *
```

Note: The `Instant` and `Duration` classes are immutable, and all methods, such as `multipliedBy` or `minus`, return a new instance.

The example program in Listing 6.1 uses the `Instant` and `Duration` classes for timing two algorithms.

Note: The approach of the example program is too naïve in practice, since it does not deal with issues such as the "warming up" of the just-in-time compiler in the JVM. If you need to compare algorithms, you should use a dedicated benchmarking tool such as the Java Microbenchmark Harness (JMH). The article at https://https://www.oracle.com/technical-

resources/articles/java/architect-benchmarking.html gives useful advice.

Listing 1.1 timeline/Timeline.java

```
1  package timeline;
2
3  /**
4   * @version 1.02 2023-08-27
5   * @author Cay Horstmann
6   */
7
8  import java.time.*;
9  import java.util.*;
10 import java.util.random.*;
11 import java.util.stream.*;
12
13 public class Timeline
14 {
15    private static RandomGenerator generator = R
16
17    public static void main(String[] args)
18    {
19       Instant start = Instant.now();
20       runAlgorithm();
21       Instant end = Instant.now();
22       Duration timeElapsed = Duration.between(s
```

```
23          long millis = timeElapsed.toMillis();
24          System.out.printf("%d milliseconds\n", mi
25
26          Instant start2 = Instant.now();
27          runAlgorithm2();
28          Instant end2 = Instant.now();
29          Duration timeElapsed2 = Duration.between(
30          System.out.printf("%d milliseconds\n", ti
31          boolean overTenTimesFaster = timeElapsed
32             .minus(timeElapsed2).isNegative();
33          System.out.printf("The first algorithm is
34             overTenTimesFaster ? "" : "not ");
35       }
36
37       public static void runAlgorithm()
38       {
39          int size = 10;
40          ArrayList<Integer> list = generator.ints(
41             .boxed().collect(Collectors.toCollecti
42          Collections.sort(list);
43          System.out.println(list);
44       }
45
46       public static void runAlgorithm2()
47       {
48          int size = 10;
49          List<Integer> list = generator.ints().map
50             .boxed().collect(Collectors.toCollecti
```

```
51          while (!IntStream.range(1, list.size())
52                .allMatch(i -> list.get(i - 1).comp
53             Collections.shuffle(list);
54          System.out.println(list);
55       }
56    }
```

`java.time.Instant` 8

- `static Instant now()`
  gets the current instant from the best available system clock.
- `Instant plus(TemporalAmount amountToAdd)`
- `Instant minus(TemporalAmount amountToSubtract)`
  yield an instant that is the given amount away from this `Instant`. The classes `Duration` and `Period` (see Section 6.2) implement the `TemporalAmount` interface.
- `Instant (plus|minus)(Nanos|Millis|Seconds)(long number)`
  yields an `Instant` that is the given number of nanoseconds, milliseconds, or seconds away from this `Instant`.

`java.time.Duration` 8

- `static Duration`
  `of(Nanos|Millis|Seconds|Minutes|Hours|Days)(long`

`number)`

yields a duration of the given number of time units.

- `static Duration between(Temporal startInclusive, Temporal endExclusive)`

  yields a duration between the given points in time. The `Temporal` interface is implemented by the `Instant` class as well as `LocalDate` / `LocalDateTime` / `LocalTime` (see Section 6.4) and `ZonedDateTime` (see Section 6.5).
- `long toNanos()`
- `long toMillis()`
- `long toSeconds()` 9
- `long toMinutes()`
- `long toHours()`
- `long toDays()`

  get the number of the time units in the method name for this `Duration`.
- `int to(Nanos|Millis|Seconds|Minutes|Hours)Part()` 9
- `long toDaysPart()` 9

  yield the part of the given time unit in this `Duration`. For example, in a duration of 100 seconds, the minutes part is `1` and the seconds part is `40`.

- `Duration plus(TemporalAmount amountToAdd)`
- `Duration minus(TemporalAmount amountToSubtract)`
  yield a duration that is the given amount away from this `Duration`. The classes `Duration` and `Period` (see Section 6.2) implement the `TemporalAmount` interface.
- `Duration multipliedBy(long multiplicand)`
- `Duration dividedBy(long divisor)`
- `Duration negated()`
  yield a duration that is obtained by multiplying or dividing this `Duration` by the given amount, or by –1.
- `boolean isZero()`
- `boolean isNegative()`
  return `true` if this `Duration` is zero or negative.
- `Duration` (`plus` | `minus`)
  (`Nanos` | `Millis` | `Seconds` | `Minutes` | `Hours` | `Days`) (`long number`)
  yields a `Duration` obtained by adding or subtracting the given number of time units.

1.2. Local Dates

Now let us turn from absolute time to human time. There are two kinds of human time in the Java API, *local date/time* and *zoned time*. Local date/time has a date and/or time of day, but no associated time zone information. An example of a local date is June

14, 1903 (the day on which Alonzo Church, inventor of the lambda calculus, was born). Since that date has neither a time of day nor time zone information, it does not correspond to a precise instant of time. In contrast, July 16, 1969, 09:32:00 EDT (the launch of Apollo 11) is a zoned date/time, representing a precise instant on the time line.

There are many calculations where time zones are not required, and in some cases they can even be a hindrance. Suppose you schedule a meeting every week at 10:00. If you add 7 days (that is, 7 × 24 × 60 × 60 seconds) to the last zoned time, and you happen to cross the daylight savings time boundary, the meeting will be an hour too early or too late!

For that reason, the API designers recommend that you do not use zoned time unless you really want to represent absolute time instances. Birthdays, holidays, schedule times, and so on are usually best represented as local dates or times.

A `LocalDate` is a date with a year, month, and day of the month. To construct one, you can use the `now` or `of` static methods:

```
LocalDate today = LocalDate.now(); // Today's date
LocalDate alonzosBirthday = LocalDate.of(1903, 6, 14)
alonzosBirthday = LocalDate.of(1903, Month.JUNE, 14);
```

```
    // Uses the Month enumeration
```

Unlike the irregular conventions in UNIX and `java.util.Date`, where months are zero-based and years are counted from 1900, here you supply the usual numbers for the month of year. Alternatively, you can use the `Month` enumeration.

The API notes at the end of this section show the most useful methods for working with `LocalDate` objects.

For example, *Programmer's Day* is the 256th day of the year. Here is how you can easily compute it:

```
LocalDate programmersDay = LocalDate.of(2014, 1, 1).p
   // September 13, but in a leap year it would be Se
```

Recall that the difference between two time instants is a `Duration`. The equivalent for local dates is a `Period`, which expresses a number of elapsed years, months, or days. You can call `birthday.plus(Period.ofYears(1))` to get the birthday next year. Of course, you can also just call `birthday.plusYears(1)`. But `birthday.plus(Period.ofDays(365))` won't produce the correct result in a leap year.

The `until` method yields the difference between two local dates. For example,

```
independenceDay.until(christmas)
```

yields a period of 5 months and 21 days. That is actually not terribly useful because the number of days per month varies. To find the number of days, use

```
independenceDay.until(christmas, ChronoUnit.DAYS) //
```

Caution: Some methods in the `LocalDate` API could potentially create nonexistent dates. For example, adding one month to January 31 should not yield February 31. Instead of throwing an exception, these methods return the last valid day of the month. For example,

```
LocalDate.of(2016, 1, 31).plusMonths(1)
```

and

```
LocalDate.of(2016, 3, 31).minusMonths(1)
```

yield February 29, 2016.

The `getDayOfWeek` yields the weekday, as a value of the `DayOfWeek` enumeration. `DayOfWeek.MONDAY` has the numerical value `1`, and `DayOfWeek.SUNDAY` has the value `7`. For example,

```
LocalDate.of(1900, 1, 1).getDayOfWeek().getValue()
```

yields `1`. The `DayOfWeek` enumeration has convenience methods `plus` and `minus` to compute weekdays modulo `7`. For example, `DayOfWeek.SATURDAY.plus(3)` yields `DayOfWeek.TUESDAY`.

Note: The weekend days actually come at the end of the week. This is different from `java.util.Calendar` where Sunday has value `1` and Saturday value `7`.

The useful `datesUntil` methods yield streams of `LocalDate` objects:

```
LocalDate start = LocalDate.of(2000, 1, 1);
LocalDate endExclusive = LocalDate.now();
Stream<LocalDate> allDays = start.datesUntil(endExclu
Stream<LocalDate> firstDaysInMonth = start.datesUntil
```

In addition to `LocalDate`, there are also classes `MonthDay`, `YearMonth`, and `Year` to describe partial dates. For example,

December 25 (with the year unspecified) can be represented as a `MonthDay`.

The example program in Listing 6.2 shows how to work with the `LocalDate` class.

Listing 1.2 localdates/LocalDates.java

```
1  package localdates;
2
3  /**
4   * @version 1.01 2021-09-06
5   * @author Cay Horstmann
6   */
7  import java.time.*;
8  import java.time.temporal.*;
9  import java.util.stream.*;
10
11 public class LocalDates
12 {
13    public static void main(String[] args)
14    {
15       LocalDate today = LocalDate.now(); // Toc
16       System.out.println("today: " + today);
17
18       LocalDate alonzosBirthday = LocalDate.of(
19       alonzosBirthday = LocalDate.of(1903, Mont
```

```
20        // Uses the Month enumeration
21        System.out.println("alonzosBirthday: " +
22
23        LocalDate programmersDay = LocalDate.of(2
24        // September 13, but in a leap year it wo
25        System.out.println("programmersDay: " + p
26
27        LocalDate independenceDay = LocalDate.of(
28        LocalDate christmas = LocalDate.of(2018,
29
30        System.out.println("Until christmas: " +
31        System.out.println("Until christmas: "
32           + independenceDay.until(christmas, Chr
33
34        System.out.println(LocalDate.of(2016, 1,
35        System.out.println(LocalDate.of(2016, 3,
36
37        DayOfWeek startOfLastMillennium = LocalDa
38        System.out.println("startOfLastMillenniu
39        System.out.println(startOfLastMillennium
40        System.out.println(DayOfWeek.SATURDAY.plu
41
42        LocalDate start = LocalDate.of(2000, 1, 1
43        LocalDate endExclusive = LocalDate.now();
44        Stream<LocalDate> firstDaysInMonth = star
45        System.out.println("firstDaysInMonth: "
```

```
46            + firstDaysInMonth.toList());
47    }
48 }
```

`java.time.LocalDate` 8

- `static LocalDate now()`
  gets the current `LocalDate`.
- `static LocalDate of(int year, int month, int dayOfMonth)`
- `static LocalDate of(int year, Month month, int dayOfMonth)`
  yield a local date with the given year, month (as integer between 1 and 12 or a value of the `Month` enumeration), and day of the month (between 1 and 31).
- `LocalDate` (`plus` | `minus`)(`Days` | `Weeks` | `Months` | `Years`) `(long number)`
  yields a `LocalDate` obtained by adding or subtracting the given number of time units.
- `LocalDate plus(TemporalAmount amountToAdd)`
- `LocalDate minus(TemporalAmount amountToSubtract)`
  yield a `LocalDate` that is the given amount away from this `LocalDate`. The classes `Duration` and `Period` implement the `TemporalAmount` interface.

- `LocalDate withDayOfMonth(int dayOfMonth)`
- `LocalDate withDayOfYear(int dayOfYear)`
- `LocalDate withMonth(int month)`
- `LocalDate withYear(int year)`
  return a new `LocalDate` with the day of month, day of year, month, or year changed to the given value.
- `int getDayOfMonth()`
  gets the day of the month (between 1 and 31).
- `int getDayOfYear()`
  gets the day of the year (between 1 and 366).
- `DayOfWeek getDayOfWeek()`
  gets the day of the week, returning a value of the `DayOfWeek` enumeration.
- `Month getMonth()`
- `int getMonthValue()`
  get the month as a value of the `Month` enumeration, or as a number between 1 and 12.
- `int getYear()`
  gets the year, between –999,999,999 and 999,999,999.
- `Period until(ChronoLocalDate endDateExclusive)`
  gets the period until the given end date. The `ChronoLocalDate` interface is implemented by `LocalDate` and date classes for non-Gregorian calendars.

- `boolean isBefore(ChronoLocalDate other)`
- `boolean isAfter(ChronoLocalDate other)`
  return `true` if this date is before or after the given date.
- `boolean isLeapYear()`
  returns `true` if the year is a leap year—that is, if it is divisible by 4 but not by 100, or divisible by 400. The algorithm is applied for all past years, even though that is historically inaccurate. (Leap years were invented in the year –46, and the rules involving divisibility by 100 and 400 were introduced in the Gregorian calendar reform of 1582. The reform took over 300 years to become universal.)
- `Stream<LocalDate> datesUntil(LocalDate endExclusive)` `9`
- `Stream<LocalDate> datesUntil(LocalDate endExclusive, Period step)` `9`
  yield a stream of dates from this `LocalDate` until the end, with step size 1 or the given period.

`java.time.Period` `8`

- `static Period of(int years, int months, int days)`
- `Period of(Days|Weeks|Months|Years)(int number)`
  yield a `Period` with the given number of time units.
- `int get(Days|Months|Years)()`
  gets the days, months, or years of this `Period`.

- `Period (plus|minus)(Days|Months|Years)(long number)`
  yields a `Period` obtained by adding or subtracting the given number of time units.
- `Period plus(TemporalAmount amountToAdd)`
- `Period minus(TemporalAmount amountToSubtract)`
  yield an instant that is the given amount away from this `Instant`. The classes `Duration` and `Period` implement the `TemporalAmount` interface.
- `Period with(Days|Months|Years)(int number)`
  returns a new `Period` with the days, months, or years changed to the given number.

1.3. Date Adjusters

For scheduling applications, you often need to compute dates such as "the first Tuesday of every month." The `TemporalAdjusters` class provides a number of static methods for common adjustments. You pass the result of an adjustment method to the `with` method. For example, the first Tuesday of a month can be computed like this:

```
LocalDate firstTuesday = LocalDate.of(year, month, 1)
   TemporalAdjusters.nextOrSame(DayOfWeek.TUESDAY));
```

As always, the `with` method returns a new `LocalDate` object without modifying the original. The API notes at the end of this section show the available adjusters.

You can also make your own adjuster by implementing the `TemporalAdjuster` interface. Here is an adjuster for computing the next weekday:

```
TemporalAdjuster NEXT_WORKDAY = w ->
   {
      var result = (LocalDate) w;
      do
      {
         result = result.plusDays(1);
      }
      while (result.getDayOfWeek().getValue() >= 6);
      return result;
   };

LocalDate backToWork = today.with(NEXT_WORKDAY);
```

Note that the parameter of the lambda expression has type `Temporal`, and it must be cast to `LocalDate`. You can avoid this cast with the `ofDateAdjuster` method that expects a lambda of type `UnaryOperator<LocalDate>`.

```
TemporalAdjuster NEXT_WORKDAY = TemporalAdjusters.ofD
   {
      LocalDate result = w; // No cast
      do
      {
         result = result.plusDays(1);
      }
      while (result.getDayOfWeek().getValue() >= 6);
      return result;
   });
```

`java.time.LocalDate` 9

- `LocalDate with(TemporalAdjuster adjuster)`
  returns the result of adjusting this date by the given adjuster.

`java.time.temporal.TemporalAdjusters` 9

- `static TemporalAdjuster next(DayOfWeek dayOfWeek)`
- `static TemporalAdjuster nextOrSame(DayOfWeek dayOfWeek)`
- `static TemporalAdjuster previous(DayOfWeek dayOfWeek)`
- `static TemporalAdjuster previousOrSame(DayOfWeek`

`dayOfWeek)`
return an adjuster that adjusts a date to the given day of the week.

- `static TemporalAdjuster dayOfWeekInMonth(int n, DayOfWeek dayOfWeek)`
- `static TemporalAdjuster lastInMonth(DayOfWeek dayOfWeek)`
  return an adjuster that adjusts a date to the `n` th or last given weekday of the month.
- `static TemporalAdjuster firstDayOfMonth()`
- `static TemporalAdjuster firstDayOfNextMonth()`
- `static TemporalAdjuster firstDayOfYear()`
- `static TemporalAdjuster firstDayOfNextYear()`
- `static TemporalAdjuster lastDayOfMonth()`
- `static TemporalAdjuster lastDayOfYear()`
  return an adjuster that adjusts a date to the given day of the month or year.

1.4. Local Time

A `LocalTime` represents a time of day, such as 15:30:00. You can create an instance with the `now` or `of` methods:

```
  LocalTime rightNow = LocalTime.now();
  LocalTime bedtime = LocalTime.of(22, 30); // or Local
```

The API notes show common operations with local times. The `plus` and `minus` operations wrap around a 24-hour day. For example,

```
LocalTime wakeup = bedtime.plusHours(8); // wakeup is
```

Note: `LocalTime` doesn't concern itself with AM/PM. That silliness is left to a formatter—see Section 6.6.

There is a `LocalDateTime` class representing a date and time. That class is suitable for storing points in time in a fixed time zone—for example, for a schedule of classes or events. However, if you need to make calculations that span the daylight savings time, or if you need to deal with users in different time zones, you should use the `ZonedDateTime` class that we discuss next.

`java.time.LocalTime` `8`

- `static LocalTime now()`
  gets the current `LocalTime`.
- `static LocalTime of(int hour, int minute)`
- `static LocalTime of(int hour, int minute, int second)`
- `static LocalTime of(int hour, int minute, int`

`second, int nanoOfSecond)`
yield a local time with the given hour (between 0 and 23), minute, second (between 0 and 59), and nanosecond (between 0 and 999,999,999).

- `LocalTime (plus | minus)(Hours | Minutes | Seconds | Nanos)(long number)`
  yields a `LocalTime` obtained by adding or subtracting the given number of time units.
- `LocalTime plus(TemporalAmount amountToAdd)`
- `LocalTime minus(TemporalAmount amountToSubtract)`
  yield a `LocalTime` that is the given amount away from this `LocalTime`.
- `LocalTime with(Hour | Minute | Second | Nano)(int value)`
  returns a new `LocalTime` with the hour, minute, second, or nanosecond changed to the given value.
- `int getHour()`
  gets the hour (between 0 and 23).
- `int getMinute()`
- `int getSecond()`
  get the minute or second (between 0 and 59).
- `int getNano()`
  gets the nanoseconds (between 0 and 999,999,999).

- `int toSecondOfDay()`
- `long toNanoOfDay()`
  yield the seconds or nanoseconds since midnight.
- `boolean isBefore(LocalTime other)`
- `boolean isAfter(LocalTime other)`
  return `true` if this date is before or after the given date.

1.5. Zoned Time

Time zones, perhaps because they are an entirely human creation, are even messier than the complications caused by the earth's irregular rotation. In a rational world, we'd all follow the clock in Greenwich, and some of us would eat our lunch at 02:00, others at 22:00. Our stomachs would figure it out. This is actually done in China, which spans four conventional time zones. Elsewhere, we have time zones with irregular and shifting boundaries and, to make matters worse, the daylight savings time.

As capricious as the time zones may appear to the enlightened, they are a fact of life. When you implement a calendar application, it needs to work for people who fly from one country to another. When you have a conference call at 10:00 in New York, but happen to be in Berlin, you expect to be alerted at the correct local time.

The Internet Assigned Numbers Authority (IANA) keeps a database of all known time zones around the world

(https://www.iana.org/time-zones), which is updated several times per year. The bulk of the updates deals with the changing rules for daylight savings time. Java uses the IANA database.

Each time zone has an ID, such as `America/New_York` or `Europe/Berlin`. To find out all available time zones, call `ZoneId.getAvailableZoneIds`. At the time of this writing, there are almost 600 IDs.

Given a time zone ID, the static method `ZoneId.of(id)` yields a `ZoneId` object. You can use that object to turn a `LocalDateTime` object into a `ZonedDateTime` object by calling `local.atZone(zoneId)`, or you can construct a `ZonedDateTime` by calling the static method `ZonedDateTime.of(year, month, day, hour, minute, second, nano, zoneId)`. For example,

```
ZonedDateTime apollo11launch  = ZonedDateTime.of(1969
   ZoneId.of("America/New_York"));
   // 1969-07-16T09:32-04:00[America/New_York]
```

This is a specific instant in time. Call `apollo11launch.toInstant` to get the `Instant`. Conversely, if you have an instant in time, call `instant.atZone(ZoneId.of("UTC"))` to get the `ZonedDateTime` at the Greenwich Royal Observatory, or use another `ZoneId` to get it elsewhere on the planet.

Note: UTC stands for "Coordinated Universal Time," and the acronym is a compromise between the aforementioned English and the French "Temps Universel Coordiné," having the distinction of being incorrect in either language. UTC is the time at the Greenwich Royal Observatory, without daylight savings time.

Many of the methods of `ZonedDateTime` are the same as those of `LocalDateTime` (see the API notes at the end of this section). Most are straightforward, but daylight savings time introduces some complications.

When daylight savings time starts, clocks advance by an hour. What happens when you construct a time that falls into the skipped hour? For example, in 2013, Central Europe switched to daylight savings time on March 31 at 2:00. If you try to construct nonexistent time March 31 2:30, you actually get 3:30.

```
ZonedDateTime skipped = ZonedDateTime.of(
   LocalDate.of(2013, 3, 31),
   LocalTime.of(2, 30),
   ZoneId.of("Europe/Berlin"));
   // Constructs March 31 3:30
```

Conversely, when daylight time ends, clocks are set back by an hour, and there are two instants with the same local time! When you construct a time within that span, you get the earlier of the two.

```
ZonedDateTime ambiguous = ZonedDateTime.of(
   LocalDate.of(2013, 10, 27), // End of daylight sav
   LocalTime.of(2, 30),
   ZoneId.of("Europe/Berlin"));
   // 2013-10-27T02:30+02:00[Europe/Berlin]
ZonedDateTime anHourLater = ambiguous.plusHours(1);
   // 2013-10-27T02:30+01:00[Europe/Berlin]
```

An hour later, the time has the same hours and minutes, but the zone offset has changed.

You also need to pay attention when adjusting a date across daylight savings time boundaries. For example, if you set a meeting for next week, don’t add a duration of seven days:

```
ZonedDateTime nextMeeting = meeting.plus(Duration.ofD
   // Caution! Won't work with daylight savings time
```

Instead, use the `Period` class.

```
ZonedDateTime nextMeeting = meeting.plus(Period.ofDay
```

Caution: There is also an `OffsetDateTime` class that represents times with an offset from UTC, but without time zone rules. That class is intended for specialized applications that specifically require the absence of those rules, such as certain network protocols. For human time, use `ZonedDateTime`.

The example program in Listing 6.3 demonstrates the `ZonedDateTime` class.

Listing 1.3 zonedTimes/ZonedTimes.java

```
1  package zonedTimes;
2
3  /**
4   * @version 1.0 2016-05-10
5   * @author Cay Horstmann
6   */
7
8  import java.time.*;
9
10 public class ZonedTimes
11 {
12    public static void main(String[] args)
```

```
13    {
14       ZonedDateTime apollo11launch = ZonedDateT
15          ZoneId.of("America/New_York")); // 196
16       System.out.println("apollo11launch: " + a
17
18       Instant instant = apollo11launch.toInstan
19       System.out.println("instant: " + instant)
20
21       ZonedDateTime zonedDateTime = instant.atZ
22       System.out.println("zonedDateTime: " + zo
23
24       ZonedDateTime skipped = ZonedDateTime.of(
25          LocalTime.of(2, 30), ZoneId.of("Europe
26       System.out.println("skipped: " + skipped)
27
28       ZonedDateTime ambiguous = ZonedDateTime.o
29          LocalDate.of(2013, 10, 27), // End of
30          LocalTime.of(2, 30), ZoneId.of("Europe
31          // 2013-10-27T02:30+02:00[Europe/Berli
32       ZonedDateTime anHourLater = ambiguous.plu
33          // 2013-10-27T02:30+01:00[Europe/Berli
34       System.out.println("ambiguous: " + ambigu
35       System.out.println("anHourLater: " + anHo
36
37       ZonedDateTime meeting = ZonedDateTime.of(
38          LocalTime.of(14, 30), ZoneId.of("Ameri
39       System.out.println("meeting: " + meeting)
40       ZonedDateTime nextMeeting = meeting.plus(
```

```
41          // Caution! Won't work with daylight s
42       System.out.println("nextMeeting: " + next
43       nextMeeting = meeting.plus(Period.ofDays(
44       System.out.println("nextMeeting: " + next
45    }
46 }
```

`java.time.ZonedDateTime` **8**

- `static ZonedDateTime now()`
  gets the current `ZonedDateTime`.
- `static ZonedDateTime of(int year, int month, int dayOfMonth, int hour, int minute, int second, int nanoOfSecond, ZoneId zone)`
- `static ZonedDateTime of(LocalDate date, LocalTime time, ZoneId zone)`
- `static ZonedDateTime of(LocalDateTime localDateTime, ZoneId zone)`
- `static ZonedDateTime ofInstant(Instant instant, ZoneId zone)`
  yield a `ZonedDateTime` with the given parameters and time zone.
- `ZonedDateTime` (`plus` | `minus`)
  (`Days` | `Weeks` | `Months` | `Years` | `Hours` | `Minutes` | `Seconds` | `N`

`anos` | `(long number)`
yields a `ZonedDateTime` obtained by adding or subtracting the given number of time units.

- `ZonedDateTime plus(TemporalAmount amountToAdd)`
- `ZonedDateTime minus(TemporalAmount amountToSubtract)`
  yield a `ZonedDateTime` that is the given amount away from this `ZonedDateTime`.
- `ZonedDateTime`
  `with` (`DayOfMonth` | `DayOfYear` | `Month` | `Year` | `Hour` | `Minute` | `Second` | `Nano`) `(int value)`
  returns a new `ZonedDateTime` with the given temporal unit replaced by the given value.
- `ZonedDateTime withZoneSameInstant(ZoneId zone)`
- `ZonedDateTime withZoneSameLocal(ZoneId zone)`
  return a new `ZonedDateTime` in the given time zone, either representing the same instant or the same local time.
- `int getDayOfMonth()`
  gets the day of the month (between 1 and 31).
- `int getDayOfYear()`
  gets the day of the year (between 1 and 366).
- `DayOfWeek getDayOfWeek()`
  gets the day of the week, returning a value of the `DayOfWeek` enumeration.

- `Month getMonth()`
- `int getMonthValue()`
  get the month as a value of the `Month` enumeration, or as a number between 1 and 12.
- `int getYear()`
  gets the year, between –999,999,999 and 999,999,999.
- `int getHour()`
  gets the hour (between 0 and 23).
- `int getMinute()`
- `int getSecond()`
  get the minute or second (between 0 and 59).
- `int getNano()`
  gets the nanoseconds (between 0 and 999,999,999).
- `public ZoneOffset getOffset()`
  gets the offset from UTC. Offsets can vary from –12:00 to +14:00. Some time zones have fractional offsets. Offsets change with daylight savings time.
- `LocalDate toLocalDate()`
- `LocalTime toLocalTime()`
- `LocalDateTime toLocalDateTime()`
- `Instant toInstant()`
  yield the local date, time, or date/time, or the corresponding instant.

- `boolean isBefore(ChronoZonedDateTime other)`
- `boolean isAfter(ChronoZonedDateTime other)`
  return `true` if this zoned date/time is before or after the given zoned date/time.

1.6. Formatting and Parsing

The `DateTimeFormatter` class provides three kinds of formatters to print a date/time value:

- Predefined standard formatters (see Table 6.1)
- Locale-specific formatters
- Formatters with custom patterns

To use one of the standard formatters, simply call its `format` method:

```
String formatted = DateTimeFormatter.ISO_OFFSET_DATE_
   // 1969-07-16T09:32:00-04:00"
```

Table 1.1: Predefined Formatters

Formatter	Description	Examp
`BASIC_ISO_DATE`	Year, month, day, zone offset without separators	`196907`

Formatter	Description	Examp
`ISO_LOCAL_DATE`, `ISO_LOCAL_TIME`, `ISO_LOCAL_DATE_TIME`	Separators `-`, `:`, `T`	`1969-0` `1969-0`
`ISO_OFFSET_DATE`, `ISO_OFFSET_TIME`, `ISO_OFFSET_DATE_TIME`	Like `ISO_LOCAL_`*`XXX`*, but with zone offset	`1969-0` `09:32:` `07-16T`
`ISO_ZONED_DATE_TIME`	With zone offset and zone ID	`1969-0` `04:00[`
`ISO_INSTANT`	In UTC, denoted by the `Z` zone ID	`1969-0`
`ISO_DATE`, `ISO_TIME`, `ISO_DATE_TIME`	Like `ISO_OFFSET_DATE`, `ISO_OFFSET_TIME`, and `ISO_ZONED_DATE_TIME`, but the zone information is optional	`1969-0` `09:32:` `07-16T` `04:00[`
`ISO_ORDINAL_DATE`	The year and day of	`1969-1`

Formatter	Description	Examp
	year, for `LocalDate`	
`ISO_WEEK_DATE`	The year, week, and day of week, for `LocalDate`	`1969-W`
`RFC_1123_DATE_TIME`	The standard for email timestamps, codified in RFC 822 and updated to four digits for the year in RFC 1123	`Wed, 1 09:32:`

The standard formatters are mostly intended for machine-readable timestamps. To present dates and times to human readers, use a locale-specific formatter. There are four styles, `SHORT`, `MEDIUM`, `LONG`, and `FULL`, for both date and time—see Table 6.2.

The static methods `ofLocalizedDate`, `ofLocalizedTime`, and `ofLocalizedDateTime` create such a formatter. For example:

```
DateTimeFormatter formatter = DateTimeFormatter.ofLoc
String formatted = formatter.format(apollo11launch);
```

```
    // July 16, 1969 9:32:00 AM EDT
```

These methods use the default locale. To change to a different locale, simply use the `withLocale` method.

```
formatted = formatter.withLocale(Locale.FRENCH).forma
   // 16 juillet 1969 09:32:00 EDT
```

The `DayOfWeek` and `Month` enumerations have methods `getDisplayName` for giving the names of weekdays and months in different locales and formats.

```
for (DayOfWeek w : DayOfWeek.values())
   System.out.print(w.getDisplayName(TextStyle.SHORT,
   // Prints Mon Tue Wed Thu Fri Sat Sun
```

See Chapter 7 for more information about locales.

Table 1.2: Locale-Specific Formatting Styles

Style	Date	Time
`SHORT`	`7/16/69`	`9:32 AM`

Style	Date	Time
`MEDIUM`	`Jul 16, 1969`	`9:32:00 AM`
`LONG`	`July 16, 1969`	`9:32:00 AM EDT`
`FULL`	`Wednesday, July 16, 1969`	`9:32:00 AM EDT`

Note: The `java.time.format.DateTimeFormatter` class is intended as a replacement for `java.util.DateFormat`. If you need an instance of the latter for backward compatibility, call `formatter.toFormat()`.

Finally, you can roll your own date format by specifying a pattern. For example,

```
formatter = DateTimeFormatter.ofPattern("E yyyy-MM-dd
```

formats a date in the form `Wed 1969-07-16 09:32`. Each letter denotes a different time field, and the number of times the letter is repeated selects a particular format, according to rules that are arcane and seem to have organically grown over time. Table 6.3 shows the most useful pattern elements.

Table 1.3: Commonly Used Formatting Symbols for Date/Time Formats

`ChronoField` **or Purpose**	**Examples**
`ERA`	`G: AD`, `GGGG: Anno Domini`, `GGGGG: A`
`YEAR_OF_ERA`	`yy: 69`, `yyyy: 1969`
`MONTH_OF_YEAR`	`M: 7`, `MM: 07`, `MMM: Jul`, `MMMM: July`, `MMMMM: J`
`DAY_OF_MONTH`	`d: 6`, `dd: 06`
`DAY_OF_WEEK`	`e: 3`, `E: Wed`, `EEEE: Wednesday`, `EEEEE: W`
`HOUR_OF_DAY`	`H: 9`, `HH: 09`

`ChronoField` or Purpose	Examples
`CLOCK_HOUR_OF_AM_PM`	`h` : `9` , `hh` : `09`
`AMPM_OF_DAY`	`a` : `AM`
Period of day (since Java 16)	`B` : `in the evening` , `at night` , `midnight`
`MINUTE_OF_HOUR`	`mm` : `02`
`SECOND_OF_MINUTE`	`ss` : `00`
`NANO_OF_SECOND`	`nnnnnn` : `000000`
Time zone ID	`VV` : `America/New_York`
Time zone name	`z` : `EDT` , `zzzz` : `Eastern Daylight Time` , `v` : `ET` , `vvvv` : `Eastern Time`
Zone offset	`x` : `-04` , `xx` : `-0400` , `xxx` : `-04:00` , `XXX` : same, but use `Z`

`ChronoField` or Purpose	Examples
	for zero

Caution: Pay attention to the capitalization of these letters: `M` is [illegible]s, `m` is minutes. You probably want the day of the month `d`, and not the day of the year `D`, and seconds `s` rather than fractions of a second `S`. Most perilously, `y` indicates a normal year but `Y` is a "week-numbering year," which is subtly different if January 1 falls on a Friday, Saturday, or Sunday.

The `ofLocalizedPattern` method yields a formatter that assembles parts of patterns in a locale-specific way, with the appropriate separators and ordering of the parts. For example:

```
DateTimeFormatter formatter = DateTimeFormatter.ofLoc
formatter.withLocale(Locale.US).format(apollo11launch
formatter.withLocale(Locale.GERMANY).format(apollo11l
formatter.withLocale(Locale.CHINA).format(apollo11lau
```

You only specify the symbols for the parts, in descending size. Do not include any separators. For the hours, use `j` for a localized 12- or 24-hour format:

```
formatter = DateTimeFormatter.ofLocalizedPattern("jm"
formatter.withLocale(Locale.US).format(LocalTime.of(2
formatter.withLocale(Locale.GERMANY).format(LocalTime
```

To parse a date/time value from a string, use one of the static `parse` methods. For example,

```
LocalDate churchsBirthday = LocalDate.parse("1903-06-
ZonedDateTime apollo11launch =
   ZonedDateTime.parse("1969-07-16 03:32:00-0400",
      DateTimeFormatter.ofPattern("yyyy-MM-dd HH:mm:s
```

The first call uses the standard `ISO_LOCAL_DATE` formatter, the second one a custom formatter.

The program in Listing 6.4 shows how to format and parse dates and times.

Listing 1.4 formatting/Formatting.java

```
1  package formatting;
2
3  /**
4   * @version 1.0 2016-05-10
5   * @author Cay Horstmann
```

```
 */

import java.time.*;
import java.time.format.*;
import java.util.*;

public class Formatting
{
   public static void main(String[] args)
   {
      ZonedDateTime apollo11launch = ZonedDateT
         ZoneId.of("America/New_York"));

      String formatted = DateTimeFormatter.ISO_
      // 1969-07-16T09:32:00-04:00
      System.out.println(formatted);

      DateTimeFormatter formatter = DateTimeFor
      formatted = formatter.format(apollo11laun
      // July 16, 1969 9:32:00 AM EDT
      System.out.println(formatted);
      formatted = formatter.withLocale(Locale.F
      // 16 juillet 1969 09:32:00 EDT
      System.out.println(formatted);

      formatter = DateTimeFormatter.ofPattern("
      formatted = formatter.format(apollo11laun
      System.out.println(formatted);
```

```
34
35          LocalDate churchsBirthday = LocalDate.par
36          System.out.println("churchsBirthday: " +
37          apollo11launch = ZonedDateTime.parse("196
38             DateTimeFormatter.ofPattern("yyyy-MM-d
39          System.out.println("apollo11launch: " + a
40
41          for (DayOfWeek w : DayOfWeek.values())
42             System.out.print(w.getDisplayName(Text
43       }
44    }
```

java.time.format.DateTimeFormatter 8

- `String format(TemporalAccessor temporal)` formats the given value. The classes `Instant`, `LocalDate`, `LocalTime`, `LocalDateTime`, and `ZonedDateTime`, as well as many others, implement the `TemporalAccessor` interface.
- `static DateTimeFormatter ofLocalizedDate(FormatStyle dateStyle)`
- `static DateTimeFormatter ofLocalizedTime(FormatStyle timeStyle)`
- `static DateTimeFormatter ofLocalizedDateTime(FormatStyle dateTimeStyle)`
- `static DateTimeFormatter ofLocalizedDateTime(FormatStyle dateStyle,`

`FormatStyle timeStyle)`
yield a formatter for the given styles. The `FormatStyle` enumeration has values `SHORT`, `MEDIUM`, `LONG`, and `FULL`.

- `static DateTimeFormatter ofLocalizedPattern(String requestedTemplate)` 19
  creates a formatter that can be adapted to a locale, using the parts that are specified in the template.
- `DateTimeFormatter withLocale(Locale locale)`
  yields a formatter equal to this formatter, using the given locale.
- `static DateTimeFormatter ofPattern(String pattern)`
- `static DateTimeFormatter ofPattern(String pattern, Locale locale)`
  yield a formatter using the given pattern and locale. See Table 6.3 for the pattern syntax.

`java.time.LocalDate` 8

- `static LocalDate parse(CharSequence text)`
- `static LocalDate parse(CharSequence text, DateTimeFormatter formatter)`
  yield a `LocalDate` using the default formatter, or the given formatter.

`java.time.ZonedDateTime` 8

- `static ZonedDateTime parse(CharSequence text)`
- `static ZonedDateTime parse(CharSequence text, DateTimeFormatter formatter)`
  yield a `ZonedDateTime` using the default formatter, or the given formatter.

1.7. Interoperating with Legacy Code

As a new creation, the Java Date and Time API will have to interoperate with existing classes—in particular, the ubiquitous `java.util.Date`, `java.util.GregorianCalendar`, and `java.sql.Date` / `Time` / `Timestamp`.

The `Instant` class is a close analog to `java.util.Date`. The `toInstant` method of the legacy `Date` class yields an `Instant`, and the static `from` method converts in the other direction.

Similarly, `ZonedDateTime` is a close analog to `java.util.GregorianCalendar`, and that legacy class also has conversion methods. The `toZonedDateTime` method converts a `GregorianCalendar` to a `ZonedDateTime`, and the static `from` method does the opposite conversion.

Another set of conversions is available for the date and time classes in the `java.sql` package. You can also pass a `DateTimeFormatter` to legacy code that uses `java.text.Format`. Table 6.4 summarizes these conversions.

Table 1.4: Conversions between `java.time` Classes and Legacy Classes

Classes	To Legacy Class
`Instant` ↔ `java.util.Date`	`Date.from(instant)`
`ZonedDateTime` ↔ `java.util.GregorianCalendar`	`GregorianCalendar.from(zonedDateTime)`
`Instant` ↔ `java.sql.Timestamp`	`Timestamp.from(ins`
`LocalDateTime` ↔ `java.sql.Timestamp`	`Timestamp.valueOf(localDateTime)`
`LocalDate` ↔ `java.sql.Date`	`Date.valueOf(local`

Classes	To Legacy Class
`LocalTime` ↔ `java.sql.Time`	`Time.valueOf(local`
`DateTimeFormatter` → `java.text.DateFormat`	`formatter.toFormat`
`java.util.TimeZone` ↔ `ZoneId`	`TimeZone.getTimeZo`
`java.nio.file.attribute.FileTime` ↔ `Instant`	`FileTime.from(inst`

You now know how to use the date and time library to work with date and time values around the world. The next chapter takes the discussion of programming for an international audience further. You will see how to format program messages, numbers, and currencies in the way that makes sense for your customers, wherever they may be.

1. Internationalization

There’s a big world out there; we hope that lots of its inhabitants will be interested in your software. The Internet, after all, effortlessly spans the barriers between countries. On the other hand, when you pay no attention to an international audience, *you* are putting up a barrier.

The Java programming language was the first language designed from the ground up to support internationalization. From the beginning, it had the one essential feature needed for effective internationalization: It used Unicode for all strings. Unicode support makes it easy to write Java programs that manipulate strings in most of the world's languages.

Many programmers believe that all they need to do to internationalize their application is to support Unicode and to translate the messages in the user interface. However, as this chapter demonstrates, there is a lot more to internationalizing programs than just Unicode support. Dates, times, currencies, even numbers are formatted differently in different parts of the world. You need an easy way to configure menu and button names, message strings, and keyboard shortcuts for different languages.

In this chapter, you will see how to write internationalized Java programs and how to localize dates, times, numbers, text, and GUIs. I will show you the tools that Java offers for writing internationalized programs. The chapter concludes with a complete example—a retirement calculator with a user interface in English, German, and Chinese.

1.1. Locales

When you look at an application that is adapted to an international market, the most obvious difference you notice is the language. This observation is actually a bit too limiting for true internationalization, since countries can share a common language, but you might still need to do some work to make computer users of both countries happy. As Oscar Wilde famously said: "We have really everything in common with America nowadays, except, of course, language."

1.1.1. Why Locales?

When you provide international versions of a program, all program messages need to be translated to the local language. However, simply translating the user interface text is not sufficient. There are many more subtle differences—for example, numbers are formatted quite differently in English and in German. The number

123,456.78

should be displayed as

123.456,78

for a German user—that is, the roles of the decimal point and the decimal comma separator are reversed. There are similar variations in the display of dates. In the United States, dates are (somewhat irrationally) displayed as month/day/year. Germany uses the more sensible order of day/month/year, whereas in China, the usage is year/month/day. Thus, the date

3/22/61

should be presented as

22.03.1961

to a German user. Of course, if the month names are written out explicitly, the difference in languages becomes apparent. The English

March 22, 1961

should be presented as

22. März 1961

in German, or

1961 年 3 月 22 日

in Chinese.

A *locale* captures local preferences such as these. Whenever you present numbers, dates, currency values, and other items whose formatting varies by language or location, you need to use locale-aware APIs.

1.1.2. Specifying Locales

A locale is made up of up to five components:

1. A language, specified by two or three lowercase letters, such as `en` (English), `de` (German), or `zh` (Chinese). Table 7.1 shows common codes.
2. Optionally, a script, specified by four letters with an initial uppercase, such as `Latn` (Latin), `Cyrl` (Cyrillic), or `Hant` (traditional Chinese characters). This can be useful because some languages, such as Serbian, are written in Latin or Cyrillic, and some Chinese readers prefer the traditional over the simplified characters.
3. Optionally, a country or region, specified by two uppercase letters or three digits, such as `US` (United States) or `CH` (Switzerland). Table 7.2 shows common codes.

4. Optionally, a variant, specifying miscellaneous features such as dialects or spelling rules. Variants are rarely used nowadays. There used to be a "Nynorsk" variant of Norwegian, but it is now expressed with a different language code, `nn`. What used to be variants for the Japanese imperial calendar and Thai numerals are now expressed as extensions (see the next item).
5. Optionally, an extension. Extensions describe local preferences for calendars (such as the Japanese calendar), numbers (Thai instead of Western digits), and so on. The Unicode standard specifies some of these extensions. Extensions start with `u-` and a two-letter code specifying whether the extension deals with the calendar (`ca`), numbers (`nu`), and so on. For example, the extension `u-nu-thai` denotes the use of Thai numerals. Other extensions are entirely arbitrary and start with `x-`, such as `x-java`.

Rules for locales are formulated in the "Best Current Practices" memo BCP 47 of the Internet Engineering Task Force (https://www.rfc-editor.org/info/bcp47). You can find a more accessible summary at https://www.w3.org/International/articles/language-tags.

Table 1.1: Common ISO 639-1 Language Codes

Language	Code	Language	Code

Language	Code	Language	Code
Chinese	`zh`	Italian	`it`
Danish	`da`	Japanese	`ja`
Dutch	`nl`	Korean	`ko`
English	`en`	Norwegian	`no`
French	`fr`	Portuguese	`pt`
Finnish	`fi`	Spanish	`es`
German	`de`	Swedish	`sv`
Greek	`el`	Turkish	`tr`

Table 1.2: Common ISO 3166-1 Country Codes

Country	Code	Country	Code
Austria	`AT`	Japan	`JP`

Country	Code	Country	Code
Belgium	`BE`	Korea	`KR`
Canada	`CA`	The Netherlands	`NL`
China	`CN`	Norway	`NO`
Denmark	`DK`	Portugal	`PT`
Finland	`FI`	Spain	`ES`
Germany	`DE`	Sweden	`SE`
Great Britain	`GB`	Switzerland	`CH`
Greece	`GR`	Taiwan	`TW`
Ireland	`IE`	Turkey	`TR`
Italy	`IT`	United States	`US`

The codes for languages and countries seem a bit random because some of them are derived from local languages. German in German is Deutsch, Chinese in Chinese is zhongwen: hence `de` and `zh`. And Switzerland is `CH`, deriving from the Latin term *Confoederatio Helvetica* for the Swiss confederation.

Locales are described by tags—hyphenated strings of locale elements such as `en-US`.

In Germany, you would use a locale `de-DE`. Switzerland has four official languages (German, French, Italian, and Rhaeto-Romance). A German speaker in Switzerland would want to use a locale `de-CH`. This locale uses the rules for the German language, but currency values are expressed in Swiss francs, not euros.

If you only specify the language, say, `de`, then the locale cannot be used for country-specific issues such as currencies.

You can construct a `Locale` object from a tag string like this:

```
Locale usEnglish = Locale.forLanguageTag("en-US");
```

In the common case where you only specify a language, or language and country, you can use the `Locale.of` factory method:

```
Locale german = Locale.of("de");
Locale swissGerman = Locale.of("de", "CH");
```

The `toLanguageTag` method yields the language tag for a given locale. For example, `Locale.US.toLanguageTag()` is the string `"en-US"`.

For your convenience, there are predefined locale objects for various countries:

```
Locale.CANADA
Locale.CANADA_FRENCH
Locale.CHINA
Locale.FRANCE
Locale.GERMANY
Locale.ITALY
Locale.JAPAN
Locale.KOREA
Locale.PRC
Locale.TAIWAN
Locale.UK
Locale.US
```

A number of predefined locales specify just a language without a location:

```
Locale.CHINESE
Locale.ENGLISH
Locale.FRENCH
Locale.GERMAN
Locale.ITALIAN
Locale.JAPANESE
Locale.KOREAN
Locale.SIMPLIFIED_CHINESE
Locale.TRADITIONAL_CHINESE
```

The `Locale.ROOT` has language-neutral rules that can be useful for machine-processed strings.

Finally, the static `getAvailableLocales` method returns an array of all locales known to the virtual machine. The `availableLocales` method returns a stream instead.

Note: You can get all language codes as `Locale.getISOLanguages()` and all country codes as `Locale.getISOCountries()`.

1.1.3. The Default Locale

The static `getDefault` method of the `Locale` class initially gets the default locale as stored by the local operating system. You can

change the default Java locale by calling the `setDefault` method with a different locale.

Some operating systems allow the user to specify different locales for displayed messages and for formatting. For example, a French speaker living in the United States can have French menus but currency values in dollar.

To obtain these preferences, call

```
Locale displayLocale = Locale.getDefault(Locale.Categ
Locale formatLocale = Locale.getDefault(Locale.Catego
```

Note: In UNIX, you can specify separate locales for numbers, currencies, and dates, by setting the `LC_NUMERIC`, `LC_MONETARY`, and `LC_TIME` environment variables. Java does not pay attention to these settings.

Tip: If you want to test a locale that just has language and country settings, you can supply them on the command line when you launch your program. For example, here we set the default locale to `de-CH`:

```
java -Duser.language=de -Duser.region=CH MyProgram
```

1.1.4. Display Names

Once you have a locale, what can you do with it? Initially, not much, as it turns out. The only useful methods in the `Locale` class are those for identifying the language and country codes. The most important one is `getDisplayName`. It returns a string describing the locale. This string does not contain the cryptic two-letter codes, but is in a form that can be presented to a user, such as

```
German (Switzerland)
```

Actually, there is a problem here. The display name is issued in the default locale. That might not be appropriate. If your user already selected German as the preferred language, you probably want to present the string in German. You can do just that by passing the German locale as an argument. The code

```
Locale locale = Locale.of("de", "CH");
System.out.println(locale.getDisplayName(Locale.GERMA
```

prints

```
Deutsch (Schweiz)
```

This example shows why you need `Locale` objects. You feed them to locale-aware methods that produce text that is presented to users in different locations. You will see many examples of this in the following sections.

Caution: Even such mundane operations as turning a string into lowercase or uppercase can be locale-specific. For example, in the Turkish locale, the lowercase of the letter I is a dotless ı. Programs that tried to normalize strings by storing them in lowercase have mysteriously failed for Turkish customers where I and the dotted i don't have the same lowercase version. It is a good idea to always use the variants of `toUpperCase` and `toLowerCase` with a `Locale` parameter. For example, try out:

```
String command = "QUIT".toLowerCase(Locale.of("tr"));
   // "quıt" with a dotless ı
```

Of course, in Turkey, where `Locale.getDefault()` yields just that locale, `"QUIT".toLowerCase()` is not the same as `"quit"`.

If you want to normalize English language strings to lowercase, you should pass an English locale to the `toLowerCase` method. For language-neutral processing, use `Locale.ROOT`.

Note: You can explicitly set the locale for input and output operations.

- When reading numbers from a `Scanner`, you can set its locale with the `useLocale` method.
- The `String.format` and `PrintWriter.printf` methods have overloaded forms with a `Locale` parameter.

`java.util.Locale` **1.1**

- `static Locale.of(String language)` **19**
- `static Locale.of(String language, String country)` **19**
  construct a locale with the given language and country.
- `static Locale forLanguageTag(String languageTag)` **7**
  constructs a locale corresponding to the given language tag.
- `static Locale getDefault()`
  returns the default locale.

- `static void setDefault(Locale newLocale)`
  sets the default locale.
- `String getDisplayName()`
  returns a name describing the locale, expressed in the current locale.
- `String getDisplayName(Locale inLocale)`
  returns a name describing the locale, expressed in the given locale.
- `String getLanguage()`
  returns the language code—a lowercase two-letter ISO 639 code.
- `String getDisplayLanguage()`
  returns the name of the language, expressed in the current locale.
- `String getDisplayLanguage(Locale inLocale)`
  returns the name of the language, expressed in the given locale.
- `String getCountry()`
  returns the country code as an uppercase two-letter ISO 3166 code.
- `static String[] getISOCountries()`
- `static Set<String> getISOCountries(Locale.IsoCountryCode type)` **9**
  get all two-letter country codes, or all country codes with 2, 3, or 4 letters. The type is one of the enumeration constants `PART1_ALPHA2`, `PART1_ALPHA3`, and `PART3`.

- `String getDisplayCountry()`
  returns the name of the country, expressed in the current locale.
- `String getDisplayCountry(Locale inLocale)`
  returns the name of the country, expressed in the given locale.
- `String toLanguageTag()` 7
  returns the IETF BCP 47 language tag for this locale—for example, `"de-CH"`.
- `String toString()`
  returns a description of the locale, with the language and country separated by underscores (e.g., `"de_CH"`). Use this method only for debugging.

1.2. Number Formats

I already mentioned how number and currency formatting is highly locale-dependent. The Java library supplies a collection of formatter objects that can format and parse numeric values in the `java.text` package.

1.2.1. Formatting Numeric Values

Go through the following steps to format a number for a particular locale:

1. Get the locale object, as described in the preceding section.
2. Use a "factory method" to obtain a formatter object.

3. Use the formatter object for formatting and parsing.

The factory methods are static methods of the `NumberFormat` class with a `Locale` parameter. There are three factory methods: `getNumberInstance`, `getCurrencyInstance`, and `getPercentInstance`. These methods return objects that can format and parse numbers, currency amounts, and percentages, respectively. For example, here is how you can format a currency value in German:

```
Locale locale = Locale.GERMAN;
NumberFormat formatter = NumberFormat.getCurrencyInst
double amount = 123456.78;
String result = formatter.format(amount);
```

The result is

123.456,78 €

Note that the currency symbol is € and that it is placed at the end of the string. Also, note the reversal of decimal points and decimal commas.

Java 12 adds a "compact" format with two styles: short (123K) and long (123 thousand). Here is how to obtain the short style:

```
formatter = NumberFormat.getCompactNumberInstance(loc
```

Conversely, to read in a number that was entered or stored with the conventions of a certain locale, use the `parse` method. For example, the following code parses the value that the user typed into a text field. The `parse` method can deal with decimal points and commas, as well as digits in other languages.

```
TextField inputField;
. . .
NumberFormat formatter = NumberFormat.getNumberInstan
// get the number formatter for default locale
Number input = formatter.parse(inputField.getText().s
double x = input.doubleValue();
```

The return type of `parse` is the abstract type `Number`. The returned object is either a `Double` or a `Long` wrapper object, depending on whether the parsed number was a floating-point number. If you don't care about the distinction, you can simply use the `doubleValue` method of the `Number` class to retrieve the wrapped number.

Caution: Objects of type `Number` are not automatically unboxed—you cannot simply assign a `Number` object to a primitive type.

Instead, use the `doubleValue` or `intValue` method.

If the text for the number is not in the correct form, the method throws a `ParseException`. For example, leading whitespace in the string is *not* allowed. (Call `strip` to remove it.) However, any characters that follow the number in the string are simply ignored, so no exception is thrown.

Note that the instances returned by the `getXxxInstance` factory methods are not actually of type `NumberFormat`. The `NumberFormat` type is an abstract class, and the actual formatters belong to one of its subclasses. The factory methods merely know how to locate the object that belongs to a particular locale.

You can get a list of the currently supported locales with the static `getAvailableLocales` method. That method returns an array of the locales for which number formatter objects can be obtained.

Note: You can use a `Scanner` to read localized integers and floating-point numbers. Call the `useLocale` method to set the locale.

The book companion code contains a GUI program that lets you experiment with number formatters (see Figure 7.1). The combo box at the top of the figure contains all locales with number formatters.

You can choose between number, currency, and percentage formatters. Each time you make another choice, the number in the text field is reformatted. If you go through a few locales, you can get a good impression of the many ways that a number or currency value can be formatted. You can also type a different number and click the Parse button to call the `parse` method, which tries to parse what you entered. If your input is successfully parsed, it is passed to `format` and the result is displayed. If parsing fails, a "Parse error" message is displayed in the text field.

Figure 1.1: The `NumberFormatTest` program

Listing 7.1 shows a text version of the number format explorer that is a bit easier to follow.

Listing 1.1 numberFormat/NumberFormatTest2.java

```
1 package numberFormat;
2
3 import java.text.*;
4 import java.util.*;
5 import util.*;
```

```
6
7  /**
8   * This program demonstrates formatting numbers
9   * @version 2.0 2021-09-22
10  * @author Cay Horstmann
11  */
12 public class NumberFormatTest2
13 {
14    public static void main(String[] args)
15    {
16       Scanner in = new Scanner(System.in);
17       var locales = (Locale[]) NumberFormat.get
18       Arrays.sort(locales, Comparator.comparing
19       Locale locale = Choices.choose(in, locale
20
21       var formatters = new LinkedHashMap<Number
22       formatters.put(NumberFormat.getNumberInst
23       formatters.put(NumberFormat.getCompactNum
24       formatters.put(NumberFormat.getCompactNum
25       formatters.put(NumberFormat.getPercentIns
26       formatters.put(NumberFormat.getCurrencyIn
27       NumberFormat formatter = Choices.choose(i
28
29       String operation = Choices.choose(in, "Fo
30       if (operation.equals("Format"))
31       {
32          System.out.print("Enter a floating-poi
33          double number = in.nextDouble();
```

```
34            System.out.println(formatter.format(nu
35         }
36         else
37         {
38            System.out.print("Enter a floating-poi
39            String text = in.next();
40            try
41            {
42               System.out.println(formatter.parse(
43            }
44            catch (ParseException e)
45            {
46               System.out.println("ParseException
47            }
48         }
49      }
50   }
```

`java.text.NumberFormat` **1.1**

- `static Locale[] getAvailableLocales()`
  returns an array of `Locale` objects for which `NumberFormat` formatters are available.

- `static NumberFormat getNumberInstance()`
- `static NumberFormat getNumberInstance(Locale inLocale)`
- `static NumberFormat getCurrencyInstance()`
- `static NumberFormat getCurrencyInstance(Locale inLocale)`
- `static NumberFormat getPercentInstance()`
- `static NumberFormat getPercentInstance(Locale inLocale)`
  return a formatter for numbers, currency amounts, or percentage values for the current locale or for the given locale.
- `static NumberFormat getCompactNumberInstance()` **12**
- `static NumberFormat getCompactNumberInstance(Locale locale, NumberFormat.Style formatStyle)` **12**
  return a compact number formatter in the current locale and `SHORT` style, or in the given locale and style (either `SHORT` or `LONG`).
- `String format(double number)`
- `String format(long number)`
  return the string resulting from formatting the given floating-point number or integer.
- `Number parse(String source)`
  parses the given string and returns the number value, as a `Double` if the input string describes a floating-point number or

as a `Long` otherwise. The beginning of the string must contain a number; no leading whitespace is allowed. The number can be followed by other characters, which are ignored. Throws `ParseException` if parsing was not successful.

- `void setParseIntegerOnly(boolean value)`
- `boolean isParseIntegerOnly()`

  set or get a flag to indicate whether this formatter should parse only integer values.
- `void setGroupingUsed(boolean newValue)`
- `boolean isGroupingUsed()`

  set or get a flag to indicate whether this formatter emits and recognizes decimal separators (such as `100,000`).
- `void setMinimumIntegerDigits(int newValue)`
- `int getMinimumIntegerDigits()`
- `void setMaximumIntegerDigits(int newValue)`
- `int getMaximumIntegerDigits()`
- `void setMinimumFractionDigits(int newValue)`
- `int getMinimumFractionDigits()`
- `void setMaximumFractionDigits(int newValue)`
- `int getMaximumFractionDigits()`

  set or get the maximum or minimum number of digits allowed in the integer or fractional part of a number.

1.2.2. The `DecimalFormat` Class

In most locales, the `NumberFormat` factory methods that you saw in the preceding section return an instance of the `DecimalFormat` class. This class describes the formatting variations that occur around the world. You can modify individual settings, or create an entirely new formatter. A pattern syntax makes this a bit more convenient.

The pattern describes the number of required and optional digits, and the prefixes and suffixes for positive and negative numbers. There are also a couple more esoteric settings—see Table 7.3.

Consider this example:

```
var formatter = new DecimalFormat("0.00;(#)");
```

The semicolon separates the positive and the optional negative part. From the positive part, we see that there must be at least one digit in the integer part and at least two digits in the fractional part. This holds for all numbers, regardless of sign. Negative numbers use the accounting format—a prefix `(` and a suffix `)`.

The prefix or suffix may contain a `¤` currency sign (U+00A4) to denote where the currency symbol should go.

If you need to insert a special character into the prefix or suffix, precede it with a single quote. For example, a prefix `'#` is a literal hash sign, and `o''clock` has one quotation mark.

Table 1.3: `DecimalFormat` Properties

Property Name	Description	Pattern
`groupingSize`	The number of integer digits grouped together (usually 3 or 4)	The num digits be the last the end integer p such as for a gro size of 3
`minimum` / `maximumFractionDigits`	The minimum and maximum number of digits of the	Use requ (`0`) and optional digits in fractiona `.00##` .

Property Name	Description	Pattern
	fractional part	
`minimumIntegerDigits`	The minimum number of digits of the integer part	Use requ (`0`) digi integer p `000` .
`maximumIntegerDigits`	The maximum number of integer digits	With exponen notation number digits in integer p such as `###,##` Otherwis cannot b pattern.

Property Name	Description	Pattern
—	the minimum number of digits in the exponential part	Use `0` c the `E` p `#.00E0`
`multiplier`	The multiplier for percent, per thousand	Use `%` f `‰` (U+2 1000.
`positivePrefix` / `Suffix`, `negativePrefix` / `Suffix`	The prefix and suffix for positive or negative numbers	Surrounc positive negative the patte the litera or suffix, `+#0.00` uses a `+` and no s positive

Property Name	Description	Pattern
		numbers encloses negative numbers parenthe
`decimalSeparatorAlwaysShown`	`true` if the separator is shown for a zero fractional part	Cannot b pattern.

The actual symbols for the digits, separators, and miscellaneous other number parts are taken from a `DecimalFormatSymbols` object that you can also customize. Table 7.4 lists its properties.

Table 1.4: `DecimalFormatSymbol` Properties

Property	Type	Description

Property	Type	Description
`currencySymbol`	`String`	A string such as `"EUR"` to use w or suffix has a
`decimalSeparator`, `monetaryDecimalSeparator`	`char`	The decimal sep with numbers o values
`exponentSeparator`	`String`	The string befor part, usually `"E`
`groupingSeparator`, `monetaryGroupingSeparator` (since Java 15)	`char`	The group sepa with numbers o values
`infinity`, `naN`	`String`	The strings for f `Double.POSIT` `Double.NEGAT` and `Double.Na`
`internationalCurrencySymbol`	String	The ISO 4217 c

Property	Type	Description
		—see Section 7.
`minusSign`	`char`	The minus sign when there is nc pattern
`percent`, `perMill`	`char`	The characters u percent or per n
`zeroDigit`	`char`	The character fc zero. The other subsequent nine characters.

Suppose, for example, that you want to show numbers in the US style, with `,` as group separator and `.` as decimal separator, no matter what the locale is. Customize the `DecimalFormatSymbols` and the formatter:

```
DecimalFormatSymbols symbols = new DecimalFormatSymbo
symbols.setGroupingSeparator(',');
symbols.setDecimalSeparator('.');
```

```
DecimalFormat formatter = (DecimalFormat) NumberForma
formatter.setDecimalFormatSymbols(symbols);
```

1.2.3. Currencies

To format a currency value, you can use the `NumberFormat.getCurrencyInstance` method. However, that method is not very flexible—it returns a formatter for a single currency. Suppose you prepare an invoice for an American customer in which some amounts are in dollars and others are in euros. You can't just use two formatters:

```
NumberFormat dollarFormatter = NumberFormat.getCurren
NumberFormat euroFormatter = NumberFormat.getCurrency
```

Your invoice would look very strange, with some values shown as $100,000 and others as 100.000 €. (Note that the euro value uses a decimal point, not a comma.)

Instead, use the `Currency` class to control the currency used by the formatters. You can get a `Currency` object by passing a currency identifier to the static `Currency.getInstance` method. Then call the `setCurrency` method for each formatter. Here is how you would set up the euro formatter for your American customer:

```
NumberFormat euroFormatter = NumberFormat.getCurrency
euroFormatter.setCurrency(Currency.getInstance("EUR")
```

The currency identifiers are defined by ISO 4217 (see https://www.iso.org/iso-4217-currency-codes.html). Table 7.5 provides a partial list.

Table 1.5: Currency Identifiers

Currency Value	Identifier	Numeric Code
U.S. Dollar	USD	840
Euro	EUR	978
British Pound	GBP	826
Japanese Yen	JPY	392
Chinese Renminbi (Yuan)	CNY	156
Indian Rupee	INR	356

Currency Value	Identifier	Numeric Code
Russian Ruble	RUB	643

`java.util.Currency` `1.4`

- `static Currency getInstance(String currencyCode)`
- `static Currency getInstance(Locale locale)`
  return the `Currency` instance for the given ISO 4217 currency code or the country of the given locale.
- `String toString()`
- `String getCurrencyCode()`
- `String getNumericCode()` `7`
- `String getNumericCodeAsString()` `9`
  get the ISO 4217 alphabetic or numeric currency code of this currency.
- `String getSymbol()`
- `String getSymbol(Locale locale)`
  get the formatting symbol of this currency for the default locale or the given locale. For example, the symbol for USD can be `"$"` or `"US$"`, depending on the locale.
- `int getDefaultFractionDigits()`
  gets the default number of fraction digits of this currency.

- `static Set<Currency> getAvailableCurrencies()` 7
  gets all available currencies.

1.3. Date and Time

When you are formatting date and time, you should be concerned with four locale-dependent issues:

- The names of months and weekdays should be presented in the local language.
- There will be local preferences for the order of year, month, and day.
- The Gregorian calendar might not be the local preference for expressing dates.
- The time zone of the location must be taken into account.

The `DateTimeFormatter` class from the `java.time` package handles these issues. Pick one of the formatting styles shown in Table 7.6. Then, get a formatter:

```
FormatStyle style = . . .; // One of FormatStyle.SHOR
DateTimeFormatter dateFormatter = DateTimeFormatter.o
DateTimeFormatter timeFormatter = DateTimeFormatter.o
DateTimeFormatter dateTimeFormatter = DateTimeFormatt
   // or DateTimeFormatter.ofLocalizedDateTime(dateSt
```

These formatters use the current locale. To use a different locale, use the `withLocale` method:

```
DateTimeFormatter dateFormatter =
   DateTimeFormatter.ofLocalizedDate(style).withLocal
```

Now you can format a `LocalDate`, `LocalDateTime`, `LocalTime`, or `ZonedDateTime`:

```
ZonedDateTime appointment = . . .;
String formatted = formatter.format(appointment);
```

Table 1.6: Date and Time Formatting Styles

Style	Date	Time
`SHORT`	`7/16/69`	`9:32 AM`
`MEDIUM`	`Jul 16, 1969`	`9:32:00 AM`
`LONG`	`July 16, 1969`	`9:32:00 AM EDT` in `en-US`, `9:32:00 MSZ` in `de-DE` (only for `ZonedDateTime`)

Style	Date	Time
`FULL`	`Wednesday, July 16, 1969`	`9:32:00 AM EDT` in `en-US`, `9:32 Uhr MSZ` in `de-DE` (only for `ZonedDateTime`)

Note: Here we use the `DateTimeFormatter` class from the `java.time` package. There is also a legacy `java.text.DateFormatter` class that works with `Date` and `Calendar` objects.

You can use one of the static `parse` methods of `LocalDate`, `LocalDateTime`, `LocalTime`, or `ZonedDateTime` to parse a date or time in a string:

```
  LocalTime time = LocalTime.parse("9:32 AM", formatter
```

These methods are not suitable for parsing human input, at least not without preprocessing. For example, the short time formatter for the United States will parse `"9:32 AM"` but not `"9:32AM"` or `"9:32 am"`.

Caution: Date formatters parse nonexistent dates, such as February 31, and adjust them to the last date in the given month.

Sometimes, you need to display just the names of weekdays and months, for example, in a calendar application. Call the `getDisplayName` method of the `DayOfWeek` and `Month` enumerations.

```
for (Month m : Month.values())
   System.out.println(m.getDisplayName(textStyle, loc
```

Table 7.7 shows the text styles. The `STANDALONE` versions are for display outside a formatted date. For example, in Finnish, January is "tammikuuta" inside a date, but "tammikuu" standalone.

Table 1.7: Values of the `java.time.format.TextStyle` Enumeration

Style	Example
`FULL` / `FULL_STANDALONE`	January
`SHORT` / `SHORT_STANDALONE`	Jan

Style	Example
`NARROW` / `NARROW_STANDALONE`	J

Note: The first day of the week can be Saturday, Sunday, or Monday, depending on the locale. You can obtain it like this:

```
DayOfWeek first = WeekFields.of(locale).ge
```

Listing 7.2 shows the `DateFormat` class in action. You can select a locale and see how the date and time are formatted in different places around the world.

Figure 7.2 shows a GUI version of the program, which is included in the book companion code. You may need to install Chinese fonts to see the Chinese characters displayed.



Figure 1.2: The `DateFormatTest` program

Listing 1.2 dateFormat/DateTimeFormatTest2.java

```
1  package dateFormat;
2
3  import java.text.*;
4  import java.time.*;
5  import java.time.format.*;
6  import java.util.*;
7  import util.*;
8
9  /**
10  * This program demonstrates formatting dates u
11  * @version 2.0 2021-09-23
12  * @author Cay Horstmann
13  */
14 public class DateTimeFormatTest2
15 {
16    public static void main(String[] args)
17    {
18       Scanner in = new Scanner(System.in);
19       var locales = (Locale[]) NumberFormat.get
```

```
20        Arrays.sort(locales, Comparator.comparing
21        Locale locale = Choices.choose(in, locale
22        FormatStyle style = Choices.choose(in, Fo
23              "Short", "Medium", "Long", "Full");
24        String type = Choices.choose(in, "Date",
25
26        if (type.equals("Date"))
27        {
28           DateTimeFormatter formatter = DateTime
29                 style).withLocale(locale);
30           System.out.println(formatter.format(Lo
31           System.out.print("Enter another date:
32           String input = in.nextLine();
33           LocalDate date = LocalDate.parse(input
34           System.out.println(formatter.format(da
35        }
36        else if (type.equals("Time"))
37        {
38           DateTimeFormatter formatter = DateTime
39                 style).withLocale(locale);
40           System.out.println(formatter.format(Lo
41           System.out.print("Enter another time:
42           String input = in.nextLine();
43           LocalTime time = LocalTime.parse(input
44           System.out.println(formatter.format(ti
45        }
46        else
47        {
```

```
48          DateTimeFormatter formatter = DateTime
49                style).withLocale(locale);
50          System.out.println(formatter.format(Zo
51          System.out.print("Enter another date a
52          String input = in.nextLine();
53          ZonedDateTime dateTime = ZonedDateTime
54          System.out.println(formatter.format(da
55       }
56    }
57 }
```

`java.time.format.DateTimeFormatter` **8**

- `static DateTimeFormatter ofLocalizedDate(FormatStyle dateStyle)`
- `static DateTimeFormatter ofLocalizedTime(FormatStyle dateStyle)`
- `static DateTimeFormatter ofLocalizedDateTime(FormatStyle dateTimeStyle)`
- `static DateTimeFormatter ofLocalizedDateTime(FormatStyle dateStyle, FormatStyle timeStyle)`
  return `DateTimeFormatter` instances that format dates, times, or dates and times with the specified styles.
- `DateTimeFormatter withLocale(Locale locale)`
  returns a copy of this formatter with the given locale.

- `String format(TemporalAccessor temporal)`
  returns the string resulting from formatting the given date/time.

`java.time.LocalDate` `8`

`java.time.LocalTime` `8`

`java.time.LocalDateTime` `8`

`java.time.ZonedDateTime` `8`

- `static Xxx parse(CharSequence text, DateTimeFormatter formatter)`
  parses the given string and returns the `LocalDate`, `LocalTime`, `LocalDateTime`, or `ZonedDateTime` described in it. Throws a `DateTimeParseException` if parsing was not successful.

1.4. Collation and Normalization

Most programmers know how to compare strings with the `compareTo` method of the `String` class. Unfortunately, when interacting with human users, this method is not very useful. The `compareTo` method uses the values of the UTF-16 encoding of the string, which leads to absurd results, even in English. For example,

the following five strings are ordered according to the `compareTo` method:

```
America
Zulu
able
zebra
Ångström
```

For dictionary ordering, you would want to consider upper case and lower case to be equivalent. To an English speaker, the sample list of words would be ordered as

```
able
America
Ångström
zebra
Zulu
```

However, that order would not be acceptable to a Swedish user. In Swedish, the letter Å is different from the letter A, and it is collated *after* the letter Z! That is, a Swedish user would want the words to be sorted as

```
able
America
zebra
Zulu
Ångström
```

To obtain a locale-sensitive comparator, call the static `Collator.getInstance` method:

```
Collator coll = Collator.getInstance(locale);
words.sort(coll); // Collator implements Comparator<O
```

Note: Since Java 21, you can specify unusual collators with an extension. For example, the locale with language tag `sv-u-co-trad` uses traditional Swedish collation, which does not distinguish between "v" and "w".

Since the `Collator` class implements the `Comparator` interface, you can pass a `Collator` object to the `List.sort(Comparator)` method to sort a list of strings.

There are a couple of advanced settings for collators. You can set a collator's *strength* to adjust how selective it should be. Character

differences are classified as *primary*, *secondary*, or *tertiary*. For example, in English, the difference between “A” and “Z” is considered primary, the difference between “A” and “Å” is secondary, and between “A” and “a” is tertiary.

By setting the strength of the collator to `Collator.PRIMARY`, you tell it to pay attention only to primary differences. By setting the strength to `Collator.SECONDARY`, you instruct the collator to take secondary differences into account. That is, two strings will be more likely to be considered different when the strength is set to “secondary” or “tertiary,” as shown in Table 7.8.

Table 1.8: Collations with Different Strengths (English Locale)

Primary	Secondary	Tertiary
Angstrom = Ångström	Angstrom ≠ Ångström	Angstrom ≠ Ångström
Able = able	Able = able	Able ≠ able

When the strength has been set to `Collator.IDENTICAL`, no differences are allowed. This setting is mainly useful in conjunction with a rather technical collator setting, the *decomposition mode*, which we take up next.

Occasionally, a character or sequence of characters can be described in more than one way in Unicode. For example, an "Å" can be Unicode character U+00C5, or it can be expressed as a plain "A" (U+0065) followed by a "°" ("combining ring above"; U+030A). Perhaps more surprisingly, the letter sequence "ffi" can be described with a single character "Latin small ligature ffi" with code U+FB03. (One could argue that this is a presentation issue that should not have resulted in different Unicode characters, but we don't make the rules.)

The Unicode standard defines four *normalization forms* (D, KD, C, and KC) for strings. See https://www.unicode.org/unicode/reports/tr15/tr15-23.html for the details. In the normalization form C, accented characters are always composed. For example, a sequence of "A" and a combining ring above "°" is combined into a single character "Å". In form D, accented characters are always decomposed into their base letters and combining accents: "Å" is turned into "A" followed by "°". Forms KC and KD also decompose characters such as ligatures or the trademark symbol.

You can choose the degree of normalization that you want a collator to use. The value `Collator.NO_DECOMPOSITION` does not normalize strings at all. This option is faster, but it might not be appropriate for texts that express characters in multiple forms. The

default, `Collator.CANONICAL_DECOMPOSITION`, uses the normalization form D. This is useful for texts that contain accents but not ligatures. Finally, "full decomposition" uses normalization form KD. See Table 7.9 for examples.

Table 1.9: Differences between Decomposition Modes

No Decomposition	Canonical Decomposition	Full Decomposition
Å ≠ A°	Å = A°	Å = A°
™ ≠ TM	™ ≠ TM	™ = TM

It is wasteful to have the collator decompose a string many times. If one string is compared against other strings many times, you can save the decomposition in a *collation* key object. The `getCollationKey` method returns a `CollationKey` object that you can use for further, faster comparisons. Here is an example:

```
String a = . . .;
CollationKey aKey = coll.getCollationKey(a);
if(aKey.compareTo(coll.getCollationKey(b)) == 0) // f
   . . .
```

Finally, you might want to convert strings into their normalized forms even if you don't do collation—for example, to store strings in a database or communicate with another program. The `java.text.Normalizer` class carries out the normalization process. Here is an example:

```
String name = "Ångström";
String normalized = Normalizer.normalize(name, Normal
   // uses normalization form D
```

The normalized string contains ten characters. The "Å" and "ö" are replaced by "A°" and "o¨" sequences.

However, that is not usually the best form for storage and transmission. Normalization form C first applies decomposition and then combines the accents back in a standardized order. According to the W3C, this is the recommended mode for transferring data over the Internet.

The program in Listing 7.3 lets you experiment with collation order. The book companion code also has a GUI version. Type a word into the text field and click the Add button to add it to the list of words. Each time you add another word, or change the locale, strength, or decomposition mode, the list of words is sorted again. An `=` sign indicates words that are considered identical (see Figure 7.3).



Figure 1.3: The `CollationTest` program

The locale names are displayed in sorted order, using the collator of the default locale. If you run this program with the US English locale, note that "Norwegian (Norway,Nynorsk)" comes before "Norwegian (Norway)", even though the Unicode value of the comma character is greater than the Unicode value of the closing parenthesis.

Listing 1.3 collation/CollationTest2.java

```
1  package collation;
2
3  import java.text.*;
4  import java.util.*;
5  import util.*;
6
7  /**
8   * This program demonstrates collating strings
9   * @version 2.0 2021-09-23
10  * @author Cay Horstmann
11  */
12 public class CollationTest2 {
13    public static void main(String[] args) {
14       Scanner in = new Scanner(System.in);
15       var locales = (Locale[]) NumberFormat.get
16       Arrays.sort(locales, Comparator.comparing
17       Locale locale = Choices.choose(in, locale
18
19       Collator collator = Collator.getInstance(
20       int strength = Choices.choose(in, Collato
21       int decomposition = Choices.choose(in, Co
22
23       List<String> strings = new ArrayList<>();
24       strings.add("America");
25       strings.add("able");
26       strings.add("Zulu");
```

```
27          strings.add("zebra");
28          strings.add("\u00C5ngstr\u00F6m");
29          strings.add("A\u030angstro\u0308m");
30          strings.add("Angstrom");
31          strings.add("Able");
32          strings.add("office");
33          strings.add("o\uFB03ce");
34          strings.add("Java\u2122");
35          strings.add("JavaTM");
36
37          collator.setStrength(strength);
38          collator.setDecomposition(decomposition);
39
40          strings.sort(collator);
41
42          for (int i = 0; i < strings.size(); i++)
43             String s = strings.get(i);
44             if (i > 0 && collator.compare(s, strin
45                System.out.print("= ");
46             System.out.println(s);
47          }
48       }
49    }
```

`java.text.Collator` **1.1**

- `static Locale[] getAvailableLocales()`
  returns an array of `Locale` objects for which `Collator` objects are available.
- `static Collator getInstance()`
- `static Collator getInstance(Locale l)`
  return a collator for the default locale or the given locale.
- `int compare(String a, String b)`
  returns a negative value if `a` comes before `b`, `0` if they are considered identical, and a positive value otherwise.
- `boolean equals(String a, String b)`
  returns `true` if `a` and `b` are considered identical, `false` otherwise.
- `void setStrength(int strength)`
- `int getStrength()`
  set or get the strength of the collator. Stronger collators tell more words apart. Strength values are `Collator.PRIMARY`, `Collator.SECONDARY`, and `Collator.TERTIARY`.
- `void setDecomposition(int decomp)`
- `int getDecompositon()`
  set or get the decomposition mode of the collator. The more a collator decomposes a string, the more strict it will be in deciding whether two strings should be considered identical.

Decomposition values are `Collator.NO_DECOMPOSITION`, `Collator.CANONICAL_DECOMPOSITION`, and `Collator.FULL_DECOMPOSITION`.

- `CollationKey getCollationKey(String a)`
  returns a collation key that contains a decomposition of the characters in a form that can be quickly compared against another collation key.

`java.text.CollationKey` **1.1**

- `int compareTo(CollationKey b)`
  returns a negative value if this key comes before `b`, `0` if they are considered identical, and a positive value otherwise.

`java.text.Normalizer` **6**

- `static String normalize(CharSequence str, Normalizer.Form form)`
  returns the normalized form of `str`. The `form` value is one of `NFD`, `NFKD`, `NFC`, or `NFKC`.

1.5. Message Formatting

The Java library has a `MessageFormat` class that formats text with variable parts. It is similar to formatting with the `printf` method,

but it supports locales and formats for numbers and dates. We will examine that mechanism in the following sections.

1.5.1. Formatting Numbers and Dates

Here is a typical message format string:

```
"On {2}, a {0} destroyed {1} houses and caused {3} of
```

The numbers in braces are placeholders for actual names and values. The static method `MessageFormat.format` lets you substitute values for the variables. It is a "varargs" method, so you can simply supply the parameters as follows:

```
String msg
   = MessageFormat.format("On {2}, a {0} destroyed {1
      "hurricane", 99, new GregorianCalendar(1999, 0,
```

In this example, the placeholder `{0}` is replaced with `"hurricane"`, `{1}` is replaced with `99`, and so on.

The result of our example is the string

```
On 1/1/99 12:00 AM, a hurricane destroyed 99 houses a
```

That is a start, but it is not perfect. We don't want to display the time "12:00 AM," and we want the damage amount printed as a currency value. The way we do this is by supplying an optional format for some of the placeholders:

```
"On {2,date,long}, a {0} destroyed {1} houses and cau
```

This example code prints:

```
On January 1, 1999, a hurricane destroyed 99 houses a
```

In general, the placeholder index can be followed by a *type* and a *style*. Separate the index, type, and style by commas. The type can be any of

```
number
time
date
choice
```

If the type is `number`, then the style can be

```
integer
currency
percent
```

or it can be a `DecimalFormat` pattern such as `$,##0` —see Section 7.2.2 for the possible formats.

If the type is either `time` or `date`, then the style can be

```
short
medium
long
full
```

or a date format pattern such as `yyyy-MM-dd`. (See the documentation of the `SimpleDateFormat` class for the possible formats.)

Caution: To include a brace in a message format string, surround it with single quotes, for example: `"A {0} is enclosed in '{' and '}' symbols".` It is best to use curly apostrophes for text: `"{0}’s favorite symbols are braces"`. But if you must have straight single quotes, you need to double them:

```
String template = "<a href=''{0}''>{1}</a>";
```

The static `MessageFormat.format` method uses the current locale to format the values. To format with an arbitrary locale, you have to work a bit harder because there is no "varargs" method that you can use. You need to place the values to be formatted into an `Object[]` array, like this:

```
var formatter = new MessageFormat(pattern, locale);
String message = formatter.format(new Object[] { value
```

`java.text.MessageFormat` **1.1**

- `MessageFormat(String pattern)`
- `MessageFormat(String pattern, Locale locale)`
  construct a message format object with the specified pattern and locale.
- `void applyPattern(String pattern)`
  sets the pattern of a message format object to the specified pattern.

- `void setLocale(Locale locale)`
- `Locale getLocale()`
  set or get the locale to be used for the placeholders in the message. The locale is *only* used for subsequent patterns that you set by calling the `applyPattern` method.
- `static String format(String pattern, Object... args)`
  formats the pattern string by using `args[i]` as input for placeholder `{i}`.
- `StringBuffer format(Object args, StringBuffer result, FieldPosition pos)`
  formats the pattern of this `MessageFormat`. The `args` parameter must be an array of objects. The formatted string is appended to `result`, and `result` is returned. If `pos` equals `new FieldPosition(MessageFormat.Field.ARGUMENT)`, its `beginIndex` and `endIndex` properties are set to the location of the text that replaces the `{1}` placeholder. Supply `null` if you are not interested in position information.

`java.text.Format` **1.1**

- `String format(Object obj)`
  formats the given object, according to the rules of this formatter. This method calls `format(obj, new StringBuffer(), new FieldPosition(0)).toString()`.

1.5.2. Choice Formats

Let's look closer at the pattern of the preceding section:

```
"On {2}, a {0} destroyed {1} houses and caused {3} of
```

If we replace the disaster placeholder `{0}` with `"earthquake"`, the sentence is not grammatically correct in English:

```
On January 1, 1999, a earthquake destroyed . . .
```

What we really want to do is integrate the article "a" into the placeholder:

```
"On {2}, {0} destroyed {1} houses and caused {3} of d
```

The `{0}` would then be replaced with `"a hurricane"` or `"an earthquake"`. That is especially appropriate if this message needs to be translated into a language where the gender of a word affects the article. For example, in German, the pattern would be

```
"{0} zerstörte am {2} {1} Häuser und richtete einen S
```

The placeholder would then be replaced with the grammatically correct combination of article and noun, such as `"Ein Wirbelsturm"` or `"Eine Naturkatastrophe"`.

Now let us turn to the `{1}` parameter. If the disaster wasn't all that catastrophic, `{1}` might be replaced with the number 1, and the message would read:

```
On January 1, 1999, a mudslide destroyed 1 houses and
```

Ideally, we would like the message to vary according to the placeholder value, so it would read

```
no houses
one house
2 houses
. . .
```

depending on the placeholder value. The `choice` formatting option was designed for this purpose.

A choice format is a sequence of pairs, each containing

- A *lower limit*
- A *format string*

The lower limit and format string are separated by a `#` character, and the pairs are separated by `|` characters.

For example,

```
{1,choice,0#no houses|1#one house|2#{1} houses}
```

Table 7.10 shows the effect of this format string for various values of `{1}`.

Table 1.10: String Formatted by Choice Format

{1}	Result	{1}	Result
0	"no houses"	3	"3 houses"
1	"one house"	-1	"no houses"

Why do we use `{1}` twice in the format string? When the message format applies the choice format to the `{1}` placeholder and the value is `2`, the choice format returns `"{1} houses"`. That string is then formatted again by the message format, and the answer is spliced into the result.

Note: This example shows that the designer of the choice format was a bit muddleheaded. If you have three format strings, you need two limits to separate them. In general, you need *one fewer limit* than you have format strings. As you saw in Table 7.10, the `MessageFormat` class ignores the first limit.

The syntax would have been a lot clearer if the designer of this class realized that the limits belong *between* the choices, such as

```
no houses|1|one house|2|{1} houses // not
```

You can use the `<` symbol to denote that a choice should be selected if the lower bound is strictly less than the value.

You can also use the ≤ symbol (U+2264) as a synonym for `#`. If you like, you can even use the infinity symbol (U+221E) to specify a lower bound of – ∞ for the first value.

For example,

```
-
      ∞<no houses|0<one house|2

      ≤{1} houses
```

Let’s finish our natural disaster scenario. If we put the choice string inside the original message string, we get the following format instruction:

```
String pattern = """
On {2,date,long}, {0} destroyed {1,choice,0#no houses
and caused {3,number,currency} of damage.
""";
```

Or, in German,

```
String pattern = """
{0} zerstörte am {2,date,long} {1,choice,0#kein Haus|
und richtete einen Schaden von {3,number,currency} an
""";
```

Note that the ordering of the words is different in German, but the array of objects you pass to the `format` method is the *same*. The order of the placeholders in the format string takes care of the changes in the word ordering.

1.6. Text Boundaries

The `BreakIterator` class segments text into characters, words, sentences, or lines. The iteration protocol is not very pretty:

```
String s = "A man. A plan. Panama!";
BreakIterator iter = BreakIterator.getSentenceInstanc
iter.setText(s);
int start = iter.first();
int end = iter.next();
while (end != BreakIterator.DONE) {
   String segment = s.substring(start, end);
   start = end;
   end = iter.next();
   System.out.println(segment);
}
```

There are four iterators, returned by these static methods:

- The `getCharacterInstance` method yields an iterator over the grapheme clusters—that is, the Unicode sequences that produce a

visible character.

- The `getWordInstance` method yields an iterator that produces either words or word separators. It is up to you to figure out the type of each segment.
- The iterator of the `getSentenceInstance` method segments the text into sentences.
- The `getLineInstance` iterator yields lines.

Each method has a version with no parameter, using the default locale, and one with a `Locale` parameter.

Tip: Instead of iterating over grapheme clusters with a `BreakIterator`, you can use a regular expression:

```
String[] clusters = s.split("\\b{g}");
```

1.7. Text Input and Output

As you know, the Java programming language itself is fully Unicode-based. However, Windows and Mac OS X still support legacy character encodings such as Windows-1252 or Mac Roman in Western European countries, or Big5 in Taiwan. Therefore, communicating with your users through text is not as simple as it

should be. The following sections discuss the complications that you may encounter.

1.7.1. Text Files

Nowadays, it is best to use UTF-8 for saving and loading text files. But you may need to work with legacy files. If you know the expected character encoding, you can specify it when writing or reading text files:

```
Charset windows1252 = Charset.forName("Windows-1252")
var out = new PrintWriter(filename, windows1252);
```

For a guess of the user's preferred encoding, use the "native encoding" that is derived from the system executing the Java virtual machine. As of Java 18, its name is the value of the `native.encoding` system property.

Prior to Java 18, the native encoding is the default charset, which you can obtain from the static `Charset.defaultCharset()` method.

1.7.2. Line Endings

This isn't an issue of locales but of platforms. On Windows, text files are expected to use `\r\n` at the end of each line, where UNIX-based systems only require a `\n` character. Nowadays, most Windows programs can deal with just a `\n`, but older programs and the console may give your users grief.

Any line written with the `println` method will be properly terminated. The only problem is if you print strings that contain `\n` characters. They are not automatically modified to the platform line ending.

Instead of using `\n` in strings, you can use `printf` and the `%n` format specifier to produce platform-dependent line endings. For example,

```
out.printf("Hello%nWorld%n");
```

produces

```
Hello\r\nWorld\r\n
```

on Windows and

```
Hello\nWorld\n
```

everywhere else.

1.7.3. The Console

If you write programs that communicate with the user through `System.in` / `System.out` or `System.console()`, you have to face the possibility that the console may use a character encoding that is different from the default charset. This is particularly noticeable when working with the `cmd` shell on Windows. In the US version of Windows 11, the command shell still uses the archaic `IBM437` encoding that originated with IBM personal computers in 1982. The `Charset.defaultCharset()` method will return the `Windows-1252` character set, which is quite different. For example, the euro symbol € is present in `Windows-1252` but not in `IBM437`. When you call

```
System.out.println("100 €");
```

the console will display

```
100 ?
```

Ideally, of course, your users should switch the console to UTF-8. In Windows, the command is

```
chcp 65001
```

As of Java 18, that is sufficient to make Java use UTF-8 in the console. In prior versions, it is also necessary to set the platform encoding with the `file.encoding` system property:

```
java -Dfile.encoding=UTF-8 MyProg
```

If you cannot make your users change the character encoding of the console, you can find out what it is. As of Java 18, the system properties `stdout.encoding` and `stderr.encoding` give you that information. You can also change the settings on the command line.

You can also call `System.console().charset()`, provided that `System.console()` is not `null`.

Caution: If you obtain user input from a `new Scanner(System.in)`, the scanner uses the default charset and not the console character encoding. If they don't match, this will not work for keyboard input. If `System.console()` is not `null`, use a `new Scanner(System.console().reader())` instead.

1.7.4. The UTF-8 Byte Order Mark

As already mentioned, it is a good idea to use UTF-8 for text files when you can. However, if your application has to read UTF-8 text files created by other programs, you run into another potential problem. It is perfectly legal to add a "byte order mark" character U+FEFF as the first character of a file. In the UTF-16 encoding, where each code unit is a two-byte quantity, the byte order mark tells a reader whether the file uses "big-endian" or "little-endian" byte ordering. UTF-8 is a single-byte encoding, so there is no need to specify a byte ordering. But if a file starts with bytes `0xEF 0xBB 0xBF` (the UTF-8 encoding of U+FEFF), that is a strong indication that it uses UTF-8. For that reason, the Unicode standard encourages this practice. Any reader is supposed to discard an initial byte order mark.

There is just one fly in the ointment. The Oracle Java implementation stubbornly refuses to follow the Unicode standard, citing potential compatibility issues. That means that you, the programmer, must do what the platform won't do. When you read a text file and encounter a `U+FEFF` at the beginning, ignore it.

Caution: Unfortunately, the JDK implementors do not follow this advice. When you pass the `javac` compiler a valid UTF-8 source file that starts with a byte order mark, compilation fails with an error message "illegal character: \65279".

1.7.5. Character Encoding of Source Files

You, the programmer, will need to communicate with the Java compiler—and you do that with tools on your local system. For example, if you use a Chinese or Japanese version of Windows, your Java source code files may be encoded with a local character encoding. Such source code files are *not portable*. (Only the compiled class files are portable—they use a "modified UTF-8" encoding for identifiers and strings.)

Non-portable source files are not ideal. Nowadays it is easy to configure text editors and development environments to use UTF-8 for source files. As of Java 18, the `javac` compiler expects UTF-8 encoded source files by default. With earlier versions, run the compiler as:

```
javac -encoding UTF-8 Myfile.java
```

To compile legacy source files that are not in UTF-8, specify the encoding in the same way.

1.8. Resource Bundles

When localizing an application, you'll probably have a dauntingly large number of message strings, button labels, and so on, that all

need to be translated. To make this task feasible, you'll want to define the message strings in an external location, usually called a *resource*. The person carrying out the translation can then simply edit the resource files without having to touch the source code of the program.

In Java, you can use property files to specify string resources, and you can implement classes for resources of other types.

Note: Java technology resources are not the same as Windows or Macintosh resources. A Macintosh or Windows executable program stores resources, such as menus, dialog boxes, icons, and messages, in a section separate from the program code. A resource editor can inspect and update these resources without affecting the program code.

Note: Chapter 5 of Volume I describes a concept of JAR file resources, whereby data files, sounds, and images can be placed in a JAR file. The `getResource` method of the class `Class` finds the file, opens it, and returns a URL to the resource. By placing your files into the JAR file, you leave the job of finding the files to the class loader—which already knows how to locate items

in a JAR file. However, that mechanism has no locale support.

1.8.1. Locating Resource Bundles

When localizing an application, you produce a set of *resource bundles*. Each bundle is a property file or a class that describes locale-specific items (such as messages, labels, and so on). For each bundle, you have to provide versions for all locales that you want to support.

You need to use a specific naming convention for these bundles. For example, resources specific to Germany go into a file `baseName_de_DE`, whereas those shared by all German-speaking countries go into `baseName_de`. In general, use

```
baseName_language_country
```

for all country-specific resources, and

```
baseName_language
```

for all language-specific resources. Finally, as a fallback, you can put defaults into a file without any suffix.

To load a bundle, use the command

```
ResourceBundle currentResources = ResourceBundle.getB
```

The `getBundle` method attempts to load the bundle that matches the current locale by language and country. If it is not successful, the country and the language are dropped in turn. Then the same search is applied to the default locale, and, finally, the default bundle file is consulted. If even that attempt fails, the method throws a `MissingResourceException`.

That is, the `getBundle` method tries to load the following bundles:

```
baseName_currentLocaleLanguage_currentLocaleCountry
baseName_currentLocaleLanguage
baseName_defaultLocaleLanguage_defaultLocaleCountry
baseName_defaultLocaleLanguage
baseName
```

Once the `getBundle` method has located a bundle (say, `baseName_de_DE`), it will still keep looking for `baseName_de` and `baseName`. If these bundles exist, they become the parents of the `baseName_de_DE` bundle in a resource hierarchy. Later, when looking up a resource, the parents are searched if a lookup was not

successful in the current bundle. That is, if a particular resource was not found in `baseName_de_DE`, then the `baseName_de` and `baseName` will be queried as well.

This is clearly a very useful service—and one that would be tedious to program by hand. The resource bundle mechanism of the Java programming language automatically locates the items that are the best match for a given locale. It is easy to add more and more localizations to an existing program—all you have to do is create additional resource bundles.

Note: If a locale has a script or variant, the lookup is quite a bit more complex. See the documentation of the method `ResourceBundle.Control.getCandidateLocales` for the gory details.



Tip: You need not place all resources for your application into a single bundle. You could have one bundle for button labels, one for error messages, and so on.

1.8.2. Property Files

Internationalizing strings is quite straightforward. You place all your strings into a property file such as `MyProgramStrings.properties`. This is simply a text file with one key/value pair per line. A typical file would look like this:

```
computeButton=Rechnen
colorName=black
defaultPaperSize=210×297
```

Then you name your property files as described in the preceding section, for example:

```
MyProgramStrings.properties
MyProgramStrings_en.properties
MyProgramStrings_de_DE.properties
```

You can load the bundle simply as

```
ResourceBundle bundle = ResourceBundle.getBundle("MyP
```

To look up a specific string, call

```
String computeButtonLabel = bundle.getString("compute
```

Property files are encoded as UTF-8.

Caution: Before Java 9, files for storing properties had to be ASCII files and non-ASCII characters had to be encoded using the `\uxxxx` notation. For example, `"colorName=Grün"` had to be specified as:

```
colorName=Gr\u00FCn
```

1.8.3. Bundle Classes

To provide resources that are not strings, define classes that extend the `ResourceBundle` class. Use the standard naming convention to name your classes, for example

```
MyProgramResources.java
MyProgramResources_en.java
MyProgramResources_de_DE.java
```

Load the class with the same `getBundle` method that you use to load a property file:

```
ResourceBundle bundle = ResourceBundle.getBundle("MyP
```

Caution: When searching for bundles, a bundle in a class is given preference over a property file when the two bundles have the same base names.

Each resource bundle class implements a lookup table. You need to provide a key string for each setting you want to localize, and use that key string to retrieve the setting. For example,

```
var backgroundColor = (Color) bundle.getObject("backg
double[] paperSize = (double[]) bundle.getObject("def
```

The simplest way to implement resource bundle classes is to extend the `ListResourceBundle` class. The `ListResourceBundle` lets you place all your resources into an object array and then does the lookup for you. Follow this code outline:

```
public class baseName_language_country extends ListRes
{
   private static final Object[][] contents =
   {
      { key1, value2 },
      { key2, value2 },
      . . .
```

```
    }
    public Object[][] getContents() { return contents;
}
```

For example,

```
public class ProgramResources_de extends ListResource
{
    private static final Object[][] contents =
    {
        { "backgroundColor", Color.black },
        { "defaultPaperSize", new double[] { 210, 297 }
    }
    public Object[][] getContents() { return contents;
}
public class ProgramResources_en_US extends ListResou
{
    private static final Object[][] contents =
    {
        { "backgroundColor", Color.blue },
        { "defaultPaperSize", new double[] { 216, 279 }
    }
    public Object[][] getContents() { return contents;
}
```

Note: The paper sizes are given in millimeters. Everyone on the planet, with the exception of the United States and Canada, uses ISO 216 paper sizes. For more information, see https://www.cl.cam.ac.uk/~mgk25/iso-paper.html.

Alternatively, your resource bundle classes can extend the `ResourceBundle` class. Then you need to implement two methods, to enumerate all keys and to look up the value for a given key:

```
Enumeration<String> getKeys()
Object handleGetObject(String key)
```

The `getObject` method of the `ResourceBundle` class calls the `handleGetObject` method that you supply.

`java.util.ResourceBundle` **1.1**

- `static ResourceBundle getBundle(String baseName, Locale locale)`
- `static ResourceBundle getBundle(String baseName)`

load the resource bundle class with the given name, for the given locale or the default locale, and its parent classes. If the resource bundle classes are located in a package, the base name must

contain the full package name, such as `"intl.ProgramResources"`. The resource bundle classes must be `public` so that the `getBundle` method can access them.

- `Object getObject(String name)`
  looks up an object from the resource bundle or its parents.
- `String getString(String name)`
  looks up an object from the resource bundle or its parents and casts it as a string.
- `String[] getStringArray(String name)`
  looks up an object from the resource bundle or its parents and casts it as a string array.
- `Enumeration<String> getKeys()`
  returns an enumeration object to enumerate the keys of this resource bundle. It enumerates the keys in the parent bundles as well.
- `Object handleGetObject(String key)`
  should be overridden to look up the resource value associated with the given key if you define your own resource lookup mechanism.

1.9. A Complete Example

In this section, we apply the material of this chapter to localize a retirement calculator. The program calculates whether or not you are

saving enough money for your retirement. You enter your age, how much money you save every month, and so on (see Figure 7.4).



Figure 1.4: The retirement calculator in English

The text area and the graph show the balance of the retirement account for every year. If the numbers turn negative toward the later part of your life and the bars in the graph appear below the x axis, you need to do something—for example, save more money, postpone your retirement, die earlier, or be younger.

The retirement calculator works in three locales (English, German, and Chinese). Here are some of the highlights of the internationalization:

- The labels, buttons, and messages are translated into German and Chinese. You can find them in the classes `RetireResources_de` and `RetireResources_zh`. English is used as the fallback—see the `RetireResources` file.
- Whenever the locale changes, we reset the labels and reformat the contents of the text fields.
- The text fields handle numbers, currency amounts, and percentages in the local format.
- The computation field uses a `MessageFormat`. The format string is stored in the resource bundle of each language.
- Just to show that it can be done, we use different colors for the bar graph, depending on the language chosen by the user.

Figure 7.5 shows the output in German. To see Chinese characters (as in Figure 7.6), be sure you have Chinese fonts installed and configured with your Java runtime. Otherwise, Chinese characters will show up as "missing character" icons.

Listing 7.4 shows the code of a simplified text version, sadly without colors. Listing 7.5 is the property file for the English strings. The localized strings are in Listing 7.6 (German) and Listing 7.7 (Chinese).



Figure 1.5: The retirement calculator in German



Figure 1.6: The retirement calculator in Chinese

Listing 1.4 retire2/Retire.java

```
1  package retire2;
2
3  import java.text.*;
4  import java.util.*;
5
6  import util.Choices;
7
8  /**
9   * This program shows a retirement calculator.
10  * Chinese.
11  * @version 1.3 2023-11-07
12  * @author Cay Horstmann
13  */
14 public class Retire
15 {
16    public static void main(String[] args)
17    {
18       // Get locale
19       ResourceBundle bundle = ResourceBundle.ge
20       System.out.println(bundle.getString("lang
21       Scanner in = new Scanner(System.in);
22       Locale[] locales = { Locale.US, Locale.CH
23       Locale currentLocale = Choices.choose(in,
24
25       bundle = ResourceBundle.getBundle("retire
26
```

```
27        // Prompt for parameters
28        System.out.print(bundle.getString("saving
29        double savings = in.nextDouble();
30
31        System.out.print(bundle.getString("contri
32        double contributions = in.nextDouble();
33
34        System.out.print(bundle.getString("income
35        double income = in.nextDouble();
36
37        System.out.print(bundle.getString("curren
38        int currentAge = in.nextInt();
39
40        System.out.print(bundle.getString("retire
41        int retireAge = in.nextInt();
42
43        System.out.print(bundle.getString("deathA
44        int deathAge = in.nextInt();
45
46        System.out.print(bundle.getString("inflat
47        double inflationPercent = in.nextDouble()
48
49        System.out.print(bundle.getString("invest
50        double investPercent = in.nextDouble();
51
52        // Show values
53        var retireMsg = new MessageFormat("");
54        retireMsg.setLocale(currentLocale);
```

```
55          retireMsg.applyPattern(bundle.getString('
56
57          double balance = savings;
58          for (int year = currentAge; year <= deatl
59          {
60             Object[] msgArgs = { year, balance };
61             System.out.println(retireMsg.format(ms
62             if (year < retireAge) balance += contr
63             else balance -= income;
64             balance = balance * (1 + (investPercer
65          }
66       }
67    }
```

Listing 1.5 retire2/RetireStrings.properties

```
1  language=Language
2  computeButton=Compute
3  savings=Prior Savings
4  contributions=Annual Contribution
5  income=Retirement Income
6  currentAge=Current Age
7  retireAge=Retirement Age
8  deathAge=Life Expectancy
9  inflationPercent=Inflation
10 investPercent=Investment Return
11 retire=Age: {0,number} Balance: {1,number,curre
```

Listing 1.6 retire2/RetireStrings_de.properties

```
language=Sprache
computeButton=Rechnen
savings=Vorherige Ersparnisse
contributions=Jährliche Einzahlung
income=Einkommen nach Ruhestand
currentAge=Jetziges Alter
retireAge=Ruhestandsalter
deathAge=Lebenserwartung
inflationPercent=Inflation
investPercent=Investitionsgewinn
retire=Alter: {0,number} Guthaben: {1,number,cu
```

Listing 1.7 retire2/RetireStrings_zh.properties

```
language=语言
computeButton=计算
savings=既存
contributions=每年存金
income=退休收入
currentAge=现龄
retireAge=退休年龄
deathAge=预期寿命
```

```
9  inflationPercent=通货膨涨
10 investPercent=投资报酬
11 retire=年龄: {0,number} 总结: {1,number,currenc
```

You have seen how to use the internationalization features of the Java language. You can now use resource bundles to provide translations into multiple languages, and use formatters and collators for locale-specific text processing.

In the next chapter, we will delve into scripting and compiling.

1. Compiling and Scripting

This chapter introduces two techniques for processing code. You can use the compiler API when you want to compile Java code inside your application. The scripting API lets you invoke code in a scripting language such as JavaScript or Groovy.

1.1. The Compiler API

There are quite a few tools that need to compile Java code. Obviously, development environments and programs that teach Java programming are among them, as well as testing and build automation tools. Another example is the processing of Jakarta Server Pages—web pages with embedded Java statements.

1.1.1. Invoking the Compiler

It is very easy to invoke the compiler. Here is a sample call:

```
JavaCompiler compiler = ToolProvider.getSystemJavaCom
OutputStream outStream = . . .;
OutputStream errStream = . . .;
int result = compiler.run(null, outStream, errStream,
   "-sourcepath", "src", "Test.java");
```

A `result` value of `0` indicates successful compilation.

The compiler sends its output and error messages to the provided streams. You can set these arguments to `null`, in which case `System.out` and `System.err` are used. The first argument of the `run` method is an input stream. As the compiler takes no console input, you can always leave it as `null`. (The `run` method is inherited from the generic `javax.tools.Tool` interface, which allows for tools that read input.)

The remaining arguments of the `run` method are the arguments that you would pass to `javac` if you invoked it on the command line. These can be options or file names.

1.1.2. Launching a Compilation Task

You can have more control over the compilation process with a `CompilationTask` object. This can be useful if you want to supply source from string, capture class files in memory, or process the error and warning messages.

To obtain a `CompilationTask`, start with a `compiler` object as in the preceding section. Then call

```
JavaCompiler.CompilationTask task = compiler.getTask(
   errorWriter, // Uses System.err if null
   fileManager, // Uses the standard file manager if
   diagnosticListener, // Uses System.err if null
   options, // null if no options
   classes, // For annotation processing; null if non
   sources);
```

The last three arguments are `Iterable` instances. For example, a sequence of options might be specified as

```
Iterable<String> options = List.of("-d", "bin");
```

The `sources` parameter is an `Iterable` of `JavaFileObject` instances. If you want to compile disk files, get a `StandardJavaFileManager` and call its `getJavaFileObjects` method:

```
StandardJavaFileManager stdFileManager = compiler.get
Iterable<JavaFileObject> sources
   = stdFileManager.getJavaFileObjectsFromStrings(Lis
JavaCompiler.CompilationTask task = compiler.getTask(
   null, null, null, options, null, sources);
```

Note: The `classes` parameter is only used for annotation processing. In that case, you also need to call `task.processors(annotationProcessors)` with a list of `Processor` objects. See Chapter 11 of Volume I for an example of annotation processing.

The `getTask` method returns the task object but does not yet start the compilation process. The `CompilationTask` class extends `Callable<Boolean>`. You can submit it to an `ExecutorService` for concurrent execution, or you can just make a synchronous call:

```
Boolean result = task.call();
```

1.1.3. Capturing Diagnostics

To listen to error messages, install a `DiagnosticListener`. The listener receives a `Diagnostic` object whenever the compiler reports a warning or error message. The `DiagnosticCollector` class implements this interface. It simply collects all diagnostics so that you can iterate through them after the compilation is complete.

```
var collector = new DiagnosticCollector<JavaFileObjec
compiler.getTask(null, fileManager, collector, null,
for (Diagnostic<? extends JavaFileObject> d : collect
```

```
   {
      System.out.println(d);
   }
```

A `Diagnostic` object contains information about the problem location (including file name, line number, and column number) as well as a human-readable description.

You can also install a `DiagnosticListener` to the standard file manager, in case you want to trap messages about missing files:

```
StandardJavaFileManager stdFileManager
   = compiler.getStandardFileManager(diagnosticsListe
```

1.1.4. Reading Source Files from Memory

If you generate source code on the fly, you can have it compiled from memory, without having to save files to disk. Use this class to hold the code:

```
public class StringSource extends SimpleJavaFileObjec
{
   private String code;

   StringSource(String name, String code)
```

```
    {
       super(URI.create("string:///" + name.replace(".
       this.code = code;
     }

    public CharSequence getCharContent(boolean ignoreE
    {
       return code;
    }
 }
```

Then generate the code for your classes and give the compiler a list of `StringSource` objects:

```
 List<StringSource> sources = List.of(
    new StringSource(className1, class1CodeString),
    new StringSource(className2, class2CodeString),
    . . .);
 task = compiler.getTask(null, fileManager, diagnostic
```

1.1.5. Writing Byte Codes to Memory

If you compile classes on the fly, there is no need to save the class files to disk. You can save them to memory and load them right away.

First, here is a class for holding the bytes:

```
public class ByteArrayClass extends SimpleJavaFileObj
{
   private ByteArrayOutputStream out;

   ByteArrayClass(String name)
   {
      super(URI.create("bytes:///" + name.replace("."
   }

   public byte[] getCode()
   {
      return out.toByteArray();
   }

   public OutputStream openOutputStream() throws IOEx
   {
      out = new ByteArrayOutputStream();
      return out;
   }
}
```

Next, you need to configure the file manager to use these classes for output:

```
var classes = new ArrayList<ByteArrayClass>();
StandardJavaFileManager stdFileManager
   = compiler.getStandardFileManager(null, null, null
JavaFileManager fileManager
   = new ForwardingJavaFileManager<>(stdFileManager)
      {
         public JavaFileObject getJavaFileForOutput(L
               String className, Kind kind, FileObjec
               throws IOException
         {
            if (kind == Kind.CLASS)
            {
               ByteArrayClass outfile = new ByteArray
               classes.add(outfile);
               return outfile;
            }
            else
               return super.getJavaFileForOutput(loca
         }
      };
```

To load the classes, you need a class loader (see Chapter 9):

```
public class ByteArrayClassLoader extends ClassLoader
{
   private Iterable<ByteArrayClass> classes;
```

```
    public ByteArrayClassLoader(Iterable<ByteArrayClas
    {
       this.classes = classes;
    }

    public Class<?> findClass(String name) throws Clas
    {
       for (ByteArrayClass cl : classes)
       {
          if (cl.getName().equals("/" + name.replace("
          {
             byte[] bytes = cl.getCode();
             return defineClass(name, bytes, 0, bytes.
          }
       }
       throw new ClassNotFoundException(name);
    }
 }
```

After compilation has finished, call the `Class.forName` method with that class loader:

```
 ByteArrayClassLoader loader = new ByteArrayClassLoade
 Class<?> cl = Class.forName(className, true, loader);
```

1.1.6. An Example: Dynamic Java Code Generation

In the Jakarta Server Pages (JSP) technology for dynamic web pages, you can mix HTML with snippets of Java code, for example:

```
<p>The current date and time is <b><%= LocalDateTime.
```

The JSP engine dynamically compiles the Java code into a servlet. In our sample application, we use a simpler example and generate code for a very simple worksheet format. Authors include text, Java expressions (enclosed in backticks), and Java statements (enclosed in triple backticks) into a worksheet. The worksheet is compiled into a Java class that prints the text and the values of the expressions, and executes the Java statements. Here is a sample worksheet:

````
What is your name?
```
var in = new Scanner(System.in);
String name = in.nextLine();
```
How old are you?
```
````
````

```
int age = in.nextInt();
```

Hello, `name`! Next year, you will be `age + 1`.
```

This is a very minimal text version of a programming notebook (https://docs.jupyter.org/en/latest/#what-is-a-notebook). The sheet is translated into a class whose `main` method has print statements to emit the text and expression values. The statements are included verbatim. One can envision an enhancement of this program that displays images and tables, just like a real programming notebook.

The `buildSource` method in the program of Listing 8.1 builds up this code and places it into a `StringSource` object. That object is passed to the Java compiler.

As described in the preceding section, we use a `ForwardingJavaFileManager` that constructs a `ByteArrayClass` object for every compiled class. These objects capture the class file that is generated when the class is compiled. After compilation, we use the class loader from the preceding section to load the class and execute its `main` method.

This example demonstrates how you can use dynamic compilation with in-memory source and class files.
```

Listing 1.1 compiler/CompilerTest.java

```
1  package compiler;
2
3  import java.io.*;
4  import java.nio.file.*;
5  import java.util.*;
6  import java.util.List;
7
8  import javax.tools.*;
9  import javax.tools.JavaFileObject.*;
10
11 /**
12  * @version 1.2 2023-08-16
13  * @author Cay Horstmann
14  */
15 public class CompilerTest
16 {
17    public static void main(final String[] args)
18          throws IOException, ReflectiveOperatio
19    {
20       JavaCompiler compiler = ToolProvider.getS
21
22       var classFileObjects = new ArrayList<Byte
23
24       var diagnosticsListener = new DiagnosticC
25
26       JavaFileManager fileManager = compiler.ge
```

```
27        fileManager = new ForwardingJavaFileManag
28           {
29              public JavaFileObject getJavaFileFo
30                    String className, Kind kind,
31              {
32                 if (kind == Kind.CLASS)
33                 {
34                    var fileObject = new ByteArra
35                    classFileObjects.add(fileObje
36                    return fileObject;
37                 }
38                 else return super.getJavaFileFor
39              }
40           };
41
42
43        String mainClassName = "compiler.Main";
44        String worksheetName = args.length > 0 ?
45
46        StandardJavaFileManager stdFileManager =
47        var sources = new ArrayList<JavaFileObjec
48        for (JavaFileObject file : stdFileManager
49              List.of(mainClassName.replace(".",
50           sources.add(file);
51
52        JavaFileObject source = buildSource(mainC
53        JavaCompiler.CompilationTask task = compi
54           null, null, List.of(source));
```

```
55          Boolean result = task.call();
56
57          for (Diagnostic<? extends JavaFileObject>
58             System.out.println(d.getKind() + ": "
59          fileManager.close();
60          if (!result)
61          {
62             System.out.println("Compilation failed
63             System.exit(1);
64          }
65
66          var loader = new ByteArrayClassLoader(cla
67          Class<?> mainClass = loader.loadClass(mai
68          mainClass.getMethod("main", String[].clas
69       }
70
71       /**
72        * Builds the source for the class that impl
73        * @param className the name of the class to
74        * @param worksheet the file containing the
75        * @return a file object containing the sour
76        */
77       static JavaFileObject buildSource(String cla
78             throws IOException
79       {
80          var builder = new StringBuilder();
81          int n = className.lastIndexOf(".");
82          if (n >= 0)
```

```
83          {
84             String packageName = className.substri
85             className = className.substring(n + 1)
86             builder.append("package ").append(pack
87          }
88          builder.append("import java.util.Scanner;
89          builder.append("public class ").append(cl
90          builder.append("public static void main(S
91          boolean verbatim = false;
92          for (String line : Files.readAllLines(wor
93          {
94             if (line.equals("```")) verbatim = !ve
95             else if (verbatim) builder.append(line
96             else
97             {
98                String[] fragments = line.split("`"
99                for (int i = 0; i < fragments.lengt
100               {
101                  builder.append("System.out.print
102                  if (i % 2 == 0)
103                     builder.append("\"")
104                        .append(fragments[i].repla
105                        .append("\"");
106                  else
107                     builder.append(fragments[i]);
108                  builder.append(");\n");
109               }
110               builder.append("System.out.println(
```

```
111             }
112         }
113 
114         builder.append("} }\n");
115         return new StringSource(className, builde
116     }
117 }
```

javax.tools.Tool **6**

- `int run(InputStream in, OutputStream out, OutputStream err, String... arguments)`
  runs the tool with the given input, output, and error streams and the given arguments. Returns `0` for success, a nonzero value for failure.

javax.tools.JavaCompiler **6**

- `StandardJavaFileManager getStandardFileManager(DiagnosticListener<? super JavaFileObject> diagnosticListener, Locale locale, Charset charset)`
  gets the standard file manager for this compiler. You can supply `null` for default error reporting, locale, and character set.
- `JavaCompiler.CompilationTask getTask(Writer out, JavaFileManager fileManager, DiagnosticListener<?`

`super JavaFileObject> diagnosticListener, Iterable<String> options, Iterable<String> classesForAnnotationProcessing, Iterable<? extends JavaFileObject> sourceFiles)`

gets a compilation task that, when called, will compile the given source files. See the discussion in the preceding section for details.

javax.tools.StandardJavaFileManager **6**

- `Iterable<? extends JavaFileObject> getJavaFileObjectsFromStrings(Iterable<String> fileNames)`
- `Iterable<? extends JavaFileObject> getJavaFileObjectsFromPaths(Collection<? extends Path> paths)` **13**
- `Iterable<? extends JavaFileObject> getJavaFileObjectsFromFiles(Iterable<? extends File> files)`

  translate a sequence of file names or files into a sequence of `JavaFileObject` instances.

javax.tools.JavaCompiler.CompilationTask 6

- `Boolean call()`
  performs the compilation task.

`javax.tools.DiagnosticCollector<S>` 6

- `DiagnosticCollector()`
  constructs an empty collector.
- `List<Diagnostic<? extends S>> getDiagnostics()`
  gets the collected diagnostics.

javax.tools.Diagnostic<S> 6

- `S getSource()`
  gets the source object associated with this diagnostic.
- `Diagnostic.Kind getKind()`
  gets the type of this diagnostic—one of `ERROR`, `WARNING`, `MANDATORY_WARNING`, `NOTE`, or `OTHER`.
- `String getMessage(Locale locale)`
  gets the message describing the issue raised in this diagnostic. Pass `null` for the default locale.
- `long getLineNumber()`
- `long getColumnNumber()`
  get the position of the issue raised in this diagnostic.

`javax.tools.SimpleJavaFileObject` 6

- `CharSequence getCharContent(boolean ignoreEncodingErrors)`
  override this method for a file object that represents a source file and produces the source code.
- `OutputStream openOutputStream()`
  override this method for a file object that represents a class file and produces a stream to which the bytecodes can be written.

`javax.tools.ForwardingJavaFileManager<M extends JavaFileManager>` 6

- `protected ForwardingJavaFileManager(M fileManager)`
  constructs a `JavaFileManager` that delegates all calls to the given file manager.
- `FileObject getJavaFileForOutput(JavaFileManager.Location location, String className, JavaFileObject.Kind kind, FileObject sibling)`
  Intercept this call if you want to substitute a file object for writing class files; `kind` is one of `SOURCE`, `CLASS`, `HTML`, or `OTHER`.

1.2. Scripting for the Java Platform

A scripting language is a language that avoids the usual edit/compile/link/run cycle by interpreting the program text at runtime. Scripting languages have a number of advantages:

- Rapid turnaround, encouraging experimentation
- Changing the behavior of a running program
- Enabling customization by program users

On the other hand, most scripting languages lack features that are beneficial for programming complex applications, such as strong typing, encapsulation, and modularity.

It is therefore tempting to combine the advantages of scripting and traditional languages. The scripting API lets you do just that for the Java platform. It enables you to invoke scripts written in JavaScript, Groovy, Ruby, and even exotic languages such as Scheme and Haskell, from a Java program. For example, the Renjin project (https://www.renjin.org) provides a Java implementation of the R programming language, which is commonly used for statistical programming, together with an "engine" of the scripting API.

When looking for a compatible implementation of your favorite language, search for JSR 223 support. (Java Specification Request 223 developed the scripting API before it was integrated into Java.)

The JMeter performance analysis tool (https://jmeter.apache.org/) is an example of a program that allows users to write scripts in any language with Java scripting support. The Maven build tool has a plugin (https://maven.apache.org/plugins/maven-scripting-plugin/index.html) for writing build steps in any language that has a Java scripting engine.

In the following sections, I'll show you how to select an engine for a particular language, how to execute scripts, and how to make use of advanced features that some scripting engines offer.

1.2.1. Getting a Scripting Engine

A scripting engine is a library that can execute scripts in a particular language. When the virtual machine starts, it discovers the available scripting engines. To enumerate them, construct a `ScriptEngineManager` and invoke the `getEngineFactories` method. You can ask each engine factory for the supported engine names, MIME types, and file extensions. Table 8.1 shows typical values.

The examples in this chapter use the Rhino scripting engine, available at https://github.com/mozilla/rhino, that implements an ancient version of JavaScript.

Table 1.1: Properties of Scripting Engine Factories

Engine	Names	MIME Types	Exte
Rhino (JavaScript)	rhino, Rhino, JavaScript, javascript	`application/javascript`, `application/ecmascript`, `text/javascript`, `text/ecmascript`	`js`
Groovy	groovy	None	`gro`
Renjin	Renjin	`text/x-R`	`R`, `s`

Usually, you know which engine you need, and you can simply request it by name, MIME type, or extension. For example:

```
var manager = new ScriptEngineManager();
ScriptEngine engine = manager.getEngineByName("rhino"
```

You need to provide the JAR files that implement the script engine on the classpath.

Note: The Oracle JDK used to contain a JavaScript engine called Nashorn, but it has been removed in Java

15. It is available as a standalone project at https://github.com/openjdk/nashorn.

`javax.script.ScriptEngineManager` 6

- `List<ScriptEngineFactory> getEngineFactories()`
  gets a list of all discovered engine factories.
- `ScriptEngine getEngineByName(String name)`
- `ScriptEngine getEngineByExtension(String extension)`
- `ScriptEngine getEngineByMimeType(String mimeType)`
  get the script engine with the given name, script file extension, or MIME type.

javax.script.ScriptEngineFactory 6

- `List<String> getNames()`
- `List<String> getExtensions()`
- `List<String> getMimeTypes()`
  get the names, script file extensions, and MIME types under which this factory is known.

1.2.2. Script Evaluation and Bindings

Once you have an engine, you can call a script simply by invoking

```
Object result = engine.eval(scriptString);
```

If the script is stored in a file, open a `Reader` and call

```
Object result = engine.eval(reader);
```

You can invoke multiple scripts on the same engine. If one script defines variables, functions, or classes, most scripting engines retain the definitions for later use. For example,

```
engine.eval("n = 1728");
Object result = engine.eval("n + 1");
```

will return `1729`.

Note: To find out whether it is safe to concurrently execute scripts in multiple threads, call

```
Object param = factory.getParameter("THREA
```

The returned value is one of the following:

- `null`: Concurrent execution is not safe.

- `"MULTITHREADED"` : Concurrent execution is safe. Effects from one thread might be visible from another thread.
- `"THREAD-ISOLATED"` : In addition to `"MULTITHREADED"` , different variable bindings are maintained for each thread.
- `"STATELESS"` : In addition to `"THREAD-ISOLATED"` , scripts do not alter variable bindings.

You will often want to add variable bindings to the engine. A binding consists of a name and an associated Java object. For example, consider these statements:

```
engine.put("k", 1728);
Object result = engine.eval("k + 1");
```

The script code reads the definition of `k` from the bindings in the "engine scope." This is particularly important because most scripting languages can access Java objects, often with a syntax that is simpler than the Java syntax. For example,

```
engine.put("d", LocalDate.now());
```

```
Object result = engine.eval("d.month"); // calls getM
```

Conversely, you can retrieve variables that were bound by scripting statements:

```
engine.eval("n = 1728");
Object result = engine.get("n");
```

In addition to the engine scope, there is also a global scope. Any bindings that you add to the `ScriptEngineManager` are visible to all engines.

Instead of adding bindings to the engine or global scope, you can collect them in an object of type `Bindings` and pass it to the `eval` method:

```
Bindings scope = engine.createBindings();
scope.put("d", LocalDate.now());
engine.eval(scriptString, scope);
```

This is useful if a set of bindings should not persist for future calls to the `eval` method.

Note: You might want to have scopes other than the engine and global scopes. For example, a web

container might need request and session scopes. However, then you are on your own. You will need to write a class that implements the `ScriptContext` interface, managing a collection of scopes. Each scope is identified by an integer number, and scopes with lower numbers should be searched first. (The standard library provides a `SimpleScriptContext` class, but it only holds global and engine scopes.)

---

javax.script.ScriptEngine **6**

- `Object eval(String script)`
- `Object eval(Reader reader)`
- `Object eval(String script, Bindings bindings)`
- `Object eval(Reader reader, Bindings bindings)`

evaluate the script given by the string or reader, subject to the given bindings.

- `Object get(String key)`
- `void put(String key, Object value)`

get or put a binding in the engine scope.

- `Bindings createBindings()`

creates an empty `Bindings` object suitable for this engine.

`javax.script.ScriptEngineManager` 6

- `Object get(String key)`
- `void put(String key, Object value)`

get or put a binding in the global scope.

javax.script.Bindings 6

- `Object get(String key)`
- `void put(String key, Object value)`

get or put a binding into the scope represented by this `Bindings` object.

1.2.3. Redirecting Input and Output

You can redirect the standard input and output of a script by calling the `setReader` and `setWriter` methods of the script context. For example,

```
var writer = new StringWriter();
engine.getContext().setWriter(new PrintWriter(writer,
```

Any output written with the JavaScript `print` or `println` functions is sent to `writer`.

The `setReader` and `setWriter` methods only affect the scripting engine's standard input and output sources. For example, if you execute the JavaScript code

```
println("Hello");
java.lang.System.out.println("World");
```

only the first output is redirected.

The Rhino engine does not have the notion of a standard input source. Calling `setReader` has no effect.

javax.script.ScriptEngine **6**

- `ScriptContext getContext()`
  gets the default script context for this engine.

javax.script.ScriptContext 6

- `Reader getReader()`
- `void setReader(Reader reader)`
- `Writer getWriter()`
- `void setWriter(Writer writer)`
- `Writer getErrorWriter()`
- `void setErrorWriter(Writer writer)`

  get or set the reader for input or writer for normal or error output.

1.2.4. Calling Scripting Functions and Methods

With some script engines, you can invoke a scripting language function directly in your Java code, without having to evaluate a script code snippet that makes the call. This is useful if you allow users to implement a service in a scripting language of their choice, so that you can call it from Java.

The script engines that offer this functionality implement the `Invocable` interface. In particular, the Rhino engine implements `Invocable`.

To call a function, call the `invokeFunction` method with the function name, followed by the function arguments:

```
// Define greet function in JavaScript
engine.eval("function greet(how, whom) { return how +

// Call the function with arguments "Hello", "World"
result = ((Invocable) engine).invokeFunction("greet",
```

If the scripting language is object-oriented, call `invokeMethod`:

```
// Define Greeter class in JavaScript
engine.eval("""
function Greeter(how) { this.how = how }
Greeter.prototype.welcome =
   function (whom) { return this.how + ', ' + whom +
""");

// Construct an instance
Object yo = engine.eval("new Greeter('Yo')");

// Call the welcome method on the instance
result = ((Invocable) engine).invokeMethod(yo, "World
```

Note: Rhino does not support the modern JavaScript class syntax. For more information on how to define classes in JavaScript the old-fashioned way, see

JavaScript—The Good Parts by Douglas Crockford (O'Reilly, 2008).

Note: If the script engine does not implement the `Invocable` interface, you might still be able to call a method in a language-independent way. The `getMethodCallSyntax` method of the `ScriptEngineFactory` interface produces a string that you can pass to the `eval` method. For this, however, all method parameters must be bound to names, whereas `invokeMethod` can be called with arbitrary values.

You can go a step further and ask the scripting engine to implement a Java interface. Then you can call scripting functions and methods with the Java method call syntax.

The details depend on the scripting engine, but typically you need to supply a function for each method of the interface. For example, consider a Java interface

```
public interface Greeter
{
   String welcome(String whom);
```

```
}
```

If you define a global function with the same name in Rhino, you can call it through this interface:

```
// Define welcome function in JavaScript
engine.eval("function welcome(whom) { return 'Hello,

// Get a Java object and call a Java method
Greeter g = ((Invocable) engine).getInterface(Greeter
result = g.welcome("World");
```

In an object-oriented scripting language, you can access a script class through a matching Java interface. For example, here is how to call an object of the JavaScript `Greeter` class with Java syntax:

```
Greeter g = ((Invocable) engine).getInterface(yo, Gre
result = g.welcome("World");
```

In summary, the `Invocable` interface is useful if you want to call scripting code from Java without worrying about the scripting language syntax.

javax.script.Invocable 6

- `Object invokeFunction(String name, Object... args)`
- `Object invokeMethod(Object thiz, String name, Object... args)`
  invoke the function or method with the given name, passing the given arguments.
- `<T> T getInterface(Class<T> clasz)`
  returns an implementation of the given interface, implementing the methods with functions in the scripting engine.
- `<T> T getInterface(Object thiz, Class<T> clasz)`
  returns an implementation of the given interface, implementing the methods with the methods of the given object.

1.2.5. Compiling a Script

Some scripting engines can compile scripting code into an intermediate form for efficient execution. Those engines implement the `Compilable` interface. The following example shows how to compile and evaluate code contained in a script file:

```
if (engine instanceof Compilable compilableEngine) {
   Reader reader = Files.newBufferedReader(path);
   CompiledScript script = compilableEngine.compile(r
```

```
    script.eval();
}
```

Of course, it only makes sense to compile a script if you need to execute it repeatedly.

javax.script.Compilable 6

- `CompiledScript compile(String script)`
- `CompiledScript compile(Reader reader)`

compile the script given by a string or reader.

`javax.script.CompiledScript` 6

- `Object eval()`
- `Object eval(Bindings bindings)`

evaluate this script.

1.2.6. An Example: Script Sheets

Have a look at the program in Listing 8.2 that executes a sheet in the same format as the example in Section 8.1.6. However, this time, the code is in a scripting language, and it is evaluated when the program runs.

The classpath must contain a scripting engine. Start the program like this:

```
java -classpath .:engineDir/\* ScriptTest engineName sh
```

For example,

```
java -classpath .:rhino/\* script.ScriptTest rhino sc
```

Listing 1.2 script/ScriptTest.java

```
1  package script;
2
3  import java.io.*;
4  import java.nio.file.*;
5  import javax.script.*;
6
7  /**
8   * @version 1.1 2023-08-17
9   * @author Cay Horstmann
10  *
11
12 Download Rhino and the Rhino engine JAR from
13 https://mvnrepository.com/artifact/org.mozilla/
14 https://mvnrepository.com/artifact/org.mozilla/
```

```
Place in a directory rhino

javac script/ScriptTest.java
java --classpath .:rhino/\* script.ScriptTest r

 */
public class ScriptTest
{
   public static void main(String[] args) throw
   {
      var manager = new ScriptEngineManager();
      String language;
      if (args.length == 0)
      {
         System.out.println("Available factorie
         for (ScriptEngineFactory factory : mar
            System.out.println(factory.getEngir
         return;
      }
      else language = args[0];

      ScriptEngine engine = manager.getEngineBy
      if (engine == null)
      {
         System.err.println("No engine for " +
         System.exit(1);
      }

```

1. Security

When Java technology first appeared on the scene, the excitement was not about a well-crafted programming language but about the possibility of safely executing applets delivered over the Internet. Obviously, serving executable applets is only practical when the recipients can be sure the code won't wreak havoc on their machines. Security therefore was and is a major concern of both the designers and the users of Java technology. This means that unlike other languages and systems, where security was implemented as an afterthought or as a reaction to break-ins, security mechanisms are an integral part of Java technology.

The security architecture was composed of three parts:

1. Language and virtual machine design features (bounds checking on arrays, no unchecked type conversions, no pointer arithmetic, and so on).
2. A *security manager* that controls what the code can do (file access, network access, and so on).
3. Code signing, whereby code authors can use standard cryptographic algorithms to authenticate Java code. Then, the users of the code can determine exactly who created the code and ensure that the code has not been altered after it was signed.

The first part has been a resounding success. C++ programs are routinely vulnerable to attacks such as buffer overruns, but Java provides strong protection. Unfortunately, the other two parts have not fared as well. The security manager was complex and had a large attack surface. It is being deprecated as of Java 17. The code signing architecture was effectively abandoned with the demise of applets and Java Web Start—two mechanisms for the secure delivery of client-side applications.

In previous editions of this book, the security manager and code signing were the highlights of this chapter, but obviously the need for such coverage has gone away. We will first discuss *class loaders* that check class files for integrity when they are loaded into the virtual machine. I will demonstrate how that mechanism can detect tampering with class files. Then, you'll learn about an authentication framework and cryptographic algorithms which are useful for many security-related operations.

1.1. Class Loaders

A Java compiler converts source instructions into code for the Java virtual machine. The virtual machine code is stored in a class file with a `.class` extension. Each class file contains the definition and implementation code for one class or interface. In the following section, you will see how the virtual machine loads these class files.

1.1.1. The Class-Loading Process

The virtual machine loads only those class files that are needed for the execution of a program. For example, suppose program execution starts with `MyProgram.class`. Here are the steps that the virtual machine carries out:

1. The virtual machine has a mechanism for loading class files—for example, by reading the files from disk or by requesting them from the Web; it uses this mechanism to load the contents of the `MyProgram` class file.
2. If the `MyProgram` class has fields or superclasses of another class type, their class files are loaded as well. (The process of loading all the classes that a given class depends on is called *resolving* the class.)
3. The virtual machine then executes the `main` method in `MyProgram`.
4. If the `main` method or a method that `main` calls requires additional classes, these are loaded next.

The class loading mechanism doesn't just use a single class loader, however. Every Java program has at least three class loaders:

- The bootstrap class loader
- The platform class loader

- The system class loader (sometimes called the application class loader)

The bootstrap class loader loads the platform classes contained in the modules

```
java.base
java.datatransfer
java.desktop
java.instrument
java.logging
java.management
java.management.rmi
java.naming
java.prefs
java.rmi
java.security.sasl
java.xml
```

as well as a number of JDK-internal modules.

There is no `ClassLoader` object corresponding to the bootstrap class loader. For example,

```
StringBuilder.class.getClassLoader()
```

returns `null`.

Prior to Java 9, the Java platform classes were located in a file `rt.jar`. Nowadays, the Java platform is modular, and each platform module is contained in a JMOD file (see Chapter 9 of Volume I). The platform class loader loads all classes of the Java platform that are not loaded by the bootstrap class loader.

The system class loader loads application classes from the module path and class path.

Note: Prior to Java 9, an "extension class loader" loaded "standard extensions" from the `jre/lib/ext` directory, and an "endorsed standards override" mechanism provided a way of overriding certain platform classes (including the CORBA and XML implementations) with newer versions. Both of these mechanisms have been removed.

1.1.2. The Class Loader Hierarchy

Class loaders have a *parent/child* relationship. Every class loader except for the bootstrap one has a parent class loader. A class loader will give its parent a chance to load any given class and will only load it if the parent has failed. For example, when the system class

loader is asked to load a platform class (say, `java.lang.StringBuilder`), it first asks the platform class loader. That class loader first asks the bootstrap class loader. The bootstrap class loader finds and loads the class, so neither of the other class loaders searches any further.

Some programs have a plugin architecture in which certain parts of the code are packaged as optional plugins. If the plugins are packaged as JAR files, you can simply load the plugin classes with an instance of `URLClassLoader`.

```
var url = new URL("file:///path/to/plugin.jar");
var pluginLoader = new URLClassLoader(new URL[] { url
Class<?> cl = pluginLoader.loadClass("mypackage.MyCla
```

Since no parent was specified in the `URLClassLoader` constructor, the parent of the `pluginLoader` is the system class loader. Figure 9.1 shows the hierarchy.



Figure 1.1: The class loader hierarchy

Caution: Prior to Java 9, the system class loader was an instance of `URLClassLoader`. Some programmers used a cast to access the `getURLs` method, or added JAR files to the class path by calling the

protected `addURLs` method through reflection. This is no longer possible.

Most of the time, you don't have to worry about the class loader hierarchy. Generally, classes are loaded because they are required by other classes, and that process is transparent to you.

Occasionally, however, you need to intervene and specify a class loader. Consider this example:

- Your application code contains a helper method that calls `Class.forName(classNameString)`.
- That method is called from a plugin class.
- The `classNameString` specifies a class that is contained in the plugin JAR.

The author of the plugin wants the class to be loaded. However, the helper method's class was loaded by the system class loader, and that is the class loader used by `Class.forName`. The classes in the plugin JAR are not visible. This phenomenon is called *classloader inversion*.

To overcome this problem, the helper method needs to use the correct class loader. It can require the class loader as a parameter. Alternatively, it can require that the correct class loader is set as the

context class loader of the current thread. This strategy is used by many frameworks (such as JAXP and JNDI).

Each thread has a reference to a class loader, called the context class loader. The main thread's context class loader is the system class loader. When a new thread is created, its context class loader is set to the creating thread's context class loader. Thus, if you don't do anything, all threads will have their context class loaders set to the system class loader.

However, you can set any class loader by calling

```
Thread t = Thread.currentThread();
t.setContextClassLoader(loader);
```

The helper method can then retrieve the context class loader:

```
Thread t = Thread.currentThread();
ClassLoader loader = t.getContextClassLoader();
Class<?> cl = loader.loadClass(className);
```

Tip: If you write a method that loads a class by name, it is a good idea to offer the caller the choice between passing an explicit class

loader and using the context class loader. Don’t simply use the class loader of the method’s class.

1.1.3. Using Class Loaders as Namespaces

Every Java programmer knows that package names are used to eliminate name conflicts. There are two classes called `Date` in the standard library, but of course their real names are `java.util.Date` and `java.sql.Date`. The simple name is only a programmer convenience and requires the inclusion of appropriate `import` statements. In a running program, all class names contain their package names.

It might surprise you, however, that you can have two different classes in the same virtual machine that have the same class *and package* name. A class is determined by its full name *and* the class loader. This technique is useful for loading code from multiple sources. For example, an application server uses separate class loaders for each application. This allows the virtual machine to separate classes from different applications, no matter what they are named. Figure 9.2 shows an example. Suppose an application server loads two different applications, and each has a class called `Util`. Since each class is loaded by a separate class loader, these classes are entirely distinct and do not conflict with each other.


Bootstrap
class loader
Platform
class loader
System
class loader
class loader
for
application #1
class loader
for
application #2
Util.class
Util.class

Figure 1.2: Two class loaders load different classes with the same name.

1.1.4. Writing Your Own Class Loader

You can write your own class loader for specialized purposes. That lets you carry out custom checks before you pass the bytecodes to the virtual machine. For example, your class loader may refuse to load a class that has not been marked as "paid for."

To write your own class loader, simply extend the `ClassLoader` class and override the method

```
findClass(String className)
```

The `loadClass` method of the `ClassLoader` superclass takes care of the delegation to the parent and calls `findClass` only if the class hasn't already been loaded and if the parent class loader was unable to load the class.

Your implementation of this method must do the following:

1. Load the bytecodes for the class from the local file system or some other source.
2. Call the `defineClass` method of the `ClassLoader` superclass to present the bytecodes to the virtual machine.

In the program of Listing 9.1, we implement a class loader that loads encrypted class files. The program asks the user for the name of the first class to load (that is, the class containing `main`) and the decryption key. It then uses a special class loader to load the specified class and calls the `main` method. The class loader decrypts the specified class and all nonsystem classes that are referenced by it. Finally, the program calls the `main` method of the loaded class.

For simplicity, we ignore the 2,000 years of progress in the field of cryptography and use the venerable Caesar cipher for encrypting the class files.

Note: David Kahn's wonderful book *The Codebreakers* (Macmillan, 1967, p. 84) refers to Suetonius as a historical source for the Caesar cipher. Caesar shifted the 24 letters of the Roman alphabet by 3 letters, which at the time baffled his adversaries.

When this chapter was first written, the U.S. government restricted the export of strong encryption methods. Therefore, I used Caesar's method for my example because it was clearly legal for export.

Our version of the Caesar cipher has as a key a number between 1 and 255. To decrypt, simply add that key to every byte and reduce modulo 256. The `Caesar.java` program of Listing 9.2 carries out the encryption.

To not confuse the regular class loader, we use a different extension, `.caesar`, for the encrypted class files.

To decrypt, the class loader simply subtracts the key from every byte. In the companion code for this book, you will find four class files, encrypted with a key value of 3—the traditional choice. To run the encrypted program, you'll need the custom class loader defined in our `ClassLoaderTest` program.

Try out the program by running it with a class name of `Calculator` and a decryption key of `3`. A calculator will pop up. But if you use a different key, the class loader will throw an exception.

Encrypting class files has a number of practical uses (provided, of course, that you use something stronger than the Caesar cipher). Without the decryption key, the class files are useless. They can neither be executed by a standard virtual machine nor readily disassembled.

This means that you can use a custom class loader to authenticate the user of the class or to ensure that a program has been paid for

before it will be allowed to run. Of course, encryption is only one application of a custom class loader. You can use other types of class loaders to solve other problems—for example, storing class files in a database.

Listing 1.1 classLoader/ClassLoaderTest.java

```
1  package classLoader;
2
3  import java.io.*;
4  import java.lang.reflect.*;
5  import java.nio.file.*;
6  import java.util.*;
7
8  /**
9   * This program demonstrates a custom class loa
10  * @version 1.3 2023-11-12
11  * @author Cay Horstmann
12  */
13 public class ClassLoaderTest
14 {
15    public static void main(String[] args) throw
16    {
17       Scanner in = new Scanner(System.in);
18       System.out.print("Class name: ");
19       String className = in.nextLine();
20       System.out.print("Decryption key: ");
```

```
21          int decryptionKey = in.nextInt();
22          var loader = new CryptoClassLoader(decryp
23          Class<?> c = loader.loadClass(className);
24          Method m = c.getMethod("main", String[].c
25          m.invoke(null, (Object) new String[] {});
26       }
27    }
28
29    /**
30     * This class loader loads encrypted class file
31     */
32    class CryptoClassLoader extends ClassLoader
33    {
34       private int key;
35
36       /**
37        * Constructs a crypto class loader.
38        * @param k the decryption key
39        */
40       public CryptoClassLoader(int k)
41       {
42          key = k;
43       }
44
45       protected Class<?> findClass(String name) th
46       {
47          try
48          {
```

```
49            byte[] classBytes = loadClassBytes(nar
50            Class<?> cl = defineClass(name, classB
51            if (cl == null) throw new ClassNotFoun
52            return cl;
53         }
54         catch (IOException e)
55         {
56            throw new ClassNotFoundException(name)
57         }
58      }
59
60      /**
61       * Loads and decrypt the class file bytes.
62       * @param name the class name
63       * @return an array with the class file byte
64       */
65      private byte[] loadClassBytes(String name) t
66      {
67         String cname = name.replace(".", "/") + "
68         byte[] bytes = Files.readAllBytes(Path.of
69         for (int i = 0; i < bytes.length; i++)
70            bytes[i] = (byte) (bytes[i] - key);
71         return bytes;
72      }
73   }
```

Listing 1.2 classLoader/Caesar.java

```
1  package classLoader;
2
3  import java.io.*;
4
5  /**
6   * Encrypts a file using the Caesar cipher.
7   * @version 1.03 2023-11-12
8   * @author Cay Horstmann
9   */
10 public class Caesar
11 {
12    public static void main(String[] args) throw
13    {
14       if (args.length != 3)
15       {
16          System.out.println("USAGE: java classL
17          return;
18       }
19
20       try (var in = new FileInputStream(args[0]
21             var out = new FileOutputStream(args
22       {
23          int key = Integer.parseInt(args[2]);
24          boolean done = false;
25          while (!done)
26          {
```

```
27                int ch = in.read();
28                if (ch == -1) done = true;
29                else out.write((byte) (ch + key));
30             }
31          }
32       }
33    }
```

`java.lang.Class` **1.0**

- `ClassLoader getClassLoader()`
  gets the class loader that loaded this class.

`java.lang.ClassLoader` **1.0**

- `ClassLoader getParent()` **1.2**
  returns the parent class loader, or `null` if the parent class loader is the bootstrap class loader.
- `static ClassLoader getSystemClassLoader()` **1.2**
  gets the system class loader—that is, the class loader that was used to load the first application class.
- `protected Class findClass(String name)` **1.2**
  should be overridden by a class loader to find the bytecodes for a class and present them to the virtual machine by calling the

`defineClass` method. In the name of the class, use `.` as package name separator, and don't use a `.class` suffix.

- `Class defineClass(String name, byte[] byteCodeData, int offset, int length)`
  adds a new class to the virtual machine whose bytecodes are provided in the given data range.

`java.net.URLClassLoader` **1.2**

- `URLClassLoader(URL[] urls)`
- `URLClassLoader(URL[] urls, ClassLoader parent)`
  construct a class loader that loads classes from the given URLs. If a URL ends in a `/`, it is assumed to be a directory, otherwise it is assumed to be a JAR file.

`java.lang.Thread` **1.0**

- `ClassLoader getContextClassLoader()` **1.2**
  gets the class loader that the creator of this thread has designated as the most reasonable class loader to use when executing this thread.
- `void setContextClassLoader(ClassLoader loader)` **1.2**
  sets a class loader for code in this thread to use for loading classes. If no context class loader is set explicitly when a thread is started, the parent thread's context class loader is used.

1.1.5. Bytecode Verification

When a class loader presents the bytecodes of a newly loaded Java platform class to the virtual machine, these bytecodes are first inspected by a *verifier.* The verifier checks that the instructions cannot perform actions that are obviously damaging. All classes except for platform classes are verified.

Here are some of the checks that the verifier carries out:

- Variables are initialized before they are used.
- Method calls match the types of object references.
- Rules for accessing private data and methods are not violated.
- Local variable accesses fall within the runtime stack.
- The runtime stack does not overflow.

If any of these checks fails, the class is considered corrupted and will not be loaded.

Note: If you are familiar with Gödel's theorem, you might wonder how the verifier can prove that a class file is free from type mismatches, uninitialized variables, and stack overflows. Gödel's theorem states that it is impossible to design algorithms that process a program and decide whether it has a particular property (such as being free from stack overflows). Is

this a conflict between the public relations department at Oracle and the laws of logic? No—in fact, the verifier is *not* a decision algorithm in the sense of Gödel. If the verifier accepts a program, it is indeed safe. However, the verifier might reject virtual machine instructions even though they would actually be safe. (You might have run into this issue when you were forced to initialize a variable with a dummy value because the verifier couldn't see that it was going to be properly initialized.)

This strict verification is an important security consideration. Accidental errors, such as uninitialized variables, can easily wreak havoc if they are not caught. More importantly, in the wide open world of the Internet, you must be protected against malicious programmers who create evil effects on purpose. For example, by modifying values on the runtime stack or by writing to the private instance fields of platform objects, a program can break through the security system of a browser.

You might wonder, however, why a special verifier is needed to check all these features. After all, the compiler would never allow you to generate a class file in which an uninitialized variable is used or in which a private instance field is accessed from another class.

Indeed, a class file generated by a compiler for the Java programming language always passes verification. However, the bytecode format used in the class files is well documented, and it is an easy matter for someone with experience in assembly programming and a hex editor to manually produce a class file containing valid but unsafe instructions for the Java virtual machine. The verifier is always guarding against maliciously altered class files —not just checking the class files produced by a compiler.

Here's an example of how to construct such an altered class file. We start with the program `VerifierTest.java` of Listing 9.3. This is a simple program that calls a method and displays the method's result. The `fun` method itself just computes 1 + 2.

```
static int fun()
{
   int m;
   int n;
   m = 1;
   n = 2;
   int r = m + n;
   return r;
}
```

As an experiment, try to compile the following modification of this program:

```
static int fun()
{
   int m = 1;
   int n;
   m = 1;
   m = 2;
   int r = m + n;
   return r;
}
```

Here, `n` is not initialized, so it could have any random value. Of course, the compiler detects that problem and refuses to compile the program. To create a bad class file, we have to work a little harder. First, run the `javap` program to find out how the compiler translates the `fun` method. The command

```
javap -c verifier.VerifierTest
```

shows the bytecodes in the class file in mnemonic form.

```
Method int fun()
   0 iconst_1
   1 istore_0
   2 iconst_2
   3 istore_1
   4 iload_0
```

```
    5 iload_1
    6 iadd
    7 istore_2
    8 iload_2
    9 ireturn
```

Use a hex editor to change instruction 3 from `istore_1` to `istore_0`. That is, local variable 0 (which is `m`) is initialized twice, and local variable 1 (which is `n`) is not initialized at all. We need to know the hexadecimal values for these instructions; these values are readily available from the Java Virtual Machine specification (https://docs.oracle.com/javase/specs/jvms/se21/html/index.html).

```
0 iconst_1 04
1 istore_0 3B
2 iconst_2 05
3 istore_1 3C
4 iload_0  1A
5 iload_1  1B
6 iadd     60
7 istore_2 3D
8 iload_2  1C
9 ireturn  AC
```

You can use any hex editor to carry out the modification. In Figure 9.3, you see the class file `VerifierTest.class` loaded into the

Gnome hex editor, with the bytecodes of the `fun` method highlighted.



Figure 1.3: Modifying bytecodes with a hex editor

Change `3C` to `3B` and save the class file. Then try running the `VerifierTest` program. You get an error message:

```
Exception in thread "main" java.lang.VerifyError: (cl
()I) Accessing value from uninitialized register 1
```

That is good—the virtual machine detected our modification.

Now run the program with the `-noverify` (or `-Xverify:none`) option:

```
java -noverify verifier.VerifierTest
```

The `fun` method returns a seemingly random value. This is actually `2` plus the value that happened to be stored in the variable `n`, which was never initialized.

Here is a typical printout:

```
1 + 2 == 15102330
```

Note: The `-noverify` and `-Xverify:none` options are deprecated and may be removed, but while they are available, they show the impact of the corruption.

Listing 1.3 verifier/VerifierTest.java

```
1 package verifier;
2
3 /**
4  * This application demonstrates the bytecode v
5  * hex editor to modify the class file, then th
6  * @version 1.10 2018-05-05
```

```
 * @author Cay Horstmann
 */
public class VerifierTest
{
   public static void main(String[] args)
   {
      System.out.println("1 + 2 == " + fun());
   }

   /**
    * A function that computes 1 + 2.
    * @return 3, if the code has not been corru
    */
   public static int fun()
   {
      int m;
      int n;
      m = 1;
      n = 2;
      // use hex editor to change to "m = 2" ir
      int r = m + n;
      return r;
   }
}
```

1.2. User Authentication

The Java API provides a framework, called the Java Authentication and Authorization Service (JAAS), that provides access to platform-provided and custom authentication mechanisms. We'll discuss the JAAS framework in the following sections.

1.2.1. The JAAS Framework

As you can tell from its name, the JAAS framework has two components. The “authentication” part is concerned with ascertaining the identity of a program user. The “authorization” part is tied to the deprecated security manager, and we will not discuss it.

JAAS is a “pluggable” API that isolates Java applications from the particular technology used to implement authentication. It supports, among others, UNIX logins, Windows logins, Kerberos authentication, and certificate-based authentication.

Here is the basic outline of the login code:

```
try
{
   System.setSecurityManager(new SecurityManager());
   var context = new LoginContext("Login1"); // defin
   context.login();
   // get the authenticated Subject
   Subject subject = context.getSubject();
```

```
   . . .
   context.logout();
}
catch (LoginException e) // thrown if login was not s
{
   exception.printStackTrace();
}
```

Now the `subject` denotes the individual who has been authenticated.

The string parameter `"Login1"` in the `LoginContext` constructor refers to an entry with the same name in the JAAS configuration file. Here is a sample configuration file:

```
Login1
{
   com.sun.security.auth.module.UnixLoginModule requi
   com.whizzbang.auth.module.RetinaScanModule suffici
};

Login2
{
   . . .
};

other
```

```
{
    . . .
};
```

The module class name and flag can be followed by any number of options that are passed on to the constructor of the module.

The special name `other` is used when the name of the login context doesn't match any of the names in the configuration.

Of course, the JDK contains no biometric login modules. The following modules are supplied in the `com.sun.security.auth.module` package:

```
UnixLoginModule
NTLoginModule
Krb5LoginModule
JndiLoginModule
KeyStoreLoginModule
```

A login policy consists of a sequence of login modules, each labeled `required`, `sufficient`, `requisite`, or `optional`. The meaning of these keywords is given by the following algorithm:

1. The modules are executed in turn, until a `sufficient` module succeeds, a `requisite` module fails, or the end of the module list is reached.
2. Authentication is successful if all `required` and `requisite` modules succeed, or if none of them were executed, if at least one `sufficient` or `optional` module succeeds.

A login authenticates a *subject*, which can have multiple *principals*. A principal describes some property of the subject, such as the username, group ID, or role. The `com.sun.security.auth.UnixPrincipal` describes the UNIX login name, and the `UnixNumericGroupPrincipal` can test for membership in a UNIX group.

The program in Listing 9.4 displays the principals of the currently logged-in user. Run the program as

```
java -Djava.security.auth.login.config=auth/jaas.conf
```

Listing 9.5 shows the login configuration.

On Windows, change `UnixLoginModule` to `NTLoginModule` in `jaas.config`.

Listing 1.4 auth/AuthTest.java

```
1  package auth;
2
3  import java.security.*;
4  import javax.security.auth.*;
5  import javax.security.auth.login.*;
6
7  /**
8   * This program obtains information about a use
9   * @version 1.03 2021-11-29
10  * @author Cay Horstmann
11  */
12 public class AuthTest
13 {
14    public static void main(final String[] args)
15    {
16       try
17       {
18          var context = new LoginContext("Login1
19          context.login();
20          System.out.println("Authentication suc
21          Subject subject = context.getSubject()
22          for (Principal p : subject.getPrincipa
23          {
24             System.out.println(p.getClass().get
25          }
26          context.logout();
```

```
27          }
28          catch (LoginException e)
29          {
30             System.out.println("Authentication fai
31             e.printStackTrace();
32          }
33       }
34    }
```

Listing 1.5 auth/jaas.config

```
1  Login1
2  {
3     com.sun.security.auth.module.UnixLoginModule
4  };
```

`javax.security.auth.login.LoginContext` **1.4**

- `LoginContext(String name)`
  constructs a login context. The `name` corresponds to the login descriptor in the JAAS configuration file.
- `void login()`
  establishes a login or throws `LoginException` if the login failed. Invokes the `login` method on the modules in the JAAS configuration file.

- `void logout()`
  logs out the subject. Invokes the `logout` method on the modules in the JAAS configuration file.
- `Subject getSubject()`
  returns the authenticated subject.

`javax.security.auth.Subject` **1.4**

- `Set<Principal> getPrincipals()`
  gets the principals of this subject.

`java.security.Principal` **1.1**

- `String getName()`
  returns the identifying name of this principal.

1.2.2. JAAS Login Modules

In this section, we'll look at a JAAS example that shows you

- How to implement your own login module
- How to implement role-based authorization

Supplying your own login module is useful if you store login information in a database.

One job of the login module is to populate the principal set of the subject that is being authenticated. If a login module supports roles, it adds `Principal` objects that describe roles. The Java library does not provide a class for this purpose, so I wrote my own (see Listing 9.6).

The login module looks up users, passwords, and roles in a text file that contains lines like this:

```
harry|secret|admin
carl|guessme|HR
```

Of course, in a realistic login module, you would store this information in a database or directory. And you would hash the passwords—see Section 9.3.8.

You can find the code for the `SimpleLoginModule` in Listing 9.7. The `checkLogin` method checks whether the username and password match a record in the password file. If so, we add two `Principal` objects to the subject's principal set:

```
Set<Principal> principals = subject.getPrincipals();
principals.add(new UserPrincipal(username));
principals.add(new RolePrincipal(role));
```

The `UserPrincipal` class is declared in the `com.sun.security.auth` package.

The remainder of `SimpleLoginModule` is straightforward plumbing. The `initialize` method receives

- The `Subject` that is being authenticated
- A handler to retrieve login information
- A `sharedState` map that can be used for communication between login modules
- An `options` map that contains the name/value pairs that are set in the login configuration

For example, we configure our module as follows:

```
  SimpleLoginModule required passwordFile="jaas/passwor
```

The `initialize` method retrieves the `passwordFile` and `debug` settings from the `options` parameter.

The login module does not gather the username and password; that is the job of a separate handler. This separation allows you to use the same login module without worrying whether the login information comes from a GUI dialog box, a console prompt, or a configuration file.

The handler is specified when you construct the `LoginContext`, for example:

```
var context = new LoginContext("Login1",
   new com.sun.security.auth.callback.TextCallbackHan
```

The `TextCallbackHandler` class prompts for username and password from the console.

However, you usually have your own user interface for collecting the username and password. In this case, the callback mechanism is overkill, but there is no other way to transfer that information. The sample application in Listing 9.8 uses a simple handler that merely stores and returns that information.

The handler has a single method, `handle`, that processes an array of `Callback` objects. A number of predefined classes, such as `NameCallback` and `PasswordCallback`, implement the `Callback` interface. You could also add your own class, such as `RetinaScanCallback`. The handler code is a bit unsightly because it needs to analyze the types of the callback objects:

```
public void handle(Callback[] callbacks)
{
   for (Callback callback : callbacks)
```

```
    {
       switch (callback)
       {
          case NameCallback c -> c.setName(username);
          case PasswordCallback c -> c.setPassword(pas
          default -> {}
       }
    }
 }
```

The `login` method of the `SimpleLoginModule` prepares an array of the callbacks that it needs for authentication:

```
 var nameCallback = new NameCallback("username: ");
 var passwordCallback = new PasswordCallback("password
 callbackHandler.handle(new Callback[] { nameCallback,
```

Depending on the handler, the `handle` method can ask the user or retrieve the information from somewhere. When the `handle` method returns, the `nameCallback` and `passwordCallback` objects have been set. Then the `login` method retrieves the username and password and checks whether they are valid.

The program in Listing 9.9 uses either the `TextCallbackHandler` or a custom login, with the username on the command line and a

prompt for the password. When the login is successful, the principals are shown. Run the program as

```
java -Djava.security.auth.login.config=jaas/jaas.conf
```

or

```
java -Djava.security.auth.login.config=jaas/jaas.conf
```

Note: It is possible to support a more complex two-phase protocol, whereby a login is *committed* if all modules in the login configuration were successful. For more information, see the login module developer's guide at https://docs.oracle.com/javase/8/docs/technotes/guides/security/jaas/JAASLMDevGuide.html.

Listing 1.6 jaas/RolePrincipal.java

```
1 package jaas;
2
3 import java.security.*;
4
```

```
5  /**
6   * A principal with a named role.
7   */
8  public record RolePrincipal(String name) implem
9  {
10    /**
11     * @return the role name.
12     */
13    public String getName()
14    {
15       return name;
16    }
17 }
```

Listing 1.7 jaas/SimpleLoginModule.java

```
1  package jaas;
2
3  import com.sun.security.auth.*;
4  import java.io.*;
5  import java.nio.file.*;
6  import java.security.*;
7  import java.util.*;
8  import javax.security.auth.*;
9  import javax.security.auth.callback.*;
10 import javax.security.auth.login.*;
11 import javax.security.auth.spi.*;
12
```

```
13 /**
14  * This login module authenticates users by rea
15  * a text file.
16  */
17 public class SimpleLoginModule implements Logi
18 {
19    private Subject subject;
20    private CallbackHandler callbackHandler;
21    private boolean debug;
22    private String passwordFile;
23
24    public void initialize(Subject subject, Cal
25          Map<String, ?> sharedState, Map<String
26    {
27       this.subject = subject;
28       this.callbackHandler = callbackHandler;
29       debug = options.get("debug").equals("true
30       passwordFile = "" + options.get("passwor
31    }
32
33    public boolean login() throws LoginExceptio
34    {
35       var nameCallback = new NameCallback("user
36       var passwordCallback = new PasswordCallba
37       try
38       {
39          if (debug)
40          {
```

```
41              System.Logger logger = System.getLo
42              logger.log(System.Logger.Level.INFO
43           }
44           if (callbackHandler == null) throw new
45
46           callbackHandler.handle(new Callback[]
47           return checkLogin(nameCallback.getName
48        }
49        catch (UnsupportedCallbackException | IOE
50        {
51           var e2 = new LoginException();
52           e2.initCause(e);
53           throw e2;
54        }
55     }
56
57     /**
58      * Checks whether the authentication informa
59      * principals for the user name and role.
60      * @param username the user name
61      * @param password a character array contair
62      * @return true if the authentication inform
63      */
64     private boolean checkLogin(String username,
65           throws IOException
66     {
67        try (var in = new Scanner(Path.of(passwor
68        {
```

```
69          while (in.hasNextLine())
70          {
71             String[] inputs = in.nextLine().spl
72             if (inputs[0].equals(username)
73                   && Arrays.equals(inputs[1].to
74             {
75                String role = inputs[2];
76                Set<Principal> principals = subj
77                principals.add(new UserPrincipal
78                principals.add(new RolePrincipal
79                return true;
80             }
81          }
82          return false;
83       }
84    }
85
86    public boolean logout()
87    {
88       return true;
89    }
90
91    public boolean abort()
92    {
93       return true;
94    }
95
96    public boolean commit()
```

```
97    {
98       return true;
99    }
100 }
```

Listing 1.8 jaas/SimpleCallbackHandler.java

```
1  package jaas;
2
3  import javax.security.auth.callback.*;
4
5  /**
6   * This simple callback handler presents the gi
7   */
8  public class SimpleCallbackHandler implements C
9  {
10    private String username;
11    private char[] password;
12
13    /**
14     * Constructs the callback handler.
15     * @param username the user name
16     * @param password a character array contair
17     */
18    public SimpleCallbackHandler(String username
19    {
20       this.username = username;
21       this.password = password;
```

```
22    }
23
24    public void handle(Callback[] callbacks)
25    {
26       for (Callback callback : callbacks)
27       {
28          switch (callback)
29          {
30             case NameCallback c -> c.setName(us
31             case PasswordCallback c -> c.setPas
32             default -> {}
33          }
34       }
35    }
36 }
```

Listing 1.9 jaas/JAASTest.java

```
1  package jaas;
2
3  import com.sun.security.auth.callback.*;
4  import java.io.*;
5  import java.security.*;
6  import javax.security.auth.*;
7  import javax.security.auth.callback.*;
8  import javax.security.auth.login.*;
9
10 /**
```

```
 * This program shows how to authenticate a use
 * @version 1.1 2023-11-12
 * @author Cay Horstmann
 */
public class JAASTest
{
   public static void main(final String[] args)
   {
      CallbackHandler handler;
      if (args.length == 0) handler = new TextC
      else
      {
         // In most apps, you have your own way
         // Here, the user provides the user na
         String username = args[0];
         Console console = System.console();
         char[] password = console.readPassword
         handler = new SimpleCallbackHandler(us
      }

      try
      {
         var context = new LoginContext("Login1
         context.login();
         Subject subject = context.getSubject()
         for (Principal p : subject.getPrincipa
         {
            System.out.println(p.getClass().get
```

```
39            }
40            context.logout();
41         }
42         catch (LoginException e)
43         {
44            e.printStackTrace();
45            Throwable cause = e.getCause();
46            if (cause != null) cause.printStackTra
47         }
48      }
49   }
```

Listing 1.10 jaas/jaas.config

```
1  Login1
2  {
3     jaas.SimpleLoginModule required passwordFile
4  };
```

`javax.security.auth.callback.CallbackHandler` **1.4**

- `void handle(Callback[] callbacks)`
  handles the given callbacks, interacting with the user if desired, and stores the security information in the callback objects.

`javax.security.auth.callback.NameCallback` **1.4**

- `NameCallback(String prompt)`
- `NameCallback(String prompt, String defaultName)`
  construct a `NameCallback` with the given prompt and default name.
- `String getName()`
- `void setName(String name)`
  get or set the name gathered by this callback.
- `String getPrompt()`
  gets the prompt to use when querying this name.
- `String getDefaultName()`
  gets the default name to use when querying this name.

`javax.security.auth.callback.PasswordCallback` **1.4**

- `PasswordCallback(String prompt, boolean echoOn)`
  constructs a `PasswordCallback` with the given prompt and a flag indicating whether the password should be displayed as it is typed.
- `char[] getPassword()`
- `void setPassword(char[] password)`
  get or set the password gathered by this callback.

- `String getPrompt()`
  gets the prompt to use when querying this password.
- `boolean isEchoOn()`
  gets the echo flag to use when querying this password.

`javax.security.auth.spi.LoginModule` **1.4**

- `void initialize(Subject subject, CallbackHandler handler, Map<String,?> sharedState, Map<String,?> options)`
  initializes this `LoginModule` for authenticating the given `subject`. During login processing, uses the given handler to gather login information. Use the `sharedState` map for communicating with other login modules. The `options` map contains the name/value pairs specified in the login configuration for this module instance.
- `boolean login()`
  carries out the authentication process and populates the subject's principals. Returns `true` if the login was successful.
- `boolean commit()`
  is called after all login modules were successful, for login scenarios that require a two-phase commit. Returns `true` if the operation was successful.

- `boolean abort()`
  is called if the failure of another login module caused the login process to abort. Returns `true` if the operation was successful.
- `boolean logout()`
  logs out this subject. Returns `true` if the operation was successful.

1.3. Digital Signatures

As already mentioned, applets were what started the Java craze. In practice, people discovered that although they could write animated applets (like the famous "nervous text"), applets could not do a whole lot of useful stuff in the JDK 1.0 security model. For example, since applets under JDK 1.0 were so closely supervised, they couldn't do much good on a corporate intranet, even though relatively little risk attaches to executing an applet from your company's secure intranet. It quickly became clear to Sun that for applets to become truly useful, users need to be able to assign *different* levels of security, depending on where the applet originated. If an applet comes from a trusted supplier and has not been tampered with, the user of that applet can decide whether to give the applet more privileges.

To give more trust to an applet, we need to know two things:

- Where did the applet come from?

- Was the code corrupted in transit?

In the past 50 years, mathematicians and computer scientists have developed sophisticated algorithms for ensuring the integrity of data and for creating electronic signatures. The `java.security` package contains implementations of many of these algorithms. Fortunately, you don't need to understand the underlying mathematics to use the algorithms in the `java.security` package. In the next sections, I'll show you how message digests can detect changes in data files and how digital signatures can prove the identity of the signer.

1.3.1. Message Digests

A message digest is a digital fingerprint of a block of data. For example, the so-called SHA-1 (Secure Hash Algorithm #1) condenses any data block, no matter how long, into a sequence of 160 bits (20 bytes). As with real fingerprints, one hopes that no two different messages have the same SHA-1 fingerprint. Of course, that cannot be true—there are only 2^{160} SHA-1 fingerprints, so there must be some messages with the same fingerprint. But 2^{160} is so large that the probability of a collision is negligible. How negligible? According to James Walsh in *True Odds: How Risks Affect Your Everyday Life* (Merritt Publishing, 1996), the chance that you will die from being struck by lightning is about one in 30,000. Now, think of

nine other people—for example, your nine least favorite managers or professors. The chance that you and *all of them* will die from lightning strikes is higher than that of a forged message having the same SHA-1 fingerprint as the original. (Of course, more than ten people, none of whom you are likely to know, *will* die from lightning strikes. However, we are talking about the far slimmer chance that *your particular choice* of people will be wiped out.)

A message digest has two essential properties:

- If one bit or several bits of the data are changed, the message digest also changes.
- A forger who is in possession of a given message cannot construct a fake message that has the same message digest as the original.

The second property is, again, a matter of probabilities. Consider the following message by the billionaire father:

> *"Upon my death, my property shall be divided equally among my children; however, my son George shall receive nothing."*

That message (with a final newline) has an SHA-1 fingerprint of

```
12 5F 09 03 E7 31 30 19 2E A6 E7 E4 90 43 84 B4 38 99
```

The distrustful father has deposited the message with one attorney and the fingerprint with another. Now, suppose George bribes the lawyer holding the message. He wants to change the message so that Bill gets nothing. Of course, that changes the fingerprint to a completely different bit pattern:

```
7D F6 AB 08 EB 40 EC CD AB 74 ED E9 86 F9 ED 99 D1 45
```

Can George find some other wording that matches the fingerprint? If he had been the proud owner of a billion computers from the time the Earth was formed, each computing a million messages a second, he would not yet have found a message he could substitute.

A number of algorithms have been designed to compute such message digests. Among them are SHA-1, the secure hash algorithm developed by the National Institute of Standards and Technology, and MD5, an algorithm invented by Ronald Rivest of MIT. Both algorithms scramble the bits of a message in ingenious ways. For details about these algorithms, see, for example, *Cryptography and Network Security, Seventh Edition*, by William Stallings (Pearson, 2017). However, subtle regularities have been discovered in both algorithms, and NIST recommends to switch to stronger alternatives. Java supports the SHA-2 and SHA-3 sets of algorithms.

The `MessageDigest` class is a *factory* for creating objects that encapsulate the fingerprinting algorithms. It has a static method, called `getInstance`, that returns an object of a class that extends the `MessageDigest` class. This means the `MessageDigest` class serves double duty:

- As a factory class
- As the superclass for all message digest algorithms

For example, here is how you obtain an object that can compute SHA fingerprints:

```
MessageDigest alg = MessageDigest.getInstance("SHA-1"
```

After you have obtained a `MessageDigest` object, feed it all the bytes in the message by repeatedly calling the `update` method. For example, the following code passes all bytes in a file to the `alg` object just created to do the fingerprinting:

```
InputStream in = . . .;
int ch;
while ((ch = in.read()) != -1)
   alg.update((byte) ch);
```

Alternatively, if you have the bytes in an array, you can update the entire array at once:

```
byte[] bytes = . . .;
alg.update(bytes);
```

When you are done, call the `digest` method. This method pads the input as required by the fingerprinting algorithm, does the computation, and returns the digest as an array of bytes.

```
byte[] hash = alg.digest();
```

The program in Listing 9.11 computes a message digest. You can specify the file and algorithm on the command line:

```
java hash.Digest hash/input.txt SHA-1
```

If you do not supply command-line arguments, you will be prompted for the file and algorithm name.

Listing 1.11 hash/Digest.java

```
1 package hash;
2
3 import java.io.*;
```

```
4  import java.nio.file.*;
5  import java.security.*;
6  import java.util.*;
7
8  /**
9   * This program computes the message digest of
10  * @version 1.21 2018-04-10
11  * @author Cay Horstmann
12  */
13 public class Digest
14 {
15    /**
16     * @param args args[0] is the filename, args
17     * (SHA-1, SHA-256, or MD5)
18     */
19    public static void main(String[] args) throw
20    {
21       var in = new Scanner(System.in);
22       String filename;
23       if (args.length >= 1)
24          filename = args[0];
25       else
26       {
27          System.out.print("File name: ");
28          filename = in.nextLine();
29       }
30       String algname;
31       if (args.length >= 2)
```

```
32            algname = args[1];
33         else
34         {
35            System.out.println("Select one of the
36            for (Provider p : Security.getProvider
37               for (Provider.Service s : p.getServ
38                  if (s.getType().equals("MessageD
39                     System.out.println(s.getAlgor
40            System.out.print("Algorithm: ");
41            algname = in.nextLine();
42         }
43         MessageDigest alg = MessageDigest.getInst
44         byte[] input = Files.readAllBytes(Path.of
45         byte[] hash = alg.digest(input);
46         for (byte h : hash)
47            System.out.printf("%02X ", h & 0xFF);
48         System.out.println();
49      }
50   }
```

`java.security.MessageDigest` **1.1**

- `static MessageDigest getInstance(String algorithmName)`
  returns a `MessageDigest` object that implements the specified algorithm. Throws `NoSuchAlgorithmException` if the algorithm is not provided.

- `void update(byte input)`
- `void update(byte[] input)`
- `void update(byte[] input, int offset, int len)`
  update the digest, using the specified bytes.
- `byte[] digest()`
  completes the hash computation, returns the computed digest, and resets the algorithm object.
- `void reset()`
  resets the digest.

1.3.2. Message Signing

In the last section, you saw how to compute a message digest—a fingerprint for the original message. If the message is altered, the fingerprint of the altered message will not match the fingerprint of the original. If the message and its fingerprint are delivered separately, the recipient can check whether the message has been tampered with. However, if both the message and the fingerprint were intercepted, it is an easy matter to modify the message and then recompute the fingerprint. After all, the message digest algorithms are publicly known, and they don’t require secret keys. In that case, the recipient of the forged message and the recomputed fingerprint would never know that the message has been altered. Digital signatures solve this problem.

To help you understand how digital signatures work, let's look at a few concepts from the field called *public key cryptography.* Public key cryptography is based on the notion of a *public* key and *private* key. The idea is that you tell everyone in the world your public key. However, only you hold the private key, and it is important that you safeguard it and don't release it to anyone else. The keys are matched by mathematical relationships, though the exact nature of these relationships is not important to us. (If you are interested, look it up in *The Handbook of Applied Cryptography* at https://cacr.uwaterloo.ca/hac/.)

The keys are quite long and complex. For example, here is a matching pair of public and private Digital Signature Algorithm (DSA) keys.

Public key:

```
p: fca682ce8e12caba26efccf7110e526db078b05edecbcd1eb4
ed0899bcd132acd50d99151bdc43ee737592e17

q: 962eddcc369cba8ebb260ee6b6a126d9346e38c5

g: 678471b27a9cf44ee91a49c5147db1a9aaf244f05a434d6486
935630e1c2062354d0da20a6c416e50be794ca4
```

```
y: c0b6e67b4ac098eb1a32c5f8c4c1f0e7e6fb9d832532e27d0b
40b927281ddb22cb9bc4df596d7de4d1b977d50
```

Private key:

```
p: fca682ce8e12caba26efccf7110e526db078b05edecbcd1eb4
ed0899bcd132acd50d99151bdc43ee737592e17

q: 962eddcc369cba8ebb260ee6b6a126d9346e38c5

g: 678471b27a9cf44ee91a49c5147db1a9aaf244f05a434d6486
935630e1c2062354d0da20a6c416e50be794ca4

x: 146c09f881656cc6c51f27ea6c3a91b85ed1d70a
```

It is believed to be practically impossible to compute one key from the other. That is, even though everyone knows your public key, they can’t, in your lifetime, compute your private key, no matter how many computing resources they have available.

It may be difficult to believe that the private key can't be computed from the public key—but nobody has found an algorithm to do this for the encryption algorithms in common use today. If the keys are sufficiently long, brute force—simply trying all possible keys—would

require more computers than can be built from all the atoms in the solar system, crunching away for thousands of years. Of course it is possible that someone could come up with algorithms for computing keys that are much more clever than brute force. For example, the RSA algorithm (the encryption algorithm invented by Rivest, Shamir, and Adleman) depends on the difficulty of factoring large numbers. For the last 20 years, many of the best mathematicians have tried to come up with good factoring algorithms, but so far with no success. For that reason, most cryptographers believe that keys with a "modulus" of 2,000 bits or more are currently completely safe from any attack. DSA is believed to be similarly secure.

Figure 9.4 illustrates how the process works in practice.



Figure 1.4: Public key signature exchange with DSA

Suppose Alice wants to send Bob a message, and Bob wants to know this message came from Alice and not an impostor. Alice writes the message and *signs* the message digest with her private key. Bob gets a copy of her public key. Bob then applies the public key to *verify* the signature. If the verification passes, Bob can be assured of two facts:

- The original message has not been altered.
- The message was signed by Alice, the holder of the private key that matches the public key that Bob used for verification.

You can see why the security of private keys is so important. If someone steals Alice's private key, or if a government can require her to turn it over, then she is in trouble. The thief or a government agent can now impersonate her by sending messages, such as money transfer instructions, that others will believe came from Alice.

1.3.3. Verifying a Signature

The JDK comes with the `keytool` program, which is a command-line tool to generate and manage a set of certificates. We expect that ultimately the functionality of this tool will be embedded in other, more user-friendly programs. But right now, we'll use `keytool` to show how Alice can sign a document and send it to Bob, and how Bob can verify that the document really was signed by Alice and not an impostor.

The `keytool` program manages *keystores*—databases of certificates and private/public key pairs. Each entry in the keystore has an *alias*. Here is how Alice creates a keystore, `alice.jks`, and generates a key pair with alias `alice`:

```
keytool -genkeypair -keyalg DSA -keystore alice.jks -
```

When creating or opening a keystore, you are prompted for a keystore password. For this example, just use `secret`. If you were to use the `keytool`-generated keystore for any serious purpose, you would need to choose a good password and safeguard this file.

When generating a key, you are prompted for the following information:

```
Enter keystore password:  secret
Reenter new password:  secret
What is your first and last name?
  [Unknown]:  Alice Lee
What is the name of your organizational unit?
  [Unknown]:  Engineering
What is the name of your organization?
  [Unknown]:  ACME Software
What is the name of your City or Locality?
  [Unknown]:  San Francisco
What is the name of your State or Province?
  [Unknown]:  CA
What is the two-letter country code for this unit?
  [Unknown]:  US
Is <CN=Alice Lee, OU=Engineering, O=ACME Software, L=
  [no]:  yes
```

The `keytool` uses names in the X.500 format, whose components are Common Name (CN), Organizational Unit (OU), Organization (O), Location (L), State (ST), and Country (C), to identify key owners and certificate issuers.

Suppose Alice wants to give her public key to Bob. She needs to export a certificate file:

```
keytool -exportcert -keystore alice.jks -alias alice
```

Now Alice can send the certificate to Bob. When Bob receives the certificate, he can print it:

```
keytool -printcert -file alice.cer
```

The printout looks like this:

```
Owner: CN=Alice Lee, OU=Engineering, O=ACME Software,
Issuer: CN=Alice Lee, OU=Engineering, O=ACME Software
Serial number: b2b46ccd99479da2
Valid from: Tue Jan 16 08:11:22 CET 2024 until: Mon A
Certificate fingerprints:
  SHA1: 41:38:E6:F2:9D:FA:90:FE:CB:36:85:F1:E6:39:62:
  SHA256: 14:CC:AD:BC:83:D5:0C:F9:98:24:52:29:B3:AF:B
```

```
Signature algorithm name: SHA256withDSA
Subject Public Key Algorithm: 2048-bit DSA key
Version: 3
```

If Bob wants to check that he got the right certificate, he can call Alice and verify the certificate fingerprint over the phone.

Note: Some certificate issuers publish certificate fingerprints on their web sites. For example, to check the DigiCert certificate in the keystore `var jdk` /lib/security/cacerts directory, use the `-list` option:

```
keytool -list -v -keystore jdk/lib/security/cacerts
```

The password for this keystore is `changeit`. One of the certificates in this keystore is

```
Owner: CN=DigiCert Assured ID Root G3, OU=www.digicer
Issuer: CN=DigiCert Assured ID Root G3, OU=www.digice
Serial number: ba15afa1ddfa0b54944afcd24a06cec
Valid from: Thu Aug 01 14:00:00 CEST 2013 until: Fri
Certificate fingerprints:
```

```
            SHA1: F5:17:A2:4F:9A:48:C6:C9:F8:A2:00:26:9F
            SHA256: 7E:37:CB:8B:4C:47:09:0C:AB:36:55:1B:
                    16:6A:95:2D:B1:00:71:7F:43:05:3F:C2
```

You can check that your certificate is valid by visiting the web site https://www.digicert.com/kb/digicert-root-certificates.htm.

Once Bob trusts the certificate, he can import it into his keystore.

```
keytool -importcert -keystore bob.jks -alias alice -f
```

Caution: Never import into a keystore a certificate that you don't fully trust. Once a certificate is added to the keystore, any program that uses the keystore assumes that the certificate can be used to verify signatures.

Now Alice can start sending signed documents to Bob. The `jarsigner` tool signs and verifies JAR files. Alice simply adds the document to be signed into a JAR file.

```
jar cvf document.jar document.txt
```

She then uses the `jarsigner` tool to add the signature to the file. She needs to specify the keystore, the JAR file, and the alias of the

key to use.

```
jarsigner -keystore alice.jks document.jar alice
```

When Bob receives the file, he uses the `-verify` option of the `jarsigner` program.

```
jarsigner -verify -keystore bob.jks document.jar
```

Bob does not need to specify the key alias. The `jarsigner` program finds the X.500 name of the key owner in the digital signature and looks for a matching certificate in the keystore.

If the JAR file is not corrupted and the signature matches, the `jarsigner` program prints

```
jar verified.
```

followed by a number of warnings that you can ignore for this simple experiment. Otherwise, the program displays an error message.

1.3.4. The Authentication Problem

Suppose you get a message from your friend Alice, signed with her private key, using the method I just showed you. You might already

have her public key, or you can easily get it by asking her for a copy or by getting it from her web page. Then, you can verify that the message was in fact authored by Alice and has not been tampered with. Now, suppose you get a message from a stranger who claims to represent a famous software company, urging you to run a program attached to the message. The stranger even sends you a copy of his public key so you can verify that he authored the message. You check that the signature is valid. This proves that the message was signed with the matching private key and has not been corrupted.

Be careful: *You still have no idea who wrote the message.* Anyone can generate a pair of public and private keys, sign the message with the private key, and send the signed message and the public key to you. The problem of determining the identity of the sender is called the *authentication problem.*

The usual way to solve the authentication problem is simple. Suppose the stranger and you have a common acquaintance you both trust. Suppose the stranger meets your acquaintance in person and hands over a disk with the public key. Your acquaintance later meets you, assures you that he met the stranger and that the stranger indeed works for the famous software company, and then gives you the disk (see Figure 9.5). That way, your acquaintance vouches for the authenticity of the stranger.



Figure 1.5: Authentication through a trusted intermediary

In fact, your acquaintance does not actually need to meet you. Instead, he can use his private key to sign the stranger's public key file (see Figure 9.6).



Figure 1.6: Authentication through a trusted intermediary's signature

When you get the public key file, you verify the signature of your friend, and because you trust him, you are confident that he did check the stranger's credentials before applying his signature.

However, you might not have a common acquaintance. Some trust models assume that there is always a "chain of trust"—a chain of

mutual acquaintances—so that you trust every member of that chain. In practice, of course, that isn't always true. You might trust your friend, Alice, and you know that Alice trusts Bob, but you don't know Bob and aren't sure that you trust him. Other trust models assume that there is a benevolent big brother—a company in which we all trust. Companies with confidence-inspiring names such as DigiCert, GlobalSign, and Entrust provide verification services.

You will often encounter digital signatures signed by one or more entities who will vouch for the authenticity, and you will need to evaluate to what degree you trust the authenticators. You might place a great deal of trust in a particular certificate authority, perhaps because you saw their logo on many web pages or because you heard that they require multiple people with black attaché cases to come together into a secure chamber whenever new master keys are to be minted.

However, you should have realistic expectations about what is actually being authenticated. You can get a "class 1" ID simply by filling out a web form and paying a small fee. The key is mailed to the e-mail address included in the certificate. Thus, you can be reasonably assured that the e-mail address is genuine, but the requestor could have filled in *any* name and organization. There are more stringent classes of IDs. For example, with a "class 3" ID, the certificate authority will require an individual requestor to appear

before a notary public, and it will check the financial rating of a corporate requestor. Other authenticators will have different procedures. Thus, when you receive an authenticated message, it is important that you understand what, in fact, is being authenticated.

1.3.5. Certificate Signing

In Section 9.3.3 you saw how Alice used a certificate to distribute a public key to Bob. However, Bob needed to ensure that the certificate was valid by verifying the fingerprint with Alice.

Suppose Alice wants to send her colleague Cindy a signed message, but Cindy doesn't want to bother with verifying lots of signature fingerprints. Now suppose there is an entity that Cindy trusts to verify signatures. In this example, Cindy trusts the Information Resources Department at ACME Software.

That department operates a *certificate authority* (CA). Everyone at ACME has the CA's public key in their keystore, installed by a system administrator who carefully checked the key fingerprint. The CA signs the keys of ACME employees. When they install each other's keys, the keystore will trust them implicitly because they are signed by a trusted key.

Here is how you can simulate this process. Create a keystore `acmesoft.jks`. Generate a key pair and export the public key:

```
keytool -genkeypair -keystore acmesoft.jks -keyalg DS
keytool -exportcert -keystore acmesoft.jks -alias acm
```

The public key is exported into a "self-signed" certificate. Then, add it to every employee's keystore:

```
keytool -importcert -keystore cindy.jks -alias acmero
```

For Alice to send messages to Cindy and to everyone else at ACME Software, she needs to bring her certificate to the Information Resources Department and have it signed. Unfortunately, this functionality is missing in the `keytool` program. In the book's companion code, I supply a `CertificateSigner` class to fill the gap. An authorized staff member at ACME Software would verify Alice's identity and generate a signed certificate as follows:

```
java CertificateSigner -keystore acmesoft.jks -alias
   -infile alice.cer -outfile alice_signedby_acmeroot
```

The certificate signer program must have access to the ACME Software keystore, and the staff member must know the keystore password. Clearly, this is a sensitive operation.

Alice gives the file `alice_signedby_acmeroot.cer` to Cindy and to anyone else in ACME Software. Alternatively, ACME Software can simply store the file in a company directory. Remember, this file contains Alice's public key and an assertion by ACME Software that this key really belongs to Alice.

Now Cindy imports the signed certificate into her keystore:

```
keytool -importcert -keystore cindy.jks -alias alice
```

The keystore verifies that the key was signed by a trusted root key that is already present in the keystore. Cindy is *not* asked to verify the certificate fingerprint.

Once Cindy has added the root certificate and the certificates of the people who regularly send her documents, she does not have to worry about the certicicates again until they expire.

1.3.6. Certificate Requests

In the preceding section, we simulated a CA with a keystore and the `CertificateSigner` tool. However, most CAs run more sophisticated software to manage certificates, and they use slightly different formats for certificates. This section shows the added steps required to interact with those software packages.

We will use the OpenSSL software package as an example. The software is preinstalled on many Linux systems and Mac OS X, and a Cygwin port for Windows is also available. You can download the software at https://www.openssl.org.

To create a CA, run the `CA` script. The exact location depends on your operating system. On Ubuntu, run

```
/usr/lib/ssl/misc/CA.pl -newca
```

This script creates a subdirectory called `demoCA` in the current directory. The directory contains a root key pair and storage for certificates and certificate revocation lists.

You will want to import the public key into the Java keystores of all employees, but it is in the Privacy Enhanced Mail (PEM) format, not the DER format that the keystore accepts easily. Copy the file `demoCA/cacert.pem` to a file `acmeroot.pem` and open that file in a text editor. Remove everything before the line

```
-----BEGIN CERTIFICATE-----
```

and after the line

```
-----END CERTIFICATE-----
```

Now you can import `acmeroot.pem` into each keystore in the usual way:

```
keytool -importcert -keystore cindy.jks -alias acmero
```

It seems quite incredible that the keytool cannot carry out this editing operation itself.

To sign Alice's public key, start by generating a *certificate request* that contains the certificate in the PEM format:

```
keytool -certreq -keystore alice.jks -alias alice -fi
```

To sign the certificate, run

```
openssl ca -in alice.pem -out alice_signedby_acmeroot
```

As before, cut out everything outside the `BEGIN CERTIFICATE` / `END CERTIFICATE` markers from `alice_signedby_acmeroot.pem`.
Then import it into Cindy's keystore:

```
keytool -importcert -keystore cindy.jks -alias alice
```

To have a certificate signed by a certificate authority, follow similar steps. Generate a certificate request, send it to the authority, and import the signed file that you receive from them.

1.3.7. Code Signing

A common use of authentication technology is signing executable programs. If you download a program, you are naturally concerned about the damage it can do. For example, the program could have been infected by a virus. If you know where the code comes from *and* that it has not been tampered with since it left its origin, your comfort level will be a lot higher than without this knowledge.

In this section, I'll show you how to sign JAR files, and how you can configure Java to verify the signature. This capability was designed for applets and Java Web Start applications. These are no longer commonly used technologies, but you may still need to support them in legacy products.

When Java was first released, applets ran in the “sandbox,” with limited permissions, as soon as they were loaded. If users wanted to use applets that can access the local file system, make network

connections, and so on, they had to explicitly agree. To ensure that the applet code was not tampered with in transit, it had to be digitally signed.

Here is a specific example. Suppose that while surfing the Internet, you encounter a web site that offers to run an applet from an unfamiliar vendor, provided you grant it the permission to do so (see Figure 9.7). Such a program is signed with a *software developer* certificate issued by a certificate authority that the Java runtime trusts. The pop-up dialog box identifies the software developer and the certificate issuer. Now you need to decide whether to authorize the program.



Figure 1.7: Launching a signed applet

What facts do you have at your disposal that might influence your decision? Here is what you know:

- Thawte sold a certificate to the software developer.
- The program really was signed with that certificate, and it hasn't been modified in transit.
- That certificate really was signed by Thawte—it was verified by the public key in the local `cacerts` file.

Of course, none of this tells you whether the code is safe to run. Can you trust a vendor if all you know is the vendor's name and the fact

that Thawte sold them a software developer certificate? This approach never made much sense.

For intranet deployment, certificates are more plausible. Administrators can install policy files and certificates on local machines so that no user interaction is required for launching trusted code. However, with the deprecation of the security manager, this approach is no longer viable.

1.3.8. Password Hashing

For obvious security reasons, one should never store passwords as plain text. Instead, their hashed values should be stored. When a user logs in, the user's password entry should also be hashed. If the values match, the user is authenticated.

However, the hash algorithms that you have seen so far are not suitable for password hashing. In order to thwart brute force attacks, the hashing mechanism should use many rounds of computations. Also, to avoid precomputing of password tables, each password should be modified with a random “salt” value.

Java provides the PBKDF2 algorithm for password hashing. The algorithm has four parameters:

- A `char` array holding the password

- An array of random salt bytes
- The number of iterations
- The number of bits for the output

A salted password isn't a message, so you don't use the `MessageDigest` interface. Instead, use a `SecretKeyFactory` like this:

```
var spec = new PBEKeySpec(password, salt, ITERATIONS,
SecretKeyFactory skf = SecretKeyFactory.getInstance("
byte[] hash = skf.generateSecret(spec).getEncoded();
```

The acronym PBE denotes “password based encryption” because the derived bytes could also be used as an encryption key. PBKDF is a “password based key derivation function”, which turns a short password into a longer encryption key. We are not interested in encryption and just store the resulting bytes. For password verification, it is also important to store the salt. Since it is good practice to increase the number of iterations over time, as processors beccome more powerful, you should store that value as well.

When storing the hash as a string, the bytes should be encoded in hex or, more efficiently, in base64:

```
Base64.Encoder encoder = Base64.getEncoder();
String hashedPassword = ITERATIONS + "|" + encoder.en
   + encoder.encodeToString(hash);
```

To verify a user-entered password, obtain the iterations and salt from the stored hash, and recompute the hash.

1.4. Encryption

So far, we have discussed one important cryptographic technique implemented in the Java security API—namely, authentication through digital signatures. A second important aspect of security is *encryption*. Even when authenticated, the information itself is plainly visible. The digital signature merely verifies that the information has not been changed. In contrast, when information is encrypted, it is not visible. It can only be decrypted with a matching key.

Authentication is sufficient for code signing—there is no need to hide the code. However, encryption is necessary when applications transfer confidential information, such as credit card numbers and other personal data.

In the past, patents and export controls prevented many companies from offering strong encryption. Fortunately, export controls are now much less stringent, and the patents for important algorithms have

expired. Nowadays, Java provides excellent encryption support as a part of the standard library.

1.4.1. Symmetric Ciphers

The Java cryptographic extensions contain a class `Cipher` that is the superclass of all encryption algorithms. To get a cipher object, call the `getInstance` method:

```
Cipher cipher = Cipher.getInstance(algorithmName);
```

or

```
Cipher cipher = Cipher.getInstance(algorithmName, pro
```

The JDK comes with ciphers by the provider named `"SunJCE"`. It is the default provider used if you don't specify another provider name. You might want another provider if you need specialized algorithms that Oracle does not support.

The algorithm name is a string such as `"AES"` or `"DES/CBC/PKCS5Padding"`.

The Data Encryption Standard (DES) is a venerable block cipher with a key length of 56 bits. Nowadays, the DES algorithm is considered

obsolete because it can be cracked with brute force. A far better alternative is its successor, the Advanced Encryption Standard (AES). See https://nvlpubs.nist.gov/nistpubs/FIPS/NIST.FIPS.197.pdf for a detailed description of the AES algorithm. I use AES in this example.

Once you have a cipher object, initialize it by setting the mode and the key:

```
int mode = . . .;
Key key = . . .;
cipher.init(mode, key);
```

The mode is one of

```
Cipher.ENCRYPT_MODE
Cipher.DECRYPT_MODE
Cipher.WRAP_MODE
Cipher.UNWRAP_MODE
```

The wrap and unwrap modes encrypt one key with another—see the next section for an example.

Now you can repeatedly call the `update` method to encrypt blocks of data:

```
int blockSize = cipher.getBlockSize();
var inBytes = new byte[blockSize];
. . . // read inBytes
int outputSize= cipher.getOutputSize(blockSize);
var outBytes = new byte[outputSize];
int outLength = cipher.update(inBytes, 0, outputSize,
. . . // write outBytes
```

When you are done, you must call the `doFinal` method once. If a final block of input data is available (with fewer than `blockSize` bytes), call

```
outBytes = cipher.doFinal(inBytes, 0, inLength);
```

If all input data have been encrypted, instead call

```
outBytes = cipher.doFinal();
```

The call to `doFinal` is necessary to carry out *padding* of the final block. Consider the DES cipher. It has a block size of eight bytes. Suppose the last block of the input data has fewer than eight bytes. Of course, we can fill the remaining bytes with `0`, to obtain one final block of eight bytes, and encrypt it. But when the blocks are decrypted, the result will have several trailing `0` bytes appended to

it, and therefore will be slightly different from the original input file. To avoid this problem, we need a *padding scheme*. A commonly used padding scheme is the one described in the Public Key Cryptography Standard (PKCS) #5 by RSA Security, Inc. (https://datatracker.ietf.org/doc/html/rfc2898).

In this scheme, the last block is not padded with a pad value of zero, but with a pad value that equals the number of pad bytes. In other words, if `L` is the last (incomplete) block, it is padded as follows:

```
L 01                                    if length(L) = 7
L 02 02                                 if length(L) = 6
L 03 03 03                              if length(L) = 5
. . .
L 07 07 07 07 07 07 07                  if length(L) = 1
```

Finally, if the length of the input is actually divisible by 8, then one block

```
08 08 08 08 08 08 08 08
```

is appended to the input and encrypted. After decryption, the very last byte of the plaintext is a count of the padding characters to discard.

1.4.2. Key Generation

To encrypt, you need to generate a key. Each cipher has a different format for keys, and you need to make sure that the key generation is random. Follow these steps:

1. Get a `KeyGenerator` for your algorithm.
2. Initialize the generator with a source for randomness. If the block length of the cipher is variable, also specify the desired block length.
3. Call the `generateKey` method.

For example, here is how you generate an AES key:

```
KeyGenerator keygen = KeyGenerator.getInstance("AES")
var random = new SecureRandom(); // see below
keygen.init(random);
Key key = keygen.generateKey();
```

Alternatively, you can produce a key from a fixed set of raw data (perhaps derived from a password or the timing of keystrokes). Construct a `SecretKeySpec` (which implements the `SecretKey` interface) like this:

```
byte[] keyData = . . .; // 16 bytes for AES
var key = new SecretKeySpec(keyData, "AES");
```

When generating keys, make sure you use *truly random* numbers. For example, the regular random number generator in the `Random` class, seeded by the current date and time, is not random enough. Suppose the computer clock is accurate to 1/10 of a second. Then there are at most 864,000 seeds per day. If an attacker knows the day a key was issued (which can often be deduced from a message date or certificate expiration date), it is an easy matter to generate all possible seeds for that day.

The `SecureRandom` class generates random numbers that are far more secure than those produced by the `Random` class. You still need to provide a seed to start the number sequence at a random spot. The best method for doing this is to obtain random input from a hardware device such as a white-noise generator. Another reasonable source for random input is to ask the user to type away aimlessly on the keyboard, with each keystroke contributing only one or two bits to the random seed. Once you gather such random bits in an array of bytes, pass it to the `setSeed` method:

```
var random = new SecureRandom();
var b = new byte[20];
// fill with truly random bits
```

```
random.setSeed(b);
```

If you don’t seed the random number generator, it will compute its own 20-byte seed by launching threads, putting them to sleep, and measuring the exact time when they are awakened.

Note: This algorithm is *not* known to be safe. In the past, algorithms that relied on the timing of some components of the computer, such as hard disk access time, were shown not to be completely random.

The sample program at the end of this section puts the AES cipher to work (see Listing 9.12). The `crypt` utility method in Listing 9.13 will be reused in other examples. To use the program, you first need to generate a secret key. Run

```
java aes.AESTest -genkey secret.key
```

The secret key is saved in the file `secret.key`.

Now you can encrypt with the command

```
java aes.AESTest -encrypt plaintextFile encryptedFile
```

Decrypt with the command

```
java aes.AESTest -decrypt encryptedFile decryptedFile
```

The program is straightforward. The `-genkey` option produces a new secret key and serializes it in the given file. The `-encrypt` and `-decrypt` options both call into the same `crypt` method that calls the `update` and `doFinal` methods of the cipher. Note how the `update` method is called so long as the input blocks have the full length, and the `doFinal` method is either called with a partial input block (which is then padded) or with no additional data (to generate one pad block).

Listing 1.12 aes/AESTest.java

```
1  package aes;
2
3  import java.io.*;
4  import java.security.*;
5  import javax.crypto.*;
6
7  /**
8   * This program tests the AES cipher. Usage:<br
9   * java aes.AESTest -genkey keyfile<br>
10  * java aes.AESTest -encrypt plaintext encrypte
```

```
 * java aes.AESTest -decrypt encrypted decrypte
 * @author Cay Horstmann
 * @version 1.02 2018-05-01
 */
public class AESTest
{
   public static void main(String[] args)
         throws IOException, GeneralSecurityExc
   {
      if (args[0].equals("-genkey"))
      {
         KeyGenerator keygen = KeyGenerator.get
         var random = new SecureRandom();
         keygen.init(random);
         SecretKey key = keygen.generateKey();
         try (var out = new ObjectOutputStream(
         {
            out.writeObject(key);
         }
      }
      else
      {
         int mode;
         if (args[0].equals("-encrypt")) mode =
         else mode = Cipher.DECRYPT_MODE;

         try (var keyIn = new ObjectInputStrean
               var in = new FileInputStream(arg
```

```
39                var out = new FileOutputStream(a
40          {
41             var key = (Key) keyIn.readObject();
42             Cipher cipher = Cipher.getInstance(
43             cipher.init(mode, key);
44             Util.crypt(in, out, cipher);
45          }
46       }
47    }
48 }
```

Listing 1.13 aes/Util.java

```
1  package aes;
2
3  import java.io.*;
4  import java.security.*;
5  import javax.crypto.*;
6
7  public class Util
8  {
9     /**
10     * Uses a cipher to transform the bytes in a
11     * to an output stream.
12     * @param in the input stream
13     * @param out the output stream
14     * @param cipher the cipher that transforms
15     */
```

```
16      public static void crypt(InputStream in, Out
17            throws IOException, GeneralSecurityExc
18      {
19         int blockSize = cipher.getBlockSize();
20         int outputSize = cipher.getOutputSize(blo
21         var inBytes = new byte[blockSize];
22         var outBytes = new byte[outputSize];
23
24         int inLength = 0;
25         boolean done = false;
26         while (!done)
27         {
28            inLength = in.read(inBytes);
29            if (inLength == blockSize)
30            {
31               int outLength = cipher.update(inByt
32               out.write(outBytes, 0, outLength);
33            }
34            else done = true;
35         }
36         if (inLength > 0) outBytes = cipher.doFir
37         else outBytes = cipher.doFinal();
38         out.write(outBytes);
39      }
40   }
```

`javax.crypto.Cipher` **1.4**

- `static Cipher getInstance(String algorithmName)`
- `static Cipher getInstance(String algorithmName, String providerName)`
  return a `Cipher` object that implements the specified algorithm. Throw a `NoSuchAlgorithmException` if the algorithm is not provided.
- `int getBlockSize()`
  returns the size (in bytes) of a cipher block, or `0` if the cipher is not a block cipher.
- `int getOutputSize(int inputLength)`
  returns the size of an output buffer that is needed if the next input has the given number of bytes. This method takes into account any buffered bytes in the cipher object.
- `void init(int mode, Key key)`
  initializes the cipher algorithm object. The mode is one of `ENCRYPT_MODE`, `DECRYPT_MODE`, `WRAP_MODE`, or `UNWRAP_MODE`.

- `byte[] update(byte[] in)`
- `byte[] update(byte[] in, int offset, int length)`
- `int update(byte[] in, int offset, int length, byte[] out)`

  transform one block of input data. The first two methods return the output. The third method returns the number of bytes placed into `out`.
- `byte[] doFinal()`
- `byte[] doFinal(byte[] in)`
- `byte[] doFinal(byte[] in, int offset, int length)`
- `int doFinal(byte[] in, int offset, int length, byte[] out)`

  transform the last block of input data and flush the buffer of this algorithm object. The first three methods return the output. The fourth method returns the number of bytes placed into `out`.

`javax.crypto.KeyGenerator` **1.4**

- `static KeyGenerator getInstance(String algorithmName)`

  returns a `KeyGenerator` object that implements the specified algorithm. Throws a `NoSuchAlgorithmException` if the algorithm is not provided.

- `void init(SecureRandom random)`
- `void init(int keySize, SecureRandom random)`
  initialize the key generator.
- `SecretKey generateKey()`
  generates a new key.

`javax.crypto.spec.SecretKeySpec` **1.4**

- `SecretKeySpec(byte[] key, String algorithmName)`
  constructs a key specification.

1.4.3. Cipher Streams

The JCE library provides a convenient set of stream classes that automatically encrypt or decrypt stream data. For example, here is how you can encrypt data to a file:

```
Cipher cipher = . . .;
cipher.init(Cipher.ENCRYPT_MODE, key);
var out = new CipherOutputStream(new FileOutputStream
var bytes = new byte[BLOCKSIZE];
int inLength = getData(bytes); // get data from data
while (inLength != -1)
{
   out.write(bytes, 0, inLength);
```

```
   inLength = getData(bytes); // get more data from d
}
out.flush();
```

Similarly, you can use a `CipherInputStream` to read and decrypt data from a file:

```
Cipher cipher = . . .;
cipher.init(Cipher.DECRYPT_MODE, key);
var in = new CipherInputStream(new FileInputStream(in
var bytes = new byte[BLOCKSIZE];
int inLength = in.read(bytes);
while (inLength != -1)
{
   putData(bytes, inLength); // put data to destinati
   inLength = in.read(bytes);
}
```

The cipher stream classes transparently handle the calls to `update` and `doFinal`, which is clearly a convenience.

`javax.crypto.CipherInputStream` **1.4**

- `CipherInputStream(InputStream in, Cipher cipher)`
  constructs an input stream that reads data from `in` and decrypts or encrypts them by using the given cipher.
- `int read()`
- `int read(byte[] b, int off, int len)`
  read data from the input stream, which is automatically decrypted or encrypted.

`javax.crypto.CipherOutputStream` **1.4**

- `CipherOutputStream(OutputStream out, Cipher cipher)`
  constructs an output stream that writes data to `out` and encrypts or decrypts them using the given cipher.
- `void write(int ch)`
- `void write(byte[] b, int off, int len)`
  write data to the output stream, which is automatically encrypted or decrypted.
- `void flush()`
  flushes the cipher buffer and carries out padding if necessary.

1.4.4. Public Key Ciphers

The AES cipher that you have seen in the preceding section is a *symmetric* cipher. The same key is used for both encryption and decryption. The Achilles heel of symmetric ciphers is key distribution. If Alice sends Bob an encrypted message, Bob needs the same key that Alice used. If Alice changes the key, she needs to send Bob both the message and, through a secure channel, the new key. But perhaps she has no secure channel to Bob—which is why she encrypts her messages to him in the first place.

Public key cryptography solves that problem. In a public key cipher, Bob has a key pair consisting of a public key and a matching private key. Bob can publish the public key anywhere, but he must closely guard the private key. Alice simply uses the public key to encrypt her messages to Bob.

Actually, it's not quite that simple. All known public key algorithms are *much* slower than symmetric key algorithms such as DES or AES. It would not be practical to use a public key algorithm to encrypt large amounts of information. However, that problem can easily be overcome by combining a public key cipher with a fast symmetric cipher, like this:

1. Alice generates a random symmetric encryption key. She uses it to encrypt her plaintext.
2. Alice encrypts the symmetric key with Bob's public key.

3. Alice sends Bob both the encrypted symmetric key and the encrypted plaintext.
4. Bob uses his private key to decrypt the symmetric key.
5. Bob uses the decrypted symmetric key to decrypt the message.

Nobody but Bob can decrypt the symmetric key because only Bob has the private key for decryption. Thus, the expensive public key encryption is only applied to a small amount of key data.

The most commonly used public key algorithm is the RSA algorithm invented by Rivest, Shamir, and Adleman. Until October 2000, the algorithm was protected by a patent assigned to RSA Security, Inc. Licenses were not cheap—typically a 3% royalty, with a minimum payment of $50,000 per year. Now the algorithm is in the public domain.

To use the RSA algorithm, you need a public/private key pair. Use a `KeyPairGenerator` like this:

```
KeyPairGenerator pairgen = KeyPairGenerator.getInstan
var random = new SecureRandom();
pairgen.initialize(KEYSIZE, random);
KeyPair keyPair = pairgen.generateKeyPair();
Key publicKey = keyPair.getPublic();
Key privateKey = keyPair.getPrivate();
```

The program in Listing 9.14 has three options. The `-genkey` option produces a key pair. The `-encrypt` option generates an AES key and *wraps* it with the public key.

```
Key key = . . .; // an AES key
Key publicKey = . . .; // a public RSA key
Cipher cipher = Cipher.getInstance("RSA");
cipher.init(Cipher.WRAP_MODE, publicKey);
byte[] wrappedKey = cipher.wrap(key);
```

It then produces a file that contains

- The length of the wrapped key
- The wrapped key bytes
- The plaintext encrypted with the AES key

The `-decrypt` option decrypts such a file. To try the program, first generate the RSA keys:

```
java rsa.RSATest -genkey public.key private.key
```

Then encrypt a file:

```
java rsa.RSATest -encrypt plaintextFile encryptedFile
```

Finally, decrypt it and verify that the decrypted file matches the plaintext:

```
java rsa.RSATest -decrypt encryptedFile decryptedFile
```

Listing 1.14 rsa/RSATest.java

```
1  package rsa;
2
3  import java.io.*;
4  import java.security.*;
5  import javax.crypto.*;
6
7  /**
8   * This program tests the RSA cipher. Usage:<br
9   * java rsa.RSATest -genkey public private<br>
10  * java rsa.RSATest -encrypt plaintext encrypte
11  * java rsa.RSATest -decrypt encrypted decrypte
12  * @author Cay Horstmann
13  * @version 1.02 2018-05-01
14  */
15 public class RSATest
16 {
17    private static final int KEYSIZE = 512;
18
19    public static void main(String[] args)
```

```
20          throws IOException, GeneralSecurityExc
21    {
22       if (args[0].equals("-genkey"))
23       {
24          KeyPairGenerator pairgen = KeyPairGene
25          var random = new SecureRandom();
26          pairgen.initialize(KEYSIZE, random);
27          KeyPair keyPair = pairgen.generateKeyP
28          try (var out = new ObjectOutputStream(
29          {
30             out.writeObject(keyPair.getPublic()
31          }
32          try (var out = new ObjectOutputStream(
33          {
34             out.writeObject(keyPair.getPrivate(
35          }
36       }
37       else if (args[0].equals("-encrypt"))
38       {
39          KeyGenerator keygen = KeyGenerator.get
40          var random = new SecureRandom();
41          keygen.init(random);
42          SecretKey key = keygen.generateKey();
43
44          // wrap with RSA public key
45          try (var keyIn = new ObjectInputStrean
46                var out = new DataOutputStream(n
47                var in = new FileInputStream(arg
```

```
48          {
49             var publicKey = (Key) keyIn.readObj
50             Cipher cipher = Cipher.getInstance(
51             cipher.init(Cipher.WRAP_MODE, publi
52             byte[] wrappedKey = cipher.wrap(key
53             out.writeInt(wrappedKey.length);
54             out.write(wrappedKey);
55
56             cipher = Cipher.getInstance("AES");
57             cipher.init(Cipher.ENCRYPT_MODE, ke
58             Util.crypt(in, out, cipher);
59          }
60       }
61       else
62       {
63          try (var in = new DataInputStream(new
64                var keyIn = new ObjectInputStrea
65                var out = new FileOutputStream(a
66          {
67             int length = in.readInt();
68             var wrappedKey = new byte[length];
69             in.read(wrappedKey, 0, length);
70
71             // unwrap with RSA private key
72             var privateKey = (Key) keyIn.readOb
73
74             Cipher cipher = Cipher.getInstance(
75             cipher.init(Cipher.UNWRAP_MODE, pri
```

```
76              Key key = cipher.unwrap(wrappedKey,
77
78              cipher = Cipher.getInstance("AES");
79              cipher.init(Cipher.DECRYPT_MODE, ke
80
81              Util.crypt(in, out, cipher);
82           }
83        }
84     }
85  }
```

In this chapter, you had a glimpse at class loaders, and you saw the services for authentication and encryption that the Java library provides. Along the way, you perhaps shed a tear that the classic Java security architecture, based on a security manager and code signing, is now a distant memory.

In the next chapter, we will delve into advanced Swing and graphics programming.

1. Graphical User Interface Programming

Java was born at a time when most computer users interacted with desktop applications via a graphical user interface (GUI). Nowadays, browser-based and mobile applications are far more common, but there are still times when it is useful to provide a desktop application. Moreover, many teachers and students enjoy learning Java through GUI applications. In this and the following chapter, I discuss the basics of user interface programming with the Swing toolkit. Chapter 12 covers more advanced techniques that can also be useful to generate images on a server. If you are not interested in writing GUI and graphics programs, you can safely skip these chapters.

1.1. A History of Java User Interface Toolkits

When Java 1.0 was introduced, it contained a class library, called the Abstract Window Toolkit (AWT), for basic GUI programming. The basic AWT library deals with user interface elements by delegating their creation and behavior to the native GUI toolkit on each target platform (Windows, Linux, Macintosh, and so on). For example, if you used the original AWT to put a text box on a Java window, an underlying "peer" text box actually handled the text input. The

resulting program could then, in theory, run on any of these platforms, with the "look-and-feel" of the target platform.

The peer-based approach worked well for simple applications, but it soon became apparent that it was fiendishly difficult to write a high-quality portable graphics library depending on native user interface elements. User interface elements such as menus, scrollbars, and text fields can have subtle differences in behavior on different platforms. It was hard, therefore, to give users a consistent and predictable experience with this approach. Moreover, some graphical environments (such as X11/Motif) do not have as rich a collection of user interface components as does Windows or the Macintosh. This further limits a portable library based on a "lowest common denominator" approach. As a result, GUI applications built with the AWT simply did not look as nice as native Windows or Macintosh applications, nor did they have the kind of functionality that users of those platforms had come to expect. More depressingly, there were *different* bugs in the AWT user interface library on the different platforms. Developers complained that they had to test their applications on each platform—a practice derisively called "write once, debug everywhere."

In 1996, Netscape created a GUI library they called the IFC (Internet Foundation Classes) that used an entirely different approach. User interface elements, such as buttons, menus, and so on, were

painted onto blank windows. The only functionality required from the underlying windowing system was a way to put up a window and to paint on it. Thus, Netscape's IFC widgets looked and behaved the same no matter which platform the program ran on. Sun Microsystems worked with Netscape to perfect this approach, creating a user interface library with the code name "Swing." Swing was available as an extension to Java 1.1 and became a part of the standard library in Java 1.2.

Swing is now the official name for the non-peer-based GUI toolkit.

Note: Swing is not a complete replacement for the AWT—it is built on top of the AWT architecture. Swing simply gives you more capable user interface components. Whenever you write a Swing program, you use the foundations of the AWT—in particular, event handling. From now on, I will say "Swing" when I mean the "painted" user interface classes, and "AWT" when I refer to the underlying mechanisms of the windowing toolkit, such as event handling.

Swing has to work hard painting every pixel of the user interface. When Swing was first released, users complained that it was slow. (You can still get a feel for the problem if you run Swing applications

on hardware such as a Raspberry Pi.) After a while, desktop computers got faster, and users complained that Swing was ugly—indeed, it had fallen behind the native widgets that had been spruced up with animations and fancy effects. More ominously, Adobe Flash was increasingly used to create user interfaces with even flashier effects that didn't use the native controls at all.

In 2007, Sun Microsystems introduced an entirely different user interface toolkit, called JavaFX, as a competitor to Flash. It ran on the Java VM but had its own programming language, called JavaFX Script. The language was optimized for programming animations and fancy effects. Programmers complained about the need to learn a new language, and they stayed away in droves. In 2011, Oracle released a new version, JavaFX 2.0, that had a Java API and no longer needed a separate programming language. Starting with Java 7 update 6, JavaFX was bundled with the JDK and JRE. However, this bundling was discontinued starting with Java 11.

Since this is a book about the core Java language and APIs, I will focus on Swing for user interface programming.

1.2. Displaying Frames

A top-level window (that is, a window that is not contained inside another window) is called a *frame* in Java. The AWT library has a

class, called `Frame`, for this top level. The Swing version of this class is called `JFrame` and extends the `Frame` class. The `JFrame` is one of the few Swing components that is not painted on a canvas. Thus, the decorations (buttons, title bar, icons, and so on) are drawn by the user's windowing system, not by Swing.

Caution: Most Swing component classes start with a "J": `JButton`, `JFrame`, and so on. There are classes such as `Button` and `Frame`, but they are AWT components. If you accidentally omit a "J", your program may still compile and run, but the mixture of Swing and AWT components can lead to visual and behavioral inconsistencies.

1.2.1. Creating a Frame

In this section, we will go over the most common methods for working with a Swing `JFrame`. Listing 10.1 lists a simple program that displays an empty frame on the screen, as illustrated in Figure 10.1.

Figure 1.1: The simplest visible frame

Listing 1.1 simpleFrame/SimpleFrameTest.java

```
1  package simpleFrame;
2
3  import java.awt.*;
4  import javax.swing.*;
5
6  /**
7   * @version 1.34 2018-04-10
8   * @author Cay Horstmann
9   */
10 public class SimpleFrameTest
11 {
12    public static void main(String[] args)
13    {
14       EventQueue.invokeLater(() ->
```

```
15          {
16             var frame = new SimpleFrame();
17             frame.setDefaultCloseOperation(JFra
18             frame.setVisible(true);
19          });
20    }
21 }
22
23 class SimpleFrame extends JFrame
24 {
25    private static final int DEFAULT_WIDTH = 300
26    private static final int DEFAULT_HEIGHT = 20
27
28    public SimpleFrame()
29    {
30       setSize(DEFAULT_WIDTH, DEFAULT_HEIGHT);
31    }
32 }
```

Let's work through this program, line by line.

The Swing classes are placed in the `javax.swing` package. The package name `java`*`x`* indicates a Java extension package, not a core package. For historical reasons, Swing is considered an extension. However, it is present in every Java implementation since version 1.2.

By default, a frame has a rather useless size of 0×0 pixels. We define a subclass `SimpleFrame` whose constructor sets the size to 300×200 pixels. This is the only difference between a `SimpleFrame` and a `JFrame`.

In the `main` method of the `SimpleFrameTest` class, we construct a `SimpleFrame` object and make it visible.

There are two technical issues that we need to address in every Swing program.

First, all Swing components must be configured from the *event dispatch thread*, the thread of control that passes events such as mouse clicks and keystrokes to the user interface components. The following code fragment is used to execute statements in the event dispatch thread:

```
EventQueue.invokeLater(() ->
   {
      statements
   });
```

Note: You will see many Swing programs that do not initialize the user interface in the event dispatch thread. It used to be perfectly acceptable to carry out

> the initialization in the main thread. Sadly, as Swing components got more complex, the developers of the JDK were no longer able to guarantee the safety of that approach. The probability of an error is extremely low, but you would not want to be one of the unlucky few who encounter an intermittent problem. It is better to do the right thing, even if the code looks rather mysterious.

Next, we define what should happen when the user closes the application's frame. For this particular program, we want the program to exit. To select this behavior, we use the statement

```
frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);
```

In other programs with multiple frames, you would not want the program to exit just because the user closed one of the frames. By default, a frame is hidden when the user closes it, but the program does not terminate. (It might have been nice if the program terminated once the *last* frame becomes invisible, but that is not how Swing works.)

Simply constructing a frame does not automatically display it. Frames start their life invisible. That gives the programmer the

chance to add components into the frame before showing it for the first time. To show the frame, the `main` method calls the `setVisible` method of the frame.

After scheduling the initialization statements, the `main` method exits. Note that exiting `main` does not terminate the program—just the main thread. The event dispatch thread keeps the program alive until it is terminated, either by closing the frame or by calling the `System.exit` method.

The running program is shown in Figure 10.1—it is a truly boring top-level window. As you can see in the figure, the title bar and the surrounding decorations, such as resize corners, are drawn by the operating system and not the Swing library. The Swing library draws everything inside the frame. In this program, it just fills the frame with a default background color.

1.2.2. Frame Properties

The `JFrame` class itself has only a few methods for changing how frames look. Of course, through the magic of inheritance, most of the methods for working with the size and position of a frame come from the various superclasses of `JFrame`. Here are some of the most important methods:

- The `setLocation` and `setBounds` methods for setting the position of the frame
- The `setIconImage` method, which tells the windowing system which icon to display in the title bar, task switcher window, and so on
- The `setTitle` method for changing the text in the title bar
- The `setResizable` method, which takes a `boolean` to determine if a frame will be resizeable by the user

Figure 10.2 illustrates the inheritance hierarchy for the `JFrame` class.



Figure 1.2: Inheritance hierarchy for the frame and component classes in AWT and Swing

As the API notes indicate, the `Component` class (which is the ancestor of all GUI objects) and the `Window` class (which is the superclass of the `Frame` class) are where you need to look for the methods to resize and reshape frames. For example, the `setLocation` method in the `Component` class is one way to reposition a component. If you make the call

```
setLocation(x, y)
```

the top left corner is located `x` pixels across and `y` pixels down, where (0, 0) is the top left corner of the screen. Similarly, the `setBounds` method in `Component` lets you resize and relocate a component (in particular, a `JFrame`) in one step, as

```
setBounds(x, y, width, height)
```

Many methods of component classes come in getter/setter pairs, such as the following methods of the `Frame` class:

```
public String getTitle()
public void setTitle(String title)
```

Such a getter/setter pair is called a *property*. A property has a name and a type. The name is obtained by changing the first letter after

the `get` or `set` to lowercase. For example, the `Frame` class has a property with name `title` and type `String`.

Conceptually, `title` is a property of the frame. When we set the property, we expect the title to change on the user's screen. When we get the property, we expect to get back the value that we have set.

There is one exception to the `get`/`set` convention: For properties of type `boolean`, the getter starts with `is`. For example, the following two methods define the `resizable` property:

```
public boolean isResizable()
public void setResizable(boolean resizable)
```

To determine an appropriate size for a frame, first find out the screen size. Call the static `getDefaultToolkit` method of the `Toolkit` class to get the `Toolkit` object. (The `Toolkit` class is a dumping ground for a variety of methods interfacing with the native windowing system.) Then call the `getScreenSize` method, which returns the screen size as a `Dimension` object. A `Dimension` object simultaneously stores a width and a height, in public (!) instance variables `width` and `height`. Then you can use a suitable percentage of the screen size to size the frame. Here is the code:

```
Toolkit kit = Toolkit.getDefaultToolkit();
Dimension screenSize = kit.getScreenSize();
int screenWidth = screenSize.width;
int screenHeight = screenSize.height;
setSize(screenWidth / 2, screenHeight / 2);
```

You can also supply a frame icon:

```
Image img = new ImageIcon("icon.gif").getImage();
setIconImage(img);
```

`java.awt.Component` **1.0**

- `boolean isVisible()`
- `void setVisible(boolean b)`
  get or set the `visible` property. Components are initially visible, with the exception of top-level components such as `JFrame`.
- `void setSize(int width, int height)` **1.1**
  resizes the component to the specified width and height.
- `void setLocation(int x, int y)` **1.1**
  moves the component to a new location. The `x` and `y` coordinates use the coordinates of the container if the component is not a top-level component, or the coordinates of

the screen if the component is top level (for example, a `JFrame`).

- `void setBounds(int x, int y, int width, int height)` **1.1**
  moves and resizes this component.
- `Dimension getSize()` **1.1**
- `void setSize(Dimension d)` **1.1**
  get or set the `size` property of this component.

`java.awt.Frame` **1.0**

- `boolean isResizable()`
- `void setResizable(boolean b)`
  get or set the `resizable` property. When the property is set, the user can resize the frame.
- `String getTitle()`
- `void setTitle(String s)`
  get or set the `title` property that determines the text in the title bar for the frame.
- `Image getIconImage()`
- `void setIconImage(Image image)`
  get or set the `iconImage` property that determines the icon for the frame. The windowing system may display the icon as part of the frame decoration or in other locations.

`java.awt.Toolkit` **1.0**

- `static Toolkit getDefaultToolkit()`
  returns the default toolkit for this platform.
- `Dimension getScreenSize()`
  gets the size of the user's screen.

`javax.swing.ImageIcon` **1.2**

- `ImageIcon(String filename)`
  constructs an icon whose image is stored in a file.
- `Image getImage()`
  gets the image of this icon.

1.3. Displaying Information in a Component

In this section, I will show you how to display information inside a frame (Figure 10.3).

Figure 1.3: A frame that displays information

You could draw the message string directly onto a frame, but that is not considered good programming practice. In Java, frames are really designed to be containers for components, such as a menu bar and other user interface elements. You normally draw on another component which you add to the frame.

The structure of a `JFrame` is surprisingly complex. Look at Figure 10.4 which shows the makeup of a `JFrame`. As you can see, four panes are layered in a `JFrame`. The root pane, layered pane, and glass pane are of no interest to us; they are required to organize the menu bar and content pane and to implement the look-and-feel. The part that most concerns Swing programmers is the *content pane*. Any components that you add to a frame are automatically placed into the content pane:

```
Component c = . . .;
frame.add(c); // added to the content pane
```



Figure 1.4: Internal structure of a JFrame

In our case, we want to add a single component to the frame onto which we will draw our message. To draw on a component, you define a class that extends `JComponent` and override the `paintComponent` method in that class.

The `paintComponent` method has one parameter of type `Graphics`. A `Graphics` object remembers a collection of settings

for drawing images and text, such as the font you set or the current color. All drawing in Java must go through a `Graphics` object. It has methods that draw patterns, images, and text.

Here's how to make a component onto which you can draw:

```
class MyComponent extends JComponent
{
   public void paintComponent(Graphics g)
   {
      code for drawing
   }
}
```

Each time a window needs to be redrawn, no matter what the reason, the event handler notifies the component. This causes the `paintComponent` methods of all components to be executed.

Never call the `paintComponent` method yourself. It is called automatically whenever a part of your application needs to be redrawn, and you should not interfere with this automatic process.

What sorts of actions trigger this automatic response? For example, painting occurs when the user increases the size of the window, or minimizes and then restores the window. If the user popped up another window that covered an existing window and then made the

overlaid window disappear, the window that was covered is now corrupted and will need to be repainted. (The graphics system does not save the pixels underneath.) And, of course, when the window is displayed for the first time, it needs to process the code that specifies how and where it should draw the initial elements.

Tip: If you need to force repainting of the screen, call the `repaint` method instead of `paintComponent`. The `repaint` method will cause `paintComponent` to be called for all components, with a properly configured `Graphics` object.

As you saw in the code fragment above, the `paintComponent` method has a single parameter of type `Graphics`. Measurement on a `Graphics` object for screen display is done in pixels. The (0, 0) coordinate denotes the top left corner of the component on whose surface you are drawing.

The `Graphics` class has various drawing methods, and displaying text is considered a special kind of drawing. Our `paintComponent` method looks like this:

```
public class NotHelloWorldComponent extends JComponen
{
   public static final int MESSAGE_X = 75;
```

```
   public static final int MESSAGE_Y = 100;

   public void paintComponent(Graphics g)
   {
      g.drawString("Not a Hello, World program", MESS
   }
   . . .
}
```

Finally, a component should tell its users how big it would like to be. Override the `getPreferredSize` method and return an object of the `Dimension` class with the preferred width and height:

```
public class NotHelloWorldComponent extends JComponen
{
   private static final int DEFAULT_WIDTH = 300;
   private static final int DEFAULT_HEIGHT = 200;
   . . .
   public Dimension getPreferredSize()
   {
      return new Dimension(DEFAULT_WIDTH, DEFAULT_HEI
   }
}
```

When you fill a frame with one or more components, and you simply want to use their preferred size, call the `pack` method instead of the `setSize` method:

```
class NotHelloWorldFrame extends JFrame
{
   public NotHelloWorldFrame()
   {
      add(new NotHelloWorldComponent());
      pack();
   }
}
```

Listing 10.2 shows the complete code.

Listing 1.2 notHelloWorld/NotHelloWorld.java

```
1  package notHelloWorld;
2
3  import javax.swing.*;
4  import java.awt.*;
5
6  /**
7   * @version 1.34 2018-04-10
8   * @author Cay Horstmann
9   */
10 public class NotHelloWorld
```

```
11 {
12    public static void main(String[] args)
13    {
14       EventQueue.invokeLater(() ->
15          {
16             var frame = new NotHelloWorldFrame(
17             frame.setTitle("NotHelloWorld");
18             frame.setDefaultCloseOperation(JFra
19             frame.setVisible(true);
20          });
21    }
22 }
23
24 /**
25  * A frame that contains a message panel.
26  */
27 class NotHelloWorldFrame extends JFrame
28 {
29    public NotHelloWorldFrame()
30    {
31       add(new NotHelloWorldComponent());
32       pack();
33    }
34 }
35
36 /**
37  * A component that displays a message.
38  */
```

```
39 class NotHelloWorldComponent extends JComponent
40 {
41    public static final int MESSAGE_X = 75;
42    public static final int MESSAGE_Y = 100;
43
44    private static final int DEFAULT_WIDTH = 300
45    private static final int DEFAULT_HEIGHT = 20
46
47    public void paintComponent(Graphics g)
48    {
49       g.drawString("Not a Hello, World program"
50    }
51
52    public Dimension getPreferredSize()
53    {
54       return new Dimension(DEFAULT_WIDTH, DEFAU
55    }
56 }
```

`javax.swing.JFrame` **1.2**

- `Component add(Component c)`
  adds and returns the given component to the content pane of this frame.

`java.awt.Component` **1.0**

- `void repaint()`
  causes a repaint of the component "as soon as possible."
- `Dimension getPreferredSize()`
  is the method to override to return the preferred size of this component.

`javax.swing.JComponent` **1.2**

- `void paintComponent(Graphics g)`
  is the method to override to describe how your component needs to be painted.

`java.awt.Window` **1.0**

- `void pack()`
  resizes this window, taking into account the preferred sizes of its components.

1.3.1. Working with 2D Shapes

Starting with Java 1.0, the `Graphics` class has methods to draw lines, rectangles, ellipses, and so on. But those drawing operations

are very limited. We will instead use the shape classes from the *Java 2D* library.

To use this library, you need to obtain an object of the `Graphics2D` class. This class is a subclass of the `Graphics` class. Ever since Java 1.2, methods such as `paintComponent` automatically receive an object of the `Graphics2D` class. Simply use a cast, as follows:

```
public void paintComponent(Graphics g)
{
   Graphics2D g2 = (Graphics2D) g;
   . . .
}
```

The Java 2D library organizes geometric shapes in an object-oriented fashion. In particular, there are classes to represent lines, rectangles, and ellipses:

```
Line2D
Rectangle2D
Ellipse2D
```

These classes all implement the `Shape` interface. The Java 2D library supports more complex shapes—arcs, quadratic and cubic curves, and general paths—that we do not discuss in this chapter.

To draw a shape, you first create an object of a class that implements the `Shape` interface and then call the `draw` method of the `Graphics2D` class. For example:

```
Rectangle2D rect = . . .;
g2.draw(rect);
```

The Java 2D library uses floating-point coordinates, not integers, for pixels. Internal calculations are carried out with single-precision `float` quantities. Single precision is sufficient—after all, the ultimate purpose of the geometric computations is to set pixels on the screen or printer. As long as any roundoff errors stay within one pixel, the visual outcome is not affected.

However, manipulating `float` values is sometimes inconvenient for the programmer because Java is adamant about requiring casts when converting `double` values into `float` values. For example, consider the following statement:

```
float f = 1.2; // ERROR--possible loss of precision
```

This statement does not compile because the constant `1.2` has type `double`, and the compiler is nervous about loss of precision. The remedy is to add an `F` suffix to the floating-point constant:

```
float f = 1.2F; // OK
```

Now consider this statement:

```
float f = r.getWidth(); // ERROR
```

This statement does not compile either, for the same reason. The `getWidth` method returns a `double`. This time, the remedy is to provide a cast:

```
float f = (float) r.getWidth(); // OK
```

These suffixes and casts are a bit of a pain, so the designers of the 2D library decided to supply *two versions* of each shape class: one with `float` coordinates for frugal programmers, and one with `double` coordinates for the lazy ones. (In this book, we fall into the second camp and use `double` coordinates whenever we can.)

The library designers chose a curious mechanism for packaging these choices. Consider the `Rectangle2D` class. This is an abstract class with two concrete subclasses, which are also static nested classes:

```
Rectangle2D.Float
Rectangle2D.Double
```

Figure 10.5 shows the inheritance diagram.



Figure 1.5: 2D rectangle classes

It is best to ignore the fact that the two concrete classes are static inner classes—that is just a gimmick to avoid names such as `FloatRectangle2D` and `DoubleRectangle2D`.

When you construct a `Rectangle2D.Float` object, you supply the coordinates as `float` numbers. For a `Rectangle2D.Double` object, you supply them as `double` numbers.

```
var floatRect = new Rectangle2D.Float(10.0F, 25.0F, 2
```

```
var doubleRect = new Rectangle2D.Double(10.0, 25.0, 2
```

The construction arguments denote the top left corner, width, and height of the rectangle.

The `Rectangle2D` methods have `double` parameter and return types. For example, the `getWidth` method returns a `double` value, even if the width is stored as a `float` in a `Rectangle2D.Float` object.

Tip: Simply use the `Double` shape classes to avoid dealing with `float` values altogether. However, if you are constructing thousands of shape objects, consider using the `Float` classes to conserve memory.

What we just discussed for the `Rectangle2D` classes holds for the other shape classes as well. Furthermore, there is a `Point2D` class with subclasses `Point2D.Float` and `Point2D.Double`. Here is how to make a point object:

```
var p = new Point2D.Double(10, 20);
```

The classes `Rectangle2D` and `Ellipse2D` both inherit from the common superclass `RectangularShape`. Admittedly, ellipses are not rectangular, but they have a *bounding rectangle* (see Figure 10.6).



Figure 1.6: The bounding rectangle of an ellipse

The `RectangularShape` class defines over 20 methods that are common to these shapes, among them such useful methods as `getWidth`, `getHeight`, `getCenterX`, and `getCenterY` (but, sadly, at the time of this writing, not a `getCenter` method that would return the center as a `Point2D` object).

Finally, a couple of legacy classes from Java 1.0 have been fitted into the shape class hierarchy. The `Rectangle` and `Point` classes,

which store a rectangle and a point with integer coordinates, extend the `Rectangle2D` and `Point2D` classes.

Figure 10.7 shows the relationships between the shape classes. However, the `Double` and `Float` subclasses are omitted. Legacy classes are marked with a gray fill.



Figure 1.7: Relationships between the shape classes

`Rectangle2D` and `Ellipse2D` objects are simple to construct. You need to specify

- The *x* and *y* coordinates of the top left corner

- The width and height

For ellipses, these refer to the bounding rectangle. For example,

```
var e = new Ellipse2D.Double(150, 200, 100, 50);
```

constructs an ellipse that is bounded by a rectangle with the top left corner at (150, 200), width of 100, and height of 50.

When constructing an ellipse, you usually know the center, width, and height, but not the corner points of the bounding rectangle (which don't even lie on the ellipse). The `setFrameFromCenter` method uses the center point, but it still requires one of the four corner points. Thus, you will usually end up constructing an ellipse as follows:

```
var ellipse =
   new Ellipse2D.Double(centerX - width / 2, centerY
```

To construct a line, you supply the start and end points, either as `Point2D` objects or as pairs of numbers:

```
var line = new Line2D.Double(start, end);
```

or

```
var line = new Line2D.Double(startX, startY, endX, en
```

The program in Listing 10.3 draws a rectangle, the ellipse that is enclosed in the rectangle, a diagonal of the rectangle, and a circle that has the same center as the rectangle. Figure 10.8 shows the result.



Figure 1.8: Drawing geometric shapes

Listing 1.3 draw/DrawTest.java

```
1  package draw;
2
3  import java.awt.*;
4  import java.awt.geom.*;
5  import javax.swing.*;
6
7  /**
8   * @version 1.34 2018-04-10
9   * @author Cay Horstmann
10  */
11 public class DrawTest
12 {
13    public static void main(String[] args)
14    {
15       EventQueue.invokeLater(() ->
16          {
17             var frame = new DrawFrame();
18             frame.setTitle("DrawTest");
19             frame.setDefaultCloseOperation(JFra
20             frame.setVisible(true);
21          });
22    }
23 }
24
25 /**
26  * A frame that contains a panel with drawings
```

```
 */
class DrawFrame extends JFrame
{
   public DrawFrame()
   {
      add(new DrawComponent());
      pack();
   }
}

/**
 * A component that displays rectangles and el
 */
class DrawComponent extends JComponent
{
   private static final int DEFAULT_WIDTH = 400
   private static final int DEFAULT_HEIGHT = 40

   public void paintComponent(Graphics g)
   {
      var g2 = (Graphics2D) g;

      // draw a rectangle

      double leftX = 100;
      double topY = 100;
      double width = 200;
      double height = 150;
```

```
55
56          var rect = new Rectangle2D.Double(leftX,
57          g2.draw(rect);
58
59          // draw the enclosed ellipse
60
61          var ellipse = new Ellipse2D.Double();
62          ellipse.setFrame(rect);
63          g2.draw(ellipse);
64
65          // draw a diagonal line
66
67          g2.draw(new Line2D.Double(leftX, topY, le
68
69          // draw a circle with the same center
70
71          double centerX = rect.getCenterX();
72          double centerY = rect.getCenterY();
73          double radius = 150;
74
75          var circle = new Ellipse2D.Double();
76          circle.setFrameFromCenter(centerX, center
77          g2.draw(circle);
78       }
79
80       public Dimension getPreferredSize()
81       {
```

```
82          return new Dimension(DEFAULT_WIDTH, DEFAU
83       }
84    }
```

`java.awt.geom.RectangularShape` **1.2**

- `double getCenterX()`
- `double getCenterY()`
- `double getMinX()`
- `double getMinY()`
- `double getMaxX()`
- `double getMaxY()`

  return the center, minimum, or maximum *x* or *y* value of the enclosing rectangle.
- `double getWidth()`
- `double getHeight()`

  return the width or height of the enclosing rectangle.
- `double getX()`
- `double getY()`

  return the *x* or *y* coordinate of the top left corner of the enclosing rectangle.

`java.awt.geom.Rectangle2D.Double` **1.2**

- `Rectangle2D.Double(double x, double y, double w, double h)`
  constructs a rectangle with the given top left corner, width, and height.

`java.awt.geom.Ellipse2D.Double` **1.2**

- `Ellipse2D.Double(double x, double y, double w, double h)`
  constructs an ellipse whose bounding rectangle has the given top left corner, width, and height.

`java.awt.geom.Point2D.Double` **1.2**

- `Point2D.Double(double x, double y)`
  constructs a point with the given coordinates.

`java.awt.geom.Line2D.Double` **1.2**

- `Line2D.Double(Point2D start, Point2D end)`
- `Line2D.Double(double startX, double startY, double endX, double endY)`
  construct a line with the given start and end points.

1.3.2. Using Color

The `setPaint` method of the `Graphics2D` class lets you select a color that is used for all subsequent drawing operations on the graphics context. For example:

```
g2.setPaint(Color.RED);
g2.drawString("Warning!", 100, 100);
```

You can fill the interiors of closed shapes (such as rectangles or ellipses) with a color. Simply call `fill` instead of `draw`:

```
Rectangle2D rect = . . .;
g2.setPaint(Color.RED);
g2.fill(rect); // fills rect with red
```

To draw in multiple colors, select a color, draw or fill, then select another color, and draw or fill again.

Note: The `fill` method paints one fewer pixel to the right and the bottom. For example, if you draw a `new Rectangle2D.Double(0, 0, 10, 20)`, then the drawing includes the pixels with $x = 10$ and $y = 20$. If

you fill the same rectangle, those pixels are not painted.

Define colors with the `Color` class. The `java.awt.Color` class offers predefined constants for the following 13 standard colors:

```
BLACK, BLUE, CYAN, DARK_GRAY, GRAY, GREEN, LIGHT_GRAY
MAGENTA, ORANGE, PINK, RED, WHITE, YELLOW
```

You can specify a custom color by creating a `Color` object by its red, green, and blue components, each a value between `0` and `255`:

```
g2.setPaint(new Color(0, 128, 128)); // a dull blue-g
g2.drawString("Welcome!", 75, 125);
```

Note: In addition to solid colors, you can call `setPaint` with instances of classes that implement the `Paint` interface. This enables drawing with gradients and textures.

To set the background color of a component, use the `setBackground` method of the `Component` class, an ancestor of

`JComponent`.

```
var component = new MyComponent();
component.setBackground(Color.PINK);
```

There is also a `setForeground` method. It specifies the default color that is used for drawing on the component.

`java.awt.Color` **1.0**

- `Color(int r, int g, int b)`
  creates a color object with the given red, green, and blue components between `0` and `255`.

`java.awt.Graphics2D` **1.2**

- `Paint getPaint()`
- `void setPaint(Paint p)`
  get or set the paint property of this graphics context. The `Color` class implements the `Paint` interface. Therefore, you can use this method to set the paint attribute to a solid color.
- `void fill(Shape s)`
  fills the shape with the current paint.

`java.awt.Component` **1.0**

- `Color getForeground()`
- `Color getBackground()`
- `void setForeground(Color c)`
- `void setBackground(Color c)`

  get or set the foreground or background color.

1.3.3. Using Fonts

The "Not a Hello World" program at the beginning of this chapter displayed a string in the default font. Sometimes, you will want to show your text in a different font. You can specify a font by its *font face name*. A font face name is composed of a *font family name*, such as "Helvetica," and an optional suffix such as "Bold." For example, the font faces "Helvetica" and "Helvetica Bold" are both considered to be part of the family named "Helvetica."

To find out which fonts are available on a particular computer, call the `getAvailableFontFamilyNames` method of the `GraphicsEnvironment` class. The method returns an array of strings containing the names of all available fonts. To obtain an instance of the `GraphicsEnvironment` class that describes the graphics environment of the user's system, use the static

`getLocalGraphicsEnvironment` method. The following program prints the names of all fonts on your system:

```
import java.awt.*;

public class ListFonts
{
   public static void main(String[] args)
   {
      String[] fontNames = GraphicsEnvironment
         .getLocalGraphicsEnvironment()
         .getAvailableFontFamilyNames();
      for (String fontName : fontNames)
         System.out.println(fontName);
   }
}
```

The AWT defines five *logical* font names:

```
SansSerif
Serif
Monospaced
Dialog
DialogInput
```

These names are always mapped to some fonts that actually exist on the client machine. For example, on a Windows system, `SansSerif` is mapped to Arial.

In addition, the Oracle JDK always includes three font families named “Lucida Sans,” “Lucida Bright,” and “Lucida Sans Typewriter.”

To draw characters in a font, you must first create an object of the class `Font`. Specify the font face name, the font style, and the point size. Here is an example of how you construct a `Font` object:

```
var sansbold14 = new Font("SansSerif", Font.BOLD, 14)
```

The third argument is the point size. Points are commonly used in typography to indicate the size of a font. There are 72 points per inch.

You can use a logical font name in place of the font face name in the `Font` constructor. Specify the style (plain, **bold**, *italic*, or ***bold italic***) by setting the second `Font` constructor argument to one of the following values:

```
Font.PLAIN
Font.BOLD
Font.ITALIC
```

```
  Font.BOLD + Font.ITALIC
```

Here's the code that displays the string "Hello, World!" in the standard sans serif font on your system, using 14-point bold type:

```
  var sansbold14 = new Font("SansSerif", Font.BOLD, 14)
  g2.setFont(sansbold14);
  var message = "Hello, World!";
  g2.drawString(message, 75, 100);
```

Next, let's *center* the string in its component instead of drawing it at an arbitrary position. We need to know the width and height of the string in pixels. These dimensions depend on three factors:

- The font used (in our case, sans serif, bold, 14 point);
- The string (in our case, "Hello, World!"); and
- The device on which the font is drawn (in our case, the user's screen).

To obtain an object that represents the font characteristics of the screen device, call the `getFontRenderContext` method of the `Graphics2D` class. It returns an object of the `FontRenderContext` class. Simply pass that object to the `getStringBounds` method of the `Font` class:

```
FontRenderContext context = g2.getFontRenderContext()
Rectangle2D bounds = sansbold14.getStringBounds(messa
```

The `getStringBounds` method returns a rectangle that encloses the string.

To interpret the dimensions of that rectangle, you should know some basic typesetting terms (see Figure 10.9). The *baseline* is the imaginary line where, for example, the bottom of a character like 'e' rests. The *ascent* is the distance from the baseline to the top of an *ascender*, which is the upper part of a letter like 'b' or 'k', or an uppercase character. The *descent* is the distance from the baseline to a *descender,* which is the lower portion of a letter like 'p' or 'g'.



Figure 1.9: Typesetting terms illustrated

Leading is the space between the descent of one line and the ascent of the next line. (The term has its origin from the strips of lead that typesetters used to separate lines.) The *height* of a font is the

distance between successive baselines, which is the same as descent + leading + ascent.

The width of the rectangle that the `getStringBounds` method returns is the horizontal extent of the string. The height of the rectangle is the sum of ascent, descent, and leading. The rectangle has its origin at the baseline of the string. The top *y* coordinate of the rectangle is negative. Thus, you can obtain string width, height, and ascent as follows:

```
double stringWidth = bounds.getWidth();
double stringHeight = bounds.getHeight();
double ascent = -bounds.getY();
```

If you need to know the descent or leading, use the `getLineMetrics` method of the `Font` class. That method returns an object of the `LineMetrics` class, which has methods to obtain the descent and leading:

```
LineMetrics metrics = f.getLineMetrics(message, conte
float descent = metrics.getDescent();
float leading = metrics.getLeading();
```

Note: When you need to compute layout dimensions outside the `paintComponent` method, you can't obtain the font render context from the `Graphics2D` object. Instead, call the `getFontMetrics` method of the `JComponent` class and then call `getFontRenderContext`.

```
FontRenderContext context = getFontMetrics
```

To show that the positioning is accurate, the sample program in Listing 10.4 centers the string in the frame and draws the baseline and the bounding rectangle. Figure 10.10 shows the screen display.

Figure 1.10: Drawing the baseline and string bounds

Listing 1.4 font/FontTest.java

```
1  package font;
2
3  import java.awt.*;
4  import java.awt.font.*;
5  import java.awt.geom.*;
6  import javax.swing.*;
7
8  /**
9   * @version 1.35 2018-04-10
10  * @author Cay Horstmann
11  */
12 public class FontTest
13 {
14    public static void main(String[] args)
15    {
16       EventQueue.invokeLater(() ->
17          {
18             var frame = new FontFrame();
19             frame.setTitle("FontTest");
20             frame.setDefaultCloseOperation(JFra
21             frame.setVisible(true);
22          });
23    }
24 }
25
26 /**
```

```
 * A frame with a text message component.
 */
class FontFrame extends JFrame
{
   public FontFrame()
   {
      add(new FontComponent());
      pack();
   }
}

/**
 * A component that shows a centered message in
 */
class FontComponent extends JComponent
{
   private static final int DEFAULT_WIDTH = 300
   private static final int DEFAULT_HEIGHT = 20

   public void paintComponent(Graphics g)
   {
      var g2 = (Graphics2D) g;

      String message = "Hello, World!";

      var f = new Font("Serif", Font.BOLD, 36);
      g2.setFont(f);

```

```
55        // measure the size of the message
56
57        FontRenderContext context = g2.getFontRen
58        Rectangle2D bounds = f.getStringBounds(me
59
60        // set (x,y) = top left corner of text
61
62        double x = (getWidth() - bounds.getWidth(
63        double y = (getHeight() - bounds.getHeigh
64
65        // add ascent to y to reach the baseline
66
67        double ascent = -bounds.getY();
68        double baseY = y + ascent;
69
70        // draw the message
71
72        g2.drawString(message, (int) x, (int) bas
73
74        g2.setPaint(Color.LIGHT_GRAY);
75
76        // draw the baseline
77
78        g2.draw(new Line2D.Double(x, baseY, x + b
79
80        // draw the enclosing rectangle
81
82        var rect = new Rectangle2D.Double(x, y, b
```

```
83          g2.draw(rect);
84       }
85
86       public Dimension getPreferredSize()
87       {
88          return new Dimension(DEFAULT_WIDTH, DEFAU
89       }
90    }
```

`java.awt.Font` **1.0**

- `Font(String name, int style, int size)`
  creates a new font object. The font name is either a font face name (such as `"Helvetica Bold"`) or a logical font name (such as `"Serif"`, `"SansSerif"`). The style is one of `Font.PLAIN`, `Font.BOLD`, `Font.ITALIC`, or `Font.BOLD + Font.ITALIC`.
- `String getFontName()`
  gets the font face name (such as `"Helvetica Bold"`).
- `String getFamily()`
  gets the font family name (such as `"Helvetica"`).
- `String getName()`
  gets the logical name (such as `"SansSerif"`) if the font was created with a logical font name; otherwise, gets the font face name.

- `Rectangle2D getStringBounds(String s, FontRenderContext context)` **1.2**
  returns a rectangle that encloses the string. The origin of the rectangle falls on the baseline. The top *y* coordinate of the rectangle equals the negative of the ascent. The height of the rectangle equals the sum of ascent, descent, and leading. The width equals the string width.
- `LineMetrics getLineMetrics(String s, FontRenderContext context)` **1.2**
  returns a line metrics object to determine the extent of the string.

`java.awt.font.LineMetrics` **1.2**

- `float getAscent()`
  gets the font ascent—the distance from the baseline to the tops of uppercase characters.
- `float getDescent()`
  gets the font descent—the distance from the baseline to the bottoms of descenders.
- `float getLeading()`
  gets the font leading—the space between the bottom of one line of text and the top of the next line.

- `float getHeight()`
  gets the total height of the font—the distance between the two baselines of text (descent + leading + ascent).

`java.awt.Graphics2D` **1.2**

- `FontRenderContext getFontRenderContext()`
  gets a font render context that specifies font characteristics in this graphics context.
- `void drawString(String str, float x, float y)`
  draws a string in the current font and color.

`javax.swing.JComponent` **1.2**

- `FontMetrics getFontMetrics(Font f)` **5.0**
  gets the font metrics for the given font. The `FontMetrics` class is a precursor to the `LineMetrics` class.

`java.awt.FontMetrics` **1.0**

- `FontRenderContext getFontRenderContext()` **1.2**
  gets a font render context for the font.

1.3.4. Displaying Images

You can use the `ImageIcon` class to read an image from a file:

```
Image image = new ImageIcon(filename).getImage();
```

Now the variable `image` contains a reference to an object that encapsulates the image data. Display the image with the `drawImage` method of the `Graphics` class.

```
public void paintComponent(Graphics g)
{
   . . .
   g.drawImage(image, x, y, null);
}
```

We can take this a little bit further and tile the window with the graphics image. The result looks like the screen shown in Figure 10.11. We do the tiling in the `paintComponent` method. We first draw one copy of the image in the top left corner and then use the `copyArea` call to copy it into the entire window:

```
for (int i = 0; i * imageWidth <= getWidth(); i++)
   for (int j = 0; j * imageHeight <= getHeight(); j+
      if (i + j > 0)
         g.copyArea(0, 0, imageWidth, imageHeight, i
```



Figure 1.11: Window with tiled graphics image

Listing 1.5 image/ImageTest.java

```
1  package image;
2
3  import java.awt.*;
4  import javax.swing.*;
5
6  /**
7   * @version 1.35 2023-10-04
8   * @author Cay Horstmann
9   */
10 public class ImageTest
11 {
12    public static void main(String[] args)
13    {
14       EventQueue.invokeLater(() ->
```

```
15          {
16             JFrame frame = new ImageFrame();
17             frame.setTitle("ImageTest");
18             frame.setDefaultCloseOperation(JFra
19             frame.setVisible(true);
20          });
21    }
22 }
23
24 /**
25  * A frame with an image component.
26  */
27 class ImageFrame extends JFrame
28 {
29    public ImageFrame()
30    {
31       add(new ImageComponent());
32       pack();
33    }
34 }
35
36 /**
37  * A component that displays a tiled image.
38  */
39 class ImageComponent extends JComponent
40 {
41    private static final int DEFAULT_WIDTH = 300
42    private static final int DEFAULT_HEIGHT = 20
```

```
43
44    private Image image;
45
46    public ImageComponent()
47    {
48       image = new ImageIcon("blue-ball.gif").ge
49    }
50
51    public void paintComponent(Graphics g)
52    {
53       if (image == null) return;
54
55       int imageWidth = image.getWidth(null);
56       int imageHeight = image.getHeight(null);
57       if (imageWidth <= 0 || imageHeight <= 0)
58
59       // draw the image in the upper-left corne
60
61       g.drawImage(image, 0, 0, null);
62       // tile the image across the component
63
64       for (int i = 0; i * imageWidth <= getWidt
65          for (int j = 0; j * imageHeight <= get
66             if (i + j > 0)
67                g.copyArea(0, 0, imageWidth, ima
68    }
```

```
69
70      public Dimension getPreferredSize() { return
71  }
```

`java.awt.Graphics` **1.0**

- `boolean drawImage(Image img, int x, int y, ImageObserver observer)`
- `boolean drawImage(Image img, int x, int y, int width, int height, ImageObserver observer)`
  draw an unscaled or scaled image. Note: This call may return before the image is drawn. The `imageObserver` object is notified of the rendering progress. This was a useful feature in the distant past. Nowadays, just pass a `null` observer.
- `void copyArea(int x, int y, int width, int height, int dx, int dy)`
  copies an area of the screen. The `dx` and `dy` parameters are the distance from the source area to the target area.

1.4. Event Handling

Any operating environment that supports GUIs constantly monitors events such as keystrokes or mouse clicks. These events are then reported to the programs that are running. Each program then decides what, if anything, to do in response to these events.

1.4.1. Basic Event Handling Concepts

In the Java AWT, *event sources* (such as buttons or scrollbars) have methods that allow you to register *event listeners*—objects that carry out the desired response to the event.

When an event listener is notified about an event, information about the event is encapsulated in an *event object*. In Java, all event objects ultimately derive from the class `java.util.EventObject.` Of course, there are subclasses for each event type, such as `ActionEvent` and `WindowEvent`.

Different event sources can produce different kinds of events. For example, a button can send `ActionEvent` objects, whereas a window can send `WindowEvent` objects.

To sum up, here's an overview of how event handling in the AWT works:

- An event listener is an instance of a class that implements a *listener interface*.
- An event source is an object that can register listener objects and send them event objects.
- The event source sends out event objects to all registered listeners when that event occurs.

- The listener objects then uses the information in the event object to determine their reaction to the event.

Figure 10.12 shows the relationship between the event handling classes and interfaces.



Figure 1.12: Relationship between event sources and listeners

Here is an example for specifying a listener:

```
ActionListener listener = . . .;
var button = new JButton("OK");
button.addActionListener(listener);
```

Now the `listener` object is notified whenever an "action event" occurs in the button. For buttons, as you might expect, an action event is a button click.

To implement the `ActionListener` interface, the listener class must have a method called `actionPerformed` that receives an `ActionEvent` object as a parameter.

```
class MyListener implements ActionListener
{
   . . .
   public void actionPerformed(ActionEvent event)
   {
      // reaction to button click goes here
      . . .
   }
}
```

Whenever the user clicks the button, the `JButton` object creates an `ActionEvent` object and calls `listener.actionPerformed(event)`, passing that event object. An event source such as a button can have multiple listeners. In that case, the button calls the `actionPerformed` methods of all listeners whenever the user clicks the button.

Figure 10.13 shows the interaction between the event source, event listener, and event object.



Figure 1.13: Event notification

1.4.2. Example: Handling a Button Click

As a way of getting comfortable with the event delegation model, let's work through all the details needed for the simple example of responding to a button click. For this example, we will show a panel populated with three buttons. Three listener objects are added as action listeners to the buttons.

With this scenario, each time a user clicks on any of the buttons on the panel, the associated listener object receives an `ActionEvent` that indicates a button click. In our sample program, the listener object will then change the background color of the panel.

Before I can show you the program that listens to button clicks, I need to explain how to create buttons and how to add them to a panel.

To create a button, specify a label string, an icon, or both in the button constructor. Here are two examples:

```
var yellowButton = new JButton("Yellow");
var blueButton = new JButton(new ImageIcon("blue-ball
```

Call the `add` method to add the buttons to a panel:

```
var yellowButton = new JButton("Yellow");
var blueButton = new JButton("Blue");
var redButton = new JButton("Red");

buttonPanel.add(yellowButton);
buttonPanel.add(blueButton);
buttonPanel.add(redButton);
```

Figure 10.14 shows the result.



Figure 1.14: A panel filled with buttons

Next, we need to add code that listens to these buttons. This requires classes that implement the `ActionListener` interface, which, as I just mentioned, has one method: `actionPerformed`, whose signature looks like this:

```
public void actionPerformed(ActionEvent event)
```

The way to use the `ActionListener` interface is the same in all situations: The `actionPerformed` method (which is the only method in `ActionListener`) has an object of type `ActionEvent` as a parameter. This event object gives you information about the event that happened.

When a button is clicked, we want the background color of the panel to change to a particular color. We store the desired color in our listener class.

```
class ColorAction implements ActionListener
{
   private Color backgroundColor;

   public ColorAction(Color c)
   {
      backgroundColor = c;
   }

   public void actionPerformed(ActionEvent event)
   {
      // set panel background color
      . . .
   }
}
```

We then construct one object for each color and set the objects as the button listeners.

```
var yellowAction = new ColorAction(Color.YELLOW);
var blueAction = new ColorAction(Color.BLUE);
var redAction = new ColorAction(Color.RED);
```

```
yellowButton.addActionListener(yellowAction);
blueButton.addActionListener(blueAction);
redButton.addActionListener(redAction);
```

For example, if a user clicks on the button marked "Yellow", the `actionPerformed` method of the `yellowAction` object is called. Its `backgroundColor` instance field is set to `Color.YELLOW`, and it can now proceed to set the panel's background color.

Just one issue remains. The `ColorAction` object doesn't have access to the `buttonPanel` variable. You can solve this problem in two ways. You can store the panel in the `ColorAction` object and set it in the `ColorAction` constructor. Or, more conveniently, you can make `ColorAction` into an inner class of the `ButtonFrame` class. Its methods can then access the outer panel automatically.

Listing 10.6 contains the complete frame class. Whenever you click one of the buttons, the appropriate action listener changes the background color of the panel.

Listing 1.6 button/ButtonFrame.java

```
1 package button;
2
3 import java.awt.*;
```

```
4  import java.awt.event.*;
5  import javax.swing.*;
6
7  /**
8   * A frame with a button panel.
9   */
10 public class ButtonFrame extends JFrame
11 {
12    private JPanel buttonPanel;
13    private static final int DEFAULT_WIDTH = 300
14    private static final int DEFAULT_HEIGHT = 20
15
16    public ButtonFrame()
17    {
18       setSize(DEFAULT_WIDTH, DEFAULT_HEIGHT);
19
20       // create buttons
21       var yellowButton = new JButton("Yellow");
22       var blueButton = new JButton("Blue");
23       var redButton = new JButton("Red");
24
25       buttonPanel = new JPanel();
26
27       // add buttons to panel
28       buttonPanel.add(yellowButton);
29       buttonPanel.add(blueButton);
30       buttonPanel.add(redButton);
31
```

```
32          // add panel to frame
33          add(buttonPanel);
34
35          // create button actions
36          var yellowAction = new ColorAction(Color
37          var blueAction = new ColorAction(Color.BL
38          var redAction = new ColorAction(Color.RED
39
40          // associate actions with buttons
41          yellowButton.addActionListener(yellowActi
42          blueButton.addActionListener(blueAction);
43          redButton.addActionListener(redAction);
44       }
45
46       /**
47        * An action listener that sets the panel's
48        */
49       private class ColorAction implements ActionL
50       {
51          private Color backgroundColor;
52
53          public ColorAction(Color c)
54          {
55             backgroundColor = c;
56          }
57
58          public void actionPerformed(ActionEvent e
59          {
```

```
60            buttonPanel.setBackground(backgroundCo
61         }
62      }
63   }
```

`javax.swing.JButton` **1.2**

- `JButton(String label)`
- `JButton(Icon icon)`
- `JButton(String label, Icon icon)`
  construct a button. The label string can be plain text or HTML; for example, `"<html><b>Ok</b></html>"`.

`java.awt.Container` **1.0**

- `Component add(Component c)`
  adds the component `c` to this container.

1.4.3. Specifying Listeners Concisely

In the preceding section, we defined a class for the event listener and constructed three objects of that class. It is not all that common to have multiple instances of a listener class. Most commonly, each listener carries out a separate action. In that case, there is no need to make a separate class. Simply use a lambda expression:

```
exitButton.addActionListener(event -> System.exit(0))
```

Now consider the case in which we have multiple related actions, such as the color buttons of the preceding section. In such a case, implement a helper method:

```
public void makeButton(String name, Color backgroundC
{
   var button = new JButton(name);
   buttonPanel.add(button);
   button.addActionListener(event ->
      buttonPanel.setBackground(backgroundColor));
}
```

Note that the lambda expression refers to the parameter variable `backgroundColor`.

Then we simply call

```
makeButton("yellow", Color.YELLOW);
makeButton("blue", Color.BLUE);
makeButton("red", Color.RED);
```

Here, we construct three listener objects, one for each color, without explicitly defining a class. Each time the helper method is called, it makes an instance of a class that implements the `ActionListener` interface. Its `actionPerformed` action references the `backGroundColor` value that is, in fact, stored with the listener object. However, all this happens without you having to explicitly define listener classes, instance variables, or constructors that set them.

Note: In older code, you will often see the use of anonymous classes:

```
exitButton.addActionListener(new ActionLis
   {
      public void actionPerformed(new Acti
      {
         System.exit(0);
      }
   });
```

Of course, this rather verbose code is no longer necessary. Using a lambda expression is simpler and clearer.

1.4.4. Adapter Classes

Not all events are as simple to handle as button clicks. Suppose you want to monitor when the user tries to close the main frame in order to put up a dialog and exit the program only when the user agrees.

When the user tries to close a window, the `JFrame` object is the source of a `WindowEvent`. If you want to catch that event, you must have an appropriate listener object and add it to the frame's list of window listeners.

```
WindowListener listener = . . .;
frame.addWindowListener(listener);
```

The window listener must be an object of a class that implements the `WindowListener` interface. There are actually seven methods in the `WindowListener` interface. The frame calls them as the responses to seven distinct events that could happen to a window. The names are self-explanatory, except that "iconified" is usually called "minimized" under Windows. Here is the complete `WindowListener` interface:

```
public interface WindowListener
{
   void windowOpened(WindowEvent e);
```

```
    void windowClosing(WindowEvent e);
    void windowClosed(WindowEvent e);
    void windowIconified(WindowEvent e);
    void windowDeiconified(WindowEvent e);
    void windowActivated(WindowEvent e);
    void windowDeactivated(WindowEvent e);
}
```

Of course, we can define a class that implements the interface, add a call to `System.exit(0)` in the `windowClosing` method, and write do-nothing functions for the other six methods. However, typing code for six methods that don't do anything is the kind of tedious busywork that nobody likes. To simplify this task, each of the AWT listener interfaces that have more than one method comes with a companion *adapter* class that implements all the methods in the interface but does nothing with them. For example, the `WindowAdapter` class has seven do-nothing methods. You extend the adapter class to specify the desired reactions to some, but not all, of the event types in the interface. (An interface such as `ActionListener` that has only a single method does not need an adapter class.)

Here is how we can define a window listener that overrides the `windowClosing` method:

```
class Terminator extends WindowAdapter
{
   public void windowClosing(WindowEvent e)
   {
      if (user agrees)
         System.exit(0);
   }
}
```

Now you can register an object of type `Terminator` as the event listener:

```
var listener = new Terminator();
frame.addWindowListener(listener);
```

Note: Nowadays, one would implement do-nothing methods of the `WindowListener` interface as default methods. However, Swing was invented many years before there were default methods.

---

java.awt.event.WindowListener **1.1**

- `void windowOpened(WindowEvent e)`
  is called after the window has been opened.

- `void windowClosing(WindowEvent e)`
  is called when the user has issued a window manager command to close the window. Note that the window will close only if its `hide` or `dispose` method is called.
- `void windowClosed(WindowEvent e)`
  is called after the window has closed.
- `void windowIconified(WindowEvent e)`
  is called after the window has been iconified.
- `void windowDeiconified(WindowEvent e)`
  is called after the window has been deiconified.
- `void windowActivated(WindowEvent e)`
  is called after the window has become active. Only a frame or dialog can be active. Typically, the window manager decorates the active window—for example, by highlighting the title bar.
- `void windowDeactivated(WindowEvent e)`
  is called after the window has become deactivated.

`java.awt.event.WindowStateListener` **1.4**

- `void windowStateChanged(WindowEvent event)`
  is called after the window has been maximized, iconified, or restored to normal size.

1.4.5. Actions

It is common to have multiple ways to activate the same command. The user can choose a certain function through a menu, a keystroke, or a button on a toolbar. This is easy to achieve in the AWT event model: link all events to the same listener. For example, suppose `blueAction` is an action listener whose `actionPerformed` method changes the background color to blue. You can attach the same object as a listener to several event sources:

- A toolbar button labeled "Blue"
- A menu item labeled "Blue"
- A keystroke Ctrl+B

The color change command will now be handled in a uniform way, no matter whether it was caused by a button click, a menu selection, or a key press.

The Swing package provides a very useful mechanism to encapsulate commands and to attach them to multiple event sources: the `Action` interface. An *action* is an object that encapsulates

- A description of the command (as a text string and an optional icon); and
- Parameters that are necessary to carry out the command (such as the requested color in our example).

The `Action` interface has the following methods:

```
void actionPerformed(ActionEvent event)
void setEnabled(boolean b)
boolean isEnabled()
void putValue(String key, Object value)
Object getValue(String key)
void addPropertyChangeListener(PropertyChangeListener
void removePropertyChangeListener(PropertyChangeListe
```

The first method is the familiar method in the `ActionListener` interface; in fact, the `Action` interface extends the `ActionListener` interface. Therefore, you can use an `Action` object whenever an `ActionListener` object is expected.

The next two methods let you enable or disable the action and check whether the action is currently enabled. When an action is attached to a menu or toolbar and the action is disabled, the option is grayed out.

The `putValue` and `getValue` methods let you store and retrieve arbitrary name/value pairs in the action object. A couple of important predefined strings, namely `Action.NAME` and `Action.SMALL_ICON`, store action names and icons into an action object:

```
action.putValue(Action.NAME, "Blue");
action.putValue(Action.SMALL_ICON, new ImageIcon("blu
```

Table 10.1 shows all predefined action table names.

Table 1.1: Predefined Action Table Names

Name	Value
`NAME`	The name of the action, displayed on buttons and menu items.
`SMALL_ICON`	A place to store a small icon for display in a button, menu item, or toolbar.
`SHORT_DESCRIPTION`	A short description of the icon for display in a tooltip.
`LONG_DESCRIPTION`	A long description of the icon for potential use in online help. No Swing component uses this value.

Name	Value
`MNEMONIC_KEY`	A mnemonic abbreviation for display in menu items.
`ACCELERATOR_KEY`	A place to store an accelerator keystroke. No Swing component uses this value.
`ACTION_COMMAND_KEY`	Historically, used in the now-obsolete `registerKeyboardAction` method.
`DEFAULT`	Potentially useful catch-all property. No Swing component uses this value.

If the action object is added to a menu or toolbar, the name and icon are automatically retrieved and displayed in the menu item or toolbar button. The `SHORT_DESCRIPTION` value turns into a tooltip.

The final two methods of the `Action` interface allow other objects, in particular menus or toolbars that trigger the action, to be notified when the properties of the action object change. For example, if a menu is added as a property change listener of an action object and

the action object is subsequently disabled, the menu is called and can gray out the action name.

Note that `Action` is an *interface*, not a class. Any class implementing this interface must implement the seven methods we just discussed. Fortunately, a friendly soul has provided a class `AbstractAction` that implements all methods except for `actionPerformed`. That class takes care of storing all name/value pairs and managing the property change listeners. You simply extend `AbstractAction` and supply an `actionPerformed` method.

Let's build an action object that can execute color change commands. We store the name of the command, an icon, and the desired color. We store the color in the table of name/value pairs that the `AbstractAction` class provides. Here is the code for the `ColorAction` class. The constructor sets the name/value pairs, and the `actionPerformed` method carries out the color change action.

```
public class ColorAction extends AbstractAction
{
   public ColorAction(String name, Icon icon, Color c
   {
      putValue(Action.NAME, name);
      putValue(Action.SMALL_ICON, icon);
      putValue("color", c);
```

```
        putValue(Action.SHORT_DESCRIPTION, "Set panel c
    }

    public void actionPerformed(ActionEvent event)
    {
        Color c = (Color) getValue("color");
        buttonPanel.setBackground(c);
    }
}
```

Our test program creates three objects of this class, such as

```
var blueAction = new ColorAction("Blue", new ImageIco
```

Next, let's associate this action with a button. That is easy because we can use a `JButton` constructor that takes an `Action` object.

```
var blueButton = new JButton(blueAction);
```

That constructor reads the name and icon from the action, sets the short description as the tooltip, and sets the action as the listener. You can see the icons and a tooltip in Figure 10.15.

As demonstrated in the next chapter, it is just as easy to add the same action to a menu.



Figure 1.15: Buttons display the icons from the action objects.

Finally, we want to add the action objects to keystrokes so that an action is carried out when the user types a keyboard command. To associate actions with keystrokes, you first need to generate objects of the `KeyStroke` class. This convenience class encapsulates the description of a key. To generate a `KeyStroke` object, don't call a constructor but instead use the static `getKeyStroke` method of the `KeyStroke` class.

```
KeyStroke ctrlBKey = KeyStroke.getKeyStroke("ctrl B")
```

To understand the next step, you need to understand the concept of *keyboard focus*. A user interface can have many buttons, menus, scrollbars, and other components. When you hit a key, it is sent to

the component that has focus. That component is usually (but not always) visually distinguished. For example, in the Java look-and-feel, a button with focus has a thin rectangular border around the button text. You can use the Tab key to move the focus between components. When you press the space bar, the button with focus is clicked. Other keys carry out different actions; for example, the arrow keys can move a scrollbar.

However, in our case, we do not want to send the keystroke to the component that has focus. Otherwise, each of the buttons would need to know how to handle the Ctrl+Y, Ctrl+B, and Ctrl+R keys.

This is a common problem, and the Swing designers came up with a convenient solution. Every `JComponent` has three *input maps*, each mapping `KeyStroke` objects to associated actions. The three input maps correspond to three different conditions (see Table 10.2).

Table 1.2: Input Map Conditions

Flag	Invoke Action
`WHEN_FOCUSED`	When this component has keyboard focus

Flag	Invoke Action
`WHEN_ANCESTOR_OF_FOCUSED_COMPONENT`	When this component contains the component that has keyboard focus
`WHEN_IN_FOCUSED_WINDOW`	When this component is contained in the same window as the component that has keyboard focus

Keystroke processing checks these maps in the following order:

1. Check the `WHEN_FOCUSED` map of the component with input focus. If the keystroke exists and its corresponding action is enabled, execute the action and stop processing.

2. Starting from the component with input focus, check the `WHEN_ANCESTOR_OF_FOCUSED_COMPONENT` maps of its parent components. As soon as a map with the keystroke and a corresponding enabled action is found, execute the action and stop processing.
3. Look at all *visible* and *enabled* components, in the window with input focus, that have this keystroke registered in a `WHEN_IN_FOCUSED_WINDOW` map. Give these components (in the order of their keystroke registration) a chance to execute the corresponding action. As soon as the first enabled action is executed, stop processing.

To obtain an input map from the component, use the `getInputMap` method. Here is an example:

```
InputMap imap = panel.getInputMap(JComponent.WHEN_FOC
```

The `WHEN_FOCUSED` condition means that this map is consulted when the current component has the keyboard focus. In our situation, that isn't the map we want. One of the buttons, not the panel, has the input focus. Either of the other two map choices works fine for inserting the color change keystrokes. We use `WHEN_ANCESTOR_OF_FOCUSED_COMPONENT` in our example program.

The `InputMap` doesn't directly map `KeyStroke` objects to `Action` objects. Instead, it maps to arbitrary objects, and a second map, implemented by the `ActionMap` class, maps objects to actions. That makes it easier to share the same actions among keystrokes that come from different input maps.

Thus, each component has three input maps and one action map. To tie them together, you need to come up with names for the actions. Here is how you can tie a key to an action:

```
imap.put(KeyStroke.getKeyStroke("ctrl Y"), "panel.yel
ActionMap amap = panel.getActionMap();
amap.put("panel.yellow", yellowAction);
```

It is customary to use the string `"none"` for a do-nothing action. That makes it easy to deactivate a key:

```
imap.put(KeyStroke.getKeyStroke("ctrl C"), "none");
```

Caution: The JDK documentation suggests using the action name as the action's key. I don't think that is a good idea. The action name is displayed on buttons and menu items; thus, it can change at the whim of the UI designer and may be translated into multiple languages. Such unstable strings are poor choices for lookup keys,

so I recommend that you come up with action names that are independent of the displayed names.

To summarize, here is what you do to carry out the same action in response to a button, a menu item, or a keystroke:

1. Implement a class that extends the `AbstractAction` class. You may be able to use the same class for multiple related actions.
2. Construct an object of the action class.
3. Construct a button or menu item from the action object. The constructor will read the label text and icon from the action object.
4. For actions that can be triggered by keystrokes, you have to carry out additional steps. First, locate the top-level component of the window, such as a panel that contains all other components.
5. Then, get the `WHEN_ANCESTOR_OF_FOCUSED_COMPONENT` input map of the top-level component. Make a `KeyStroke` object for the desired keystroke. Make an action key object, such as a string that describes your action. Add the pair (keystroke, action key) into the input map.
6. Finally, get the action map of the top-level component. Add the pair (action key, action object) into the map.

javax.swing.Action 1.2

- `boolean isEnabled()`
- `void setEnabled(boolean b)`
  get or set the `enabled` property of this action.
- `void putValue(String key, Object value)`
  places a key/value pair inside the action object. The key can be any string, but several names have predefined meanings—see Table 10.1.
- `Object getValue(String key)`
  returns the value of a stored name/value pair.

`javax.swing.KeyStroke` 1.2

- `static KeyStroke getKeyStroke(String description)`
  constructs a keystroke from a human-readable description (a sequence of whitespace-delimited strings). The description starts with zero or more modifiers (`shift` , `control` , `ctrl` , `meta` , `alt` , `altGraph`) and ends with either the string `typed` , followed by a one-character string (for example, `"typed a"`), or an optional event specifier (`pressed` or `released` , with `pressed` being the default), followed by a key code. The key code, when prefixed with `VK_` , should correspond to a

`KeyEvent` constant; for example, `"INSERT"` corresponds to `KeyEvent.VK_INSERT`.

`javax.swing.JComponent` `1.2`

- `ActionMap getActionMap()` `1.3`
  returns the map that associates action map keys (which can be arbitrary objects) with `Action` objects.
- `InputMap getInputMap(int flag)` `1.3`
  gets the input map that maps key strokes to action map keys. The flag is one of the values in Table 10.2.

1.4.6. Mouse Events

You do not need to handle mouse events explicitly if you just want the user to be able to click on a button or menu. These mouse operations are handled internally by the various components in the user interface. However, if you want to enable the user to draw with the mouse, you will need to trap the mouse move, click, and drag events.

In this section, I will show you a simple graphics editor application that allows the user to place, move, and erase squares on a canvas (see Figure 10.16).



Figure 1.16: A mouse test program

When the user clicks a mouse button, three listener methods are called: `mousePressed` when the mouse is first pressed, `mouseReleased` when the mouse is released, and, finally, `mouseClicked`. If you are only interested in complete clicks, you can ignore the first two methods. By using the `getX` and `getY` methods on the `MouseEvent` parameter, you can obtain the *x* and *y* coordinates of the mouse pointer when the mouse was clicked. To distinguish between single, double, and triple (!) clicks, use the `getClickCount` method.

In our sample program, we supply both a `mousePressed` and a `mouseClicked` method. When you click on a pixel that is not inside any of the squares that have been drawn, a new square is added. We implemented this in the `mousePressed` method so that the user receives immediate feedback and does not have to wait until the mouse button is released. When a user double-clicks inside an

existing square, it is erased. We implemented this in the `mouseClicked` method because we need the click count.

```
public void mousePressed(MouseEvent event)
{
   current = find(event.getPoint());
   if (current == null) // not inside a square
      add(event.getPoint());
}

public void mouseClicked(MouseEvent event)
{
   current = find(event.getPoint());
   if (current != null && event.getClickCount() >= 2)
      remove(current);
}
```

As the mouse moves over a window, the window receives a steady stream of mouse movement events. Note that there are separate `MouseListener` and `MouseMotionListener` interfaces. This is done for efficiency—there are a lot of mouse events as the user moves the mouse around, and a listener that just cares about mouse *clicks* will not be bothered with unwanted mouse *moves*.

Our test application traps mouse motion events to change the cursor to a different shape (a cross hair) when it is over a square. This is

done with the `getPredefinedCursor` method of the `Cursor` class. Table 10.3 lists the constants to use with this method along with what the cursors look like under Windows.

Table 1.3: Sample Cursor Shapes

Icon	Constant	Icon	Constant
	`DEFAULT_CURSOR`		`NE_RESIZE_CURSOR`
	`CROSSHAIR_CURSOR`		`E_RESIZE_CURSOR`
	`HAND_CURSOR`		`SE_RESIZE_CURSOR`
	`MOVE_CURSOR`		`S_RESIZE_CURSOR`
	`TEXT_CURSOR`		`SW_RESIZE_CURSOR`

Icon	Constant	Icon	Constant
	`WAIT_CURSOR`		`W_RESIZE_CURSOR`
	`N_RESIZE_CURSOR`		`NW_RESIZE_CURSOR`

Here is the `mouseMoved` method of the `MouseMotionListener` in our example program:

```
public void mouseMoved(MouseEvent event)
{
   if (find(event.getPoint()) == null)
      setCursor(Cursor.getDefaultCursor());
   else
      setCursor(Cursor.getPredefinedCursor(Cursor.CRO
}
```

If the user presses a mouse button while the mouse is in motion, `mouseDragged` calls are generated instead of `mouseMoved` calls. Our test application lets a user drag the square under the cursor. We simply update the currently dragged rectangle to be centered under

the mouse position. Then, we repaint the canvas to show the new mouse position.

```
public void mouseDragged(MouseEvent event)
{
   if (current != null)
   {
      int x = event.getX();
      int y = event.getY();

      current.setFrame(x - SIDELENGTH / 2, y - SIDELE
      repaint();
   }
}
```

Note: The `mouseMoved` method is only called as long as the mouse stays inside the component. However, the `mouseDragged` method keeps getting called even when the mouse is being dragged outside the component.

There are two other mouse event methods: `mouseEntered` and `mouseExited`. These methods are called when the mouse enters or exits a component.

Finally, let's see how to listen to mouse events. Mouse clicks are reported through the `mouseClicked` method, which is part of the `MouseListener` interface. Many applications are only interested in mouse clicks and not in mouse moves; with the mouse move events occurring so frequently, the mouse move and drag events are defined in a separate interface called `MouseMotionListener`.

In our program we are interested in both types of mouse events. We define two inner classes: `MouseHandler` and `MouseMotionHandler`. The `MouseHandler` class extends the `MouseAdapter` class because it defines only two of the five `MouseListener` methods. (The `MouseAdapter` class defines all of them as do-nothing methods.) The `MouseMotionHandler` implements the `MouseMotionListener` and defines both methods of that interface. Listing 10.7 is the program listing.

Listing 1.7 mouse/MouseComponent.java

```
1  package mouse;
2
3  import java.awt.*;
4  import java.awt.event.*;
5  import java.awt.geom.*;
6  import java.util.*;
7  import javax.swing.*;
8
```

```
 9  /**
10   * A component with mouse operations for adding
11   */
12  public class MouseComponent extends JComponent
13  {
14     private static final int DEFAULT_WIDTH = 300
15     private static final int DEFAULT_HEIGHT = 20
16
17     private static final int SIDELENGTH = 10;
18     private ArrayList<Rectangle2D> squares;
19     private Rectangle2D current; // the square c
20
21     public MouseComponent()
22     {
23        squares = new ArrayList<>();
24        current = null;
25
26        addMouseListener(new MouseHandler());
27        addMouseMotionListener(new MouseMotionHan
28     }
29
30     public Dimension getPreferredSize()
31     {
32        return new Dimension(DEFAULT_WIDTH, DEFAU
33     }
34
35     public void paintComponent(Graphics g)
36     {
```

```
37          var g2 = (Graphics2D) g;
38
39          // draw all squares
40          for (Rectangle2D r : squares)
41             g2.draw(r);
42       }
43
44       /**
45        * Finds the first square containing a point
46        * @param p a point
47        * @return the first square that contains p
48        */
49       public Rectangle2D find(Point2D p)
50       {
51          for (Rectangle2D r : squares)
52          {
53             if (r.contains(p)) return r;
54          }
55          return null;
56       }
57
58       /**
59        * Adds a square to the collection.
60        * @param p the center of the square
61        */
62       public void add(Point2D p)
63       {
64          double x = p.getX();
```

```
65          double y = p.getY();
66
67          current = new Rectangle2D.Double(x - SIDE
68             SIDELENGTH, SIDELENGTH);
69          squares.add(current);
70          repaint();
71       }
72
73       /**
74        * Removes a square from the collection.
75        * @param s the square to remove
76        */
77       public void remove(Rectangle2D s)
78       {
79          if (s == null) return;
80          if (s == current) current = null;
81          squares.remove(s);
82          repaint();
83       }
84
85       private class MouseHandler extends MouseAdap
86       {
87          public void mousePressed(MouseEvent event
88          {
89             // add a new square if the cursor isn
90             current = find(event.getPoint());
91             if (current == null) add(event.getPoi
92          }
```

```
93
94          public void mouseClicked(MouseEvent event
95          {
96             // remove the current square if double
97             current = find(event.getPoint());
98             if (current != null && event.getClickC
99          }
100      }
101
102      private class MouseMotionHandler implements
103      {
104         public void mouseMoved(MouseEvent event)
105         {
106            // set the mouse cursor to cross hairs
107
108            if (find(event.getPoint()) == null) se
109            else setCursor(Cursor.getPredefinedCur
110         }
111
112         public void mouseDragged(MouseEvent event
113         {
114            if (current != null)
115            {
116               int x = event.getX();
117               int y = event.getY();
118
119               // drag the current rectangle to ce
120               current.setFrame(x - SIDELENGTH / 2
```

```
121                repaint();
122             }
123          }
124       }
125    }
```

`java.awt.event.MouseEvent` **1.1**

- `int getX()`
- `int getY()`
- `Point getPoint()`
  return the *x* (horizontal) and *y* (vertical) coordinates of the point where the event happened, measured from the top left corner of the component that is the event source.
- `int getClickCount()`
  returns the number of consecutive mouse clicks associated with this event. (The time interval for what constitutes "consecutive" is system-dependent.)

`java.awt.Component` **1.0**

- `public void setCursor(Cursor cursor)` **1.1**
  sets the cursor image to the specified cursor.

1.4.7. The AWT Event Hierarchy

The `EventObject` class has a subclass `AWTEvent`, which is the parent of all AWT event classes. Figure 10.17 shows the inheritance diagram of the AWT events.



Figure 1.17: Inheritance diagram of AWT event classes

Some of the Swing components generate event objects of yet more event types; these directly extend `EventObject`, not `AWTEvent`.

The event objects encapsulate information about the event that the event source communicates to its listeners. When necessary, you can then analyze the event objects that were passed to the listener object, as we did in the button example with the `getSource` and `getActionCommand` methods.

Some of the AWT event classes are of no practical use for the Java programmer. For example, the AWT inserts `PaintEvent` objects into the event queue, but these objects are not delivered to listeners. Java programmers don't listen to paint events; instead, they override the `paintComponent` method to control repainting. The AWT also generates a number of events that are needed only by systems programmers, to provide input systems for ideographic languages, automated testing robots, and so on.

The AWT makes a useful distinction between *low-level* and *semantic* events. A semantic event is one that expresses what the user is doing, such as "clicking that button"; an `ActionEvent` is a semantic event. Low-level events are those events that make this possible. In the case of a button click, this is a mouse down, a series of mouse moves, and a mouse up (but only if the mouse up is inside the button area). Or it might be a keystroke, which happens if the user selects the button with the Tab key and then activates it with the space bar. Similarly, adjusting a scrollbar is a semantic event, but dragging the mouse is a low-level event.

Here are the most commonly used semantic event classes in the `java.awt.event` package:

- `ActionEvent` (for a button click, a menu selection, selecting a list item, or Enter typed in a text field)
- `AdjustmentEvent` (the user adjusted a scrollbar)
- `ItemEvent` (the user made a selection from a set of checkbox or list items)

Five low-level event classes are commonly used:

- `KeyEvent` (a key was pressed or released)
- `MouseEvent` (the mouse button was pressed, released, moved, or dragged)
- `MouseWheelEvent` (the mouse wheel was rotated)
- `FocusEvent` (a component got focus or lost focus)
- `WindowEvent` (the window state changed)

Table 10.4 shows the most important AWT listener interfaces, events, and event sources.

Table 1.4: Event Handling Summary

Interface	Methods	Param

Interface	Methods	Param
`ActionListener`	`actionPerformed`	`Acti` • `ge` • `ge`
`AdjustmentListener`	`adjustmentValueChanged`	`Adju` • `ge` • `ge` • `ge`
`ItemListener`	`itemStateChanged`	`Item` • `ge` • `ge` • `ge`
`FocusListener`	`focusGained` `focusLost`	`Focu` • `is`

Interface	Methods	Param

`KeyListener`	`keyPressed`
	`keyReleased`
	`keyTyped`
		`KeyEv`
		• `ge`
		• `ge`
		• `ge`
		• `ge`
		• `is`

`MouseListener`	`mousePressed`
	`mouseReleased`
	`mouseEntered`
	`mouseExited`
	`mouseClicked`
		`Mouse`
		• `ge`
		• `ge`
		• `ge`
		• `ge`
		• `tr`

`MouseMotionListener`	`mouseDragged` `mouseMoved`	`Mouse`

Interface	Methods	Param
`MouseWheelListener`	`mouseWheelMoved`	`Mouse` • `ge` • `ge`

`WindowListener`	`windowClosing`
	`windowOpened`
	`windowIconified`
	`windowDeiconified`
	`windowClosed`
	`windowActivated`
	`windowDeactivated`
		`Windo`
		• `ge`

`WindowFocusListener`	`windowGainedFocus` `windowLostFocus`	`Windo` • `ge`
`WindowStateListener`	`windowStateChanged`	`Windo` • `ge`

Interface	Methods	Param
	• `ge`	

1.5. The Preferences API

I end this chapter with a discussion of the `java.util.prefs` API. In a desktop program, you will often want to store user preferences, such as the last file that the user worked on, the last window location, and so on.

As you have seen in Chapter 9 of Volume I, the `Properties` class makes it simple to load and save configuration information of a program. However, using property files has these disadvantages:

- Some operating systems have no concept of a home directory, making it difficult to find a uniform location for configuration files.
- There is no standard convention for naming configuration files, increasing the likelihood of name clashes as users install multiple Java applications.

Some operating systems have a central repository for configuration information. The best-known example is the registry in Microsoft

Windows. The `Preferences` class provides such a central repository in a platform-independent manner. In Windows, the `Preferences` class uses the registry for storage; on Linux, the information is stored in the local file system instead. Of course, the repository implementation is transparent to the programmer using the `Preferences` class.

The `Preferences` repository has a tree structure, with node path names such as `/com/mycompany/myapp.` As with package names, name clashes are avoided as long as programmers start the paths with reversed domain names. In fact, the designers of the API suggest that the configuration node paths match the package names in your program.

Each node in the repository has a separate table of key/value pairs that you can use to store numbers, strings, or byte arrays. No provision is made for storing serializable objects. The API designers felt that the serialization format is too fragile for long-term storage. Of course, if you disagree, you can save serialized objects in byte arrays.

For additional flexibility, there are multiple parallel trees. Each program user has one tree; an additional tree, called the system tree, is available for settings that are common to all users. The

`Preferences` class uses the operating system's notion of the "current user" for accessing the appropriate user tree.

To access a node in the tree, start with the user or system root:

```
  Preferences root = Preferences.userRoot();
```

or

```
  Preferences root = Preferences.systemRoot();
```

Then access the node. You can simply provide a node path name:

```
  Preferences node = root.node("/com/mycompany/myapp");
```

A convenient shortcut gets a node whose path name equals the package name of a class. Simply take an object of that class and call

```
  Preferences node = Preferences.userNodeForPackage(obj
```

or

```
Preferences node = Preferences.systemNodeForPackage(o
```

Typically, `obj` will be the `this` reference.

Once you have a node, you can access the key/value table with methods

```
String get(String key, String def)
int getInt(String key, int def)
long getLong(String key, long def)
float getFloat(String key, float def)
double getDouble(String key, double def)
boolean getBoolean(String key, boolean def)
byte[] getByteArray(String key, byte[] def)
```

Note that you must specify a default value when reading the information, in case the repository data is not available. Defaults are required for several reasons. The data might be missing because the user never specified a preference. Certain resource-constrained platforms might not have a repository, and mobile devices might be temporarily disconnected from the repository.

Conversely, you can write data to the repository with `put` methods such as

```
put(String key, String value)
putInt(String key, int value)
```

and so on.

You can enumerate all keys stored in a node with the method

```
String[] keys()
```

There is currently no way to find out the type of the value of a particular key.

Note: Node names and keys are limited to 80 characters, and string values to 8,192 characters.

Central repositories such as the Windows registry traditionally suffer from two problems:

- They turn into a “dumping ground” filled with obsolete information.
- Configuration data gets entangled into the repository, making it difficult to move preferences to a new platform.

The `Preferences` class has a solution for the second problem. You can export the preferences of a subtree (or, less commonly, a single

node) by calling the methods

```
void exportSubtree(OutputStream out)
void exportNode(OutputStream out)
```

The data are saved in XML format. You can import them into another repository by calling

```
void importPreferences(InputStream in)
```

Here is a sample file:

```
<?xml version="1.0" encoding="UTF-8"?>
<!DOCTYPE preferences SYSTEM "http://java.sun.com/dtd
<preferences EXTERNAL_XML_VERSION="1.0">
   <root type="user">
      <map/>
      <node name="com">
         <map/>
         <node name="horstmann">
            <map/>
            <node name="corejava">
               <map>
            <entry key="height" value="200.0"/>
            <entry key="left" value="1027.0"/>
            <entry key="filename" value="/home/cay/bo
```

```
            <entry key="top" value="380.0"/>
            <entry key="width" value="300.0"/>
               </map>
            </node>
         </node>
      </node>
   </root>
</preferences>
```

If your program uses preferences, you should give your users the opportunity of exporting and importing them, so they can easily migrate their settings from one computer to another. The program in Listing 10.8 demonstrates this technique. The program simply saves the window location and the last loaded filename. Try resizing the window, then export your preferences, move the window, exit, and restart the application. The window will be just like you left it when you exited. Import your preferences, and the window reverts to its prior location.

Listing 1.8 preferences/ImageViewer.java

```
1  package preferences;
2
3  import java.awt.EventQueue;
4  import java.awt.event.*;
5  import java.io.*;
```

```
6  import java.util.prefs.*;
7  import javax.swing.*;
8
9  /**
10  * A program to test preference settings. The p
11  * frame position, size, and last selected file
12  * @version 1.10 2018-04-10
13  * @author Cay Horstmann
14  */
15 public class ImageViewer
16 {
17    public static void main(String[] args)
18    {
19       EventQueue.invokeLater(() ->
20          {
21             var frame = new ImageViewerFrame();
22             frame.setTitle("ImageViewer");
23             frame.setDefaultCloseOperation(JFra
24             frame.setVisible(true);
25          });
26    }
27 }
28
29 /**
30  * An image viewer that restores position, size
31  * preferences and updates the preferences upon
32  */
33 class ImageViewerFrame extends JFrame
```

```
34 {
35    private static final int DEFAULT_WIDTH = 300
36    private static final int DEFAULT_HEIGHT = 20
37    private String image;
38
39    public ImageViewerFrame()
40    {
41       Preferences root = Preferences.userRoot()
42       Preferences node = root.node("/com/horstm
43       // get position, size, title from propert
44       int left = node.getInt("left", 0);
45       int top = node.getInt("top", 0);
46       int width = node.getInt("width", DEFAULT_
47       int height = node.getInt("height", DEFAUL
48       setBounds(left, top, width, height);
49       image = node.get("image", null);
50       var label = new JLabel();
51       if (image != null) label.setIcon(new Imag
52
53       addWindowListener(new WindowAdapter()
54       {
55          public void windowClosing(WindowEvent
56          {
57             node.putInt("left", getX());
58             node.putInt("top", getY());
59             node.putInt("width", getWidth());
60             node.putInt("height", getHeight());
61             if (image != null) node.put("image"
```

```
62          }
63       });
64
65       // use a label to display the images
66       add(label);
67
68       // set up the file chooser
69       var chooser = new JFileChooser();
70       chooser.setCurrentDirectory(new File(".")
71
72       // set up the menu bar
73       var menuBar = new JMenuBar();
74       setJMenuBar(menuBar);
75
76       var menu = new JMenu("File");
77       menuBar.add(menu);
78
79       var openItem = new JMenuItem("Open");
80       menu.add(openItem);
81       openItem.addActionListener(event ->
82          {
83             // show file chooser dialog
84             int result = chooser.showOpenDialog
85
86             // if file selected, set it as icon
87             if (result == JFileChooser.APPROVE_
88             {
89                image = chooser.getSelectedFile(
```

```
90                label.setIcon(new ImageIcon(imag
91             }
92          });
93
94       var exitItem = new JMenuItem("Exit");
95       menu.add(exitItem);
96       exitItem.addActionListener(event -> Syste
97    }
98 }
```

`java.util.prefs.Preferences` **1.4**

- `Preferences userRoot()`
  returns the root preferences node of the user of the calling program.
- `Preferences systemRoot()`
  returns the systemwide root preferences node.
- `Preferences node(String path)`
  returns a node that can be reached from the current node by the given path. If `path` is absolute (that is, starts with a `/`), then the node is located starting from the root of the tree containing this preference node. If there isn't a node with the given path, it is created.

- `Preferences userNodeForPackage(Class cl)`
- `Preferences systemNodeForPackage(Class cl)`
  return a node in the current user's tree or the system tree whose absolute node path corresponds to the package name of the class `cl`.
- `String[] keys()`
  returns all keys belonging to this node.
- `String get(String key, String def)`
- `int getInt(String key, int def)`
- `long getLong(String key, long def)`
- `float getFloat(String key, float def)`
- `double getDouble(String key, double def)`
- `boolean getBoolean(String key, boolean def)`
- `byte[] getByteArray(String key, byte[] def)`
  return the value associated with the given key—or the supplied default value if no value is associated with the key, the associated value is not of the correct type, or the preferences store is unavailable.

- `void put(String key, String value)`
- `void putInt(String key, int value)`
- `void putLong(String key, long value)`
- `void putFloat(String key, float value)`
- `void putDouble(String key, double value)`
- `void putBoolean(String key, boolean value)`
- `void putByteArray(String key, byte[] value)`
  store a key/value pair with this node.
- `void exportSubtree(OutputStream out)`
  writes the preferences of this node and its children to the specified stream.
- `void exportNode(OutputStream out)`
  writes the preferences of this node (but not its children) to the specified stream.
- `void importPreferences(InputStream in)`
  imports the preferences contained in the specified stream.

This concludes our introduction into graphical user interface programming. The next chapter shows you how to work with the most common Swing components.

1. User Interface Components with Swing

The previous chapter was written primarily to show you how to use the event model in Java. In the process, you took the first steps toward learning how to build a graphical user interface. This chapter shows you the most important tools you'll need to build more full-featured GUIs.

We start out with a tour of the architectural underpinnings of Swing. Knowing what goes on "under the hood" is important in understanding how to use some of the more advanced components effectively. I then show you the most common user interface components in Swing, such as text fields, radio buttons, and menus. Next, you will learn how to use layout managers to arrange these components. Finally, you'll see how to implement dialog boxes in Swing.

This chapter covers the basic Swing components such as text components, buttons, and sliders. These are the essential user interface components that you will need most frequently. We will cover advanced Swing components in Chapter 12.

1.1. Swing and the Model-View-Controller Design Pattern

Let's step back for a minute and think about the pieces that make up a user interface component such as a button, a checkbox, a text field, or a sophisticated tree control. Every component has three characteristics:

- Its *content*, such as the state of a button (pushed in or not), or the text in a text field
- Its *visual appearance* (color, size, and so on)
- Its *behavior* (reaction to events)

Even a seemingly simple component such as a button exhibits some moderately complex interaction among these characteristics. Obviously, the visual appearance of a button depends on the look-and-feel. A Metal button looks different from a Windows button or a Motif button. In addition, the appearance depends on the button state; when a button is pushed in, it needs to be redrawn to look different. The state depends on the events that the button receives. When the user depresses the mouse inside the button, the button is pushed in.

Of course, when you use a button in your programs, you simply consider it as a *button*; you don't think too much about the inner

workings and characteristics. That, after all, is the job of the programmer who implemented the button. However, programmers who implement buttons and all other user interface components are motivated to think a little harder about them, so that they work well no matter what look-and-feel is in effect.

To do this, the Swing designers turned to a well-known design pattern: the *model-view-controller* (MVC) pattern. This design pattern tells us to provide three separate objects:

- The *model,* which stores the content
- The *view,* which displays the content
- The *controller,* which handles user input

The pattern specifies precisely how these three objects interact. The model stores the content and has *no user interface*. For a button, the content is pretty trivial—just a small set of flags that tells whether the button is currently pushed in or out, whether it is active or inactive, and so on. For a text field, the content is a bit more interesting. It is a string object that holds the current text. This is *not the same* as the view of the content—if the content is larger than the text field, the user sees only a portion of the text displayed (see Figure 11.1).



Figure 1.1: Model and view of a text field

The model must implement methods to change the content and to discover what the content is. For example, a text model has methods to add or remove characters in the current text and to return the current text as a string. Again, keep in mind that the model is completely nonvisual. It is the job of a view to draw the data stored in the model.

Note: The term "model" is perhaps unfortunate because we often think of a model as a representation of an abstract concept. Car and airplane designers build models to simulate real cars and planes. But that analogy really leads you astray when thinking about the model-view-controller pattern. In this design pattern, the model stores the complete content, and the view gives a (complete or incomplete) visual representation of the content. A better analogy might be the model who poses for an artist. It is up to the artist to look at the model and create a view. Depending on the artist, that view might be a formal

portrait, an impressionist painting, or a cubist drawing with strangely contorted limbs.

One of the advantages of the model-view-controller pattern is that a model can have multiple views, each showing a different part or aspect of the full content. For example, an HTML editor can offer two *simultaneous* views of the same content: a WYSIWYG view and a "raw tag" view (see Figure 11.2). When the model is updated through the controller of one of the views, it tells both attached views about the change. When the views are notified, they refresh themselves automatically. Of course, for a simple user interface component such as a button, you won't have multiple views of the same model.



Figure 1.2: Two separate views of the same model

The controller handles the user-input events, such as mouse clicks and keystrokes. It then decides whether to translate these events into changes in the model or the view. For example, if the user presses a character key in a text box, the controller calls the "insert character" command of the model. The model then tells the view to update itself. The view never knows why the text changed. But if the user presses a cursor key, the controller may tell the view to scroll. Scrolling the view has no effect on the underlying text, so the model never knows that this event happened.

Figure 11.3 shows the interactions among model, view, and controller objects.



Figure 1.3: Interactions among model, view, and controller objects

For most Swing components, the model class implements an interface whose name ends in `Model`; in this case, the interface is

called `ButtonModel`. Classes implementing that interface can define the state of the various kinds of buttons. Actually, buttons aren't all that complicated, and the Swing library contains a single class, called `DefaultButtonModel`, that implements this interface.

You can get a sense of the sort of data maintained by a button model by looking at the properties of the `ButtonModel` interface—see Table 11.1.

Table 1.1: Properties of the `ButtonModel` Interface

Property Name	Value
`actionCommand`	The action command string associated with this button
`mnemonic`	The keyboard mnemonic for this button
`armed`	`true` if the button was pressed and the mouse is still over the button
`enabled`	`true` if the button is selectable
`pressed`	`true` if the button was pressed but the mouse button hasn't yet been released

Property Name	Value
`rollover`	`true` if the mouse is over the button
`selected`	`true` if the button has been toggled on (used for checkboxes and radio buttons)

Each `JButton` object stores a button model object which you can retrieve.

```
var button = new JButton("Blue");
ButtonModel model = button.getModel();
```

In practice, you won't care—the minutiae of the button state are only of interest to the view that draws it. All the important information—such as whether a button is enabled—is available from the `JButton` class. (Of course, the `JButton` then asks its model to retrieve that information.)

Have another look at the `ButtonModel` interface to see what *isn't* there. The model does *not* store the button label or icon. There is no way to find out what's on the face of a button just by looking at its

model. (Actually, as you will see in Section 11.4.2, this purity of design is the source of some grief for the programmer.)

It is also worth noting that the *same* model (namely, `DefaultButtonModel`) is used for push buttons, radio buttons, checkboxes, and even menu items. Of course, each of these button types has different views and controllers. When using the Metal look-and-feel, the `JButton` uses a class called `BasicButtonUI` for the view and a class called `ButtonUIListener` as controller. In general, each Swing component has an associated view object that ends in `UI`. But not all Swing components have dedicated controller objects.

So, having read this short introduction to what is going on under the hood in a `JButton`, you may be wondering: Just what is a `JButton` really? It is simply a wrapper class inheriting from `JComponent` that holds the `DefaultButtonModel` object, some view data (such as the button label and icons), and a `BasicButtonUI` object that is responsible for the button view and installs a `BasicButtonListener` with button-specific controller functionality.

1.2. Introduction to Layout Management

Before we go on to discussing individual Swing components, such as text fields and radio buttons, let's briefly cover how to arrange these components inside a frame.

Of course, Java development environments have drag-and-drop GUI builders. Nevertheless, it is important to know exactly what goes on "under the hood" because even the best of these tools will usually require hand-tweaking.

1.2.1. Layout Managers

Let's start by reviewing the program from Chapter 10 that used buttons to change the background color of a frame.

The buttons are contained in a `JPanel` object and are managed by the *flow layout manager*, the default layout manager for a panel. Figure 11.4 shows what happens when you add more buttons to the panel. As you can see, a new row is started when there is no more room.



Figure 1.4: A panel with six buttons managed by a flow layout

Moreover, the buttons stay centered in the panel, even when the user resizes the frame (see Figure 11.5).



Figure 1.5: Changing the panel size rearranges the buttons automatically.

In general, *components* are placed inside *containers*, and a *layout manager* determines the positions and sizes of components in a container.

Buttons, text fields, and other user interface elements extend the class `Component`. Components can be placed inside containers, such as panels. Containers can themselves be put inside other containers, so the class `Container` extends `Component`. Figure 11.6 shows the inheritance hierarchy for `Component`.



Figure 1.6: Inheritance hierarchy for the `Component` class

Note: Unfortunately, the inheritance hierarchy is somewhat unclean in two respects. First, top-level windows, such as `JFrame`, are subclasses of `Container` and hence `Component`, but they cannot be placed inside other containers. Moreover, `JComponent` is a subclass of `Container`, not `Component`. Therefore one can add other components into a `JButton`. (However, those components would not be displayed.)

Each container has a default layout manager, but you can always set your own. For example, the statement

```
panel.setLayout(new GridLayout(4, 4));
```

uses the `GridLayout` class to lay out the components in four rows and four columns. When you add components to the container, the `add` method of the container passes the component and any placement directions to the layout manager.

`java.awt.Container` **1.0**

- `void setLayout(LayoutManager m)`
  sets the layout manager for this container.
- `Component add(Component c)`
- `Component add(Component c, Object constraints)` **1.1**
  add a component to this container and return the component reference.

`java.awt.FlowLayout` **1.0**

- `FlowLayout()`
- `FlowLayout(int align)`
- `FlowLayout(int align, int hgap, int vgap)`
  construct a new `FlowLayout`. The `align` parameter is one of `LEFT`, `CENTER`, or `RIGHT`.

1.2.2. Border Layout

The *border layout manager* is the default layout manager of the content pane of every `JFrame`. Unlike the flow layout manager, which completely controls the position of each component, the border layout manager lets you choose where you want to place each component. You can choose to place the component in the center, north, south, east, or west of the content pane (see Figure 11.7).



Figure 1.7: Border layout

For example:

```
frame.add(component, BorderLayout.SOUTH);
```

The edge components are laid out first, and the remaining available space is occupied by the center. When the container is resized, the dimensions of the edge components are unchanged, but the center component changes its size. Add components by specifying a constant `CENTER`, `NORTH`, `SOUTH`, `EAST`, or `WEST` of the `BorderLayout` class. Not all of the positions need to be occupied. If you don't supply any value, `CENTER` is assumed.

Note: The `BorderLayout` constants are defined as strings. For example, `BorderLayout.SOUTH` is defined as the string `"South"`. This is safer than using strings. If you accidentally misspell a string, for example, `frame.add(component, "south")`, the compiler won't catch that error.

Unlike the flow layout, the border layout grows all components to fill the available space. (The flow layout leaves each component at its preferred size.) This is a problem when you add a button:

```
frame.add(yellowButton, BorderLayout.SOUTH); // don't
```

Figure 11.8 shows what happens when you use the preceding code fragment. The button has grown to fill the entire southern region of the frame. And, if you were to add another button to the southern region, it would just displace the first button.

Figure 1.8: A single button managed by a border layout

To solve this problem, use additional panels. For example, look at Figure 11.9. The three buttons at the bottom of the screen are all contained in a panel. The panel is put into the southern region of the content pane.



Figure 1.9: Panel placed at the southern region of the frame

To achieve this configuration, first create a new `JPanel` object, then add the individual buttons to the panel. The default layout manager for a panel is a `FlowLayout`, which is a good choice for this situation. Add the individual buttons to the panel, using the `add` method you have seen before. The position and size of the buttons is under the control of the `FlowLayout` manager. This means the buttons stay centered within the panel and do not expand to fill the entire panel area. Finally, add the panel to the content pane of the frame.

```
var panel = new JPanel();
panel.add(yellowButton);
panel.add(blueButton);
panel.add(redButton);
```

```
  frame.add(panel, BorderLayout.SOUTH);
```

The border layout expands the size of the panel to fill the entire southern region.

`java.awt.BorderLayout` **1.0**

- `BorderLayout()`
- `BorderLayout(int hgap, int vgap)`

construct a new `BorderLayout`.

1.2.3. Grid Layout

The grid layout arranges all components in rows and columns like a spreadsheet. All components are given the same size. The calculator program in Figure 11.10 uses a grid layout to arrange the calculator buttons. When you resize the window, the buttons grow and shrink, but all buttons have identical sizes.



Figure 1.10: A calculator

In the constructor of the grid layout object, you specify how many rows and columns you need.

```
panel.setLayout(new GridLayout(4, 4));
```

Add the components, starting with the first entry in the first row, then the second entry in the first row, and so on.

```
panel.add(new JButton("1"));
panel.add(new JButton("2"));
```

Of course, few applications have as rigid a layout as the face of a calculator. In practice, small grids (usually with just one row or one column) can be useful to organize partial areas of a window. For example, if you want to have a row of buttons of identical sizes, you can put the buttons inside a panel that is governed by a grid layout with a single row.

`java.awt.GridLayout` **1.0**

- `GridLayout(int rows, int columns)`
- `GridLayout(int rows, int columns, int hgap, int vgap)`
  construct a new `GridLayout`. One of `rows` and `columns` (but not both) may be zero, denoting an arbitrary number of components per row or column.

1.3. Text Input

We are finally ready to start introducing the Swing user interface components. Let's begin with the components that let a user input and edit text. You can use the `JTextField` and `JTextArea` components for text input. A text field can accept only one line of text; a text area can accept multiple lines of text. A `JPasswordField` accepts one line of text without showing the contents.

All three of these classes inherit from a class called `JTextComponent`. You will not be able to construct a `JTextComponent` yourself because it is an abstract class. On the other hand, as is so often the case in Java, when you go searching through the API documentation, you may find that the methods you are looking for are actually in the parent class `JTextComponent` rather than the derived class. For example, the methods that get or set the text in a text field or text area are actually in `JTextComponent`.

`javax.swing.text.JTextComponent` **1.2**

- `String getText()`
- `void setText(String text)`
  get or set the text of this text component.
- `boolean isEditable()`
- `void setEditable(boolean b)`
  get or set the `editable` property that determines whether the user can edit the content of this text component.

1.3.1. Text Fields

The usual way to add a text field to a window is to add it to a panel or other container—just as you would add a button:

```
var panel = new JPanel();
var textField = new JTextField("Default input", 20);
panel.add(textField);
```

This code adds a text field and initializes it by placing the string `"Default input"` inside it. The second parameter of this constructor sets the width. In this case, the width is 20 "columns." Unfortunately, a column is a rather imprecise measurement. One column is the expected width of one character in the font you are using for the text. The idea is that if you expect the inputs to be *n* characters or less, you are supposed to specify *n* as the column width. In practice, this measurement doesn't work out too well, and you should add 1 or 2 to the maximum input length to be on the safe side. Also, keep in mind that the number of columns is only a hint to the AWT that gives the *preferred* size. If the layout manager needs to grow or shrink the text field, it can adjust its size. The column width that you set in the `JTextField` constructor is not an upper limit on the number of characters the user can enter. The user can still type in longer strings, but the input scrolls when the text exceeds the length of the field. Users tend to find scrolling text fields irritating, so you should size the fields generously. If you need to reset the number of columns at runtime, you can do that with the `setColumns` method.

Tip: After changing the size of a text box with the `setColumns` method, call the `revalidate` method of the surrounding container.

```
textField.setColumns(10);
panel.revalidate();
```

The `revalidate` method recomputes the size and layout of all components in a container. After you use the `revalidate` method, the layout manager resizes the container, and the changed size of the text field will be visible.

The `revalidate` method belongs to the `JComponent` class. It doesn’t immediately resize the component but merely marks it for resizing. This approach avoids repetitive calculations if multiple components request to be resized. However, if you want to recompute all components inside a `JFrame`, you have to call the `validate` method— `JFrame` doesn’t extend `JComponent`.

In general, users add text (or edit an existing text) in a text field. Quite often these text fields start out blank. To make a blank text field, just don't provide a string argument for the `JTextField` constructor:

```
var textField = new JTextField(20);
```

You can change the content of the text field at any time by using the `setText` method from the `JTextComponent` parent class mentioned in the previous section. For example:

```
textField.setText("Hello!");
```

And, as was mentioned in the previous section, you can find out what the user typed by calling the `getText` method. This method returns the exact text that the user has typed. To strip any extraneous leading and trailing spaces from the data in a text field, apply the `strip` method to the return value of `getText`:

```
String text = textField.getText().strip();
```

To change the font in which the user text appears, use the `setFont` method.

`javax.swing.JTextField` **1.2**

- `JTextField(int columns)`
  constructs an empty `JTextField` with the specified number of columns.

- `JTextField(String text, int columns)`
  constructs a new `JTextField` with an initial string and the specified number of columns.
- `int getColumns()`
- `void setColumns(int columns)`
  get or set the number of columns that this text field should use.

`javax.swing.JComponent` **1.2**

- `void revalidate()`
  causes the position and size of a component to be recomputed.
- `void setFont(Font f)`
  sets the font of this component.

`java.awt.Component` **1.0**

- `void validate()`
  recomputes the position and size of a component. If the component is a container, the positions and sizes of its components are recomputed.
- `Font getFont()`
  gets the font of this component.

1.3.2. Labels and Labeling Components

Labels are components that hold text. They have no decorations (for example, no boundaries). They also do not react to user input. You can use a label to identify components. For example, unlike buttons, text fields have no label to identify them. To label a component that does not itself come with an identifier:

1. Construct a `JLabel` component with the correct text.
2. Place it close enough to the component you want to identify so that the user can see that the label identifies the correct component.

The constructor for a `JLabel` lets you specify the initial text or icon and, optionally, the alignment of the content. Use constants from the `SwingConstants` interface to specify alignment. That interface defines a number of useful constants such as `LEFT`, `RIGHT`, `CENTER`, `NORTH`, `EAST`, and so on. The `JLabel` class is one of several Swing classes that implement this interface. Therefore, you can specify a right-aligned label either as

```
var label = new JLabel("User name: ", SwingConstants.
```

or

```
var label = new JLabel("User name: ", JLabel.RIGHT);
```

The `setText` and `setIcon` methods let you set the text and icon of the label at runtime.

Tip: You can use both plain and HTML text in buttons, labels, and menu items. I don't recommend HTML in buttons—it interferes with the look-and-feel. But HTML in labels can be very effective. Simply surround the label string with `<html>. . .</html>`, like this:

```
label = new JLabel("<html><b>Required</b> entry:</htm
```

Note that the first component with an HTML label may take some time to be displayed because the rather complex HTML rendering code must be loaded.

Labels can be positioned inside a container like any other component. This means you can use the techniques you have seen before to place your labels where you need them.

`javax.swing.JLabel` **1.2**

- `JLabel(String text)`
- `JLabel(Icon icon)`
- `JLabel(String text, int align)`
- `JLabel(String text, Icon icon, int align)`

  construct a label. The `align` parameter is one of the `SwingConstants` constants `LEFT` (default), `CENTER`, or `RIGHT`.
- `String getText()`
- `void setText(String text)`

  get or set the text of this label.
- `Icon getIcon()`
- `void setIcon(Icon icon)`

  get or set the icon of this label.

1.3.3. Password Fields

Password fields are a special kind of text fields. To prevent nosy bystanders from seeing your password, the characters that the user enters are not actually displayed. Instead, each typed character is represented by an *echo character,* such as a bullet (•). Swing supplies a `JPasswordField` class that implements such a text field.

The password field is another example of the power of the model-view-controller architecture pattern. The password field uses the same model to store the data as a regular text field, but its view has been changed to display all characters as echo characters.

`javax.swing.JPasswordField` **1.2**

- `JPasswordField(String text, int columns)`
  constructs a new password field.
- `void setEchoChar(char echo)`
  sets the echo character for this password field. This is advisory; a particular look-and-feel may insist on its own choice of echo character. A value of `0` resets the echo character to the default.
- `char[] getPassword()`
  returns the text contained in this password field. For stronger security, you should overwrite the content of the returned array after use. (The password is not returned as a `String` because a string would stay in the virtual machine until it is garbage-collected.)

1.3.4. Text Areas

Sometimes, you need to collect user input that is more than one line long. As mentioned earlier, you can use the `JTextArea` component for this. When you place a text area component in your program, a

user can enter any number of lines of text, using the Enter key to separate them. Each line ends with a `'\n'` (even on Windows). Figure 11.11 shows a text area at work.



Figure 1.11: Text components

In the constructor for the `JTextArea` component, specify the number of rows and columns for the text area. For example,

```
textArea = new JTextArea(8, 40); // 8 lines of 40 col
```

where the `columns` parameter works as before—and you still need to add a few more columns for safety's sake. Also, as before, the user is not restricted to the number of rows and columns; the text simply scrolls when the user inputs too much. You can also use the `setColumns` method to change the number of columns and the `setRows` method to change the number of rows. These numbers only indicate the preferred size—the layout manager can still grow or shrink the text area.

If there is more text than the text area can display, the remaining text is simply clipped. You can avoid clipping long lines by turning on line wrapping:

```
textArea.setLineWrap(true); // long lines are wrapped
```

This wrapping is a visual effect only; the text in the document is not changed—no automatic `'\n'` characters are inserted into the text.

1.3.5. Scroll Panes

In Swing, a text area does not have scrollbars. If you want scrollbars, you have to place the text area inside a *scroll pane.*

```
textArea = new JTextArea(8, 40);
```

```
var scrollPane = new JScrollPane(textArea);
```

The scroll pane now manages the view of the text area. Scrollbars automatically appear if there is more text than the text area can display, and they vanish again if text is deleted and the remaining text fits inside the area. The scrolling is handled internally by the scroll pane—your program does not need to process scroll events.

This is a general mechanism that works for any component, not just text areas. To add scrollbars to a component, put them inside a scroll pane.

Listing 11.1 demonstrates the various text components. This program shows a text field, a password field, and a text area with scrollbars. The text field and password field are labeled. Click on "Insert" to insert the field contents into the text area.

Note: The `JTextArea` component displays plain text only, without special fonts or formatting. To display formatted text (such as HTML), you can use the `JEditorPane` class that is discussed in Chapter 12.

Listing 1.1 text/TextComponentFrame.java

```
1  package text;
2
3  import java.awt.BorderLayout;
4  import java.awt.GridLayout;
5
6  import javax.swing.JButton;
7  import javax.swing.JFrame;
8  import javax.swing.JLabel;
9  import javax.swing.JPanel;
10 import javax.swing.JPasswordField;
11 import javax.swing.JScrollPane;
12 import javax.swing.JTextArea;
13 import javax.swing.JTextField;
14 import javax.swing.SwingConstants;
15
16 /**
17  * A frame with sample text components.
18  */
19 public class TextComponentFrame extends JFrame
20 {
21    private static final int TEXTAREA_ROWS = 8;
22    private static final int TEXTAREA_COLUMNS =
23
24    public TextComponentFrame()
25    {
26       var textField = new JTextField();
```

```
27        var passwordField = new JPasswordField();
28
29        var northPanel = new JPanel();
30        northPanel.setLayout(new GridLayout(2, 2)
31        northPanel.add(new JLabel("User name: ",
32        northPanel.add(textField);
33        northPanel.add(new JLabel("Password: ", S
34        northPanel.add(passwordField);
35
36        add(northPanel, BorderLayout.NORTH);
37
38        var textArea = new JTextArea(TEXTAREA_ROW
39        var scrollPane = new JScrollPane(textArea
40
41        add(scrollPane, BorderLayout.CENTER);
42
43        // add button to append text into the tex
44
45        var southPanel = new JPanel();
46
47        var insertButton = new JButton("Insert");
48        southPanel.add(insertButton);
49        insertButton.addActionListener(event ->
50           textArea.append("User name: " + textFi
51              + new String(passwordField.getPassw
52
53        add(southPanel, BorderLayout.SOUTH);
```

```
54          pack();
55       }
56    }
```

`javax.swing.JTextArea` **1.2**

- `JTextArea()`
- `JTextArea(int rows, int columns)`
- `JTextArea(String text, int rows, int columns)`
  construct a new text area.
- `void setColumns(int columns)`
  tells the text area the preferred number of columns it should use.
- `void setRows(int rows)`
  tells the text area the preferred number of rows it should use.
- `void append(String newText)`
  appends the given text to the end of the text already in the text area.
- `void setLineWrap(boolean wrap)`
  turns line wrapping on or off.
- `void setWrapStyleWord(boolean word)`
  If `word` is `true`, long lines are wrapped at word boundaries. If it is `false`, long lines are broken without taking word boundaries into account.

- `void setTabSize(int c)`
  sets tab stops every `c` columns. Note that the tabs aren't converted to spaces but cause alignment with the next tab stop.

`javax.swing.JScrollPane` **1.2**

- `JScrollPane(Component c)`
  creates a scroll pane that displays the content of the specified component. Scrollbars are supplied when the component is larger than the view.

1.4. Choice Components

You now know how to collect text input from users, but there are many occasions where you would rather give users a finite set of choices than have them enter the data in a text component. Using a set of buttons or a list of items tells your users what choices they have. (It also saves you the trouble of error checking.) In this section, you will learn how to program checkboxes, radio buttons, lists of choices, and sliders.

1.4.1. Checkboxes

If you want to collect just a "yes" or "no" input, use a checkbox component. Checkboxes automatically come with labels that identify them. The user can check the box by clicking inside it and turn off

the checkmark by clicking inside the box again. Pressing the space bar when the focus is in the checkbox also toggles the checkmark.

Figure 11.12 shows a simple program with two checkboxes, one for turning the italic attribute of a font on or off, and the other for boldface. Note that the second checkbox has focus, as indicated by the rectangle around the label. Each time the user clicks one of the checkboxes, the screen is refreshed, using the new font attributes.



Figure 1.12: Checkboxes

Checkboxes need a label next to them to identify their purpose. Give the label text in the constructor:

```
bold = new JCheckBox("Bold");
```

Use the `setSelected` method to turn a checkbox on or off. For example:

```
bold.setSelected(true);
```

The `isSelected` method then retrieves the current state of each checkbox. It is `false` if unchecked, `true` if checked.

When the user clicks on a checkbox, this triggers an action event. As always, you attach an action listener to the checkbox. In our program, the two checkboxes share the same action listener.

```
ActionListener listener = . . .;
bold.addActionListener(listener);
italic.addActionListener(listener);
```

The listener queries the state of the `bold` and `italic` checkboxes and sets the font of the panel to plain, bold, italic, or both bold and italic.

```
ActionListener listener = event ->
   {
      int mode = 0;
      if (bold.isSelected()) mode += Font.BOLD;
```

```
      if (italic.isSelected()) mode += Font.ITALIC;
      label.setFont(new Font(Font.SERIF, mode, FONTSI
   };
```

Listing 11.2 is the program listing for the checkbox example.

Listing 1.2 checkBox/CheckBoxFrame.java

```
1  package checkBox;
2
3  import java.awt.*;
4  import java.awt.event.*;
5  import javax.swing.*;
6
7  /**
8   * A frame with a sample text label and check b
9   * attributes.
10  */
11 public class CheckBoxFrame extends JFrame
12 {
13    private JLabel label;
14    private JCheckBox bold;
15    private JCheckBox italic;
16    private static final int FONTSIZE = 24;
17
18    public CheckBoxFrame()
19    {
```

```
20          // add the sample text label
21
22          label = new JLabel("The quick brown fox j
23          label.setFont(new Font("Serif", Font.BOLD
24          add(label, BorderLayout.CENTER);
25
26          // this listener sets the font attribute
27          // the label to the check box state
28
29          ActionListener listener = event ->
30             {
31                int mode = 0;
32                if (bold.isSelected()) mode += Font
33                if (italic.isSelected()) mode += Fo
34                label.setFont(new Font("Serif", mod
35             };
36
37          // add the check boxes
38          var buttonPanel = new JPanel();
39
40          bold = new JCheckBox("Bold");
41          bold.addActionListener(listener);
42          bold.setSelected(true);
43          buttonPanel.add(bold);
44
45          italic = new JCheckBox("Italic");
46          italic.addActionListener(listener);
47          buttonPanel.add(italic);
```

```
48
49          add(buttonPanel, BorderLayout.SOUTH);
50          pack();
51       }
52    }
```

`javax.swing.JCheckBox` **1.2**

- `JCheckBox(String label)`
- `JCheckBox(String label, Icon icon)`
  construct a checkbox that is initially unselected.
- `JCheckBox(String label, boolean state)`
  constructs a checkbox with the given label and initial state.
- `boolean isSelected()`
- `void setSelected(boolean state)`
  get or set the selection state of the checkbox.

1.4.2. Radio Buttons

In the previous example, the user could check either, both, or neither of the two checkboxes. In many cases, we want the user to check only one of several boxes. When another box is checked, the previous box is automatically unchecked. Such a group of boxes is often called a *radio button group* because the buttons work like the station selector buttons on a radio. When you push in one button,

the previously depressed button pops out. Figure 11.13 shows a typical example. We allow the user to select a font size from among the choices—Small, Medium, Large, or Extra large—but, of course, we will allow selecting only one size at a time.

Figure 1.13: A radio button group

Implementing radio button groups is easy in Swing. You construct one object of type `ButtonGroup` for every group of buttons. Then, you add objects of type `JRadioButton` to the button group. The button group object is responsible for turning off the previously set button when a new button is clicked.

```
var group = new ButtonGroup();

var smallButton = new JRadioButton("Small", false);
group.add(smallButton);
```

```
var mediumButton = new JRadioButton("Medium", true);
group.add(mediumButton);
. . .
```

The second argument of the constructor is `true` for the button that should be checked initially and `false` for all others. Note that the button group controls only the *behavior* of the buttons; if you want to group the buttons for layout purposes, you also need to add them to a container such as a `JPanel`.

If you look again at Figure 11.12, you will note that the appearance of the radio buttons is different from that of checkboxes in Figure 11.13. Checkboxes are square and contain a checkmark when selected. Radio buttons are round and contain a dot when selected.

The event notification mechanism for radio buttons is the same as for any other buttons. When the user checks a radio button, the button generates an action event. In our example program, we define an action listener that sets the font size to a particular value:

```
ActionListener listener = event ->
   label.setFont(new Font("Serif", Font.PLAIN, size))
```

Compare this listener setup to that of the checkbox example. Each radio button gets a different listener object. Each listener object knows exactly what it needs to do—set the font size to a particular value. With checkboxes, we used a different approach: Both checkboxes have the same action listener that calls a method looking at the current state of both checkboxes.

Could we follow the same approach here? We could have a single listener that computes the size as follows:

```
if (smallButton.isSelected()) size = 8;
else if (mediumButton.isSelected()) size = 12;
. . .
```

However, we prefer to use separate action listener objects because they tie the size values more closely to the buttons.

Note: If you have a group of radio buttons, you know that only one of them is selected. It would be nice to be able to quickly find out which, without having to query all the buttons in the group. The `ButtonGroup` object controls all buttons, so it would be convenient if this object could give us a reference to the selected button. Indeed, the `ButtonGroup` class has a `getSelection` method, but that method doesn't

return the radio button that is selected. Instead, it returns a `ButtonModel` reference to the model attached to the button. Unfortunately, none of the `ButtonModel` methods are very helpful. The `ButtonModel` interface inherits a method `getSelectedObjects` from the `ItemSelectable` interface that, rather uselessly, returns `null`. The `getActionCommand` method looks promising because the "action command" of a radio button is its text label. But the action command of its model is `null`. Only if you explicitly set the action commands of all radio buttons with the `setActionCommand` method do the action command values of the models also get set. Then you can retrieve the action command of the currently selected button with `buttonGroup.getSelection().getActionCommand()`.

Listing 11.3 is the complete program for font size selection that puts a set of radio buttons to work.

Listing 1.3 radioButton/RadioButtonFrame.java

```
1  package radioButton;
2
3  import java.awt.*;
4  import java.awt.event.*;
5  import javax.swing.*;
6
7  /**
8   * A frame with a sample text label and radio b
9   */
10 public class RadioButtonFrame extends JFrame
11 {
12    private JPanel buttonPanel;
13    private ButtonGroup group;
14    private JLabel label;
15    private static final int DEFAULT_SIZE = 36;
16
17    public RadioButtonFrame()
18    {
19       // add the sample text label
20
21       label = new JLabel("The quick brown fox j
22       label.setFont(new Font("Serif", Font.PLAI
23       add(label, BorderLayout.CENTER);
24
25       // add the radio buttons
26
```

```
27          buttonPanel = new JPanel();
28          group = new ButtonGroup();
29
30          addRadioButton("Small", 8);
31          addRadioButton("Medium", 12);
32          addRadioButton("Large", 18);
33          addRadioButton("Extra large", 36);
34
35          add(buttonPanel, BorderLayout.SOUTH);
36          pack();
37       }
38
39       /**
40        * Adds a radio button that sets the font si
41        * @param name the string to appear on the b
42        * @param size the font size that this butto
43        */
44       public void addRadioButton(String name, int
45       {
46          boolean selected = size == DEFAULT_SIZE;
47          var button = new JRadioButton(name, selec
48          group.add(button);
49          buttonPanel.add(button);
50
51          // this listener sets the label font size
52
53          ActionListener listener = event -> label
54
```

```
55          button.addActionListener(listener);
56       }
57    }
```

`javax.swing.JRadioButton` **1.2**

- `JRadioButton(String label, Icon icon)`
  constructs a radio button that is initially unselected.
- `JRadioButton(String label, boolean state)`
  constructs a radio button with the given label and initial state.

`javax.swing.ButtonGroup` **1.2**

- `void add(AbstractButton b)`
  adds the button to the group.
- `ButtonModel getSelection()`
  returns the button model of the selected button.

`javax.swing.ButtonModel` **1.2**

- `String getActionCommand()`
  returns the action command for this button model.

`javax.swing.AbstractButton` 1.2

- `void setActionCommand(String s)`
  sets the action command for this button and its model.

1.4.3. Borders

If you have multiple groups of radio buttons in a window, you will want to visually indicate which buttons are grouped. Swing provides a set of useful *borders* for this purpose. You can apply a border to any component that extends `JComponent`. The most common usage is to place a border around a panel and fill that panel with other user interface elements, such as radio buttons.

You can choose from quite a few borders, but you need to follow the same steps for all of them.

1. Call a static method of the `BorderFactory` to create a border. You can choose among the following styles (see Figure 11.14):
   1. Lowered bevel
   2. Raised bevel
   3. Etched
   4. Line
   5. Matte

6. Empty (just to create some blank space around the component)



Figure 1.14: Testing border types

2. If you like, add a title to your border by passing your border to `BorderFactory.createTitledBorder`.
3. If you really want to go all out, combine several borders with a call to `BorderFactory.createCompoundBorder`.
4. Add the resulting border to your component by calling the `setBorder` method of the `JComponent` class.

For example, here is how you add an etched border with a title to a panel:

```
Border etched = BorderFactory.createEtchedBorder();
Border titled = BorderFactory.createTitledBorder(etch
panel.setBorder(titled);
```

Different borders have different options for setting border widths and colors; see the API notes for details. True border enthusiasts will appreciate that there is also a `SoftBevelBorder` class for beveled borders with softened corners and that a `LineBorder` can have rounded corners as well. You can construct these borders only by using one of the class constructors—there is no `BorderFactory` method for them.

`javax.swing.BorderFactory` **1.2**

- `static Border createLineBorder(Color color)`
- `static Border createLineBorder(Color color, int thickness)`
  create a simple line border.
- `static MatteBorder createMatteBorder(int top, int left, int bottom, int right, Color color)`
- `static MatteBorder createMatteBorder(int top, int left, int bottom, int right, Icon tileIcon)`
  create a thick border that is filled with a color or a repeating icon.
- `static Border createEmptyBorder()`
- `static Border createEmptyBorder(int top, int left, int bottom, int right)`
  create an empty border.

- `static Border createEtchedBorder()`
- `static Border createEtchedBorder(Color highlight, Color shadow)`
- `static Border createEtchedBorder(int type)`
- `static Border createEtchedBorder(int type, Color highlight, Color shadow)`
  create a line border with a 3D effect. The `type` parameter is one of `EtchedBorder.RAISED`, `EtchedBorder.LOWERED`.
- `static Border createBevelBorder(int type)`
- `static Border createBevelBorder(int type, Color highlight, Color shadow)`
- `static Border createLoweredBevelBorder()`
- `static Border createRaisedBevelBorder()`
  create a border that gives the effect of a lowered or raised surface. The `type` parameter is one of `BevelBorder.RAISED`, `BevelBorder.LOWERED`.
- `static TitledBorder createTitledBorder(String title)`
- `static TitledBorder createTitledBorder(Border border)`
- `static TitledBorder createTitledBorder(Border border, String title)`
- `static TitledBorder createTitledBorder(Border border, String title, int justification, int`

`position)`

- `static TitledBorder createTitledBorder(Border border, String title, int justification, int position, Font font)`
- `static TitledBorder createTitledBorder(Border border, String title, int justification, int position, Font font, Color color)`
  create a titled border with the specified properties. The `justification` parameter is one of the `TitledBorder` constants `LEFT`, `CENTER`, `RIGHT`, `LEADING`, `TRAILING`, or `DEFAULT_JUSTIFICATION` (left), and `position` is one of `ABOVE_TOP`, `TOP`, `BELOW_TOP`, `ABOVE_BOTTOM`, `BOTTOM`, `BELOW_BOTTOM`, or `DEFAULT_POSITION` (top).
- `static CompoundBorder createCompoundBorder(Border outsideBorder, Border insideBorder)`
  combines two borders to a new border.

`javax.swing.border.SoftBevelBorder` **1.2**

- `SoftBevelBorder(int type)`
- `SoftBevelBorder(int type, Color highlight, Color shadow)`
  create a bevel border with softened corners. The `type` parameter is one of `SoftBevelBorder.RAISED`, `SoftBevelBorder.LOWERED`.

`javax.swing.border.LineBorder` 1.2

- `public LineBorder(Color color, int thickness, boolean roundedCorners)`
  creates a line border with the given color and thickness. If `roundedCorners` is `true`, the border has rounded corners.

`javax.swing.JComponent` 1.2

- `void setBorder(Border border)`
  sets the border of this component.

1.4.4. Combo Boxes

If you have more than a handful of alternatives, radio buttons are not a good choice because they take up too much screen space. Instead, you can use a combo box. When the user clicks on this component, a list of choices drops down, and the user can then select one of them (see Figure 11.15).



Figure 1.15: A combo box

If the drop-down list box is set to be *editable*, you can edit the current selection as if it were a text field. For that reason, this component is called a *combo box*—it combines the flexibility of a text field with a set of predefined choices. The `JComboBox` class provides a combo box component.

As of Java 7, the `JComboBox` class is a generic class. For example, a `JComboBox<String>` holds objects of type `String`, and a `JComboBox<Integer>` holds integers.

Call the `setEditable` method to make the combo box editable. Note that editing affects only the selected item. It does not change

the list of choices in any way.

You can obtain the current selection, which may have been edited if the combo box is editable, by calling the `getSelectedItem` method. However, for an editable combo box, that item may have any type, depending on the editor that takes the user edits and turns the result into an object. (See Chapter 12 for a discussion of editors.) If your combo box isn't editable, you are better off calling

```
combo.getItemAt(combo.getSelectedIndex())
```

which gives you the selected item with the correct type.

In the example program, the user can choose a font style from a list of styles (Serif, SansSerif, Monospaced, etc.). The user can also type in another font.

Add the choice items with the `addItem` method. In our program, `addItem` is called only in the constructor, but you can call it any time.

```
var faceCombo = new JComboBox<String>();
faceCombo.addItem("Serif");
faceCombo.addItem("SansSerif");
. . .
```

This method adds the string to the end of the list. You can add new items anywhere in the list with the `insertItemAt` method:

```
faceCombo.insertItemAt("Monospaced", 0); // add at th
```

You can add items of any type—the combo box invokes each item's `toString` method to display it.

If you need to remove items at runtime, use the `removeItem` or `removeItemAt` method, depending on whether you supply the item to be removed or its position.

```
faceCombo.removeItem("Monospaced");
faceCombo.removeItemAt(0); // remove first item
```

The `removeAllItems` method removes all items at once.

Tip: If you need to add a large number of items to a combo box, the `addItem` method will perform poorly. Instead, construct a `DefaultComboBoxModel`, populate it by calling `addElement`, and then call the `setModel` method of the `JComboBox` class.

When the user selects an item from a combo box, the combo box generates an action event. To find out which item was selected, call `getSource` on the event parameter to get a reference to the combo box that sent the event. Then call the `getSelectedItem` method to retrieve the currently selected item. You will need to cast the returned value to the appropriate type, usually `String`.

```
ActionListener listener = event ->
   label.setFont(new Font(
      faceCombo.getItemAt(faceCombo.getSelectedIndex(
      Font.PLAIN,
      DEFAULT_SIZE));
```

Listing 11.4 shows the complete program.

Listing 1.4 comboBox/ComboBoxFrame.java

```
1  package comboBox;
2
3  import java.awt.BorderLayout;
4  import java.awt.Font;
5
6  import javax.swing.JComboBox;
7  import javax.swing.JFrame;
8  import javax.swing.JLabel;
9  import javax.swing.JPanel;
```

```
10
11  /**
12   * A frame with a sample text label and a combo
13   */
14  public class ComboBoxFrame extends JFrame
15  {
16     private JComboBox<String> faceCombo;
17     private JLabel label;
18     private static final int DEFAULT_SIZE = 24;
19
20     public ComboBoxFrame()
21     {
22        // add the sample text label
23
24        label = new JLabel("The quick brown fox j
25        label.setFont(new Font("Serif", Font.PLAI
26        add(label, BorderLayout.CENTER);
27
28        // make a combo box and add face names
29
30        faceCombo = new JComboBox<>();
31        faceCombo.addItem("Serif");
32        faceCombo.addItem("SansSerif");
33        faceCombo.addItem("Monospaced");
34        faceCombo.addItem("Dialog");
35        faceCombo.addItem("DialogInput");
36
37        // the combo box listener changes the lab
```

```
38
39          faceCombo.addActionListener(event ->
40             label.setFont(
41                new Font(faceCombo.getItemAt(faceCo
42                   Font.PLAIN, DEFAULT_SIZE)));
43
44          // add combo box to a panel at the frame
45
46          var comboPanel = new JPanel();
47          comboPanel.add(faceCombo);
48          add(comboPanel, BorderLayout.SOUTH);
49          pack();
50       }
51    }
```

`javax.swing.JComboBox` **1.2**

- `boolean isEditable()`
- `void setEditable(boolean b)`
  get or set the `editable` property of this combo box.
- `void addItem(Object item)`
  adds an item to the item list.
- `void insertItemAt(Object item, int index)`
  inserts an item into the item list at a given index.
- `void removeItem(Object item)`
  removes an item from the item list.

- `void removeItemAt(int index)`
  removes the item at an index.
- `void removeAllItems()`
  removes all items from the item list.
- `Object getSelectedItem()`
  returns the currently selected item.

1.4.5. Sliders

Combo boxes let users choose from a discrete set of values. Sliders offer a choice from a continuum of values—for example, any number between 1 and 100.

The most common way of constructing a slider is as follows:

```
var slider = new JSlider(min, max, initialValue);
```

If you omit the minimum, maximum, and initial values, they are initialized with `0`, `100`, and `50`, respectively.

Or if you want the slider to be vertical, use the following constructor call:

```
var slider = new JSlider(SwingConstants.VERTICAL, min
```

These constructors create a plain slider, such as the top slider in Figure 11.16. You will see presently how to add decorations to a slider.



Figure 1.16: Sliders

As the user slides the slider bar, the *value* of the slider moves between the minimum and the maximum values. When the value changes, a `ChangeEvent` is sent to all change listeners. To be

notified of the change, call the `addChangeListener` method and install an object that implements the functional `ChangeListener` interface. In the callback, retrieve the slider value:

```
ChangeListener listener = event ->
   {
      JSlider slider = (JSlider) event.getSource();
      int value = slider.getValue();
      . . .
   };
```

You can embellish the slider by showing *ticks.* For example, in the sample program, the second slider uses the following settings:

```
slider.setMajorTickSpacing(20);
slider.setMinorTickSpacing(5);
```

The slider is decorated with large tick marks every 20 units and small tick marks every 5 units. The units refer to slider values, not pixels.

These instructions only set the units for the tick marks. To actually have the tick marks appear, call

```
slider.setPaintTicks(true);
```

The major and minor tick marks are independent. For example, you can set major tick marks every 20 units and minor tick marks every 7 units, but that will give you a very messy scale.

You can force the slider to *snap to ticks.* Whenever the user has finished dragging a slider in snap mode, it is immediately moved to the closest tick. You activate this mode with the call

```
slider.setSnapToTicks(true);
```

Caution: The "snap to ticks" behavior doesn't work as well as you might imagine. Until the slider has actually snapped, the change listener still reports slider values that don't correspond to ticks. And if you click next to the slider—an action that normally advances the slider a bit in the direction of the click—a slider with "snap to ticks" does not move to the next tick.

You can display *tick mark labels* for the major tick marks by calling

```
slider.setPaintLabels(true);
```

For example, with a slider ranging from 0 to 100 and major tick spacing of 20, the ticks are labeled 0, 20, 40, 60, 80, and 100.

You can also supply other tick mark labels, such as strings or icons (see Figure 11.16). The process is a bit convoluted. You need to fill a hash table with keys of type `Integer` and values of type `Component`. You then call the `setLabelTable` method. The components are placed under the tick marks. Usually, `JLabel` objects are used. Here is how you can label ticks as A, B, C, D, E, and F:

```
var labelTable = new Hashtable<Integer, Component>();
labelTable.put(0, new JLabel("A"));
labelTable.put(20, new JLabel("B"));
. . .
labelTable.put(100, new JLabel("F"));
slider.setLabelTable(labelTable);
```

Listing 11.5 also shows a slider with icons as tick labels.

Tip: If your tick marks or labels don't show, double-check that you have `setPaintTicks(true)` and `setPaintLabels(true)`.

The fourth slider in Figure 11.16 has no track. To suppress the "track" in which the slider moves, call

```
slider.setPaintTrack(false);
```

The fifth slider has its direction reversed by a call to

```
slider.setInverted(true);
```

The example program in Listing 11.5 shows all these visual effects with a collection of sliders. Each slider has a change event listener installed that places the current slider value into the text field at the bottom of the frame.

Listing 1.5 slider/SliderFrame.java

```
1  package slider;
2
3  import java.awt.*;
4  import java.util.*;
5  import javax.swing.*;
6  import javax.swing.event.*;
7
8  /**
9   * A frame with many sliders and a text field t
10  */
```

```
11 public class SliderFrame extends JFrame
12 {
13    private JPanel sliderPanel;
14    private JTextField textField;
15    private ChangeListener listener;
16
17    public SliderFrame()
18    {
19       sliderPanel = new JPanel();
20       sliderPanel.setLayout(new GridBagLayout()
21
22       // common listener for all sliders
23       listener = event ->
24          {
25             // update text field when the slide
26             JSlider source = (JSlider) event.ge
27             textField.setText("" + source.getVa
28          };
29
30       // add a plain slider
31
32       var slider = new JSlider();
33       addSlider(slider, "Plain");
34
35       // add a slider with major and minor tick
36
37       slider = new JSlider();
38       slider.setPaintTicks(true);
```

```
39        slider.setMajorTickSpacing(20);
40        slider.setMinorTickSpacing(5);
41        addSlider(slider, "Ticks");
42
43        // add a slider that snaps to ticks
44
45        slider = new JSlider();
46        slider.setPaintTicks(true);
47        slider.setSnapToTicks(true);
48        slider.setMajorTickSpacing(20);
49        slider.setMinorTickSpacing(5);
50        addSlider(slider, "Snap to ticks");
51
52        // add a slider with no track
53
54        slider = new JSlider();
55        slider.setPaintTicks(true);
56        slider.setMajorTickSpacing(20);
57        slider.setMinorTickSpacing(5);
58        slider.setPaintTrack(false);
59        addSlider(slider, "No track");
60
61        // add an inverted slider
62
63        slider = new JSlider();
64        slider.setPaintTicks(true);
65        slider.setMajorTickSpacing(20);
66        slider.setMinorTickSpacing(5);
```

```
67        slider.setInverted(true);
68        addSlider(slider, "Inverted");
69
70        // add a slider with numeric labels
71
72        slider = new JSlider();
73        slider.setPaintTicks(true);
74        slider.setPaintLabels(true);
75        slider.setMajorTickSpacing(20);
76        slider.setMinorTickSpacing(5);
77        addSlider(slider, "Labels");
78
79        // add a slider with alphabetic labels
80
81        slider = new JSlider();
82        slider.setPaintLabels(true);
83        slider.setPaintTicks(true);
84        slider.setMajorTickSpacing(20);
85        slider.setMinorTickSpacing(5);
86
87        var labelTable = new Hashtable<Integer, C
88        labelTable.put(0, new JLabel("A"));
89        labelTable.put(20, new JLabel("B"));
90        labelTable.put(40, new JLabel("C"));
91        labelTable.put(60, new JLabel("D"));
92        labelTable.put(80, new JLabel("E"));
93        labelTable.put(100, new JLabel("F"));
94
```

```
95        slider.setLabelTable(labelTable);
96        addSlider(slider, "Custom labels");
97
98        // add a slider with icon labels
99
100       slider = new JSlider();
101       slider.setPaintTicks(true);
102       slider.setPaintLabels(true);
103       slider.setSnapToTicks(true);
104       slider.setMajorTickSpacing(20);
105       slider.setMinorTickSpacing(20);
106
107       labelTable = new Hashtable<>();
108
109       // add card images
110
111       labelTable.put(0, new JLabel(new ImageIc
112       labelTable.put(20, new JLabel(new ImageI
113       labelTable.put(40, new JLabel(new ImageI
114       labelTable.put(60, new JLabel(new ImageI
115       labelTable.put(80, new JLabel(new ImageI
116       labelTable.put(100, new JLabel(new Image
117
118       slider.setLabelTable(labelTable);
119       addSlider(slider, "Icon labels");
120
121       // add the text field that displays the s
122
```

```
123         textField = new JTextField();
124         add(sliderPanel, BorderLayout.CENTER);
125         add(textField, BorderLayout.SOUTH);
126         pack();
127      }
128
129      /**
130       * Adds a slider to the slider panel and hoo
131       * @param slider the slider
132       * @param description the slider descriptior
133       */
134      public void addSlider(JSlider slider, String
135      {
136         slider.addChangeListener(listener);
137         var panel = new JPanel();
138         panel.add(slider);
139         panel.add(new JLabel(description));
140         panel.setAlignmentX(Component.LEFT_ALIGNM
141         var gbc = new GridBagConstraints();
142         gbc.gridy = sliderPanel.getComponentCount
143         gbc.anchor = GridBagConstraints.WEST;
144         sliderPanel.add(panel, gbc);
145      }
146   }
```

`javax.swing.JSlider` **1.2**

- `JSlider()`
- `JSlider(int direction)`
- `JSlider(int min, int max)`
- `JSlider(int min, int max, int initialValue)`
- `JSlider(int direction, int min, int max, int initialValue)`
  construct a slider with the given direction and minimum, maximum, and initial values. The `direction` parameter is one of `SwingConstants.HORIZONTAL` or `SwingConstants.VERTICAL`. The default is horizontal. Defaults for the minimum, initial, and maximum are `0`, `50`, and `100`.
- `void setPaintTicks(boolean b)`
  displays ticks if `b` is `true`.
- `void setMajorTickSpacing(int units)`
- `void setMinorTickSpacing(int units)`
  set major or minor ticks at multiples of the given slider units.
- `void setPaintLabels(boolean b)`
  displays tick labels if `b` is `true`.
- `void setLabelTable(Dictionary table)`
  sets the components to use for the tick labels. Each key/value pair in the table has the form `Integer.valueOf(`*`value`*`)/`*`component`*`.`

- `void setSnapToTicks(boolean b)`
  If `b` is `true`, then the slider snaps to the closest tick after each adjustment.
- `void setPaintTrack(boolean b)`
  If `b` is `true`, a track is displayed in which the slider runs.

1.5. Menus

This chapter started by introducing the most common components that you might want to place into a window, such as various kinds of buttons, text fields, and combo boxes. Swing also supports another type of user interface element—pull-down menus that are familiar from GUI applications.

A *menu bar* at the top of a window contains the names of the pull-down menus. Clicking on a name opens the menu containing *menu items* and *submenus*. When the user clicks on a menu item, all menus are closed and a message is sent to the program. Figure 11.17 shows a typical menu with a submenu.



Figure 1.17: A menu with a submenu

1.5.1. Menu Building

Building menus is straightforward. First, create a menu bar:

```
var menuBar = new JMenuBar();
```

A menu bar is just a component that you can add anywhere you like. Normally, you want it to appear at the top of a frame. You can add it there with the `setJMenuBar` method:

```
frame.setJMenuBar(menuBar);
```

For each menu, you create a menu object:

```
var editMenu = new JMenu("Edit");
```

Add the top-level menus to the menu bar:

```
menuBar.add(editMenu);
```

Add menu items, separators, and submenus to the menu object:

```
var pasteItem = new JMenuItem("Paste");
editMenu.add(pasteItem);
editMenu.addSeparator();
JMenu optionsMenu = . . .; // a submenu
editMenu.add(optionsMenu);
```

You can see separators in Figure 11.17 below the Paste and Read-only menu items.

When the user selects a menu item, an action event is triggered. You need to install an action listener for each menu item:

```
ActionListener listener = . . .;
pasteItem.addActionListener(listener);
```

The method `JMenu.add(String s)` conveniently adds a menu item to the end of a menu. For example:

```
editMenu.add("Paste");
```

The `add` method returns the created menu item, so you can capture it and add the listener, as follows:

```
JMenuItem pasteItem = editMenu.add("Paste");
pasteItem.addActionListener(listener);
```

It often happens that menu items trigger commands that can also be activated through other user interface elements such as toolbar buttons. In Chapter 10, you saw how to specify commands through `Action` objects. You define a class that implements the `Action` interface, usually by extending the `AbstractAction` convenience class, specify the menu item label in the constructor of the `AbstractAction` object, and override the `actionPerformed` method to hold the menu action handler. For example:

```
var exitAction = new AbstractAction("Exit") // menu i
   {
      public void actionPerformed(ActionEvent event)
      {
         // action code goes here
```

```
            System.exit(0);
         }
      };
```

You can then add the action to the menu:

```
JMenuItem exitItem = fileMenu.add(exitAction);
```

This command adds a menu item to the menu, using the action name. The action object becomes its listener. This is just a convenient shortcut for

```
var exitItem = new JMenuItem(exitAction);
fileMenu.add(exitItem);
```

`javax.swing.JMenu` **1.2**

- `JMenu(String label)`
  constructs a menu with the given label.
- `JMenuItem add(JMenuItem item)`
  adds a menu item (or a menu).
- `JMenuItem add(String label)`
  adds a menu item with the given label to this menu and returns the item.

- `JMenuItem add(Action a)`
  adds a menu item with the given action to this menu and returns the item.
- `void addSeparator()`
  adds a separator line to the menu.
- `JMenuItem insert(JMenuItem menu, int index)`
  adds a new menu item (or submenu) to the menu at a specific index.
- `JMenuItem insert(Action a, int index)`
  adds a new menu item with the given action at a specific index.
- `void insertSeparator(int index)`
  adds a separator to the menu.
- `void remove(int index)`
- `void remove(JMenuItem item)`
  remove a specific item from the menu.

`javax.swing.JMenuItem` **1.2**

- `JMenuItem(String label)`
  constructs a menu item with a given label.
- `JMenuItem(Action a)` **1.3**
  constructs a menu item for the given action.

`javax.swing.AbstractButton` 1.2

- `void setAction(Action a)` 1.3
  sets the action for this button or menu item.

`javax.swing.JFrame` 1.2

- `void setJMenuBar(JMenuBar menubar)`
  sets the menu bar for this frame.

1.5.2. Icons in Menu Items

Menu items are very similar to buttons. In fact, the `JMenuItem` class extends the `AbstractButton` class. Just like buttons, menus can have just a text label, just an icon, or both. You can specify the icon with the `JMenuItem(String, Icon)` or `JMenuItem(Icon)` constructor, or you can set it with the `setIcon` method that the `JMenuItem` class inherits from the `AbstractButton` class. Here is an example:

```
var cutItem = new JMenuItem("Cut", new ImageIcon("cut
```

In Figure 11.17, you can see icons next to several menu items. By default, the menu item text is placed to the right of the icon. If you

prefer the text to be placed on the left, call the `setHorizontalTextPosition` method that the `JMenuItem` class inherits from the `AbstractButton` class. For example, the call

```
cutItem.setHorizontalTextPosition(SwingConstants.LEFT
```

moves the menu item text to the left of the icon.

You can also add an icon to an action:

```
cutAction.putValue(Action.SMALL_ICON, new ImageIcon("
```

Whenever you construct a menu item out of an action, the `Action.NAME` value becomes the text of the menu item and the `Action.SMALL_ICON` value becomes the icon.

Alternatively, you can set the icon in the `AbstractAction` constructor:

```
cutAction = new
   AbstractAction("Cut", new ImageIcon("cut.gif"))
      {
         public void actionPerformed(ActionEvent even
         {
```

```
            . . .
         }
      };
```

`javax.swing.JMenuItem` 1.2

- `JMenuItem(String label, Icon icon)`
  constructs a menu item with the given label and icon.

`javax.swing.AbstractButton` 1.2

- `void setHorizontalTextPosition(int pos)`
  sets the horizontal position of the text relative to the icon. The `pos` parameter is `SwingConstants.RIGHT` (text is to the right of icon) or `SwingConstants.LEFT`.

`javax.swing.AbstractAction` 1.2

- `AbstractAction(String name, Icon smallIcon)`
  constructs an abstract action with the given name and icon.

1.5.3. Checkbox and Radio Button Menu Items

Checkbox and *radio button* menu items display a checkbox or radio button next to the name (see Figure 11.17). When the user selects

the menu item, the item automatically toggles between checked and unchecked.

Apart from the button decoration, treat these menu items just as you would any others. For example, here is how you create a checkbox menu item:

```
var readonlyItem = new JCheckBoxMenuItem("Read-only")
optionsMenu.add(readonlyItem);
```

The radio button menu items work just like regular radio buttons. You must add them to a button group. When one of the buttons in a group is selected, all others are automatically deselected.

```
var group = new ButtonGroup();
var insertItem = new JRadioButtonMenuItem("Insert");
insertItem.setSelected(true);
var overtypeItem = new JRadioButtonMenuItem("Overtype
group.add(insertItem);
group.add(overtypeItem);
optionsMenu.add(insertItem);
optionsMenu.add(overtypeItem);
```

With these menu items, you don’t necessarily want to be notified when the user selects the item. Instead, you can simply use the

`isSelected` method to test the current state of the menu item. (Of course, that means you should keep a reference to the menu item stored in an instance field.) Use the `setSelected` method to set the state.

`javax.swing.JCheckBoxMenuItem` **1.2**

- `JCheckBoxMenuItem(String label)`
  constructs the checkbox menu item with the given label.
- `JCheckBoxMenuItem(String label, boolean state)`
  constructs the checkbox menu item with the given label and the given initial state (`true` is checked).

`javax.swing.JRadioButtonMenuItem` **1.2**

- `JRadioButtonMenuItem(String label)`
  constructs the radio button menu item with the given label.
- `JRadioButtonMenuItem(String label, boolean state)`
  constructs the radio button menu item with the given label and the given initial state (`true` is checked).

`javax.swing.AbstractButton` 1.2

- `boolean isSelected()`
- `void setSelected(boolean state)`

  get or set the selection state of this item (`true` is checked).

1.5.4. Pop-Up Menus

A *pop-up menu* is a menu that is not attached to a menu bar but floats somewhere (see Figure 11.18).



Figure 1.18: A pop-up menu

Create a pop-up menu just as you create a regular menu, except that a pop-up menu has no title.

```
var popup = new JPopupMenu();
```

Then, add your menu items as usual:

```
var item = new JMenuItem("Cut");
item.addActionListener(listener);
popup.add(item);
```

Unlike the regular menu bar that is always shown at the top of the frame, you must explicitly display a pop-up menu by using the `show` method. Specify the parent component and the location of the pop-up, using the coordinate system of the parent. For example:

```
popup.show(panel, x, y);
```

Usually, you want to pop up a menu when the user clicks a particular mouse button—the so-called *pop-up trigger.* In Windows and Linux, the pop-up trigger is the nonprimary (usually, the right) mouse button. To pop up a menu when the user clicks on a component, using the pop-up trigger, simply call the method

```
component.setComponentPopupMenu(popup);
```

Very occasionally, you may place a component inside another component that has a pop-up menu. The child component can inherit the parent component's pop-up menu by calling

```
child.setInheritsPopupMenu(true);
```

`javax.swing.JPopupMenu` **1.2**

- `void show(Component c, int x, int y)`
  shows the pop-up menu over the component `c` with the top left corner at `(x, y)` (in the coordinate space of `c`).
- `boolean isPopupTrigger(MouseEvent event)` **1.3**
  returns `true` if the mouse event is the pop-up menu trigger.

`java.awt.event.MouseEvent` **1.1**

- `boolean isPopupTrigger()`
  returns `true` if this mouse event is the pop-up menu trigger.

`javax.swing.JComponent` **1.2**

- `JPopupMenu getComponentPopupMenu()` **5.0**
- `void setComponentPopupMenu(JPopupMenu popup)` **5.0**
  get or set the pop-up menu for this component.

- `boolean getInheritsPopupMenu()` **5.0**
- `void setInheritsPopupMenu(boolean b)` **5.0**

  get or set the `inheritsPopupMenu` property. If the property is set and this component's pop-up menu is `null`, it uses its parent's pop-up menu.

1.5.5. Keyboard Mnemonics and Accelerators

It is a real convenience for the experienced user to select menu items by *keyboard mnemonics.* You can create a keyboard mnemonic for a menu item by specifying a mnemonic letter in the menu item constructor:

```
var aboutItem = new JMenuItem("About", 'A');
```

The keyboard mnemonic is displayed automatically in the menu, with the mnemonic letter underlined (see Figure 11.19). For example, in the item defined in the last example, the label will be displayed as "About" with an underlined letter 'A'. When the menu is displayed, the user just needs to press the A key, and the menu item is selected. (If the mnemonic letter is not part of the menu string, then typing it still selects the item, but the mnemonic is not displayed in the menu. Naturally, such invisible mnemonics are of dubious utility.)

Figure 1.19: Keyboard mnemonics

Sometimes, you don't want to underline the first letter of the menu item that matches the mnemonic. For example, if you have a mnemonic "A" for the menu item "Save As," then it makes more sense to underline the second "A" (Save As). You can specify which character you want to have underlined by calling the `setDisplayedMnemonicIndex` method.

If you have an `Action` object, you can add the mnemonic as the value of the `Action.MNEMONIC_KEY` key, as follows:

```
  aboutAction.putValue(Action.MNEMONIC_KEY, Integer.val
```

You can supply a mnemonic letter only in the constructor of a menu item, not in the constructor for a menu. To attach a mnemonic to a

menu, call the `setMnemonic` method:

```
var helpMenu = new JMenu("Help");
helpMenu.setMnemonic('H');
```

To select a top-level menu from the menu bar, press the Alt key together with the mnemonic letter. For example, press Alt+H to select the Help menu from the menu bar.

Keyboard mnemonics let you select a submenu or menu item from the currently open menu. In contrast, *accelerators* are keyboard shortcuts that let you select menu items without ever opening a menu. For example, many programs attach the accelerators Ctrl+O and Ctrl+S to the Open and Save items in the File menu. Use the `setAccelerator` method to attach an accelerator key to a menu item. The `setAccelerator` method takes an object of type `Keystroke`. For example, the following call attaches the accelerator Ctrl+O to the `openItem` menu item:

```
openItem.setAccelerator(KeyStroke.getKeyStroke("ctrl
```

Typing the accelerator key combination automatically selects the menu option and fires an action event, as if the user had selected the menu option manually.

You can attach accelerators only to menu items, not to menus. Accelerator keys don't actually open the menu. Instead, they directly fire the action event associated with a menu.

Conceptually, adding an accelerator to a menu item is similar to the technique of adding an accelerator to a Swing component. However, when the accelerator is added to a menu item, the key combination is automatically displayed in the menu (see Figure 11.20).



Figure 1.20: Accelerators

Note: Under Windows, Alt+F4 closes a window. But this is not an accelerator to be programmed in Java. It is a shortcut defined by the operating system. This key combination will always trigger the `WindowClosing`

event for the active window regardless of whether there is a Close item on the menu.

`javax.swing.JMenuItem` **1.2**

- `JMenuItem(String label, int mnemonic)`
  constructs a menu item with a given label and mnemonic.
- `void setAccelerator(KeyStroke k)`
  sets the keystroke `k` as accelerator for this menu item. The accelerator key is displayed next to the label.

`javax.swing.AbstractButton` **1.2**

- `void setMnemonic(int mnemonic)`
  sets the mnemonic character for the button. This character will be underlined in the label.
- `void setDisplayedMnemonicIndex(int index)` **1.4**
  sets the index of the character to be underlined in the button text. Use this method if you don't want the first occurrence of the mnemonic character to be underlined.

1.5.6. Enabling and Disabling Menu Items

Occasionally, a particular menu item should be selected only in certain contexts. For example, when a document is opened in read-

only mode, the Save menu item is not meaningful. Of course, we could remove the item from the menu with the `JMenu.remove` method, but users would react with some surprise to menus whose content keeps changing. Instead, it is better to deactivate the menu items that lead to temporarily inappropriate commands. A deactivated menu item is shown in gray and cannot be selected (see Figure 11.21).



Figure 1.21: Disabled menu items

To enable or disable a menu item, use the `setEnabled` method:

```
saveItem.setEnabled(false);
```

There are two strategies for enabling and disabling menu items. Each time circumstances change, you can call `setEnabled` on the

relevant menu items or actions. For example, as soon as a document has been set to read-only mode, you can locate the Save and Save As menu items and disable them. Alternatively, you can disable items just before displaying the menu. To do this, you must register a listener for the "menu selected" event. The `javax.swing.event` package defines a `MenuListener` interface with three methods:

```
void menuSelected(MenuEvent event)
void menuDeselected(MenuEvent event)
void menuCanceled(MenuEvent event)
```

The `menuSelected` method is called *before* the menu is displayed. It can therefore be used to disable or enable menu items. The following code shows how to disable the Save and Save As actions whenever the Read Only checkbox menu item is selected:

```
public void menuSelected(MenuEvent event)
{
   saveAction.setEnabled(!readonlyItem.isSelected());
   saveAsAction.setEnabled(!readonlyItem.isSelected()
}
```

Caution: Disabling menu items just before displaying the menu is a good idea, but it does not work for menu items that also have

accelerator keys. Since the menu is never opened when the accelerator key is pressed, the action is never disabled, and is still triggered by the accelerator key.

`javax.swing.JMenuItem` **1.2**

- `void setEnabled(boolean b)`
  enables or disables the menu item.

`javax.swing.event.MenuListener` **1.2**

- `void menuSelected(MenuEvent e)`
  is called when the menu has been selected, before it is opened.
- `void menuDeselected(MenuEvent e)`
  is called when the menu has been deselected, after it has been closed.
- `void menuCanceled(MenuEvent e)`
  is called when the menu has been canceled, for example, by a user clicking outside the menu.

Listing 11.6 is a sample program that generates a set of menus. It shows all the features that you saw in this section: nested menus, disabled menu items, checkbox and radio button menu items, a pop-up menu, and keyboard mnemonics and accelerators.

Listing 1.6 menu/MenuFrame.java

```
1  package menu;
2
3  import java.awt.event.*;
4  import javax.swing.*;
5
6  /**
7   * A frame with a sample menu bar.
8   */
9  public class MenuFrame extends JFrame
10 {
11    private static final int DEFAULT_WIDTH = 300
12    private static final int DEFAULT_HEIGHT = 20
13    private Action saveAction;
14    private Action saveAsAction;
15    private JCheckBoxMenuItem readonlyItem;
16
17    /**
18     * A sample action that prints the action na
19     */
20    class TestAction extends AbstractAction
21    {
22       public TestAction(String name)
23       {
24          super(name);
25       }
26
```

```
27          public void actionPerformed(ActionEvent e
28          {
29             System.out.println(getValue(Action.NAM
30          }
31       }
32
33       public MenuFrame()
34       {
35          setSize(DEFAULT_WIDTH, DEFAULT_HEIGHT);
36
37          var fileMenu = new JMenu("File");
38          fileMenu.add(new TestAction("New"));
39
40          // demonstrate accelerators
41
42          var openItem = fileMenu.add(new TestActio
43          openItem.setAccelerator(KeyStroke.getKeyS
44
45          fileMenu.addSeparator();
46
47          saveAction = new TestAction("Save");
48          JMenuItem saveItem = fileMenu.add(saveAct
49          saveItem.setAccelerator(KeyStroke.getKeyS
50
51          saveAsAction = new TestAction("Save As");
52          fileMenu.add(saveAsAction);
53          fileMenu.addSeparator();
54
```

```
55          fileMenu.add(new AbstractAction("Exit")
56             {
57                public void actionPerformed(ActionE
58                {
59                   System.exit(0);
60                }
61             });
62
63          // demonstrate checkbox and radio button
64
65          readonlyItem = new JCheckBoxMenuItem("Rea
66          readonlyItem.addActionListener(event -> {
67             boolean saveOk = !readonlyItem.isSelec
68             saveAction.setEnabled(saveOk);
69             saveAsAction.setEnabled(saveOk);
70          });
71
72          var group = new ButtonGroup();
73
74          var insertItem = new JRadioButtonMenuItem
75          insertItem.setSelected(true);
76          var overtypeItem = new JRadioButtonMenuIt
77
78          group.add(insertItem);
79          group.add(overtypeItem);
80
81          // demonstrate icons
82
```

```
83        var cutAction = new TestAction("Cut");
84        cutAction.putValue(Action.SMALL_ICON, new
85        var copyAction = new TestAction("Copy");
86        copyAction.putValue(Action.SMALL_ICON, ne
87        var pasteAction = new TestAction("Paste")
88        pasteAction.putValue(Action.SMALL_ICON, n
89
90        var editMenu = new JMenu("Edit");
91        editMenu.add(cutAction);
92        editMenu.add(copyAction);
93        editMenu.add(pasteAction);
94
95        // demonstrate nested menus
96
97        var optionMenu = new JMenu("Options");
98
99        optionMenu.add(readonlyItem);
100       optionMenu.addSeparator();
101       optionMenu.add(insertItem);
102       optionMenu.add(overtypeItem);
103
104       editMenu.addSeparator();
105       editMenu.add(optionMenu);
106
107       // demonstrate mnemonics
108
109       var helpMenu = new JMenu("Help");
110       helpMenu.setMnemonic('H');
```

```
111
112         var indexItem = new JMenuItem("Index");
113         indexItem.setMnemonic('I');
114         helpMenu.add(indexItem);
115
116         // you can also add the mnemonic key to a
117         var aboutAction = new TestAction("About")
118         aboutAction.putValue(Action.MNEMONIC_KEY,
119         helpMenu.add(aboutAction);
120
121         // add all top-level menus to menu bar
122
123         var menuBar = new JMenuBar();
124         setJMenuBar(menuBar);
125
126         menuBar.add(fileMenu);
127         menuBar.add(editMenu);
128         menuBar.add(helpMenu);
129
130         // demonstrate pop-ups
131
132         JPopupMenu popup = new JPopupMenu();
133         popup.add(cutAction);
134         popup.add(copyAction);
135         popup.add(pasteAction);
136
137         var panel = new JPanel();
138         panel.setComponentPopupMenu(popup);
```

```
139         add(panel);
140     }
141 }
```

1.5.7. Toolbars

A toolbar is a button bar that gives quick access to the most commonly used commands in a program (see Figure 11.22).



Figure 1.22: A toolbar

What makes toolbars special is that you can move them elsewhere. You can drag the toolbar to one of the four borders of the frame (see Figure 11.23). When you release the mouse button, the toolbar is dropped into the new location (see Figure 11.24).



Figure 1.23: Dragging the toolbar



Figure 1.24: The toolbar has been dragged to another border

Note: Toolbar dragging works if the toolbar is inside a container with a border layout, or any other layout

manager that supports the `North`, `East`, `South`, and `West` constraints.

The toolbar can even be completely detached from the frame. A detached toolbar is contained in its own frame (see Figure 11.25). When you close the frame containing a detached toolbar, the toolbar jumps back into the original frame.



Figure 1.25: Detaching the toolbar

Toolbars are straightforward to program. Add components into the toolbar:

```
var toolbar = new JToolBar();
toolbar.add(blueButton);
```

The `JToolBar` class also has a method to add an `Action` object. Simply populate the toolbar with `Action` objects, like this:

```
toolbar.add(blueAction);
```

The small icon of the action is displayed in the toolbar.

You can separate groups of buttons with a separator:

```
toolbar.addSeparator();
```

For example, the toolbar in Figure 11.22 has a separator between the third and fourth buttons.

Then, add the toolbar to the frame:

```
add(toolbar, BorderLayout.NORTH);
```

You can also specify a title for the toolbar that appears when the toolbar is undocked:

```
toolbar = new JToolBar(titleString);
```

By default, toolbars are initially horizontal. To have a toolbar start out vertical, use

```
toolbar = new JToolBar(SwingConstants.VERTICAL)
```

or

```
toolbar = new JToolBar(titleString, SwingConstants.VE
```

Buttons are the most common components inside toolbars. But there is no restriction on the components that you can add to a toolbar. For example, you can add a combo box to a toolbar.

1.5.8. Tooltips

A disadvantage of toolbars is that users are often mystified by the meanings of the tiny icons in toolbars. To solve this problem, user interface designers invented *tooltips*. A tooltip is activated when the cursor rests for a moment over a button. The tooltip text is displayed inside a colored rectangle. When the user moves the mouse away, the tooltip disappears. (See Figure 11.26.)

Figure 1.26: A tooltip

In Swing, you can add tooltips to any `JComponent` simply by calling the `setToolTipText` method:

```
exitButton.setToolTipText("Exit");
```

Alternatively, if you use `Action` objects, you associate the tooltip with the `SHORT_DESCRIPTION` key:

```
exitAction.putValue(Action.SHORT_DESCRIPTION, "Exit")
```

`javax.swing.JToolBar` **1.2**

- `JToolBar()`
- `JToolBar(String titleString)`
- `JToolBar(int orientation)`
- `JToolBar(String titleString, int orientation)`
  construct a toolbar with the given title string and orientation. `orientation` is one of `SwingConstants.HORIZONTAL` (the default) or `SwingConstants.VERTICAL`.
- `JButton add(Action a)`
  constructs a new button inside the toolbar with name, icon, short description, and action callback from the given action, and adds the button to the end of the toolbar.
- `void addSeparator()`
  adds a separator to the end of the toolbar.

`javax.swing.JComponent` **1.2**

- `void setToolTipText(String text)`
  sets the text that should be displayed as a tooltip when the mouse hovers over the component.

1.6. The Grid Bag Layout

So far we've been using only the border layout, flow layout, and grid layout for the user interface of our sample applications. For more complex tasks, this is not going to be enough.

Since Java 1.0, the AWT includes the *grid bag layout* that lays out components in rows and columns. The row and column sizes are flexible, and components can span multiple rows and columns. This layout manager is very flexible, but also very complex. The mere mention of the words "grid bag layout" has been known to strike fear in the hearts of Java programmers.

In an unsuccessful attempt to design a layout manager that would free programmers from the tyranny of the grid bag layout, the Swing designers came up with the *box layout*. According to the JDK documentation of the `BoxLayout` class: "Nesting multiple panels with different combinations of horizontal and vertical [*sic*] gives an effect similar to `GridBagLayout`, without the complexity." However, as each box is laid out independently, you cannot use box layouts to arrange neighboring components both horizontally and vertically.

Java 1.4 saw yet another attempt to design a replacement for the grid bag layout—the *spring layout* where you use imaginary springs to connect the components in a container. As the container is resized, the springs stretch or shrink, thereby adjusting the positions

of the components. This sounds tedious and confusing, and it is. The spring layout quickly sank into obscurity.

The NetBeans IDE combines a layout tool (called "Matisse") and a layout manager. A user interface designer uses the tool to drop components into a container and to indicate which components should line up. The tool translates the designer's intentions into instructions for the *group layout manager.* This is much more convenient than writing the layout management code by hand.

In the coming sections, I will cover the grid bag layout because it is commonly used and is still the easiest mechanism for programmatically producing layout code. I will show you a strategy that makes grid bag layouts relatively painless in common situations.

1.6.1. Grid Bag Basics

The grid bag layout is the mother of all layout managers. You can think of a grid bag layout as a grid layout without the limitations. In a grid bag layout, the rows and columns can have variable sizes. You can join adjacent cells to make room for larger components. (Many word processors, as well as HTML, provide similar capabilities for tables: You can start out with a grid and then merge adjacent cells as necessary.) The components need not fill the entire cell area, and you can specify their alignment within cells.

Consider the font selector of Figure 11.27. It consists of the following components:

- Two combo boxes to specify the font face and size
- Labels for these two combo boxes
- Two checkboxes to select bold and italic
- A text area for the sample string



Figure 1.27: A font selector

Now, chop up the container into a grid of cells, as shown in Figure 11.28. (The rows and columns need not have equal size.) Each checkbox spans two columns, and the text area spans four rows.



Figure 1.28: Dialog box grid used in design

To describe the layout to the grid bag manager, use the following procedure:

1. Create an object of type `GridBagLayout`. You don't need to tell it how many rows and columns the underlying grid has. Instead, the layout manager will try to guess it from the information you give it later.
2. Set this `GridBagLayout` object to be the layout manager for the component.
3. For each component, create an object of type `GridBagConstraints`. Set field values of the `GridBagConstraints` object to specify how the components are laid out within the grid bag.
4. Finally, add each component with its constraints by using the call

```
add(component, constraints);
```

Here’s an example of the code needed. (We'll go over the various constraints in more detail in the sections that follow—so don’t worry if you don’t know what some of the constraints do.)

```
var layout = new GridBagLayout();
panel.setLayout(layout);
var constraints = new GridBagConstraints();
constraints.weightx = 100;
constraints.weighty = 100;
constraints.gridx = 0;
constraints.gridy = 2;
constraints.gridwidth = 2;
constraints.gridheight = 1;
panel.add(component, constraints);
```

The trick is knowing how to set the state of the `GridBagConstraints` object. We'll discuss this object in the sections that follow.

1.6.2. The `gridx`, `gridy`, `gridwidth`, and `gridheight` Parameters

The `gridx`, `gridy`, `gridwidth`, and `gridheight` constraints define where the component is located in the grid. The `gridx` and `gridy` values specify the column and row positions of the upper left corner of the component to be added. The `gridwidth` and `gridheight` values determine how many columns and rows the component occupies.

The grid coordinates start with `0`. In particular, `gridx = 0` and `gridy = 0` denotes the top left corner. The text area in our example has `gridx = 2`, `gridy = 0` because it starts in column 2 (that is, the third column) of row 0. It has `gridwidth = 1` and `gridheight = 4` because it spans one column and four rows.

1.6.3. Weight Fields

You always need to set the *weight* fields (`weightx` and `weighty`) for each area in a grid bag layout. If you set the weight to `0`, the area never grows or shrinks beyond its initial size in that direction. In the grid bag layout for Figure 11.27, we set the `weightx` field of the labels to be `0`. This allows the labels to keep constant width when you resize the window. On the other hand, if you set the weights for all areas to `0`, the container will huddle in the center of its allotted area instead of stretching to fill it.

Conceptually, the problem with the weight parameters is that weights are properties of rows and columns, not individual cells. But you need to specify them for cells because the grid bag layout does not expose the rows and columns. The row and column weights are computed as the maxima of the cell weights in each row or column. Thus, if you want a row or column to stay at a fixed size, you need to set the weights of all components in it to zero.

Note that the weights don't actually give the relative sizes of the columns. They tell what proportion of the "slack" space should be allocated to each area if the container exceeds its preferred size. This isn't particularly intuitive. I recommend that you set all weights at `100`. Then, run the program and see how the layout looks. Resize the dialog to see how the rows and columns adjust. If you find that a particular row or column should not grow, set the weights of all components in it to zero. You can tinker with other weight values, but it is usually not worth the effort.

1.6.4. The `fill` and `anchor` Parameters

If you don't want a component to stretch out and fill the entire area, set the `fill` constraint. You have four possibilities for this parameter: the valid values are `GridBagConstraints.NONE`, `GridBagConstraints.HORIZONTAL`,

`GridBagConstraints.VERTICAL`, and `GridBagConstraints.BOTH`.

If the component does not fill the entire area, you can specify where in the area you want it by setting the `anchor` field. The valid values are `GridBagConstraints.CENTER` (the default), `GridBagConstraints.NORTH`, `GridBagConstraints.NORTHEAST`, `GridBagConstraints.EAST`, and so on.

1.6.5. Padding

You can surround a component with additional blank space by setting the `insets` field of `GridBagConstraints`. Set the `left`, `top`, `right`, and `bottom` values of the `Insets` object to the amount of space that you want to have around the component. This is called the *external padding*.

The `ipadx` and `ipady` values set the *internal padding*. These values are added to the minimum width and height of the component. This ensures that the component does not shrink down to its minimum size.

1.6.6. Alternative Method to Specify the `gridx`, `gridy`, `gridwidth`, and `gridheight` Parameters

The AWT documentation recommends that instead of setting the `gridx` and `gridy` values to absolute positions, you set them to the constant `GridBagConstraints.RELATIVE`. Then, add the components to the grid bag layout in a standardized order, going from left to right in the first row, then moving along the next row, and so on.

You would still specify the number of rows and columns spanned, by giving the appropriate `gridheight` and `gridwidth` fields. However, if the component extends to the *last* row or column, you don't need to specify the actual number, but the constant `GridBagConstraints.REMAINDER`. This tells the layout manager that the component is the last one in its row.

This scheme does seem to work. But it sounds really goofy to hide the actual placement information from the layout manager and hope that it will rediscover it.

1.6.7. A Grid Bag Layout Recipe

In practice, the following recipe makes grid bag layouts relatively trouble-free:

1. Sketch out the component layout on a piece of paper.
2. Find a grid such that the small components are each contained in a cell and the larger components span multiple cells.

3. Label the rows and columns of your grid with 0, 1, 2, 3, . . . You can now read off the `gridx`, `gridy`, `gridwidth`, and `gridheight` values.
4. For each component, ask yourself whether it needs to fill its cell horizontally or vertically. If not, how do you want it aligned? This tells you the `fill` and `anchor` parameters.
5. Set all weights to `100`. However, if you want a particular row or column to always stay at its default size, set the `weightx` or `weighty` to `0` in all components that belong to that row or column.
6. Write the code. Carefully double-check your settings for the `GridBagConstraints`. One wrong constraint can ruin your whole layout.
7. Compile, run, and enjoy.

1.6.8. A Helper Class to Tame the Grid Bag Constraints

The most tedious aspect of the grid bag layout is writing the code that sets the constraints. Most programmers write helper functions or a small helper class for this purpose. I present such a class after the complete code for the font dialog example. This class has the following features:

- Its name is short: `GBC` instead of `GridBagConstraints`.

- It extends `GridBagConstraints`, so you can use shorter names such as `GBC.EAST` for the constants.
- Use a `GBC` object when adding a component, such as

```
add(component, new GBC(1, 2));
```

- There are two constructors to set the most common parameters: `gridx` and `gridy`, or `gridx`, `gridy`, `gridwidth`, and `gridheight`.

```
add(component, new GBC(1, 2, 1, 4));
```

- There are convenient setters for the fields that come in `x`/`y` pairs:

```
add(component, new GBC(1, 2).setWeight(100, 100));
```

- The setter methods return `this`, so you can chain them:

```
add(component, new GBC(1, 2).setAnchor(GBC.EAST).se
```

- The `setInsets` methods construct the `Insets` object for you. To get one-pixel insets, simply call

```
add(component, new GBC(1, 2).setAnchor(GBC.EAST).se
```

Listing 11.7 shows the frame class for the font dialog example. The `GBC` helper class is in Listing 11.8. Here is the code that adds the components to the grid bag:

```
add(faceLabel, new GBC(0, 0).setAnchor(GBC.EAST));
add(face, new GBC(1, 0).setFill(GBC.HORIZONTAL).setWe
add(sizeLabel, new GBC(0, 1).setAnchor(GBC.EAST));
add(size, new GBC(1, 1).setFill(GBC.HORIZONTAL).setWe
add(bold, new GBC(0, 2, 2, 1).setAnchor(GBC.CENTER).s
add(italic, new GBC(0, 3, 2, 1).setAnchor(GBC.CENTER)
add(sample, new GBC(2, 0, 1, 4).setFill(GBC.BOTH).set
```

Once you understand the grid bag constraints, this kind of code is fairly easy to read and debug.

Listing 1.7 gridbag/FontFrame.java

```
1  package gridbag;
2
3  import java.awt.Font;
4  import java.awt.GridBagLayout;
5  import java.awt.event.ActionListener;
6
```

```
 7 import javax.swing.BorderFactory;
 8 import javax.swing.JCheckBox;
 9 import javax.swing.JComboBox;
10 import javax.swing.JFrame;
11 import javax.swing.JLabel;
12 import javax.swing.JTextArea;
13
14 /**
15  * A frame that uses a grid bag layout to arran
16  */
17 public class FontFrame extends JFrame
18 {
19    private static final int TEXT_ROWS = 10;
20    private static final int TEXT_COLUMNS = 20;
21
22    private JComboBox<String> face;
23    private JComboBox<Integer> size;
24    private JCheckBox bold;
25    private JCheckBox italic;
26    private JTextArea sample;
27
28    public FontFrame()
29    {
30       var layout = new GridBagLayout();
31       setLayout(layout);
32
33       ActionListener listener = event -> update
34
```

```
35        // construct components
36
37        var faceLabel = new JLabel("Face: ");
38
39        face = new JComboBox<>(new String[] { "Se
40           "Dialog", "DialogInput" });
41
42        face.addActionListener(listener);
43
44        var sizeLabel = new JLabel("Size: ");
45
46        size = new JComboBox<>(new Integer[] { 8,
47
48        size.addActionListener(listener);
49
50        bold = new JCheckBox("Bold");
51        bold.addActionListener(listener);
52
53        italic = new JCheckBox("Italic");
54        italic.addActionListener(listener);
55
56        sample = new JTextArea(TEXT_ROWS, TEXT_CO
57        sample.setText("The quick brown fox jumps
58        sample.setEditable(false);
59        sample.setLineWrap(true);
60        sample.setBorder(BorderFactory.createEtch
61
62        // add components to grid, using GBC conv
```

```
63
64          add(faceLabel, new GBC(0, 0).setAnchor(GB
65          add(face, new GBC(1, 0).setFill(GBC.HORIZ
66          add(sizeLabel, new GBC(0, 1).setAnchor(GB
67          add(size, new GBC(1, 1).setFill(GBC.HORIZ
68          add(bold, new GBC(0, 2, 2, 1).setAnchor(G
69          add(italic, new GBC(0, 3, 2, 1).setAnchor
70          add(sample, new GBC(2, 0, 1, 4).setFill(G
71          pack();
72          updateSample();
73       }
74
75       public void updateSample()
76       {
77          var fontFace = (String) face.getSelectedI
78          int fontStyle = (bold.isSelected() ? Font
79             + (italic.isSelected() ? Font.ITALIC
80          int fontSize = size.getItemAt(size.getSel
81          var font = new Font(fontFace, fontStyle,
82          sample.setFont(font);
83          sample.repaint();
84       }
85    }
```

Listing 1.8 gridbag/GBC.java

```
1  package gridbag;
2
3  import java.awt.*;
4
5  /**
6   * This class simplifies the use of the GridBag
7   * @version 1.01 2004-05-06
8   * @author Cay Horstmann
9   */
10 public class GBC extends GridBagConstraints
11 {
12    /**
13     * Constructs a GBC with a given gridx and g
14     * bag constraint values set to the default
15     * @param gridx the gridx position
16     * @param gridy the gridy position
17     */
18    public GBC(int gridx, int gridy)
19    {
20       this.gridx = gridx;
21       this.gridy = gridy;
22    }
23
24    /**
25     * Constructs a GBC with given gridx, gridy,
26     * other grid bag constraint values set to t
```

```
27      * @param gridx the gridx position
28      * @param gridy the gridy position
29      * @param gridwidth the cell span in x-direc
30      * @param gridheight the cell span in y-dire
31      */
32     public GBC(int gridx, int gridy, int gridwic
33     {
34        this.gridx = gridx;
35        this.gridy = gridy;
36        this.gridwidth = gridwidth;
37        this.gridheight = gridheight;
38     }
39
40     /**
41      * Sets the anchor.
42      * @param anchor the anchor value
43      * @return this object for further modificat
44      */
45     public GBC setAnchor(int anchor)
46     {
47        this.anchor = anchor;
48        return this;
49     }
50
51     /**
52      * Sets the fill direction.
53      * @param fill the fill direction
54      * @return this object for further modificat
```

```
55      */
56     public GBC setFill(int fill)
57     {
58        this.fill = fill;
59        return this;
60     }
61
62     /**
63      * Sets the cell weights.
64      * @param weightx the cell weight in x-direc
65      * @param weighty the cell weight in y-direc
66      * @return this object for further modificat
67      */
68     public GBC setWeight(double weightx, double
69     {
70        this.weightx = weightx;
71        this.weighty = weighty;
72        return this;
73     }
74
75     /**
76      * Sets the insets of this cell.
77      * @param distance the spacing to use in all
78      * @return this object for further modificat
79      */
80     public GBC setInsets(int distance)
81     {
82        this.insets = new Insets(distance, distan
```

```
83          return this;
84       }
85
86       /**
87        * Sets the insets of this cell.
88        * @param top the spacing to use on top
89        * @param left the spacing to use to the lef
90        * @param bottom the spacing to use on the b
91        * @param right the spacing to use to the ri
92        * @return this object for further modificat
93        */
94       public GBC setInsets(int top, int left, int
95       {
96          this.insets = new Insets(top, left, botto
97          return this;
98       }
99
100      /**
101       * Sets the internal padding.
102       * @param ipadx the internal padding in x-di
103       * @param ipady the internal padding in y-di
104       * @return this object for further modificat
105       */
106      public GBC setIpad(int ipadx, int ipady)
107      {
108         this.ipadx = ipadx;
109         this.ipady = ipady;
```

```
110         return this;
111      }
112   }
```

`java.awt.GridBagConstraints` **1.0**

- `int gridx, gridy`
  specify the starting column and row of the cell. The default is `0`.
- `int gridwidth, gridheight`
  specify the column and row extent of the cell. The default is `1`.
- `double weightx, weighty`
  specify the capacity of the cell to grow. The default is `0`.
- `int anchor`
  indicates the alignment of the component inside the cell. You can choose between absolute positions:

  `NORTHWEST` `NORTH` `NORTHEAST`

  `WEST` `CENTER` `EAST`

  `SOUTHWEST` `SOUTH` `SOUTHEAST`

  or their orientation-independent counterparts:

  `FIRST_LINE_START` `LINE_START` `FIRST_LINE_END`

`PAGE_START`	`CENTER`	`PAGE_END`
`LAST_LINE_START`	`LINE_END`	`LAST_LINE_END`

Use the latter if your application may be localized for right-to-left or top-to-bottom text. The default is `CENTER`.

- `int fill`
  specifies the fill behavior of the component inside the cell: one of `NONE`, `BOTH`, `HORIZONTAL`, or `VERTICAL`. The default is `NONE`.
- `int ipadx, ipady`
  specify the "internal" padding around the component. The default is `0`.
- `Insets insets`
  specifies the "external" padding along the cell boundaries. The default is no padding.
- `GridBagConstraints(int gridx, int gridy, int gridwidth, int gridheight, double weightx, double weighty, int anchor, int fill, Insets insets, int ipadx, int ipady)` **1.2**
  constructs a `GridBagConstraints` with all its fields specified in the parameters. This constructor should only be used by

> automatic code generators because it makes your source code very hard to read.

1.7. Custom Layout Managers

You can design your own `LayoutManager` class that manages components in a special way. As a fun example, let's arrange all components in a container to form a circle (see Figure 11.29).



Figure 1.29: Circle layout

Your own layout manager must implement the `LayoutManager` interface. You need to override the following five methods:

```
void addLayoutComponent(String s, Component c)
void removeLayoutComponent(Component c)
Dimension preferredLayoutSize(Container parent)
Dimension minimumLayoutSize(Container parent)
void layoutContainer(Container parent)
```

The first two methods are called when a component is added or removed. If you don't keep any additional information about the components, you can make them do nothing. The next two methods compute the space required for the minimum and the preferred layout of the components. These are usually the same quantity. The fifth method does the actual work and invokes `setBounds` on all components.

Note: The AWT has a second interface, called `LayoutManager2`, with ten methods to implement rather than five. The main point of the `LayoutManager2` interface is to allow you to use the `add` method with constraints. For example, the `BorderLayout` and `GridBagLayout` implement the `LayoutManager2` interface.

Listing 11.9 shows the code for the `CircleLayout` manager which, uselessly enough, lays out the components along a circle inside the parent. The frame class of the sample program is in Listing 11.10.

Listing 1.9 circleLayout/CircleLayout.java

```
1 package circleLayout;
2
3 import java.awt.*;
```

```
4
5  /**
6   * A layout manager that lays out components al
7   */
8  public class CircleLayout implements LayoutMana
9  {
10    private int minWidth = 0;
11    private int minHeight = 0;
12    private int preferredWidth = 0;
13    private int preferredHeight = 0;
14    private boolean sizesSet = false;
15    private int maxComponentWidth = 0;
16    private int maxComponentHeight = 0;
17
18    public void addLayoutComponent(String name,
19    {
20    }
21
22    public void removeLayoutComponent(Component
23    {
24    }
25
26    public void setSizes(Container parent)
27    {
28       if (sizesSet) return;
29       int n = parent.getComponentCount();
30
31       preferredWidth = 0;
```

```
32          preferredHeight = 0;
33          minWidth = 0;
34          minHeight = 0;
35          maxComponentWidth = 0;
36          maxComponentHeight = 0;
37
38          // compute the maximum component widths a
39          // and set the preferred size to the sum
40          for (int i = 0; i < n; i++)
41          {
42             Component c = parent.getComponent(i);
43             if (c.isVisible())
44             {
45                Dimension d = c.getPreferredSize();
46                maxComponentWidth = Math.max(maxCom
47                maxComponentHeight = Math.max(maxCo
48                preferredWidth += d.width;
49                preferredHeight += d.height;
50             }
51          }
52          minWidth = preferredWidth / 2;
53          minHeight = preferredHeight / 2;
54          sizesSet = true;
55       }
56
57       public Dimension preferredLayoutSize(Contain
58       {
59          setSizes(parent);
```

```
60          Insets insets = parent.getInsets();
61          int width = preferredWidth + insets.left
62          int height = preferredHeight + insets.top
63          return new Dimension(width, height);
64       }
65
66       public Dimension minimumLayoutSize(Container
67       {
68          setSizes(parent);
69          Insets insets = parent.getInsets();
70          int width = minWidth + insets.left + inse
71          int height = minHeight + insets.top + ins
72          return new Dimension(width, height);
73       }
74
75       public void layoutContainer(Container parent
76       {
77          setSizes(parent);
78
79          // compute center of the circle
80
81          Insets insets = parent.getInsets();
82          int containerWidth = parent.getSize().wid
83          int containerHeight = parent.getSize().he
84
85          int xcenter = insets.left + containerWidt
86          int ycenter = insets.top + containerHeigh
87
```

```
88          // compute radius of the circle
89
90          int xradius = (containerWidth - maxCompor
91          int yradius = (containerHeight - maxCompo
92          int radius = Math.min(xradius, yradius);
93
94          // lay out components along the circle
95
96          int n = parent.getComponentCount();
97          for (int i = 0; i < n; i++)
98          {
99             Component c = parent.getComponent(i);
100            if (c.isVisible())
101            {
102               double angle = 2 * Math.PI * i / n;
103
104               // center point of component
105               int x = xcenter + (int) (Math.cos(a
106               int y = ycenter + (int) (Math.sin(a
107
108               // move component so that its cente
109               // and its size is its preferred si
110               Dimension d = c.getPreferredSize();
111               c.setBounds(x - d.width / 2, y - d
112            }
```

```
      }
   }
}
```

Listing 1.10 circleLayout/CircleLayoutFrame.java

```
package circleLayout;

import javax.swing.*;

/**
 * A frame that shows buttons arranged along a
 */
public class CircleLayoutFrame extends JFrame
{
   public CircleLayoutFrame()
   {
      setLayout(new CircleLayout());
      add(new JButton("Yellow"));
      add(new JButton("Blue"));
      add(new JButton("Red"));
      add(new JButton("Green"));
      add(new JButton("Orange"));
      add(new JButton("Fuchsia"));
      add(new JButton("Indigo"));
```

```
20          pack();
21       }
22    }
```

java.awt.LayoutManager **1.0**

- `void addLayoutComponent(String name, Component comp)`
  adds a component to the layout.
- `void removeLayoutComponent(Component comp)`
  removes a component from the layout.
- `Dimension preferredLayoutSize(Container cont)`
  returns the preferred size dimensions for the container under this layout.
- `Dimension minimumLayoutSize(Container cont)`
  returns the minimum size dimensions for the container under this layout.
- `void layoutContainer(Container cont)`
  lays out the components in a container.

1.8. Dialog Boxes

In GUI applications, you usually want separate dialog boxes to pop up to give information to, or get information from, the user.

Just as with most windowing systems, AWT distinguishes between *modal* and *modeless* dialog boxes. A modal dialog box won't let users interact with the remaining windows of the application until he or she deals with it. Use a modal dialog box when you need information from the user before you can proceed with execution. For example, when the user wants to read a file, a modal file dialog box is the one to pop up. The user must specify a file name before the program can begin the read operation. Only when the user closes the modal dialog box can the application proceed.

A modeless dialog box lets the user enter information in both the dialog box and the remainder of the application. One example of a modeless dialog is a toolbar. The toolbar can stay in place as long as needed, and the user can interact with both the application window and the toolbar.

Let's start this section with the simplest dialogs—modal dialogs with just a single message. Swing has a convenient `JOptionPane` class that lets you put up a simple dialog without writing any special dialog box code. Next, you will see how to write more complex dialogs by implementing your own dialog windows. Finally, you will see how to transfer data from your application into a dialog and back.

We'll conclude the discussion of dialog boxes by looking at the Swing `JFileChooser`.

1.8.1. Option Panes

Swing has a set of ready-made simple dialogs that suffice to ask the user for a single piece of information. The `JOptionPane` has four static methods to show these simple dialogs:

`showMessageDialog`	Show a message and wait for the user to click OK
`showConfirmDialog`	Show a message and get a confirmation (like OK/Cancel)
`showOptionDialog`	Show a message and get a user option (typically from a sequence of buttons)
`showInputDialog`	Show a message and get user input (typically from an input field or combo box)

Figure 11.30 shows a typical dialog. As you can see, the dialog has the following components:

- An icon
- A message
- One or more option buttons

Figure 1.30: A `JOptionPane`

The input dialog has an additional component for user input. This can be a text field into which the user can type an arbitrary string, or a combo box from which the user can select one item.

The exact layout of these dialogs and the choice of icons for standard message types depend on the pluggable look-and-feel.

The icon on the left side depends on one of five *message types*:

```
ERROR_MESSAGE
INFORMATION_MESSAGE
WARNING_MESSAGE
QUESTION_MESSAGE
PLAIN_MESSAGE
```

The `PLAIN_MESSAGE` type has no icon. Each dialog type also has a method that lets you supply your own icon instead.

For each dialog type, you can specify a message. This message can be a string, an icon, a user interface component, or any other object. Here is how the message object is displayed:

`String`	Draw the string
`Icon`	Show the icon
`Component`	Show the component
`Object[]`	Show all objects in the array, stacked on top of each other
Any other object	Apply `toString` and show the resulting string

Of course, supplying a message string is by far the most common case. Supplying a `Component` gives you ultimate flexibility because you can make the `paintComponent` method draw anything you want.

The buttons at the bottom depend on the dialog type and the *option type*. When calling `showMessageDialog` and `showInputDialog`, you get only a standard set of buttons (OK and OK/Cancel, respectively). When calling `showConfirmDialog`, you can choose among four option types:

```
DEFAULT_OPTION
YES_NO_OPTION
YES_NO_CANCEL_OPTION
OK_CANCEL_OPTION
```

With the `showOptionDialog` you can specify an arbitrary set of options. You supply an array of objects for the options. Each array element is rendered as follows:

`String`	Make a button with the string as label
`Icon`	Make a button with the icon as label

`Component`	Show the component
Any other object	Apply `toString` and make a button with the resulting string as label

The return values of these functions are as follows:

`showMessageDialog`	None
`showConfirmDialog`	An integer representing the chosen option
`showOptionDialog`	An integer representing the chosen option
`showInputDialog`	The string that the user supplied or selected

The `showConfirmDialog` and `showOptionDialog` return integers to indicate which button the user chose. For the option dialog, this is simply the index of the chosen option or the value `CLOSED_OPTION` if the user closed the dialog instead of choosing an option. For the confirmation dialog, the return value can be one of the following:

```
OK_OPTION
CANCEL_OPTION
YES_OPTION
NO_OPTION
CLOSED_OPTION
```

This all sounds like a bewildering set of choices, but in practice it is simple. Follow these steps:

1. Choose the dialog type (message, confirmation, option, or input).
2. Choose the icon (error, information, warning, question, none, or custom).
3. Choose the message (string, icon, custom component, or a stack of them).
4. For a confirmation dialog, choose the option type (default, Yes/No, Yes/No/Cancel, or OK/Cancel).
5. For an option dialog, choose the options (strings, icons, or custom components) and the default option.
6. For an input dialog, choose between a text field and a combo box.
7. Locate the appropriate method to call in the `JOptionPane` API.

For example, suppose you want to show the dialog in Figure 11.30. The dialog shows a message and asks the user to confirm or cancel. Thus, it is a confirmation dialog. The icon is a question icon. The

message is a string. The option type is `OK_CANCEL_OPTION`. Here is the call you would make:

```
int selection = JOptionPane.showConfirmDialog(parent,
   "Message", "Title",
   JOptionPane.OK_CANCEL_OPTION,
   JOptionPane.QUESTION_MESSAGE);
if (selection == JOptionPane.OK_OPTION) . . .
```

Tip: The message string can contain newline (`'\n'`) characters. Such a string is displayed in multiple lines.

`javax.swing.JOptionPane` **1.2**

- `static void showMessageDialog(Component parent, Object message, String title, int messageType, Icon icon)`
- `static void showMessageDialog(Component parent, Object message, String title, int messageType)`
- `static void showMessageDialog(Component parent, Object message)`
- `static void showInternalMessageDialog(Component parent, Object message, String title, int`

`messageType, Icon icon)`

- `static void showInternalMessageDialog(Component parent, Object message, String title, int messageType)`
- `static void showInternalMessageDialog(Component parent, Object message)`

  show a message dialog or an internal message dialog. (An internal dialog is rendered entirely within its owner's frame.) The parent component can be `null`. The message to show on the dialog can be a string, icon, component, or an array of them. The `messageType` parameter is one of `ERROR_MESSAGE`, `INFORMATION_MESSAGE`, `WARNING_MESSAGE`, `QUESTION_MESSAGE`, or `PLAIN_MESSAGE`.

- `static int showConfirmDialog(Component parent, Object message, String title, int optionType, int messageType, Icon icon)`
- `static int showConfirmDialog(Component parent, Object message, String title, int optionType, int messageType)`
- `static int showConfirmDialog(Component parent, Object message, String title, int optionType)`
- `static int showConfirmDialog(Component parent, Object message)`
- `static int showInternalConfirmDialog(Component parent, Object message, String title, int optionType, int messageType, Icon icon)`
- `static int showInternalConfirmDialog(Component parent, Object message, String title, int optionType, int messageType)`
- `static int showInternalConfirmDialog(Component parent, Object message, String title, int optionType)`
- `static int showInternalConfirmDialog(Component parent, Object message)`

  show a confirmation dialog or an internal confirmation dialog. (An internal dialog is rendered entirely within its owner's frame.) Returns the option selected by the user (one of `OK_OPTION`,

`CANCEL_OPTION`, `YES_OPTION`, `NO_OPTION`), or `CLOSED_OPTION` if the user closed the dialog. The parent component can be `null`. The message to show on the dialog can be a string, icon, component, or an array of them. The `messageType` parameter is one of `ERROR_MESSAGE`, `INFORMATION_MESSAGE`, `WARNING_MESSAGE`, `QUESTION_MESSAGE`, or `PLAIN_MESSAGE`, and `optionType` is one of `DEFAULT_OPTION`, `YES_NO_OPTION`, `YES_NO_CANCEL_OPTION`, or `OK_CANCEL_OPTION`.

- `static int showOptionDialog(Component parent, Object message, String title, int optionType, int messageType, Icon icon, Object[] options, Object default)`
- `static int showInternalOptionDialog(Component parent, Object message, String title, int optionType, int messageType, Icon icon, Object[] options, Object default)`
  show an option dialog or an internal option dialog. (An internal dialog is rendered entirely within its owner's frame.) Returns the index of the option selected by the user, or `CLOSED_OPTION` if the user canceled the dialog. The parent component can be `null`. The message to show on the dialog can be a string, icon, component, or an array of them. The `messageType` parameter is one of `ERROR_MESSAGE`, `INFORMATION_MESSAGE`,

`WARNING_MESSAGE`, `QUESTION_MESSAGE`, or `PLAIN_MESSAGE`, and `optionType` is one of `DEFAULT_OPTION`, `YES_NO_OPTION`, `YES_NO_CANCEL_OPTION`, or `OK_CANCEL_OPTION`. The `options` parameter is an array of strings, icons, or components.

- `static Object showInputDialog(Component parent, Object message, String title, int messageType, Icon icon, Object[] values, Object default)`
- `static String showInputDialog(Component parent, Object message, String title, int messageType)`
- `static String showInputDialog(Component parent, Object message)`
- `static String showInputDialog(Object message)`
- `static String showInputDialog(Component parent, Object message, Object default)` **1.4**
- `static String showInputDialog(Object message, Object default)` **1.4**
- `static Object showInternalInputDialog(Component parent, Object message, String title, int`

`messageType, Icon icon, Object[] values, Object default)`

- `static String showInternalInputDialog(Component parent, Object message, String title, int messageType)`
- `static String showInternalInputDialog(Component parent, Object message)`
  show an input dialog or an internal input dialog. (An internal dialog is rendered entirely within its owner's frame.) Returns the input string typed by the user, or `null` if the user canceled the dialog. The parent component can be `null`. The message to show on the dialog can be a string, icon, component, or an array of them. The `messageType` parameter is one of `ERROR_MESSAGE`, `INFORMATION_MESSAGE`, `WARNING_MESSAGE`, `QUESTION_MESSAGE`, or `PLAIN_MESSAGE`.

1.8.2. Creating Dialogs

In the last section, you saw how to use the `JOptionPane` class to show a simple dialog. In this section, you will see how to create such a dialog by hand.

Figure 11.31 shows a typical modal dialog box—a program information box that is displayed when the user clicks the About button.



Figure 1.31: An About dialog box

To implement a dialog box, you extend the `JDialog` class. This is essentially the same process as extending `JFrame` for the main window for an application. More precisely:

1. In the constructor of your dialog box, call the constructor of the superclass `JDialog`.
2. Add the user interface components of the dialog box.
3. Add the event handlers.
4. Set the size for the dialog box.

When you call the superclass constructor, you will need to supply the *owner frame*, the title of the dialog, and the *modality*.

The owner frame controls where the dialog is displayed. You can supply `null` as the owner; then, the dialog is owned by a hidden

frame.

The modality specifies which other windows of your application are blocked while the dialog is displayed. A modeless dialog does not block other windows. A modal dialog blocks all other windows of the application (except for the children of the dialog). You would use a modeless dialog for a toolbox that the user can always access. On the other hand, you would use a modal dialog if you want to force the user to supply required information before continuing.

Here's the code for a dialog box:

```
public AboutDialog extends JDialog
{
   public AboutDialog(JFrame owner)
   {
      super(owner, "About DialogTest", true);
      add(new JLabel(
         "<html><h1><i>Core Java</i></h1><hr>By Cay H
         BorderLayout.CENTER);
```

```
      var panel = new JPanel();
      var ok = new JButton("OK");

      ok.addActionListener(event -> setVisible(false)
      panel.add(ok);
```

```
        add(panel, BorderLayout.SOUTH);
        setSize(250, 150);
    }
}
```

As you can see, the constructor adds user interface elements—in this case, labels and a button. It adds a handler to the button and sets the size of the dialog.

To display the dialog box, create a new dialog object and make it visible:

```
var dialog = new AboutDialog(this);
dialog.setVisible(true);
```

Actually, in the sample code below, we create the dialog box only once, and we can reuse it whenever the user clicks the About button.

```
if (dialog == null) // first time
   dialog = new AboutDialog(this);
dialog.setVisible(true);
```

When the user clicks the OK button, the dialog box should close. This is handled in the event handler of the OK button:

```
ok.addActionListener(event -> setVisible(false));
```

When the user closes the dialog by clicking the Close button, the dialog is also hidden. Just as with a `JFrame`, you can override this behavior with the `setDefaultCloseOperation` method.

Listing 11.11 is the code for the frame class of the test program. Listing 11.12 shows the dialog class.

Listing 1.11 dialog/DialogFrame.java

```
1  package dialog;
2
3  import javax.swing.JFrame;
4  import javax.swing.JMenu;
5  import javax.swing.JMenuBar;
6  import javax.swing.JMenuItem;
7
8  /**
9   * A frame with a menu whose File->About actior
10  */
11 public class DialogFrame extends JFrame
12 {
13    private static final int DEFAULT_WIDTH = 300
14    private static final int DEFAULT_HEIGHT = 20
15    private AboutDialog dialog;
16
```

```
17    public DialogFrame()
18    {
19       setSize(DEFAULT_WIDTH, DEFAULT_HEIGHT);
20
21       // construct a File menu
22
23       var menuBar = new JMenuBar();
24       setJMenuBar(menuBar);
25       var fileMenu = new JMenu("File");
26       menuBar.add(fileMenu);
27
28       // add About and Exit menu items
29
30       // the About item shows the About dialog
31
32       var aboutItem = new JMenuItem("About");
33       aboutItem.addActionListener(event ->
34          {
35             if (dialog == null) // first time
36                dialog = new AboutDialog(DialogF
37             dialog.setVisible(true); // pop up
38          });
39       fileMenu.add(aboutItem);
40
41       // the Exit item exits the program
42
43       var exitItem = new JMenuItem("Exit");
44       exitItem.addActionListener(event -> Syste
```

```
45          fileMenu.add(exitItem);
46       }
47    }
```

Listing 1.12 dialog/AboutDialog.java

```
1  package dialog;
2
3  import java.awt.BorderLayout;
4
5  import javax.swing.JButton;
6  import javax.swing.JDialog;
7  import javax.swing.JFrame;
8  import javax.swing.JLabel;
9  import javax.swing.JPanel;
10
11 /**
12  * A sample modal dialog that displays a messag
13  * the OK button.
14  */
15 public class AboutDialog extends JDialog
16 {
17    public AboutDialog(JFrame owner)
18    {
19       super(owner, "About DialogTest", true);
20
21       // add HTML label to center
22
```

```
23          add(
24             new JLabel(
25                "<html><h1><i>Core Java</i></h1><hr
26             BorderLayout.CENTER);
27
28          // OK button closes the dialog
29
30          var ok = new JButton("OK");
31          ok.addActionListener(event -> setVisible(
32
33          // add OK button to southern border
34
35          var panel = new JPanel();
36          panel.add(ok);
37          add(panel, BorderLayout.SOUTH);
38
39          pack();
40       }
41    }
```

`javax.swing.JDialog` **1.2**

- `public JDialog(Frame parent, String title, boolean modal)`
  constructs a dialog. The dialog is not visible until it is explicitly shown.

1.8.3. Data Exchange

The most common reason to put up a dialog box is to get information from the user. You have already seen how easy it is to make a dialog box object: Give it initial data and call `setVisible(true)` to display the dialog box on the screen. Now let's see how to transfer data in and out of a dialog box.

Consider the dialog box in Figure 11.32 that could be used to obtain a username and a password to connect to some online service.



Figure 1.32: Password dialog box

Your dialog box should provide methods to set default data. For example, the `PasswordChooser` class of the example program has a method, `setUser`, to place default values into the next fields:

```
public void setUser(User u)
{
   username.setText(u.getName());
}
```

Once you set the defaults (if desired), show the dialog by calling `setVisible(true)`. The dialog is now displayed.

The user then fills in the information and clicks the OK or Cancel button. The event handlers for both buttons call `setVisible(false)`, which terminates the call to `setVisible(true)`. Alternatively, the user may close the dialog. If you did not install a window listener for the dialog, the default window closing operation applies: The dialog becomes invisible, which also terminates the call to `setVisible(true)`.

The important issue is that the call to `setVisible(true)` blocks until the user has dismissed the dialog. This makes it easy to implement modal dialogs.

You want to know whether the user has accepted or canceled the dialog. Our sample code sets the `ok` flag to `false` before showing the dialog. Only the event handler for the OK button sets the `ok` flag to `true`; that's how you retrieve the user input from the dialog.

Note: Transferring data out of a modeless dialog is not as simple. When a modeless dialog is displayed, the call to `setVisible(true)` does not block and the program continues running while the dialog is displayed. If the user selects items on a modeless dialog and then clicks OK, the dialog needs to send an event to some listener in the program.

The example program contains another useful improvement. When you construct a `JDialog` object, you need to specify the owner frame. However, quite often you want to show the same dialog with different owner frames. It is better to pick the owner frame *when you are ready to show the dialog*, not when you construct the `PasswordChooser` object.

The trick is to have the `PasswordChooser` extend `JPanel` instead of `JDialog`. Build a `JDialog` object on the fly in the `showDialog` method:

```
public boolean showDialog(Frame owner, String title)
{
   ok = false;

   if (dialog == null || dialog.getOwner() != owner)
   {
```

```
         dialog = new JDialog(owner, true);
         dialog.add(this);
         dialog.pack();
      }

      dialog.setTitle(title);
      dialog.setVisible(true);
      return ok;
   }
```

Note that it is safe to have `owner` equal to `null`.

You can do even better. Sometimes, the owner frame isn't readily available. It is easy enough to compute it from any `parent` component, like this:

```
   Frame owner;
   if (parent instanceof Frame)
      owner = (Frame) parent;
   else
      owner = (Frame) SwingUtilities.getAncestorOfClass(
```

We use this enhancement in our sample program. The `JOptionPane` class also uses this mechanism.

Many dialogs have a *default button*, which is automatically selected if the user presses a trigger key (Enter in most look-and-feel implementations). The default button is specially marked, often with a thick outline.

Set the default button in the *root pane* of the dialog:

```
dialog.getRootPane().setDefaultButton(okButton);
```

If you follow the suggestion of laying out the dialog in a panel, then you must be careful to set the default button only after you wrapped the panel into a dialog. The panel dialog itself has no root pane.

Listing 11.13 is for the frame class of the program that illustrates the data flow into and out of a dialog box. Listing 11.14 shows the dialog class.

Listing 1.13 dataExchange/DataExchangeFrame.java

```
1  package dataExchange;
2
3  import java.awt.*;
4  import java.awt.event.*;
5  import javax.swing.*;
6
```

```
7  /**
8   * A frame with a menu whose File->Connect acti
9   */
10 public class DataExchangeFrame extends JFrame
11 {
12    public static final int TEXT_ROWS = 20;
13    public static final int TEXT_COLUMNS = 40;
14    private PasswordChooser dialog = null;
15    private JTextArea textArea;
16
17    public DataExchangeFrame()
18    {
19       // construct a File menu
20
21       var mbar = new JMenuBar();
22       setJMenuBar(mbar);
23       var fileMenu = new JMenu("File");
24       mbar.add(fileMenu);
25
26       // add Connect and Exit menu items
27
28       var connectItem = new JMenuItem("Connect"
29       connectItem.addActionListener(new Connect
30       fileMenu.add(connectItem);
31
32       // the Exit item exits the program
33
34       var exitItem = new JMenuItem("Exit");
```

```
35          exitItem.addActionListener(event -> Syste
36          fileMenu.add(exitItem);
37
38          textArea = new JTextArea(TEXT_ROWS, TEXT_
39          add(new JScrollPane(textArea), BorderLayo
40          pack();
41       }
42
43       /**
44        * The Connect action pops up the password d
45        */
46       private class ConnectAction implements Actio
47       {
48          public void actionPerformed(ActionEvent e
49          {
50             // if first time, construct dialog
51
52             if (dialog == null) dialog = new Passw
53
54             // set default values
55             dialog.setUser(new User("yourname", nu
56
57             // pop up dialog
58             if (dialog.showDialog(DataExchangeFram
59             {
60                // if accepted, retrieve user input
61                User u = dialog.getUser();
62                textArea.append("user name = " + u
```

```
63                  + (new String(u.getPassword()))
64          }
65       }
66    }
67 }
```

Listing 1.14 dataExchange/PasswordChooser.java

```
1  package dataExchange;
2
3  import java.awt.BorderLayout;
4  import java.awt.Component;
5  import java.awt.Frame;
6  import java.awt.GridLayout;
7
8  import javax.swing.JButton;
9  import javax.swing.JDialog;
10 import javax.swing.JLabel;
11 import javax.swing.JPanel;
12 import javax.swing.JPasswordField;
13 import javax.swing.JTextField;
14 import javax.swing.SwingUtilities;
15
16 /**
17  * A password chooser that is shown inside a di
18  */
19 public class PasswordChooser extends JPanel
20 {
```

```
21    private JTextField username;
22    private JPasswordField password;
23    private JButton okButton;
24    private boolean ok;
25    private JDialog dialog;
26
27    public PasswordChooser()
28    {
29       setLayout(new BorderLayout());
30
31       // construct a panel with username and pa
32
33       var panel = new JPanel();
34       panel.setLayout(new GridLayout(2, 2));
35       panel.add(new JLabel("User name:"));
36       panel.add(username = new JTextField(""));
37       panel.add(new JLabel("Password:"));
38       panel.add(password = new JPasswordField("
39       add(panel, BorderLayout.CENTER);
40
41       // create Ok and Cancel buttons that term
42
43       okButton = new JButton("Ok");
44       okButton.addActionListener(event ->
45          {
46             ok = true;
47             dialog.setVisible(false);
48          });
```

```
49
50          var cancelButton = new JButton("Cancel");
51          cancelButton.addActionListener(event -> c
52
53          // add buttons to southern border
54
55          var buttonPanel = new JPanel();
56          buttonPanel.add(okButton);
57          buttonPanel.add(cancelButton);
58          add(buttonPanel, BorderLayout.SOUTH);
59       }
60
61       /**
62        * Sets the dialog defaults.
63        * @param u the default user information
64        */
65       public void setUser(User u)
66       {
67          username.setText(u.getName());
68       }
69
70       /**
71        * Gets the dialog entries.
72        * @return a User object whose state represe
73        */
74       public User getUser()
75       {
76          return new User(username.getText(), passw
```

```
77      }
78
79      /**
80       * Show the chooser panel in a dialog.
81       * @param parent a component in the owner fr
82       * @param title the dialog window title
83       */
84      public boolean showDialog(Component parent,
85      {
86         ok = false;
87
88         // locate the owner frame
89
90         Frame owner = (Frame) SwingUtilities.getA
91
92         // if first time, or if owner has changed
93
94         if (dialog == null || dialog.getOwner()
95         {
96            dialog = new JDialog(owner, true);
97            dialog.add(this);
98            dialog.getRootPane().setDefaultButton(
99            dialog.pack();
100        }
101
102        // set title and show dialog
103
104        dialog.setTitle(title);
```

```
105         dialog.setVisible(true);
106         return ok;
107      }
108   }
```

`javax.swing.SwingUtilities` **1.2**

- `Container getAncestorOfClass(Class c, Component comp)`
  returns the innermost parent container of the given component that belongs to the given class or one of its subclasses.

`javax.swing.JComponent` **1.2**

- `JRootPane getRootPane()`
  gets the root pane enclosing this component, or `null` if this component does not have an ancestor with a root pane.

`javax.swing.JRootPane` **1.2**

- `void setDefaultButton(JButton button)`
  sets the default button for this root pane. To deactivate the default button, call this method with a `null` argument.

`javax.swing.JButton` 1.2

- `boolean isDefaultButton()`
  returns `true` if this button is the default button of its root pane.

1.8.4. File Dialogs

In an application, you often want to be able to open and save files. A good file dialog box that shows files and directories and lets the user navigate the file system is hard to write, and you definitely don't want to reinvent that wheel. Fortunately, Swing provides a `JFileChooser` class that allows you to display a file dialog box similar to the one that most native applications use. `JFileChooser` dialogs are always modal. Note that the `JFileChooser` class is not a subclass of `JDialog`. Instead of calling `setVisible(true)`, call `showOpenDialog` to display a dialog for opening a file, or call `showSaveDialog` to display a dialog for saving a file. The button for accepting a file is then automatically labeled Open or Save. You can also supply your own button label with the `showDialog` method. Figure 11.33 shows an example of the file chooser dialog box.



Figure 1.33: A file chooser dialog box

Here are the steps to put up a file dialog box and recover what the user chooses from the box:

1. Make a `JFileChooser` object. Unlike the constructor for the `JDialog` class, you do not supply the parent component. This allows you to reuse a file chooser dialog with multiple frames. For example:

   ```
   var chooser = new JFileChooser();
   ```

   Tip: Reusing a file chooser object is a good idea because the `JFileChooser` constructor can be quite slow, especially on Windows when the user has many mapped network drives.

2. Set the directory by calling the `setCurrentDirectory` method. For example, to use the current working directory

```
chooser.setCurrentDirectory(new File("."));
```

   you need to supply a `File` object. `File` objects are explained in detail in Chapter 2. All you need to know for now is that the constructor `File(String filename)` turns a file or directory name into a `File` object.
3. If you have a default file name that you expect the user to choose, supply it with the `setSelectedFile` method:

```
chooser.setSelectedFile(new File(filename));
```

4. To enable the user to select multiple files in the dialog, call the `setMultiSelectionEnabled` method. This is, of course, entirely optional and not all that common.

```
chooser.setMultiSelectionEnabled(true);
```

5. If you want to restrict the display of files in the dialog to those of a particular type (for example, all files with extension `.gif`), you need to set a *file filter*. We discuss file filters later in this section.

6. By default, a user can select only files with a file chooser. If you want the user to select directories, use the `setFileSelectionMode` method. Call it with `JFileChooser.FILES_ONLY` (the default), `JFileChooser.DIRECTORIES_ONLY`, or `JFileChooser.FILES_AND_DIRECTORIES`.
7. Show the dialog box by calling the `showOpenDialog` or `showSaveDialog` methods. You must supply the parent component in these calls:

```
int result = chooser.showOpenDialog(parent);
```

or

```
int result = chooser.showSaveDialog(parent);
```

The only difference between these calls is the label of the "approve button"—the button that the user clicks to finish the file selection. You can also call the `showDialog` method and pass an explicit text for the approve button:

```
int result = chooser.showDialog(parent, "Select");
```

These calls return only when the user has approved, canceled, or dismissed the file dialog. The return value is `JFileChooser.APPROVE_OPTION`, `JFileChooser.CANCEL_OPTION`, or `JFileChooser.ERROR_OPTION`.

8. Get the selected file or files with the `getSelectedFile()` or `getSelectedFiles()` method. These methods return either a single `File` object or an array of `File` objects. If you just need the name of the file object, call its `getPath` method. For example:

```
String filename = chooser.getSelectedFile().getPath
```

For the most part, these steps are simple. The major difficulty with using a file dialog is to specify a subset of files from which the user should choose. For example, suppose the user should choose a GIF image file. Then, the file chooser should only display files with the extension `.gif`. It should also give the user some kind of feedback that the displayed files are of a particular category, such as "GIF Images." But the situation can be more complex. If the user should choose a JPEG image file, the extension can be either `.jpg` or `.jpeg`. Instead of a way to codify these complexities, the designers of the file chooser provided a more elegant mechanism: to restrict the displayed files, supply an object that extends the abstract class

`javax.swing.filechooser.FileFilter`. The file chooser passes each file to the file filter and displays only those files that the filter accepts.

At the time of this writing, two such subclasses are supplied: the default filter that accepts all files, and a filter that accepts all files with a given extension. However, it is easy to write ad-hoc file filters. Simply implement the two abstract methods of the `FileFilter` superclass:

```
public boolean accept(File f);
public String getDescription();
```

The first method tests whether a file should be accepted. The second method returns a description of the file type that can be displayed in the file chooser dialog.

Note: An unrelated `FileFilter` interface in the `java.io` package has a single method, `boolean accept(File f)`. It is used in the `listFiles` method of the `File` class to list files in a directory. I do not know why the designers of Swing didn't extend this interface—perhaps the Java class library had, way back in 1998, become so complex that they were no longer aware of all the standard classes and interfaces.

You will need to resolve the name conflict between these two identically named types if you import both the `java.io` and the `javax.swing.filechooser` packages. The simplest remedy is to import `javax.swing.filechooser.FileFilter`, not `javax.swing.filechooser.*`.

Once you have a file filter object, use the `setFileFilter` method of the `JFileChooser` class to install it into the file chooser object:

```
chooser.setFileFilter(new FileNameExtensionFilter("Im
```

You can install multiple filters to the file chooser by calling

```
chooser.addChoosableFileFilter(filter1);
chooser.addChoosableFileFilter(filter2);
. . .
```

The user selects a filter from the combo box at the bottom of the file dialog. By default, the "All files" filter is always present in the combo box. This is a good idea—just in case a user of your program needs to select a file with a nonstandard extension. However, if you want to suppress the "All files" filter, call

```
chooser.setAcceptAllFileFilterUsed(false);
```

Caution: If you reuse a single file chooser for loading and saving different file types, call

```
chooser.resetChoosableFilters();
```

to clear any old file filters before adding new ones.

Finally, you can customize the file chooser by providing special icons and file descriptions for each file that the file chooser displays. Do this by supplying an object of a class extending the `FileView` class in the `javax.swing.filechooser` package. This is definitely an advanced technique. Normally, you don't need to supply a file view—the pluggable look-and-feel supplies one for you. But if you want to show different icons for special file types, you can install your own file view. You need to extend the `FileView` class and implement five methods:

```
Icon getIcon(File f)
String getName(File f)
String getDescription(File f)
String getTypeDescription(File f)
Boolean isTraversable(File f)
```

Then, use the `setFileView` method to install your file view into the file chooser.

The file chooser calls your methods for each file or directory that it wants to display. If your method returns `null` for the icon, name, or description, the file chooser then consults the default file view of the look-and-feel. That is good, because it means you need to deal only with the file types for which you want to do something different.

The file chooser calls the `isTraversable` method to decide whether to open a directory when a user clicks on it. Note that this method returns a `Boolean` object, not a `boolean` value! This seems weird, but it is actually convenient—if you aren't interested in deviating from the default file view, just return `null`. The file chooser will then consult the default file view. In other words, the method returns a `Boolean` to let you choose among three options: true (`Boolean.TRUE`), false (`Boolean.FALSE`), or don't care (`null`).

The example program contains a simple file view class. That class shows a particular icon whenever a file matches a file filter. We use it to display a palette icon for all image files.

```
class FileIconView extends FileView
{
   private FileFilter filter;
   private Icon icon;

   public FileIconView(FileFilter aFilter, Icon anIco
   {
      filter = aFilter;
      icon = anIcon;
   }

   public Icon getIcon(File f)
   {
      if (!f.isDirectory() && filter.accept(f))
         return icon;
      else return null;
   }
}
```

Install this file view into your file chooser with the `setFileView` method:

```
chooser.setFileView(new FileIconView(filter,
   new ImageIcon("palette.gif")));
```

The file chooser will then show the palette icon next to all files that pass the `filter` and use the default file view to show all other files. Naturally, we use the same filter that we set in the file chooser.

Finally, you can customize a file dialog by adding an *accessory* component. For example, Figure 11.34 shows a preview accessory next to the file list. This accessory displays a thumbnail view of the currently selected file.



Figure 1.34: A file dialog with a preview accessory

An accessory can be any Swing component. In our case, we extend the `JLabel` class and set its icon to a scaled copy of the graphics image:

```
class ImagePreviewer extends JLabel
{
   public ImagePreviewer(JFileChooser chooser)
   {
      setPreferredSize(new Dimension(100, 100));
      setBorder(BorderFactory.createEtchedBorder());
   }

   public void loadImage(File f)
   {
      var icon = new ImageIcon(f.getPath());
      if(icon.getIconWidth() > getWidth())
         icon = new ImageIcon(icon.getImage().getScal
            getWidth(), -1, Image.SCALE_DEFAULT));
      setIcon(icon);
      repaint();
   }
}
```

There is just one challenge. We want to update the preview image whenever the user selects a different file. The file chooser uses the "JavaBeans" mechanism of notifying interested listeners whenever one of its properties changes. The selected file is a property that you can monitor by installing a `PropertyChangeListener`. Here is the code that you need to trap the notifications:

```
chooser.addPropertyChangeListener(event ->
   {
      if (event.getPropertyName() == JFileChooser.SEL
      {
         var newFile = (File) event.getNewValue();
         // update the accessory
         . . .
      }
   });
```

`javax.swing.JFileChooser` **1.2**

- `JFileChooser()`
  creates a file chooser dialog box that can be used for multiple frames.
- `void setCurrentDirectory(File dir)`
  sets the initial directory for the file dialog box.
- `void setSelectedFile(File file)`
- `void setSelectedFiles(File[] file)`
  set the default file choice for the file dialog box.
- `void setMultiSelectionEnabled(boolean b)`
  sets or clears the multiple selection mode.

- `void setFileSelectionMode(int mode)`
  lets the user select files only (the default), directories only, or both files and directories. The `mode` parameter is one of `JFileChooser.FILES_ONLY`, `JFileChooser.DIRECTORIES_ONLY`, and `JFileChooser.FILES_AND_DIRECTORIES`.
- `int showOpenDialog(Component parent)`
- `int showSaveDialog(Component parent)`
- `int showDialog(Component parent, String approveButtonText)`
  show a dialog in which the approve button is labeled "Open", "Save", or with the `approveButtonText` string. Return `APPROVE_OPTION`, `CANCEL_OPTION` (if the user selected the cancel button or dismissed the dialog), or `ERROR_OPTION` (if an error occurred).
- `File getSelectedFile()`
- `File[] getSelectedFiles()`
  get the file or files that the user selected (or return `null` if the user didn't select any file).
- `void setFileFilter(FileFilter filter)`
  sets the file mask for the file dialog box. All files for which `filter.accept` returns `true` will be displayed. Also, adds the filter to the list of choosable filters.

- `void addChoosableFileFilter(FileFilter filter)`
  adds a file filter to the list of choosable filters.
- `void setAcceptAllFileFilterUsed(boolean b)`
  includes or suppresses an "All files" filter in the filter combo box.
- `void resetChoosableFileFilters()`
  clears the list of choosable filters. Only the "All files" filter remains unless it is explicitly suppressed.
- `void setFileView(FileView view)`
  sets a file view to provide information about the files that the file chooser displays.
- `void setAccessory(JComponent component)`
  sets an accessory component.

`javax.swing.filechooser.FileFilter` **1.2**

- `boolean accept(File f)`
  returns `true` if the file chooser should display this file.
- `String getDescription()`
  returns a description of this file filter—for example, `"Image files (*.gif,*.jpeg)"`.

`javax.swing.filechooser.FileNameExtensionFilter` **6**

- `FileNameExtensionFilter(String description,`

`String... extensions)`
constructs a file filter with the given description that accepts all directories and all files whose names end in a period followed by one of the given extension strings.

`javax.swing.filechooser.FileView` **1.2**

- `String getName(File f)`
  returns the name of the file `f`, or `null`. Normally, this method simply returns `f.getName()`.
- `String getDescription(File f)`
  returns a human-readable description of the file `f`, or `null`. For example, if `f` is an HTML document, this method might return its title.
- `String getTypeDescription(File f)`
  returns a human-readable description of the type of the file `f`, or `null`. For example, if `f` is an HTML document, this method might return a string `"Hypertext document"`.
- `Icon getIcon(File f)`
  returns an icon for the file `f`, or `null`. For example, if `f` is a JPEG file, this method might return a thumbnail icon.
- `Boolean isTraversable(File f)`
  returns `Boolean.TRUE` if `f` is a directory that the user can open. This method might return `Boolean.FALSE` if a directory is conceptually a compound document. Like all `FileView`

> methods, this method can return `null` to signify that the file chooser should consult the default view instead.

The coverage of GUI and graphics programming continues with the next chapter, which covers more advanced Swing components and sophisticated graphics techniques.

1. Advanced Swing and Graphics

In this chapter, we continue our discussion of the Swing user interface toolkit and AWT graphics from Volume I. We focus on techniques that are applicable to both client-side user interfaces and server-side generation of graphics and images. Swing has sophisticated components for rendering tables and trees. With the 2D graphics API, you can produce vector art of arbitrary complexity. The ImageIO API lets you manipulate raster images. Finally, you can use the printing API to generate printouts and PostScript files.

1.1. Tables

The `JTable` component displays a two-dimensional grid of objects. Tables are common in user interfaces, and the Swing team has put a lot of effort into the table control. Tables are inherently complex, but—perhaps more successfully than other Swing classes—the `JTable` component hides much of that complexity. You can produce fully functional tables with rich behavior by writing a few lines of code. You can also write more code and customize the display and behavior for your specific applications.

In the following sections, I'll explain how to make simple tables, how the user interacts with them, and how to make some of the most common adjustments. As with the other complex Swing controls, it

is impossible to cover all aspects in complete detail. For more information, look in *Graphic Java™, Third Edition*, by David M. Geary (Prentice Hall, 1999), or *Core Swing* by Kim Topley (Prentice Hall, 1999).

1.1.1. A Simple Table

A `JTable` does not store its own data but obtains them from a *table model*. The `JTable` class has a constructor that wraps a two-dimensional array of objects into a default model. That is the strategy that we use in our first example; later in this chapter, we will turn to table models.

Figure 12.1 shows a typical table, describing the properties of the planets of the solar system. (A planet is *gaseous* if it consists mostly of hydrogen and helium. You should take the "Color" entries with a grain of salt—that column was added because it will be useful in later code examples.)



Figure 1.1: A simple table

As you can see from the code in Listing 12.1, the data of the table is stored as a two-dimensional array of `Object` values:

```
Object[][] cells =
   {
      { "Mercury", 2440.0, 0, false, Color.YELLOW },
      { "Venus", 6052.0, 0, false, Color.YELLOW },
      . . .
   }
```

Note: Here, we take advantage of autoboxing. The entries in the second, third, and fourth columns are automatically converted into objects of type `Double`, `Integer`, and `Boolean`.

The table simply invokes the `toString` method on each object to display it. That's why the colors show up as `java.awt.Color[r=. . .,g=. . .,b=. . .]`.

Supply the column names in a separate array of strings:

```
String[] columnNames = { "Planet", "Radius", "Moons",
```

Then, construct a table from the cell and column name arrays:

```
var table = new JTable(cells, columnNames);
```

You can add scroll bars in the usual way—by wrapping the table in a `JScrollPane`:

```
var pane = new JScrollPane(table);
```

When you scroll the table, the table header doesn't scroll out of view.

Next, click on one of the column headers and drag it to the left or right. See how the entire column becomes detached (see Figure 12.2). You can drop it in a different location. This rearranges the columns *in the view only*. The data model is not affected.



Figure 1.2: Moving a column

To *resize* columns, simply place the cursor between two columns until the cursor shape changes to an arrow. Then, drag the column boundary to the desired place (see Figure 12.3).



Figure 1.3: Resizing columns

Users can select rows by clicking anywhere in a row. The selected rows are highlighted; you will see later how to get selection events. Users can also edit the table entries by clicking on a cell and typing into it. However, in this code example, the edits do not change the

underlying data. In your programs, you should either make cells uneditable or handle cell editing events and update your model. We will discuss those topics later in this section.

Finally, click on a column header. The rows are automatically sorted. Click again, and the sort order is reversed. This behavior is activated by the call

```
table.setAutoCreateRowSorter(true);
```

You can print a table with the call

```
table.print();
```

Caution: If you don't wrap a table into a scroll pane, you need to explicitly add the header:

```
add(table.getTableHeader(), BorderLayout.NORTH);
```

Listing 1.1 table/TableTest.java

```
1 package table;
2
3 import java.awt.*;
```

```
4  import java.awt.print.*;
5
6  import javax.swing.*;
7
8  /**
9   * This program demonstrates how to show a simp
10  * @version 1.14 2018-05-01
11  * @author Cay Horstmann
12  */
13 public class TableTest
14 {
15    public static void main(String[] args)
16    {
17       EventQueue.invokeLater(() ->
18          {
19             var frame = new PlanetTableFrame();
20             frame.setTitle("TableTest");
21             frame.setDefaultCloseOperation(JFra
22             frame.setVisible(true);
23          });
24    }
25 }
26
27 /**
28  * This frame contains a table of planet data.
29  */
30 class PlanetTableFrame extends JFrame
31 {
```

```
32    private String[] columnNames = { "Planet", "
33    private Object[][] cells =
34    {
35       { "Mercury", 2440.0, 0, false, Color.YELL
36       { "Venus", 6052.0, 0, false, Color.YELLOW
37       { "Earth", 6378.0, 1, false, Color.BLUE }
38       { "Mars", 3397.0, 2, false, Color.RED },
39       { "Jupiter", 71492.0, 16, true, Color.ORA
40       { "Saturn", 60268.0, 18, true, Color.ORAN
41       { "Uranus", 25559.0, 17, true, Color.BLUE
42       { "Neptune", 24766.0, 8, true, Color.BLUE
43       { "Pluto", 1137.0, 1, false, Color.BLACK
44    };
45
46    public PlanetTableFrame()
47    {
48       var table = new JTable(cells, columnNames
49       table.setAutoCreateRowSorter(true);
50       add(new JScrollPane(table), BorderLayout
51       var printButton = new JButton("Print");
52       printButton.addActionListener(event ->
53          {
54             try { table.print(); }
55             catch (SecurityException | PrinterE
56          });
57       var buttonPanel = new JPanel();
58       buttonPanel.add(printButton);
59       add(buttonPanel, BorderLayout.SOUTH);
```

```
60          pack();
61       }
62    }
```

`javax.swing.JTable` **1.2**

- `JTable(Object[][] entries, Object[] columnNames)`
  constructs a table with a default table model.
- `void print()` **5.0**
  displays a print dialog box and prints the table.
- `boolean getAutoCreateRowSorter()` **6**
- `void setAutoCreateRowSorter(boolean newValue)` **6**
  get or set the `autoCreateRowSorter` property. The default is `false`. When set, a default row sorter is automatically set whenever the model changes.
- `boolean getFillsViewportHeight()` **6**
- `void setFillsViewportHeight(boolean newValue)` **6**
  get or set the `fillsViewportHeight` property. The default is `false`. When set, the table always fills the enclosing viewport.

1.1.2. Table Models

In the preceding example, the table data were stored in a two-dimensional array. However, you should generally not use that

strategy in your own code. Instead of dumping data into an array to display it as a table, consider implementing your own table model.

Table models are particularly simple to implement because you can take advantage of the `AbstractTableModel` class that implements most of the required methods. You only need to supply three methods:

```
public int getRowCount();
public int getColumnCount();
public Object getValueAt(int row, int column);
```

There are many ways of implementing the `getValueAt` method. For example, if you want to display the contents of a `RowSet` that contains the result of a database query, simply provide this method:

```
public Object getValueAt(int r, int c)
{
   try
   {
      rowSet.absolute(r + 1);
      return rowSet.getObject(c + 1);
   }
   catch (SQLException e)
   {
      e.printStackTrace();
```

```
        return null;
    }
}
```

Our sample program is even simpler. We construct a table that shows some computed values—namely, the growth of an investment under different interest rate scenarios (see Figure 12.4).



5%	6%	7%	8%	9%	10%
100000.00	100000.00	100000.00	100000.00	100000.00	100000.00
105000.00	106000.00	107000.00	108000.00	109000.00	110000.00
110250.00	112360.00	114490.00	116640.00	118810.00	121000.00
115762.50	119101.60	122504.30	125971.20	129502.90	133100.00
121550.63	126247.70	131079.60	136048.90	141158.16	146410.00
127628.16	133822.56	140255.17	146932.81	153862.40	161051.00
134009.56	141851.91	150073.04	158687.43	167710.01	177156.10
140710.04	150363.03	160578.15	171382.43	182803.91	194871.71
147745.54	159384.81	171818.62	185093.02	199256.26	214358.88
155132.82	168947.90	183845.92	199900.46	217189.33	235794.77
162889.46	179084.77	196715.14	215892.50	236736.37	259374.25
171033.94	189829.86	210485.20	233163.90	258042.64	285311.67
179585.63	201219.65	225219.16	251817.01	281266.48	313842.84
188564.91	213292.83	240984.50	271962.37	306580.46	345227.12
197993.16	226090.40	257853.42	293719.36	334172.70	379749.83
207892.82	239655.82	275903.15	317216.91	364248.25	417724.82

Figure 1.4: Growth of an investment

The `getValueAt` method computes the appropriate value and formats it:

```
public Object getValueAt(int r, int c)
{
   double rate = (c + minRate) / 100.0;
   int nperiods = r;
```

```
    double futureBalance = INITIAL_BALANCE * Math.pow(
    return "%.2f".formatted(futureBalance);
  }
```

The `getRowCount` and `getColumnCount` methods simply return the number of rows and columns:

```
  public int getRowCount() { return years; }
  public int getColumnCount() {  return maxRate - minRa
```

If you don't supply column names, the `getColumnName` method of the `AbstractTableModel` names the columns A, B, C, and so on. To change the default column names, override the `getColumnName` method. In this example, we simply label each column with the interest rate.

```
  public String getColumnName(int c) { return (c + minR
```

You can find the complete source code in Listing 12.2.

Listing 1.2 tableModel/InvestmentTable.java

```
1  package tableModel;
2
3  import java.awt.*;
4
5  import javax.swing.*;
6  import javax.swing.table.*;
7
8  /**
9   * This program shows how to build a table fron
10  * @version 1.05 2021-09-09
11  * @author Cay Horstmann
12  */
13 public class InvestmentTable
14 {
15    public static void main(String[] args)
16    {
17       EventQueue.invokeLater(() ->
18          {
19             var frame = new InvestmentTableFran
20             frame.setTitle("InvestmentTable");
21             frame.setDefaultCloseOperation(JFra
22             frame.setVisible(true);
23          });
24    }
25 }
26
```

```
27 /**
28  * This frame contains the investment table.
29  */
30 class InvestmentTableFrame extends JFrame
31 {
32    public InvestmentTableFrame()
33    {
34       var model = new InvestmentTableModel(30,
35       var table = new JTable(model);
36       add(new JScrollPane(table));
37       pack();
38    }
39 }
40
41 /**
42  * This table model computes the cell entries e
43  * shows the growth of an investment for a numb
44  */
45 class InvestmentTableModel extends AbstractTabl
46 {
47    private static double INITIAL_BALANCE = 1000
48
49    private int years;
50    private int minRate;
51    private int maxRate;
52
53    /**
54     * Constructs an investment table model.
```

```
55      * @param y the number of years
56      * @param r1 the lowest interest rate to tab
57      * @param r2 the highest interest rate to ta
58      */
59     public InvestmentTableModel(int y, int r1, i
60     {
61        years = y;
62        minRate = r1;
63        maxRate = r2;
64     }
65
66     public int getRowCount()
67     {
68        return years;
69     }
70
71     public int getColumnCount()
72     {
73        return maxRate - minRate + 1;
74     }
75
76     public Object getValueAt(int r, int c)
77     {
78        double rate = (c + minRate) / 100.0;
79        int nperiods = r;
80        double futureBalance = INITIAL_BALANCE *
81        return "%.2f".formatted(futureBalance);
82     }
```

```
83
84      public String getColumnName(int c)
85      {
86         return (c + minRate) + "%";
87      }
88  }
```

`javax.swing.table.TableModel` **1.2**

- `int getRowCount()`
- `int getColumnCount()`
  get the number of rows and columns in the table model.
- `Object getValueAt(int row, int column)`
  gets the value at the given row and column.
- `void setValueAt(Object newValue, int row, int column)`
  sets a new value at the given row and column.
- `boolean isCellEditable(int row, int column)`
  returns `true` if the cell at the given row and column is editable.
- `String getColumnName(int column)`
  gets the column title.

1.2. Working with Rows and Columns

In the following subsections, you will see how to manipulate the rows and columns in a table. As you read through this material, keep

in mind that a Swing table is quite asymmetric—the operations that you can carry out on rows and columns are different. The table component was optimized to display rows of information with the same structure, such as the result of a database query, not an arbitrary two-dimensional grid of objects. You will see this asymmetry throughout this subsection.

1.2.1. Column Classes

In the next example, we again display our planet data, but this time we want to give the table more information about the column types. This is achieved by defining the method

```
Class<?> getColumnClass(int columnIndex)
```

of the table model to return the class that describes the column type.

The `JTable` class uses this information to pick an appropriate renderer for the class. Table 12.1 shows the default rendering actions.

Table 1.1: Default Rendering Actions

Type	Rendered As

Type	Rendered As
`Boolean`	Checkbox
`Icon`	Image
`Object`	String

You can see the checkboxes and images in Figure 12.5. (Thanks to Jim Evins for providing the planet images!)



Figure 1.5: A table with planet data

To render other types, you can install a custom renderer—see Section 12.3.

1.2.2. Accessing Table Columns

The `JTable` class stores information about table columns in objects of type `TableColumn`. A `TableColumnModel` object manages the columns. (Figure 12.6 shows the relationships among the most important table classes.) If you don't want to insert or remove columns dynamically, you won't use the column model much. The

most common use for the column model is simply to get a `TableColumn` object:

```
int columnIndex = . . .;
TableColumn column = table.getColumnModel().getColumn
```



Figure 1.6: Relationship between table classes

1.2.3. Resizing Columns

The `TableColumn` class gives you control over the resizing behavior of columns. You can set the preferred, minimum, and maximum width with the methods

```
void setPreferredWidth(int width)
void setMinWidth(int width)
void setMaxWidth(int width)
```

This information is used by the table component to lay out the columns.

Use the method

```
void setResizable(boolean resizable)
```

to control whether the user is allowed to resize the column.

You can programmatically resize a column with the method

```
void setWidth(int width)
```

When a column is resized, the default is to leave the total size of the table unchanged. Of course, the width increase or decrease of the resized column must then be distributed over other columns. The default behavior is to change the size of all columns to the right of

the resized column. That's a good default because it allows a user to adjust all columns to a desired width, moving from left to right.

You can set another behavior from Table 12.2 by using the method

```
void setAutoResizeMode(int mode)
```

of the `JTable` class.

Table 1.2: Resize Modes

Mode	Behavior
`AUTO_RESIZE_OFF`	Don't resize other columns; change the table width.
`AUTO_RESIZE_NEXT_COLUMN`	Resize the next column only.
`AUTO_RESIZE_SUBSEQUENT_COLUMNS`	Resize all subsequent columns equally; this is the default behavior.

Mode	Behavior
`AUTO_RESIZE_LAST_COLUMN`	Resize the last column only.
`AUTO_RESIZE_ALL_COLUMNS`	Resize all columns in the table; this is not a good choice because it prevents the user from adjusting multiple columns to a desired size.

1.2.4. Resizing Rows

Row heights are managed directly by the `JTable` class. If your cells are taller than the default, you may want to set the row height:

```
table.setRowHeight(height);
```

By default, all rows of the table have the same height. You can set the heights of individual rows with the call

```
table.setRowHeight(row, height);
```

The actual row height equals the row height set with these methods, reduced by the row margin. The default row margin is 1 pixel, but you can change it with the call

```
table.setRowMargin(margin);
```

1.2.5. Selecting Rows, Columns, and Cells

Depending on the selection mode, the user can select rows, columns, or individual cells in the table. By default, row selection is enabled. Clicking inside a cell selects the entire row (see Figure 12.5). Call

```
table.setRowSelectionAllowed(false);
```

to disable row selection.

When row selection is enabled, you can control whether the user is allowed to select a single row, a contiguous set of rows, or any set of rows. You need to retrieve the *selection model* and use its `setSelectionMode` method:

```
table.getSelectionModel().setSelectionMode(mode);
```

Here, `mode` is one of the three values:

```
ListSelectionModel.SINGLE_SELECTION
ListSelectionModel.SINGLE_INTERVAL_SELECTION
ListSelectionModel.MULTIPLE_INTERVAL_SELECTION
```

Column selection is disabled by default. You can turn it on with the call

```
table.setColumnSelectionAllowed(true);
```

Enabling both row and column selection is equivalent to enabling cell selection. The user then selects ranges of cells (see Figure 12.7). You can also enable that setting with the call

```
table.setCellSelectionEnabled(true);
```



Figure 1.7: Selecting a range of cells

Run the program in Listing 12.3 to watch cell selection in action. Enable row, column, or cell selection in the Selection menu and watch how the selection behavior changes.

You can find out which rows and columns are selected by calling the `getSelectedRows` and `getSelectedColumns` methods. Both return an `int[]` array of the indexes of the selected items. Note that the index values are those of the table view, not the underlying table model. Try selecting rows and columns, then drag columns to different places and sort the rows by clicking on column headers.

Use the Print Selection menu item to see which rows and columns are reported as selected.

If you need to translate the table index values to table model index values, use the `JTable` methods `convertRowIndexToModel` and `convertColumnIndexToModel`.

1.2.6. Sorting Rows

As you have seen in our first table example, it is easy to add row sorting to a `JTable` simply by calling the `setAutoCreateRowSorter` method. However, to have finer-grained control over the sorting behavior, install a `TableRowSorter<M>` object into a `JTable` and customize it. The type parameter `M` denotes the table model; it needs to be a subtype of the `TableModel` interface.

```
var sorter = new TableRowSorter<TableModel>(model);
table.setRowSorter(sorter);
```

Some columns should not be sortable, such as the image column in our planet data. Turn sorting off by calling

```
sorter.setSortable(IMAGE_COLUMN, false);
```

You can install a custom comparator for each column. In our example, we will sort the colors in the Color column by preferring blue and green over red. When you click on the Color column, you will see that the blue planets go to the bottom of the table. This is achieved with the following call:

```
sorter.setComparator(COLOR_COLUMN, new Comparator<Col
   {
      public int compare(Color c1, Color c2)
      {
         int d = c1.getBlue() - c2.getBlue();
         if (d != 0) return d;
         d = c1.getGreen() - c2.getGreen();
         if (d != 0) return d;
         return c1.getRed() - c2.getRed();
      }
   });
```

If you do not specify a comparator for a column, the sort order is determined as follows:

1. If the column class is `String`, use the default collator returned by `Collator.getInstance()`. It sorts strings in a way that is appropriate for the current locale. (See Chapter 7 for more information about locales and collators.)

2. If the column class implements `Comparable`, use its `compareTo` method.
3. If a `TableStringConverter` has been set for the sorter, sort the strings returned by the converter's `toString` method with the default collator. If you want to use this approach, define a converter as follows:

```
sorter.setStringConverter(new TableStringConverter(
   {
      public String toString(TableModel model, int
      {
         Object value = model.getValueAt(row, colum
         convert value to a string and return it
      }
   });
```

4. Otherwise, call the `toString` method on the cell values and sort them with the default collator.

1.2.7. Filtering Rows

In addition to sorting rows, the `TableRowSorter` can also selectively hide rows—a process called *filtering*. To activate filtering, set a `RowFilter`. For example, to include all rows that contain at least one moon, call

```
sorter.setRowFilter(RowFilter.numberFilter(Comparison
```

Here, we use a predefined number filter. To construct a number filter, supply

- The comparison type (one of `EQUAL`, `NOT_EQUAL`, `AFTER`, or `BEFORE`).
- An object of a subclass of `Number` (such as an `Integer` or `Double`). Only objects that have the same class as the given `Number` object are considered.
- Zero or more column index values. If no index values are supplied, all columns are searched.

The static `RowFilter.dateFilter` method constructs a date filter in the same way; you need to supply a `Date` object instead of the `Number` object.

Finally, the static `RowFilter.regexFilter` method constructs a filter that looks for strings matching a regular expression. For example,

```
sorter.setRowFilter(RowFilter.regexFilter(".*[^s]$",
```

only displays those planets whose name doesn't end with an "s". (See Chapter 2 for more information on regular expressions.)

You can also combine filters with the `andFilter`, `orFilter`, and `notFilter` methods. To filter for planets not ending in an "s" with at least one moon, you can use this filter combination:

```
sorter.setRowFilter(RowFilter.andFilter(List.of(
   RowFilter.regexFilter(".*[^s]$", PLANET_COLUMN),
   RowFilter.numberFilter(ComparisonType.NOT_EQUAL, 0
```

To implement your own filter, provide a subclass of `RowFilter` and implement an `include` method to indicate which rows should be displayed. This is easy to do, but the glorious generality of the `RowFilter` class makes it a bit scary.

The `RowFilter<M, I>` class has two type parameters—the types for the model and for the row identifier. When dealing with tables, the model is always a subtype of `TableModel` and the identifier type is `Integer`. (At some point in the future, other components might also support row filtering. For example, to filter rows in a `JTree`, one might use a `RowFilter<TreeModel, TreePath>`.)

A row filter must implement the method

```
public boolean include(RowFilter.Entry<? extends M, ?
```

The `RowFilter.Entry` class supplies methods to obtain the model, the row identifier, and the value at a given index. Therefore, you can filter both by row identifier and by the contents of the row.

For example, this filter displays every other row:

```
var filter = new RowFilter<TableModel, Integer>()
   {
      public boolean include(Entry<? extends TableMod
      {
         return entry.getIdentifier() % 2 == 0;
      }
   };
```

If you wanted to include only those planets with an even number of moons, you would instead test for

```
((Integer) entry.getValue(MOONS_COLUMN)) % 2 == 0
```

In our sample program, we allow the user to hide arbitrary rows. We store the hidden row indexes in a set. The row filter shows all rows whose indexes are not in that set.

The filtering mechanism wasn't designed for filters with criteria changing over time. In our sample program, we keep calling

```
sorter.setRowFilter(filter);
```

whenever the set of hidden rows changes. Setting a filter causes it to be applied immediately.

1.2.8. Hiding and Displaying Columns

As you saw in the preceding section, you can filter table rows by either their contents or their row identifier. Hiding table columns uses a completely different mechanism.

The `removeColumn` method of the `JTable` class removes a column from the table view. The column data are not actually removed from the model—they are just hidden from view. The `removeColumn` method has a parameter of type `TableColumn`. If you have the column number (for example, from a call to `getSelectedColumns`), you need to ask the table model for the actual table column object:

```
TableColumnModel columnModel = table.getColumnModel()
TableColumn column = columnModel.getColumn(i);
```

```
table.removeColumn(column);
```

If you remember the column, you can later add it back in:

```
table.addColumn(column);
```

This method adds the column to the end. If you want it to appear elsewhere, call the `moveColumn` method.

You can also add a new column that corresponds to a column index in the table model, by adding a new `TableColumn` object:

```
table.addColumn(new TableColumn(modelColumnIndex));
```

You can have multiple table columns that view the same column of the model.

The program in Listing 12.3 demonstrates selection and filtering of rows and columns.

Listing 1.3
tableRowColumn/PlanetTableFrame.java

```
1  package tableRowColumn;
2
3  import java.awt.*;
4  import java.util.*;
5
6  import javax.swing.*;
7  import javax.swing.table.*;
8
9  /**
10  * This frame contains a table of planet data.
11  */
12 public class PlanetTableFrame extends JFrame
13 {
14    private static final int DEFAULT_WIDTH = 600
15    private static final int DEFAULT_HEIGHT = 50
16
17    public static final int COLOR_COLUMN = 4;
18    public static final int IMAGE_COLUMN = 5;
19
20    private JTable table;
21    private HashSet<Integer> removedRowIndices;
22    private ArrayList<TableColumn> removedColumn
23    private JCheckBoxMenuItem rowsItem;
24    private JCheckBoxMenuItem columnsItem;
25    private JCheckBoxMenuItem cellsItem;
```

```
26
27    private String[] columnNames = { "Planet", "
28
29    private Object[][] cells = {
30       { "Mercury", 2440.0, 0, false, Color.YELL
31          new ImageIcon(getClass().getResource("
32       { "Venus", 6052.0, 0, false, Color.YELLOW
33          new ImageIcon(getClass().getResource("
34       { "Earth", 6378.0, 1, false, Color.BLUE,
35          new ImageIcon(getClass().getResource("
36       { "Mars", 3397.0, 2, false, Color.RED,
37          new ImageIcon(getClass().getResource("
38       { "Jupiter", 71492.0, 16, true, Color.ORA
39          new ImageIcon(getClass().getResource("
40       { "Saturn", 60268.0, 18, true, Color.ORAN
41          new ImageIcon(getClass().getResource("
42       { "Uranus", 25559.0, 17, true, Color.BLUE
43          new ImageIcon(getClass().getResource("
44       { "Neptune", 24766.0, 8, true, Color.BLUE
45          new ImageIcon(getClass().getResource("
46       { "Pluto", 1137.0, 1, false, Color.BLACK,
47          new ImageIcon(getClass().getResource("
48
49    public PlanetTableFrame()
50    {
51       setSize(DEFAULT_WIDTH, DEFAULT_HEIGHT);
52
53       var model = new DefaultTableModel(cells,
```

```
54          {
55             public Class<?> getColumnClass(int
56             {
57                return cells[0][c].getClass();
58             }
59          };
60
61       table = new JTable(model);
62
63       table.setRowHeight(100);
64       table.getColumnModel().getColumn(COLOR_CO
65       table.getColumnModel().getColumn(IMAGE_CO
66
67       var sorter = new TableRowSorter<TableMode
68       table.setRowSorter(sorter);
69       sorter.setComparator(COLOR_COLUMN, Compar
70          .thenComparing(Color::getGreen).thenCo
71       sorter.setSortable(IMAGE_COLUMN, false);
72       add(new JScrollPane(table), BorderLayout
73
74       removedRowIndices = new HashSet<>();
75       removedColumns = new ArrayList<>();
76
77       var filter = new RowFilter<TableModel, In
78          {
79             public boolean include(Entry<? exte
80             {
81                return !removedRowIndices.contai
```

```
82              }
83           };
84
85        // create menu
86
87        var menuBar = new JMenuBar();
88        setJMenuBar(menuBar);
89
90        var selectionMenu = new JMenu("Selection"
91        menuBar.add(selectionMenu);
92
93        rowsItem = new JCheckBoxMenuItem("Rows");
94        columnsItem = new JCheckBoxMenuItem("Colu
95        cellsItem = new JCheckBoxMenuItem("Cells"
96
97        rowsItem.setSelected(table.getRowSelectio
98        columnsItem.setSelected(table.getColumnSe
99        cellsItem.setSelected(table.getCellSelect
100
101       rowsItem.addActionListener(event ->
102          {
103             table.clearSelection();
104             table.setRowSelectionAllowed(rowsIt
105             updateCheckboxMenuItems();
106          });
107       selectionMenu.add(rowsItem);
108
109       columnsItem.addActionListener(event ->
```

```
110          {
111             table.clearSelection();
112             table.setColumnSelectionAllowed(col
113             updateCheckboxMenuItems();
114          });
115       selectionMenu.add(columnsItem);
116
117       cellsItem.addActionListener(event ->
118          {
119             table.clearSelection();
120             table.setCellSelectionEnabled(cells
121             updateCheckboxMenuItems();
122          });
123       selectionMenu.add(cellsItem);
124
125       var tableMenu = new JMenu("Edit");
126       menuBar.add(tableMenu);
127
128       var hideColumnsItem = new JMenuItem("Hide
129       hideColumnsItem.addActionListener(event -
130          {
131             int[] selected = table.getSelectedC
132             TableColumnModel columnModel = tabl
133
134             // remove columns from view, starti
135             // index so that column numbers are
136
137             for (int i = selected.length - 1; i
```

```
138             {
139                TableColumn column = columnModel
140                table.removeColumn(column);
141
142                // store removed columns for "sh
143
144                removedColumns.add(column);
145             }
146          });
147       tableMenu.add(hideColumnsItem);
148
149       var showColumnsItem = new JMenuItem("Show
150       showColumnsItem.addActionListener(event -
151          {
152             // restore all removed columns
153             for (TableColumn tc : removedColumn
154                table.addColumn(tc);
155             removedColumns.clear();
156          });
157       tableMenu.add(showColumnsItem);
158
159       var hideRowsItem = new JMenuItem("Hide Ro
160       hideRowsItem.addActionListener(event ->
161          {
162             int[] selected = table.getSelectedR
163             for (int i : selected)
164                removedRowIndices.add(table.conv
165             sorter.setRowFilter(filter);
```

```
166            });
167         tableMenu.add(hideRowsItem);
168
169         var showRowsItem = new JMenuItem("Show Ro
170         showRowsItem.addActionListener(event ->
171            {
172               removedRowIndices.clear();
173               sorter.setRowFilter(filter);
174            });
175         tableMenu.add(showRowsItem);
176
177         var printSelectionItem = new JMenuItem("P
178         printSelectionItem.addActionListener(ever
179            {
180               int[] selected = table.getSelectedR
181               System.out.println("Selected rows:
182               selected = table.getSelectedColumns
183               System.out.println("Selected columr
184            });
185         tableMenu.add(printSelectionItem);
186      }
187
188      private void updateCheckboxMenuItems()
189      {
190         rowsItem.setSelected(table.getRowSelectio
191         columnsItem.setSelected(table.getColumnSe
```

```
192         cellsItem.setSelected(table.getCellSelect
193      }
194   }
```

`javax.swing.table.TableModel` **1.2**

- `Class getColumnClass(int columnIndex)`
  gets the class for the values in this column. This information is used for sorting and rendering.

`javax.swing.JTable` **1.2**

- `TableColumnModel getColumnModel()`
  gets the column model that describes the arrangement of the table columns.
- `void setAutoResizeMode(int mode)`
  sets the mode for automatic resizing of table columns. . The `mode` parameter is one of `AUTO_RESIZE_OFF`, `AUTO_RESIZE_NEXT_COLUMN`, `AUTO_RESIZE_SUBSEQUENT_COLUMNS`, `AUTO_RESIZE_LAST_COLUMN`, and `AUTO_RESIZE_ALL_COLUMNS`
- `int getRowMargin()`
- `void setRowMargin(int margin)`
  get or set the amount of empty space between cells in adjacent rows.

- `int getRowHeight()`
- `void setRowHeight(int height)`
  get or set the default height of all rows of the table.
- `int getRowHeight(int row)`
- `void setRowHeight(int row, int height)`
  get or set the height of the given row of the table.
- `ListSelectionModel getSelectionModel()`
  returns the list selection model. You need that model to choose between row, column, and cell selection.
- `boolean getRowSelectionAllowed()`
- `void setRowSelectionAllowed(boolean b)`
  get or set the `rowSelectionAllowed` property. If `true`, rows are selected when the user clicks on cells.
- `boolean getColumnSelectionAllowed()`
- `void setColumnSelectionAllowed(boolean b)`
  get or set the `columnSelectionAllowed` property. If `true`, columns are selected when the user clicks on cells.
- `boolean getCellSelectionEnabled()`
  returns `true` if both `rowSelectionAllowed` and `columnSelectionAllowed` are `true`.
- `void setCellSelectionEnabled(boolean b)`
  sets both `rowSelectionAllowed` and `columnSelectionAllowed` to `b`.

- `void addColumn(TableColumn column)`
  adds a column as the last column of the table view.
- `void moveColumn(int from, int to)`
  moves the column whose table index is `from` so that its index becomes `to`. Only the view is affected.
- `void removeColumn(TableColumn column)`
  removes the given column from the view.
- `int convertRowIndexToModel(int index)` **6**
- `int convertColumnIndexToModel(int index)`
  return the model index of the row or column with the given index. This value is different from `index` when rows are sorted or filtered, or when columns are moved or removed.
- `void setRowSorter(RowSorter<? extends TableModel> sorter)`
  sets the row sorter.

`javax.swing.table.TableColumnModel` **1.2**

- `TableColumn getColumn(int index)`
  gets the table column object that describes the column with the given view index.

`javax.swing.table.TableColumn` **1.2**

- `TableColumn(int modelColumnIndex)`
  constructs a table column for viewing the model column with the given index.
- `void setPreferredWidth(int width)`
- `void setMinWidth(int width)`
- `void setMaxWidth(int width)`
  set the preferred, minimum, and maximum width of this table column to `width`.
- `void setWidth(int width)`
  sets the actual width of this column to `width`.
- `void setResizable(boolean b)`
  If `b` is `true`, this column is resizable.

`javax.swing.ListSelectionModel` **1.2**

- `void setSelectionMode(int mode)`
  sets the selection mode to one of `SINGLE_SELECTION`, `SINGLE_INTERVAL_SELECTION`, and `MULTIPLE_INTERVAL_SELECTION`

`javax.swing.DefaultRowSorter<M, I>` 6

- `void setComparator(int column, Comparator<?> comparator)`
  sets the comparator to be used with the given column.
- `void setSortable(int column, boolean enabled)`
  enables or disables sorting for the given column.
- `void setRowFilter(RowFilter<? super M,? super I> filter)`
  sets the row filter.

`javax.swing.table.TableRowSorter<M extends TableModel>` 6

- `void setStringConverter(TableStringConverter stringConverter)`
  sets the string converter used for sorting and filtering.

`javax.swing.table.TableStringConverter` 6

- `abstract String toString(TableModel model, int row, int column)`
  converts the model value at the given location to a string; you can override this method.

`javax.swing.RowFilter<M, I>` 6

- `boolean include(RowFilter.Entry<? extends M,? extends I> entry)`
  specifies the rows that are retained; you can override this method.
- `static <M,I> RowFilter<M,I> numberFilter(RowFilter.ComparisonType type, Number number, int... indices)`
- `static <M,I> RowFilter<M,I> dateFilter(RowFilter.ComparisonType type, Date date, int... indices)`
  return a filter that includes rows containing values that match the given comparison to the given number or date. The comparison type is one of `EQUAL`, `NOT_EQUAL`, `AFTER`, or `BEFORE`. If any column model indexes are given, only those columns are searched; otherwise, all columns are searched. For the number filter, the class of the cell value must match the class of `number`.
- `static <M,I> RowFilter<M,I> regexFilter(String regex, int... indices)`
  returns a filter that includes rows that have a string value matching the given regular expression. If any column model indexes are given, only those columns are searched; otherwise,

all columns are searched. Note that the string returned by the `getStringValue` method of `RowFilter.Entry` is matched.

- `static <M,I> RowFilter<M,I> andFilter(Iterable<? extends RowFilter<? super M,? super I>> filters)`
- `static <M,I> RowFilter<M,I> orFilter(Iterable<? extends RowFilter<? super M,? super I>> filters)`
  return a filter that includes the entries included by all filters, or at least one of the filters.
- `static <M,I> RowFilter<M,I> notFilter(RowFilter<M,I> filter)`
  returns a filter that includes the entries not included by the given filter.

`javax.swing.RowFilter.Entry<M, I>` 6

- `I getIdentifier()`
  returns the identifier of this row entry.
- `M getModel()`
  returns the model of this row entry.
- `Object getValue(int index)`
  returns the value stored at the given index of this row.
- `int getValueCount()`
  returns the number of values stored in this row.

- `String getStringValue(int index)`
  returns the value stored at the given index of this row, converted to a string. The `TableRowSorter` produces entries whose `getStringValue` calls the sorter's string converter.

1.3. Cell Rendering and Editing

As you saw in Section 12.2.2, the column type determines how the cells are rendered. There are default renderers for the types `Boolean` and `Icon` that render a checkbox or icon. For all other types, you need to install a custom renderer.

1.3.1. Rendering Cells

Table cell renderers are similar to the list cell renderers that you saw earlier. They implement the `TableCellRenderer` interface that has a single method:

```
Component getTableCellRendererComponent(JTable table,
      boolean isSelected, boolean hasFocus, int row,
```

That method is called when the table needs to draw a cell. You return a component whose `paint` method is then invoked to fill the cell area.

The table in Figure 12.8 contains cells of type `Color`. The renderer simply returns a panel with a background color that is the color object stored in the cell. The color is passed as the `value` parameter.

```
class ColorTableCellRenderer extends JPanel implement
{
   public Component getTableCellRendererComponent(JTa
         boolean isSelected, boolean hasFocus, int ro
   {
      setBackground((Color) value);
      if (hasFocus)
         setBorder(UIManager.getBorder("Table.focusCe
      else
         setBorder(null);
   return this;
   }
}
```



Figure 1.8: A table with cell renderers

As you can see, the renderer draws a border when the cell has focus. (We ask the `UIManager` for the correct border. To find the lookup key, we peeked into the source code of the `DefaultTableCellRenderer` class.)

Tip: If your renderer simply draws a text string or an icon, you can extend the `DefaultTableCellRenderer` class. It takes care of rendering the focus and selection status for you.

You need to tell the table to use this renderer with all objects of type `Color`. The `setDefaultRenderer` method of the `JTable` class

lets you establish this association. Supply a `Class` object and the renderer:

```
table.setDefaultRenderer(Color.class, new ColorTableC
```

That renderer is now used for all objects of the given type in this table.

If you want to select a renderer based on some other criterion, you need to subclass the `JTable` class and override the `getCellRenderer` method.

1.3.2. Rendering the Header

To display an icon in the header, set the header value:

```
moonColumn.setHeaderValue(new ImageIcon("Moons.gif"))
```

However, the table header isn't smart enough to choose an appropriate renderer for the header value. You have to install the renderer manually. For example, to show an image icon in a column header, call

```
moonColumn.setHeaderRenderer(table.getDefaultRenderer
```

1.3.3. Editing Cells

To enable cell editing, the table model must indicate which cells are editable by defining the `isCellEditable` method. Most commonly, you will want to make certain columns editable. In the example program, we allow editing in four columns.

```
public boolean isCellEditable(int r, int c)
{
   return c == PLANET_COLUMN || c == MOONS_COLUMN ||
      || c == COLOR_COLUMN;
}
```

Note: The `AbstractTableModel` defines the `isCellEditable` method to always return `false`. The `DefaultTableModel` overrides the method to always return `true`.

If you run the sample program at the end of this section, note that you can click the checkboxes in the Gaseous column and turn the check marks on and off. If you click a cell in the Moons column, a

combo box appears (see Figure 12.9). You will shortly see how to install such a combo box as a cell editor.



Figure 1.9: A cell editor

Finally, click a cell in the first column. The cell gains focus. You can start typing, and the cell contents change.

What you just saw in action are the three variations of the `DefaultCellEditor` class. A `DefaultCellEditor` can be constructed with a `JTextField`, a `JCheckBox`, or a `JComboBox`. The `JTable` class automatically installs a checkbox editor for `Boolean` cells and a text field editor for all editable cells that don't supply their own renderer. The text fields let the user edit the strings

that result from applying `toString` to the return value of the `getValueAt` method of the table model.

When the edit is complete, the edited value is retrieved by calling the `getCellEditorValue` method of your editor. That method should return a value of the correct type (that is, the type returned by the `getColumnType` method of the model).

To get a combo box editor, set a cell editor manually—the `JTable` component has no idea what values might be appropriate for a particular type. For the Moons column, we wanted to enable the user to pick any value between 0 and 20. Here is the code for initializing the combo box:

```
var moonCombo = new JComboBox();
for (int i = 0; i <= 20; i++)
   moonCombo.addItem(i);
```

To construct a `DefaultCellEditor`, supply the combo box in the constructor:

```
var moonEditor = new DefaultCellEditor(moonCombo);
```

Next, we need to install the editor. Unlike the color cell renderer, this editor does not depend on the object *type*—we don't necessarily

want to use it for all objects of type `Integer`. Instead, we need to install it into a particular column:

```
moonColumn.setCellEditor(moonEditor);
```

1.3.4. Custom Editors

Run the example program again and click a color. A *color chooser* pops up and lets you pick a new color for the planet. Select a color and click OK. The cell color is updated (see Figure 12.10).



Figure 1.10: Editing the cell color with a color chooser

The color cell editor is not a standard table cell editor but a custom implementation. To create a custom cell editor, implement the `TableCellEditor` interface. That interface is a bit tedious, and an `AbstractCellEditor` class is provided to take care of the event handling details.

The `getTableCellEditorComponent` method of the `TableCellEditor` interface requests a component to render the cell. It is exactly the same as the `getTableCellRendererComponent` method of the `TableCellRenderer` interface, except that there is no `focus` parameter. When the cell is being edited, it is presumed to have focus. The editor component temporarily *replaces* the renderer when the editing is in progress. In our example, we return a blank panel that is not colored. This is an indication to the user that the cell is currently being edited.

Next, you want to have your editor pop up when the user clicks on the cell.

The `JTable` class calls your editor with an event (such as a mouse click) to find out if that event is acceptable to initiate the editing process. The `AbstractCellEditor` class defines the method to accept all events.

```
public boolean isCellEditable(EventObject anEvent)
{
   return true;
}
```

However, if you override this method to return `false`, the table would not go through the trouble of inserting the editor component.

Once the editor component is installed, the `shouldSelectCell` method is called, presumably with the same event. You should initiate editing in this method—for example, by popping up an external edit dialog box.

```
public boolean shouldSelectCell(EventObject anEvent)
{
   colorDialog.setVisible(true);
   return true;
}
```

If the user cancels the edit, the table calls the `cancelCellEditing` method. If the user has clicked on another table cell, the table calls the `stopCellEditing` method. In both cases, you should hide the dialog box. When your `stopCellEditing` method is called, the table would like to use the partially edited value. You should return `true` if the current value is valid. In the color chooser, any value is

valid. But if you edit other data, you can ensure that only valid data are retrieved from the editor.

Also, you should call the superclass methods that take care of event firing—otherwise, the editing won't be properly canceled.

```
public void cancelCellEditing()
{
   colorDialog.setVisible(false);
   super.cancelCellEditing();
}
```

Finally, you need a method that yields the value that the user supplied in the editing process:

```
public Object getCellEditorValue()
{
   return colorChooser.getColor();
}
```

To summarize, your custom editor should do the following:

1. Extend the `AbstractCellEditor` class and implement the `TableCellEditor` interface.
2. Define the `getTableCellEditorComponent` method to supply a component. This can either be a dummy component (if you pop

up a dialog box) or a component for in-place editing such as a combo box or text field.
3. Define the `shouldSelectCell`, `stopCellEditing`, and `cancelCellEditing` methods to handle the start, completion, and cancellation of the editing process. The `stopCellEditing` and `cancelCellEditing` methods should call the superclass methods to ensure that listeners are notified.
4. Define the `getCellEditorValue` method to return the value that is the result of the editing process.

Finally, indicate when the user is finished editing by calling the `stopCellEditing` and `cancelCellEditing` methods. When constructing the color dialog box, we install the accept and cancel callbacks that fire these events.

```
   colorDialog = JColorChooser.createDialog(null, "Plane
      EventHandler.create(ActionListener.class, this, "s
      EventHandler.create(ActionListener.class, this, "c
```

This completes the implementation of the custom editor.

You now know how to make a cell editable and how to install an editor. There is one remaining issue—how to update the model with the value that the user edited. When editing is complete, the `JTable` class calls the following method of the table model:

```
void setValueAt(Object value, int r, int c)
```

You need to override the method to store the new value. The `value` parameter is the object that was returned by the cell editor. If you implemented the cell editor, you know the type of the object you return from the `getCellEditorValue` method. In the case of the `DefaultCellEditor`, there are three possibilities for that value. It is a `Boolean` if the cell editor is a checkbox, a string if it is a text field, and, if the value comes from a combo box, it is the object that the user selected.

If the `value` object does not have the appropriate type, you need to convert it. That happens most commonly when a number is edited in a text field. In our example, we populated the combo box with `Integer` objects so that no conversion is necessary.

Listing 1.4 tableCellRender/TableCellRenderFrame.java

```
1  package tableCellRender;
2
3  import java.awt.*;
4  import javax.swing.*;
5  import javax.swing.table.*;
6
```

```
/**
 * This frame contains a table of planet data.
 */
public class TableCellRenderFrame extends JFram
{
   private static final int DEFAULT_WIDTH = 600
   private static final int DEFAULT_HEIGHT = 40

   public TableCellRenderFrame()
   {
      setSize(DEFAULT_WIDTH, DEFAULT_HEIGHT);

      var model = new PlanetTableModel();
      var table = new JTable(model);
      table.setRowSelectionAllowed(false);

      // set up renderers and editors

      table.setDefaultRenderer(Color.class, new
      table.setDefaultEditor(Color.class, new C

      var moonCombo = new JComboBox<Integer>();
      for (int i = 0; i <= 20; i++)
         moonCombo.addItem(i);

      TableColumnModel columnModel = table.getC
      TableColumn moonColumn = columnModel.getC
      moonColumn.setCellEditor(new DefaultCellE
```

```
35          moonColumn.setHeaderRenderer(table.getDef
36          moonColumn.setHeaderValue(new ImageIcon(g
37
38          // show table
39
40          table.setRowHeight(100);
41          add(new JScrollPane(table), BorderLayout
42       }
43    }
```

Listing 1.5 tableCellRender/PlanetTableModel.java

```
1  package tableCellRender;
2
3  import java.awt.*;
4  import javax.swing.*;
5  import javax.swing.table.*;
6
7  /**
8   * The planet table model specifies the values
9   * planet data.
10  */
11 public class PlanetTableModel extends AbstractT
12 {
13    public static final int PLANET_COLUMN = 0;
14    public static final int MOONS_COLUMN = 2;
```

```
15    public static final int GASEOUS_COLUMN = 3;
16    public static final int COLOR_COLUMN = 4;
17
18    private Object[][] cells =
19    {
20       { "Mercury", 2440.0, 0, false, Color.YELL
21          new ImageIcon(getClass().getResource('
22       { "Venus", 6052.0, 0, false, Color.YELLOW
23          new ImageIcon(getClass().getResource('
24       { "Earth", 6378.0, 1, false, Color.BLUE,
25          new ImageIcon(getClass().getResource('
26       { "Mars", 3397.0, 2, false, Color.RED,
27          new ImageIcon(getClass().getResource('
28       { "Jupiter", 71492.0, 16, true, Color.ORA
29          new ImageIcon(getClass().getResource('
30       { "Saturn", 60268.0, 18, true, Color.ORAN
31          new ImageIcon(getClass().getResource('
32       { "Uranus", 25559.0, 17, true, Color.BLUE
33          new ImageIcon(getClass().getResource('
34       { "Neptune", 24766.0, 8, true, Color.BLUE
35          new ImageIcon(getClass().getResource('
36       { "Pluto", 1137.0, 1, false, Color.BLACK,
37          new ImageIcon(getClass().getResource('
38    };
39
40    private String[] columnNames = { "Planet", "
41          "Color", "Image" };
42
```

```
43      public String getColumnName(int c)
44      {
45         return columnNames[c];
46      }
47
48      public Class<?> getColumnClass(int c)
49      {
50         return cells[0][c].getClass();
51      }
52
53      public int getColumnCount()
54      {
55         return cells[0].length;
56      }
57
58      public int getRowCount()
59      {
60         return cells.length;
61      }
62
63      public Object getValueAt(int r, int c)
64      {
65         return cells[r][c];
66      }
67
68      public void setValueAt(Object obj, int r, in
69      {
70         cells[r][c] = obj;
```

```
71    }
72
73    public boolean isCellEditable(int r, int c)
74    {
75       return c == PLANET_COLUMN || c == MOONS_C
76             || c == COLOR_COLUMN;
77    }
78 }
```

Listing 1.6 tableCellRender/ColorTableCellRenderer.java

```
1  package tableCellRender;
2
3  import java.awt.*;
4  import javax.swing.*;
5  import javax.swing.table.*;
6
7  /**
8   * This renderer renders a color value as a par
9   */
10 public class ColorTableCellRenderer extends JPa
11 {
12    public Component getTableCellRendererCompone
13          boolean isSelected, boolean hasFocus,
14    {
15       setBackground((Color) value);
```

```
16          if (hasFocus) setBorder(UIManager.getBorc
17          else setBorder(null);
18          return this;
19       }
20    }
```

Listing 1.7 tableCellRender/ColorTableCellEditor.java

```
1  package tableCellRender;
2
3  import java.awt.*;
4  import java.awt.event.*;
5  import java.beans.*;
6  import java.util.*;
7  import javax.swing.*;
8  import javax.swing.table.*;
9
10 /**
11  * This editor pops up a color dialog to edit a
12  */
13 public class ColorTableCellEditor extends Abstr
14 {
15    private JColorChooser colorChooser;
16    private JDialog colorDialog;
17    private JPanel panel;
18
```

```
19    public ColorTableCellEditor()
20    {
21       panel = new JPanel();
22       // prepare color dialog
23
24       colorChooser = new JColorChooser();
25       colorDialog = JColorChooser.createDialog(
26             EventHandler.create(ActionListener
27             EventHandler.create(ActionListener
28    }
29
30    public Component getTableCellEditorComponent
31          boolean isSelected, int row, int colum
32    {
33       // this is where we get the current Color
34       // user starts editing
35       colorChooser.setColor((Color) value);
36       return panel;
37    }
38
39    public boolean shouldSelectCell(EventObject
40    {
41       // start editing
42       colorDialog.setVisible(true);
43
44       // tell caller it is ok to select this ce
45       return true;
46    }
```

```
47
48    public void cancelCellEditing()
49    {
50       // editing is canceled--hide dialog
51       colorDialog.setVisible(false);
52       super.cancelCellEditing();
53    }
54
55    public boolean stopCellEditing()
56    {
57       // editing is complete--hide dialog
58       colorDialog.setVisible(false);
59       super.stopCellEditing();
60
61       // tell caller it is ok to use color valu
62       return true;
63    }
64
65    public Object getCellEditorValue()
66    {
67       return colorChooser.getColor();
68    }
69 }
```

`javax.swing.JTable` **1.2**

- `TableCellRenderer getDefaultRenderer(Class<?> type)`
  gets the default renderer for the given type.

- `TableCellEditor getDefaultEditor(Class<?> type)`
  gets the default editor for the given type.

`javax.swing.table.TableCellRenderer` **1.2**

- `Component getTableCellRendererComponent(JTable table, Object value, boolean selected, boolean hasFocus, int row, int column)`
  returns a component whose `paint` method is invoked to render a table cell.

`javax.swing.table.TableColumn` **1.2**

- `void setCellEditor(TableCellEditor editor)`
- `void setCellRenderer(TableCellRenderer renderer)`
  set the cell editor or renderer for all cells in this column.
- `void setHeaderRenderer(TableCellRenderer renderer)`
  sets the cell renderer for the header cell in this column.
- `void setHeaderValue(Object value)`
  sets the value to be displayed for the header in this column.

`javax.swing.DefaultCellEditor` **1.2**

- `DefaultCellEditor(JComboBox comboBox)`
  constructs a cell editor that presents the combo box for selecting cell values.

`javax.swing.table.TableCellEditor` **1.2**

- `Component getTableCellEditorComponent(JTable table, Object value, boolean selected, int row, int column)`
  returns a component whose `paint` method renders a table cell.

`javax.swing.CellEditor` **1.2**

- `boolean isCellEditable(EventObject event)`
  returns `true` if the event is suitable for initiating the editing process for this cell.
- `boolean shouldSelectCell(EventObject anEvent)`
  starts the editing process. Returns `true` if the edited cell should be *selected*. Normally, you want to return `true`, but you can return `false` if you don't want the editing process to change the cell selection.
- `void cancelCellEditing()`
  cancels the editing process. You can abandon partial edits.
- `boolean stopCellEditing()`
  stops the editing process, with the intent of using the result. Returns `true` if the edited value is in a proper state for retrieval.
- `Object getCellEditorValue()`
  returns the edited result.

- `void addCellEditorListener(CellEditorListener l)`
- `void removeCellEditorListener(CellEditorListener l)`

add or remove the obligatory cell editor listener.

1.4. Trees

Every computer user who has worked with a hierarchical file system has seen tree displays. Of course, directories and files are only one of the many examples of tree-like organizations. Many tree structures arise in everyday life, such as the hierarchy of countries, states, and cities shown in Figure 12.11.



Figure 1.11: A hierarchy of countries, states, and cities

As programmers, we often need to display tree structures. Fortunately, the Swing library has a `JTree` class for this purpose. The `JTree` class (together with its helper classes) takes care of

laying out the tree and processing user requests for expanding and collapsing nodes. In this section, you will learn how to put the `JTree` class to use.

As with the other complex Swing components, we must focus on the common and useful cases and cannot cover every nuance. If you want to achieve something unusual, we recommend that you consult *Graphic Java™, Third Edition*, by David M. Geary or *Core Swing* by Kim Topley.

Before going any further, let's settle on some terminology (see Figure 12.12). A *tree* is composed of *nodes*. Every node is either a *leaf* or it has *child nodes*. Every node, with the exception of the root node, has exactly one *parent*. A tree has exactly one root node. Sometimes you have a collection of trees, each with its own root node. Such a collection is called a *forest*.



Figure 1.12: Tree terminology

1.4.1. Simple Trees

In our first example program, we will simply display a tree with a few nodes (see Figure 12.14). As with many other Swing components, you need to provide a model of the data, and the component displays it for you. To construct a `JTree`, supply the tree model in the constructor:

```
TreeModel model = . . .;
var tree = new JTree(model);
```

Note: There are also constructors that construct trees out of a collection of elements:

```
JTree(Object[] nodes)
JTree(Vector<?> nodes)
JTree(Hashtable<?, ?> nodes) // the values
```

These constructors are not very useful. They merely build a forest of trees, each with a single node. The third constructor seems particularly useless because the nodes appear in the seemingly random order determined by the hash codes of the keys.

How do you obtain a tree model? You can construct your own model by creating a class that implements the `TreeModel` interface. You will see later in this chapter how to do that. For now, we will stick with the `DefaultTreeModel` that the Swing library supplies.

To construct a default tree model, you must supply a root node.

```
TreeNode root = . . .;
var model = new DefaultTreeModel(root);
```

`TreeNode` is another interface. Populate the default tree model with objects of any class that implements the interface. For now, we will use the concrete node class that Swing supplies—namely, `DefaultMutableTreeNode`. This class implements the

`MutableTreeNode` interface, a subinterface of `TreeNode` (see Figure 12.13).



Figure 1.13: Tree classes

A default mutable tree node holds an object—the *user object*. The tree renders the user objects for all nodes. Unless you specify a renderer, the tree displays the string that is the result of the `toString` method.

In our first example, we use strings as user objects. In practice, you would usually populate a tree with more expressive user objects. For

example, when displaying a directory tree, it makes sense to use `File` objects for the nodes.

You can specify the user object in the constructor, or you can set it later with the `setUserObject` method.

```
var node = new DefaultMutableTreeNode("Texas");
. . .
node.setUserObject("California");
```

Next, you need to establish the parent/child relationships between the nodes. Start with the root node and use the `add` method to add the children:

```
var root = new DefaultMutableTreeNode("World");
var country = new DefaultMutableTreeNode("USA");
root.add(country);
var state = new DefaultMutableTreeNode("California");
country.add(state);
```

Figure 12.14 illustrates how the tree will look.

Figure 1.14: A simple tree

Link up all nodes in this fashion. Then, construct a `DefaultTreeModel` with the root node. Finally, construct a `JTree` with the tree model.

```
var treeModel = new DefaultTreeModel(root);
var tree = new JTree(treeModel);
```

Or, as a shortcut, you can simply pass the root node to the `JTree` constructor. Then the tree automatically constructs a default tree model:

```
var tree = new JTree(root);
```

Listing 12.8 contains the complete code.

Listing 1.8 tree/SimpleTreeFrame.java

```
1  package tree;
2
3  import javax.swing.*;
4  import javax.swing.tree.*;
5
6  /**
7   * This frame contains a simple tree that displ
8   */
9  public class SimpleTreeFrame extends JFrame
10 {
11    private static final int DEFAULT_WIDTH = 300
12    private static final int DEFAULT_HEIGHT = 20
13
14    public SimpleTreeFrame()
15    {
16       setSize(DEFAULT_WIDTH, DEFAULT_HEIGHT);
17
18       // set up tree model data
19
20       var root = new DefaultMutableTreeNode("Wo
21       var country = new DefaultMutableTreeNode(
22       root.add(country);
23       var state = new DefaultMutableTreeNode("C
24       country.add(state);
25       var city = new DefaultMutableTreeNode("Sa
26       state.add(city);
```

```
27          city = new DefaultMutableTreeNode("Cupert
28          state.add(city);
29          state = new DefaultMutableTreeNode("Michi
30          country.add(state);
31          city = new DefaultMutableTreeNode("Ann Ar
32          state.add(city);
33          country = new DefaultMutableTreeNode("Ger
34          root.add(country);
35          state = new DefaultMutableTreeNode("Schle
36          country.add(state);
37          city = new DefaultMutableTreeNode("Kiel")
38          state.add(city);
39
40          // construct tree and put it in a scroll
41
42          var tree = new JTree(root);
43          add(new JScrollPane(tree));
44       }
45    }
```

When you run the program, the tree first looks as in Figure 12.15. Only the root node and its children are visible. Click on the circle icons (the *handles*) to open up the subtrees. The line sticking out from the handle icon points to the right when the subtree is collapsed and down when the subtree is expanded (see Figure 12.16). We don't know what the designers of the Metal look-and-feel

had in mind, but we think of the icon as a door handle. You push down on the handle to open the subtree.

Figure 1.15: The initial tree display



Figure 1.16: Collapsed and expanded subtrees

Note: Of course, the display of the tree depends on the selected look-and-feel. We just described the Metal look-and-feel. In the Windows look-and-feel, the

handles have the more familiar look—a "`-`" or "`+`" in a box (see Figure 12.17).



Figure 1.17: A tree with the Windows look-and-feel

You can use the following magic incantation to turn off the lines joining parents and children (see Figure 12.18):

```
tree.putClientProperty("JTree.lineStyle", "None");
```

Figure 1.18: A tree with no connecting lines

Conversely, to make sure that the lines are shown, use

```
tree.putClientProperty("JTree.lineStyle", "Angled");
```

Another line style, `"Horizontal"`, is shown in Figure 12.19. The tree is displayed with horizontal lines separating only the children of the root. I'm not quite sure what it is good for.



Figure 1.19: A tree with the horizontal line style

By default, there is no handle for collapsing the root of the tree. If you like, you can add one with the call

```
tree.setShowsRootHandles(true);
```

Figure 12.20 shows the result. Now you can collapse the entire tree into the root node.



Figure 1.20: A tree with a root handle

Conversely, you can hide the root altogether. You will thus display a *forest*—a set of trees, each with its own root. You still must join all trees in the forest to a common root; then, hide the root with the instruction

```
tree.setRootVisible(false);
```

Look at Figure 12.21. There appear to be two roots, labeled "USA" and "Germany." The actual root that joins the two is made invisible.

Figure 1.21: A forest

Let's turn from the root to the leaves of the tree. Note that the leaves have an icon different from the other nodes (see Figure 12.22).



Figure 1.22: Leaf and folder icons

When the tree is displayed, each node is drawn with an icon. There are actually three kinds of icons: a leaf icon, an opened nonleaf icon, and a closed nonleaf icon. For simplicity, we refer to the last two as folder icons.

The node renderer needs to know which icon to use for each node. By default, the decision process works like this: If the `isLeaf` method of a node returns `true`, then the leaf icon is used; otherwise, a folder icon is used.

The `isLeaf` method of the `DefaultMutableTreeNode` class returns `true` if the node has no children. Thus, nodes with children get folder icons, and nodes without children get leaf icons.

Sometimes, that behavior is not appropriate. Suppose we added a node "Montana" to our sample tree, but we're at a loss as to what cities to add. We would not want the state node to get a leaf icon because, conceptually, only the cities are leaves.

The `JTree` class has no idea which nodes should be leaves. It asks the tree model. If a childless node isn't automatically a conceptual leaf, you can ask the tree model to use a different criterion for leafiness—namely, to query the "allows children" node property.

For those nodes that should not have children, call

```
node.setAllowsChildren(false);
```

Then, tell the tree model to ask the value of the "allows children" property to determine whether a node should be displayed with a leaf icon. Use the `setAsksAllowsChildren` method of the `DefaultTreeModel` class to set this behavior:

```
model.setAsksAllowsChildren(true);
```

With this decision criterion, nodes that allow children get folder icons, and nodes that don't allow children get leaf icons.

Alternatively, if you construct the tree from the root node, supply the setting for the "asks allows children" property in the constructor.

```
var tree = new JTree(root, true); // nodes that don't
```

`javax.swing.JTree` **1.2**

- `JTree(TreeModel model)`
  constructs a tree from a tree model.

- `JTree(TreeNode root)`
- `JTree(TreeNode root, boolean asksAllowChildren)`
  construct a tree with a default tree model that displays the root and its children.
- `void setShowsRootHandles(boolean b)`
  If `b` is `true`, the root node has a handle for collapsing or expanding its children.
- `void setRootVisible(boolean b)`
  If `b` is true, then the root node is displayed. Otherwise, it is hidden.

`javax.swing.tree.TreeNode` **1.2**

- `boolean isLeaf()`
  returns `true` if this node is conceptually a leaf.
- `boolean getAllowsChildren()`
  returns `true` if this node can have child nodes.

`javax.swing.tree.MutableTreeNode` **1.2**

- `void setUserObject(Object userObject)`
  sets the "user object" that the tree node uses for rendering.

`javax.swing.tree.TreeModel` **1.2**

- `boolean isLeaf(Object node)`
  returns `true` if `node` should be displayed as a leaf node.

`javax.swing.tree.DefaultTreeModel` **1.2**

- `void setAsksAllowsChildren(boolean b)`
  If `b` is `true`, nodes are displayed as leaves when their `getAllowsChildren` method returns `false`. Otherwise, they are displayed as leaves when their `isLeaf` method returns `true`.

`javax.swing.tree.DefaultMutableTreeNode` **1.2**

- `DefaultMutableTreeNode(Object userObject)`
  constructs a mutable tree node with the given user object.
- `void add(MutableTreeNode child)`
  adds a node as the last child of this node.
- `void setAllowsChildren(boolean b)`
  If `b` is `true`, children can be added to this node.

`javax.swing.JComponent` 1.2

- `void putClientProperty(Object key, Object value)` adds a key/value pair to a small table that each component manages. This is an "escape hatch" mechanism that some Swing components use for storing properties specific to a look-and-feel.

1.4.2. Editing Trees and Tree Paths

In the next example program, you will see how to edit a tree. Figure 12.23 shows the user interface. If you click the Add Sibling or Add Child button, the program adds a new node (with title New) to the tree. If you click the Delete button, the program deletes the currently selected node.

Figure 1.23: Editing a tree

To implement this behavior, you need to find out which tree node is currently selected. The `JTree` class has a surprising way of

identifying nodes in a tree. It does not deal with tree nodes but with *paths of objects*, called *tree paths*. A tree path starts at the root and consists of a sequence of child nodes (see Figure 12.24).



Figure 1.24: A tree path

You might wonder why the `JTree` class needs the whole path. Couldn't it just get a `TreeNode` and keep calling the `getParent` method? In fact, the `JTree` class knows nothing about the `TreeNode` interface. That interface is never used by the `TreeModel` interface; it is only used by the `DefaultTreeModel` implementation. You can have other tree models in which the nodes do not implement the `TreeNode` interface at all. If you use a tree model that manages other types of objects, those objects might not have `getParent` and `getChild` methods. They would of course need to have some other connection to each other. It is the job of

the tree model to link nodes together. The `JTree` class itself has no clue about the nature of their linkage. For that reason, the `JTree` class always needs to work with complete paths.

The `TreePath` class manages a sequence of `Object` (not `TreeNode`!) references. A number of `JTree` methods return `TreePath` objects. When you have a tree path, you usually just need to know the terminal node, which you can get with the `getLastPathComponent` method. For example, to find out the currently selected node in a tree, use the `getSelectionPath` method of the `JTree` class. You will get a `TreePath` object back, from which you can retrieve the actual node.

```
  TreePath selectionPath = tree.getSelectionPath();
  var selectedNode = (DefaultMutableTreeNode) selection
```

Actually, since this particular query is so common, there is a convenience method that gives the selected node immediately:

```
  var selectedNode = (DefaultMutableTreeNode) tree.getL
```

This method is not called `getSelectedNode` because the tree does not know that it contains nodes—its tree model deals only with paths of objects.

Note: Tree paths are one of the two ways in which the `JTree` class describes nodes. Quite a few `JTree` methods take or return an integer index—the *row position*. A row position is simply the row number (starting with 0) of the node in the tree display. Only visible nodes have row numbers, and the row number of a node changes if other nodes before it are expanded, collapsed, or modified. For that reason, you should avoid row positions. All `JTree` methods that use row positions have equivalents that use tree paths instead.

Once you have the selected node, you can edit it. However, do not simply add children to a tree node:

```
selectedNode.add(newNode); // No!
```

If you change the structure of the nodes, you change the model but the associated view is not notified. You could send out a notification yourself, but if you use the `insertNodeInto` method of the `DefaultTreeModel` class, the model class takes care of that. For example, the following call appends a new node as the last child of the selected node and notifies the tree view:

```
model.insertNodeInto(newNode, selectedNode, selectedN
```

The analogous call `removeNodeFromParent` removes a node and notifies the view:

```
model.removeNodeFromParent(selectedNode);
```

If you keep the node structure in place but change the user object, you should call the following method:

```
model.nodeChanged(changedNode);
```

The automatic notification is a major advantage of using the `DefaultTreeModel`. If you supply your own tree model, you have to implement automatic notification by hand. (See *Core Swing* by Kim Topley for details.)

Caution: The `DefaultTreeModel` class has a `reload` method that reloads the entire model. However, don't call `reload` simply to update the tree after making a few changes. When the tree is regenerated, all nodes beyond the root's children are collapsed again. It will be quite disconcerting to your users if they have to keep expanding the tree after every change.

When the view is notified of a change in the node structure, it updates the display but does not automatically expand a node to show newly added children. In particular, if a user in our sample program adds a new child node to a node for which children are currently collapsed, the new node is silently added to the collapsed subtree. This gives the user no feedback that the command was actually carried out. In such a case, you should make a special effort to expand all parent nodes so that the newly added node becomes visible. Use the `makeVisible` method of the `JTree` class for this purpose. The `makeVisible` method expects a tree path leading to the node that should become visible.

Thus, you need to construct a tree path from the root to the newly inserted node. To get a tree path, first call the `getPathToRoot` method of the `DefaultTreeModel` class. It returns a `TreeNode[]` array of all nodes from a node to the root node. Pass that array to a `TreePath` constructor.

For example, here is how you make the new node visible:

```
TreeNode[] nodes = model.getPathToRoot(newNode);
var path = new TreePath(nodes);
tree.makeVisible(path);
```

Note: It is curious that the `DefaultTreeModel` class feigns almost complete ignorance of the `TreePath` class, even though its job is to communicate with a `JTree`. The `JTree` class uses tree paths a lot, and it never uses arrays of node objects.

Now, suppose your tree is contained inside a scroll pane. After the tree node expansion, the new node might still not be visible because it falls outside the viewport. To overcome that problem, call

```
tree.scrollPathToVisible(path);
```

instead of calling `makeVisible`. This call expands all nodes along the path and tells the ambient scroll pane to scroll the node at the end of the path into view (see Figure 12.25).



Figure 1.25: The scroll pane scrolls to display a new node.

By default, tree nodes cannot be edited. However, if you call

```
tree.setEditable(true);
```

the user can edit a node simply by double-clicking, editing the string, and pressing the Enter key. Double-clicking invokes the *default cell editor*, which is implemented by the `DefaultCellEditor` class (see Figure 12.26). It is possible to install other cell editors, using the same process that you have seen in our discussion of table cell editors.

Figure 1.26: The default cell editor

Listing 12.9 shows the complete source code of the tree editing program. Run the program, add a few nodes, and edit them by double-clicking. Observe how collapsed nodes expand to show added children and how the scroll pane keeps added nodes in the viewport.

Listing 1.9 treeEdit/TreeEditFrame.java

```
1  package treeEdit;
2
3  import java.awt.*;
4  import javax.swing.*;
5  import javax.swing.tree.*;
6
7  /**
8   * A frame with a tree and buttons to edit the
9   */
10 public class TreeEditFrame extends JFrame
11 {
12    private static final int DEFAULT_WIDTH = 400
13    private static final int DEFAULT_HEIGHT = 20
14
15    private DefaultTreeModel model;
16    private JTree tree;
17
18    public TreeEditFrame()
19    {
20       setSize(DEFAULT_WIDTH, DEFAULT_HEIGHT);
21
22       // construct tree
23
24       TreeNode root = makeSampleTree();
25       model = new DefaultTreeModel(root);
26       tree = new JTree(model);
```

```
27          tree.setEditable(true);
28
29          // add scroll pane with tree
30
31          var scrollPane = new JScrollPane(tree);
32          add(scrollPane, BorderLayout.CENTER);
33
34          makeButtons();
35       }
36
37       public TreeNode makeSampleTree()
38       {
39          var root = new DefaultMutableTreeNode("Wo
40          var country = new DefaultMutableTreeNode(
41          root.add(country);
42          var state = new DefaultMutableTreeNode("C
43          country.add(state);
44          var city = new DefaultMutableTreeNode("Sa
45          state.add(city);
46          city = new DefaultMutableTreeNode("San Di
47          state.add(city);
48          state = new DefaultMutableTreeNode("Michi
49          country.add(state);
50          city = new DefaultMutableTreeNode("Ann Ar
51          state.add(city);
52          country = new DefaultMutableTreeNode("Ger
53          root.add(country);
54          state = new DefaultMutableTreeNode("Schle
```

```
55          country.add(state);
56          city = new DefaultMutableTreeNode("Kiel")
57          state.add(city);
58          return root;
59       }
60
61       /**
62        * Makes the buttons to add a sibling, add a
63        */
64       public void makeButtons()
65       {
66          var panel = new JPanel();
67          var addSiblingButton = new JButton("Add S
68          addSiblingButton.addActionListener(event
69             {
70                var selectedNode = (DefaultMutableT
71
72                if (selectedNode == null) return;
73
74                var parent = (DefaultMutableTreeNod
75
76                if (parent == null) return;
77
78                var newNode = new DefaultMutableTre
79
80                int selectedIndex = parent.getIndex
81                model.insertNodeInto(newNode, paren
82
```

```
83              // now display new node
84
85              TreeNode[] nodes = model.getPathTo
86              var path = new TreePath(nodes);
87              tree.scrollPathToVisible(path);
88           });
89        panel.add(addSiblingButton);
90
91        var addChildButton = new JButton("Add Ch
92        addChildButton.addActionListener(event -
93           {
94              var selectedNode = (DefaultMutable
95
96              if (selectedNode == null) return;
97
98              var newNode = new DefaultMutableTre
99              model.insertNodeInto(newNode, selec
100
101             // now display new node
102
103             TreeNode[] nodes = model.getPathTo
104             var path = new TreePath(nodes);
105             tree.scrollPathToVisible(path);
106          });
107       panel.add(addChildButton);
108
109       var deleteButton = new JButton("Delete");
110       deleteButton.addActionListener(event ->
```

```
111             {
112                var selectedNode = (DefaultMutableT
113
114                if (selectedNode != null && selecte
115                      .removeNodeFromParent(selecte
116             });
117          panel.add(deleteButton);
118          add(panel, BorderLayout.SOUTH);
119       }
120    }
```

`javax.swing.JTree` **1.2**

- `TreePath getSelectionPath()`
  gets the path to the currently selected node, or the path to the first selected node if multiple nodes are selected. Returns `null` if no node is selected.
- `Object getLastSelectedPathComponent()`
  gets the node object that represents the currently selected node, or the first node if multiple nodes are selected. Returns `null` if no node is selected.
- `void makeVisible(TreePath path)`
  expands all nodes along the path.
- `void scrollPathToVisible(TreePath path)`
  expands all nodes along the path and, if the tree is contained in a scroll pane, scrolls to ensure that the last node on the path is

visible.

`javax.swing.tree.TreePath` **1.2**

- `Object getLastPathComponent()`
  gets the last object on this path—that is, the node object that the path represents.

`javax.swing.tree.TreeNode` **1.2**

- `TreeNode getParent()`
  returns the parent node of this node.
- `TreeNode getChildAt(int index)`
  looks up the child node at the given index. The index must be between 0 and `getChildCount()` – 1.
- `int getChildCount()`
  returns the number of children of this node.
- `Enumeration children()`
  returns an enumeration object that iterates through all children of this node.

`javax.swing.tree.DefaultTreeModel` **1.2**

- `void insertNodeInto(MutableTreeNode newChild, MutableTreeNode parent, int index)`
  inserts `newChild` as a new child node of `parent` at the given index and notifies the tree model listeners.
- `void removeNodeFromParent(MutableTreeNode node)`
  removes `node` from this model and notifies the tree model listeners.
- `void nodeChanged(TreeNode node)`
  notifies the tree model listeners that `node` has changed.
- `void nodesChanged(TreeNode parent, int[] changedChildIndexes)`
  notifies the tree model listeners that all child nodes of `parent` with the given indexes have changed.
- `void reload()`
  reloads all nodes into the model. This is a drastic operation that you should use only if the nodes have changed completely because of some outside influence.

1.4.3. Node Enumeration

Sometimes you need to find a node in a tree by starting at the root and visiting all children until you have found a match. The

`DefaultMutableTreeNode` class has several convenience methods for iterating through nodes.

The `breadthFirstEnumeration` and `depthFirstEnumeration` methods return enumeration objects whose `nextElement` method visits all children of the current node, using either a breadth-first or depth-first traversal. Figure 12.27 shows the traversals for a sample tree—the node labels indicate the order in which the nodes are traversed.



Figure 1.27: Tree traversal orders

Breadth-first enumeration is the easiest to visualize. The tree is traversed in layers. The root is visited first, followed by all of its children, then the grandchildren, and so on.

To visualize depth-first enumeration, imagine a rat trapped in a tree-shaped maze. It rushes along the first path until it comes to a leaf. Then, it backtracks and turns around to the next path, and so on.

Computer scientists also call this *postorder traversal* because the search process visits the children before visiting the parents. The `postOrderEnumeration` method is a synonym for `depthFirstEnumeration`. For completeness, there is also a `preOrderEnumeration`, a depth-first search that enumerates parents before the children.

Here is the typical usage pattern:

```
Enumeration breadthFirst = node.breadthFirstEnumerati
while (breadthFirst.hasMoreElements())
   do something with breadthFirst.nextElement();
```

Finally, a related method, `pathFromAncestorEnumeration`, finds a path from an ancestor to a given node and enumerates the nodes along that path. That's no big deal—it just keeps calling `getParent` until the ancestor is found and then presents the path in reverse order.

In our next example program, we put node enumeration to work. The program displays inheritance trees of classes. Type the name of

a class into the text field on the bottom of the frame. The class and all of its superclasses are added to the tree (see Figure 12.28).



Figure 1.28: An inheritance tree

In this example, we take advantage of the fact that the user objects of the tree nodes can be objects of any type. Since our nodes describe classes, we store `Class` objects in the nodes.

We don’t want to add the same class object twice, so we need to check whether a class already exists in the tree. The following method finds the node with a given user object if it exists in the tree:

```
public DefaultMutableTreeNode findUserObject(Object o
{
   Enumeration e = root.breadthFirstEnumeration();
```

```
      while (e.hasMoreElements())
      {
         DefaultMutableTreeNode node = (DefaultMutableTr
         if (node.getUserObject().equals(obj))
            return node;
      }
      return null;
   }
```

1.4.4. Rendering Nodes

In your applications, you will often need to change the way a tree component draws the nodes. The most common change is, of course, to choose different icons for nodes and leaves. Other changes might involve changing the font of the node labels or drawing images at the nodes. All these changes are possible by installing a new *tree cell renderer* into the tree. By default, the `JTree` class uses `DefaultTreeCellRenderer` objects to draw each node. The `DefaultTreeCellRenderer` class extends the `JLabel` class. The label contains the node icon and the node label.

Note: The cell renderer does not draw the "handles" for expanding and collapsing subtrees. The handles are

part of the look-and-feel, and it is recommended that you do not change them.

You can customize the display in three ways.

- You can change the icons, font, and background color used by a `DefaultTreeCellRenderer`. These settings are used for all nodes in the tree.
- You can install a renderer that extends the `DefaultTreeCellRenderer` class and vary the icons, fonts, and background color for each node.
- You can install a renderer that implements the `TreeCellRenderer` interface to draw a custom image for each node.

Let us look at these possibilities one by one. The easiest customization is to construct a `DefaultTreeCellRenderer` object, change the icons, and install it into the tree:

```
var renderer = new DefaultTreeCellRenderer();
renderer.setLeafIcon(new ImageIcon("blue-ball.gif"));
renderer.setClosedIcon(new ImageIcon("red-ball.gif"))
renderer.setOpenIcon(new ImageIcon("yellow-ball.gif")
tree.setCellRenderer(renderer);
```

You can see the effect in Figure 12.28. We just use the "ball" icons as placeholders—presumably your user interface designer would supply you with appropriate icons to use for your applications.

We don't recommend that you change the font or background color for an entire tree—that is really the job of the look-and-feel.

However, it can be useful to change the font of some nodes in a tree to highlight them. If you look carefully at Figure 12.28, you will notice that the *abstract* classes are set in italics.

To change the appearance of individual nodes, install a tree cell renderer. Tree cell renderers are very similar to the list cell renderers we discussed earlier in this chapter. The `TreeCellRenderer` interface has a single method:

```
Component getTreeCellRendererComponent(JTree tree, Ob
      boolean expanded, boolean leaf, int row, boolea
```

The `getTreeCellRendererComponent` method of the `DefaultTreeCellRenderer` class returns `this`—in other words, a label. (The `DefaultTreeCellRenderer` class extends the `JLabel` class.) To customize the component, extend the `DefaultTreeCellRenderer` class. Override the `getTreeCellRendererComponent` method as follows: Call the

superclass method so it can prepare the label data, customize the label properties, and finally return `this`.

```
class MyTreeCellRenderer extends DefaultTreeCellRende
{
   public Component getTreeCellRendererComponent(JTre
         boolean expanded, boolean leaf, int row, boo
   {
      Component comp = super.getTreeCellRendererCompo
            expanded, leaf, row, hasFocus);
      DefaultMutableTreeNode node = (DefaultMutableTr
      look at node.getUserObject();
      Font font = appropriate font;
      comp.setFont(font);
      return comp;
   }
}
```

Caution: The `value` parameter of the `getTreeCellRendererComponent` method is the *node* object, *not* the user object! Recall that the user object is a feature of the `DefaultMutableTreeNode`, and that a `JTree` can contain nodes of an arbitrary type. If your tree uses `DefaultMutableTreeNode` nodes, you must retrieve the user object in a second step, as we did in the preceding code sample.

Caution: The `DefaultTreeCellRenderer` uses the *same* label object for all nodes, only changing the label text for each node. If you change the font for a particular node, you must set it back to its default value when the method is called again. Otherwise, all subsequent nodes will be drawn in the changed font! Look at the code in Listing 12.10 to see how to restore the font to the default.

The `ClassNameTreeCellRenderer` in Listing 12.10 sets the class name in either the normal or italic font, depending on the `ABSTRACT` modifier of the `Class` object. We don't want to set a particular font because we don't want to change whatever font the look-and-feel normally uses for labels. For that reason, we use the font from the label and *derive* an italic font from it. Recall that only a single shared `JLabel` object is returned by all calls. We need to hang on to the original font and restore it in the next call to the `getTreeCellRendererComponent` method.

Also, note how we change the node icons in the `ClassTreeFrame` constructor.

`javax.swing.tree.DefaultMutableTreeNode` **1.2**

- `Enumeration breadthFirstEnumeration()`
- `Enumeration depthFirstEnumeration()`
- `Enumeration preOrderEnumeration()`
- `Enumeration postOrderEnumeration()`

  return enumeration objects for visiting all nodes of the tree model in a particular order. In breadth-first traversal, children that are closer to the root are visited before those that are farther away. In depth-first traversal, all children of a node are completely enumerated before its siblings are visited. The `postOrderEnumeration` method is a synonym for `depthFirstEnumeration`. The preorder traversal is identical to the postorder traversal except that parents are enumerated before their children.

`javax.swing.tree.TreeCellRenderer` **1.2**

- `Component getTreeCellRendererComponent(JTree tree, Object value, boolean selected, boolean expanded, boolean leaf, int row, boolean hasFocus)`

  returns a component whose `paint` method is invoked to render a tree cell.

`javax.swing.tree.DefaultTreeCellRenderer` 1.2

- `void setLeafIcon(Icon icon)`
- `void setOpenIcon(Icon icon)`
- `void setClosedIcon(Icon icon)`

  set the icon to show for a leaf node, an expanded node, and a collapsed node.

1.4.5. Listening to Tree Events

Most commonly, a tree component is paired with some other component. When the user selects tree nodes, some information shows up in another window. See Figure 12.29 for an example. When the user selects a class, the instance and static variables of that class are displayed in the text area to the right.



Figure 1.29: A class browser

To obtain this behavior, you need to install a *tree selection listener*. The listener must implement the `TreeSelectionListener` interface—an interface with a single method:

```
void valueChanged(TreeSelectionEvent event)
```

That method is called whenever the user selects or deselects tree nodes.

Add the listener to the tree in the normal way:

```
tree.addTreeSelectionListener(listener);
```

You can specify whether the user is allowed to select a single node, a contiguous range of nodes, or an arbitrary, potentially discontiguous, set of nodes. The `JTree` class uses a `TreeSelectionModel` to manage node selection. You need to retrieve the model to set the selection state to one of `SINGLE_TREE_SELECTION`, `CONTIGUOUS_TREE_SELECTION`, or `DISCONTIGUOUS_TREE_SELECTION`. (Discontiguous selection mode is the default.) For example, in our class browser, we want to allow selection of only a single class:

```
int mode = TreeSelectionModel.SINGLE_TREE_SELECTION;
```

```
tree.getSelectionModel().setSelectionMode(mode);
```

Apart from setting the selection mode, you need not worry about the tree selection model.

Note: How the user selects multiple items depends on the look-and-feel. In the Metal look-and-feel, hold down the Ctrl key while clicking an item to add it to the selection, or to remove it if it is currently selected. Hold down the Shift key while clicking an item to select a *range* of items, extending from the previously selected item to the new item.

To find out the current selection, query the tree with the `getSelectionPaths` method:

```
TreePath[] selectedPaths = tree.getSelectionPaths();
```

If you restricted the user to single-item selection, you can use the convenience method `getSelectionPath` which returns the first selected path or `null` if no path was selected.

Caution: The `TreeSelectionEvent` class has a `getPaths` method that returns an array of `TreePath` objects, but that array describes *selection changes*, not the current selection.

Listing 12.10 shows the frame class for the class tree program. The program displays inheritance hierarchies and customizes the display to show abstract classes in italics. (See Listing 12.11 for the cell renderer.) You can type the name of any class into the text field at the bottom of the frame. Press the Enter key or click the Add button to add the class and its superclasses to the tree. You must enter the full package name, such as `java.util.ArrayList`.

This program is a bit tricky because it uses reflection to construct the class tree. This work is done inside the `addClass` method. (The details are not that important. We use the class tree in this example because inheritance yields a nice supply of trees without laborious coding. When you display trees in your applications, you will have your own source of hierarchical data.) The method uses the breadth-first search algorithm to find whether the current class is already in the tree by calling the `findUserObject` method that we implemented in the preceding section. If the class is not already in the tree, we add the superclasses to the tree, then make the new class node a child and make that node visible.

When you select a tree node, the text area to the right is filled with the fields of the selected class. In the frame constructor, we restrict the user to single-item selection and add a tree selection listener. When the `valueChanged` method is called, we ignore its event parameter and simply ask the tree for the current selection path. As always, we need to get the last node of the path and look up its user object. We then call the `getFieldDescription` method which uses reflection to assemble a string with all fields of the selected class.

Listing 1.10 treeRender/ClassTreeFrame.java

```
1  package treeRender;
2
3  import java.awt.*;
4  import java.awt.event.*;
5  import java.lang.reflect.*;
6  import java.util.*;
7
8  import javax.swing.*;
9  import javax.swing.tree.*;
10
11 /**
12  * This frame displays the class tree, a text f
13  * into the tree.
14  */
```

```
15 public class ClassTreeFrame extends JFrame
16 {
17    private static final int DEFAULT_WIDTH = 400
18    private static final int DEFAULT_HEIGHT = 30
19
20    private DefaultMutableTreeNode root;
21    private DefaultTreeModel model;
22    private JTree tree;
23    private JTextField textField;
24    private JTextArea textArea;
25
26    public ClassTreeFrame()
27    {
28       setSize(DEFAULT_WIDTH, DEFAULT_HEIGHT);
29
30       // the root of the class tree is Object
31       root = new DefaultMutableTreeNode(java.la
32       model = new DefaultTreeModel(root);
33       tree = new JTree(model);
34
35       // add this class to populate the tree wi
36       addClass(getClass());
37
38       // set up node icons
39       var renderer = new ClassNameTreeCellRende
40       renderer.setClosedIcon(new ImageIcon(getC
41       renderer.setOpenIcon(new ImageIcon(getCla
42       renderer.setLeafIcon(new ImageIcon(getCla
```

```
43        tree.setCellRenderer(renderer);
44
45        // set up selection mode
46        tree.addTreeSelectionListener(event ->
47           {
48              // the user selected a different no
49              TreePath path = tree.getSelectionPa
50              if (path == null) return;
51              var selectedNode = (DefaultMutableT
52              Class<?> c = (Class<?>) selectedNod
53              String description = getFieldDescri
54              textArea.setText(description);
55           });
56        int mode = TreeSelectionModel.SINGLE_TREE
57        tree.getSelectionModel().setSelectionMode
58
59        // this text area holds the class descrip
60        textArea = new JTextArea();
61
62        // add tree and text area
63        var panel = new JPanel();
64        panel.setLayout(new GridLayout(1, 2));
65        panel.add(new JScrollPane(tree));
66        panel.add(new JScrollPane(textArea));
67
68        add(panel, BorderLayout.CENTER);
69
70        addTextField();
```

```
71    }
72
73    /**
74     * Add the text field and "Add" button to ac
75     */
76    public void addTextField()
77    {
78       var panel = new JPanel();
79
80       ActionListener addListener = event ->
81          {
82             // add the class whose name is in t
83             try
84             {
85                String text = textField.getText(
86                addClass(Class.forName(text)); /
87                textField.setText("");
88             }
89             catch (ClassNotFoundException e)
90             {
91                JOptionPane.showMessageDialog(nu
92             }
93          };
94
95       // new class names are typed into this te
96       textField = new JTextField(20);
97       textField.addActionListener(addListener);
98       panel.add(textField);
```

```
99
100         var addButton = new JButton("Add");
101         addButton.addActionListener(addListener);
102         panel.add(addButton);
103
104         add(panel, BorderLayout.SOUTH);
105      }
106
107      /**
108       * Finds an object in the tree.
109       * @param obj the object to find
110       * @return the node containing the object or
111       */
112      public DefaultMutableTreeNode findUserObject
113      {
114         // find the node containing a user object
115         var e = (Enumeration<TreeNode>) root.brea
116         while (e.hasMoreElements())
117         {
118            var node = (DefaultMutableTreeNode) e
119            if (node.getUserObject().equals(obj))
120         }
121         return null;
122      }
123
124      /**
125       * Adds a new class and any parent classes t
126       * @param c the class to add
```

```
127      * @return the newly added node
128      */
129     public DefaultMutableTreeNode addClass(Class
130     {
131        // add a new class to the tree
132
133        // skip non-class types
134        if (c.isInterface() || c.isPrimitive()) r
135
136        // if the class is already in the tree, r
137        DefaultMutableTreeNode node = findUserObj
138        if (node != null) return node;
139
140        // class isn't present--first add class p
141
142        Class<?> s = c.getSuperclass();
143
144        DefaultMutableTreeNode parent;
145        if (s == null) parent = root;
146        else parent = addClass(s);
147
148        // add the class as a child to the parent
149        var newNode = new DefaultMutableTreeNode(
150        model.insertNodeInto(newNode, parent, par
151
152        // make node visible
153        var path = new TreePath(model.getPathToRo
154        tree.makeVisible(path);
```

```
155
156         return newNode;
157      }
158
159      /**
160       * Returns a description of the fields of a
161       * @param c the class to be described
162       * @return a string containing all field typ
163       */
164      public static String getFieldDescription(Cla
165      {
166         // use reflection to find types and names
167         var r = new StringBuilder();
168         Field[] fields = c.getDeclaredFields();
169         for (int i = 0; i < fields.length; i++)
170         {
171            Field f = fields[i];
172            if (Modifier.isStatic(f.getModifiers()
173            r.append(f.getType().getName());
174            r.append(" ");
175            r.append(f.getName());
176            r.append("\n");
177         }
178         return r.toString();
179      }
180   }
```

Listing 1.11 treeRender/ClassNameTreeCellRenderer.java

```
1  package treeRender;
2
3  import java.awt.*;
4  import java.lang.reflect.*;
5  import javax.swing.*;
6  import javax.swing.tree.*;
7
8  /**
9   * This class renders a class name either in pl
10  */
11 public class ClassNameTreeCellRenderer extends
12 {
13    private Font plainFont = null;
14    private Font italicFont = null;
15
16    public Component getTreeCellRendererComponer
17          boolean expanded, boolean leaf, int ro
18    {
19       super.getTreeCellRendererComponent(tree,
20             row, hasFocus);
21       // get the user object
22       var node = (DefaultMutableTreeNode) value
23       Class<?> c = (Class<?>) node.getUserObjec
24
25       // the first time, derive italic font fro
```

```
26          if (plainFont == null)
27          {
28             plainFont = getFont();
29             // the tree cell renderer is sometimes
30             if (plainFont != null) italicFont = pl
31          }
32
33          // set font to italic if the class is abs
34          if (Modifier.isAbstract(c.getModifiers())
35          else setFont(plainFont);
36          return this;
37       }
38    }
```

`javax.swing.JTree` **1.2**

- `TreePath getSelectionPath()`
- `TreePath[] getSelectionPaths()`

  return the first selected path, or an array of paths to all selected nodes. If no paths are selected, both methods return `null`.

`javax.swing.event.TreeSelectionListener` **1.2**

- `void valueChanged(TreeSelectionEvent event)`

  is called whenever nodes are selected or deselected.

`javax.swing.event.TreeSelectionEvent` 1.2

- `TreePath getPath()`
- `TreePath[] getPaths()`

  get the first path or all paths that have *changed* in this selection event. If you want to know the current selection, not the selection change, call `JTree.getSelectionPaths` instead.

1.4.6. Custom Tree Models

In the final example, we implement a program that inspects the contents of an object, just like a debugger does (see Figure 12.30).



Figure 1.30: An object inspection tree

Before going further, compile and run the example program. Each node corresponds to an instance field. If the field is an object, expand it to see *its* instance fields. The program inspects the contents of the frame window. If you poke around a few of the instance fields, you should be able to find some familiar classes. You'll also gain some respect for how complex the Swing user interface components are under the hood.

What's remarkable about the program is that the tree does not use the `DefaultTreeModel`. If you already have data that are hierarchically organized, you might not want to build a duplicate tree and worry about keeping both trees synchronized. That is the situation in our case—the inspected objects are already linked to each other through the object references, so there is no need to replicate the linking structure.

The `TreeModel` interface has only a handful of methods. The first group of methods enables the `JTree` to find the tree nodes by first getting the root, then the children. The `JTree` class calls these methods only when the user actually expands a node.

```
Object getRoot()
int getChildCount(Object parent)
Object getChild(Object parent, int index)
```

This example shows why the `TreeModel` interface, like the `JTree` class itself, does not need an explicit notion of nodes. The root and its children can be any objects. The `TreeModel` is responsible for telling the `JTree` how they are connected.

The next method of the `TreeModel` interface is the reverse of `getChild`:

```
int getIndexOfChild(Object parent, Object child)
```

Actually, this method can be implemented in terms of the first three—see the code in Listing 12.12.

The tree model tells the `JTree` which nodes should be displayed as leaves:

```
boolean isLeaf(Object node)
```

If your code changes the tree model, the tree needs to be notified so it can redraw itself. The tree adds itself as a `TreeModelListener` to the model. Thus, the model must support the usual listener management methods:

```
void addTreeModelListener(TreeModelListener l)
```

```
void removeTreeModelListener(TreeModelListener l)
```

You can see the implementations for these methods in Listing 12.13.

When the model modifies the tree contents, it calls one of the four methods of the `TreeModelListener` interface:

```
void treeNodesChanged(TreeModelEvent e)
void treeNodesInserted(TreeModelEvent e)
void treeNodesRemoved(TreeModelEvent e)
void treeStructureChanged(TreeModelEvent e)
```

The `TreeModelEvent` object describes the location of the change. The details of assembling a tree model event that describes an insertion or removal event are quite technical. You only need to worry about firing these events if your tree can actually have nodes added and removed. In Listing 12.12, we show how to fire one event by replacing the root with a new object.

Tip: To simplify the code for event firing, use the `javax.swing.EventListenerList` convenience class that collects listeners. The last three methods of Listing 12.13 show how to use the class.

Finally, if the user edits a tree node, your model is called with the change:

```
void valueForPathChanged(TreePath path, Object newVal
```

If you don't allow editing, this method is never called.

If you don't need to support editing, constructing a tree model is easily done. Implement the three methods:

```
Object getRoot()
int getChildCount(Object parent)
Object getChild(Object parent, int index)
```

These methods describe the structure of the tree. Supply routine implementations of the other five methods, as in Listing 12.12. You are then ready to display your tree.

Now let's turn to the implementation of the example program. Our tree will contain objects of type `Variable`.

Note: Had we used the `DefaultTreeModel`, our nodes would have been objects of type

`DefaultMutableTreeNode` with *user objects* of type `Variable`.

For example, suppose you inspect the variable

```
Employee joe;
```

That variable has a *type* `Employee.class`, a *name* `"joe"`, and a *value*—the value of the object reference `joe`. In Listing 12.14, we define a class `Variable` that describes a variable in a program:

```
var v = new Variable(Employee.class, "joe", joe);
```

If the type of the variable is a primitive type, you must use an object wrapper for the value.

```
new Variable(double.class, "salary", Double.valueOf(s
```

If the type of the variable is a class, the variable has *fields*. Using reflection, we enumerate all fields and collect them in an `ArrayList`. Since the `getFields` method of the `Class` class does not return the fields of the superclass, we need to call `getFields` on all superclasses as well. You can find the code in the

`Variable` constructor. The `getFields` method of our `Variable` class returns the array of fields. Finally, the `toString` method of the `Variable` class formats the node label. The label always contains the variable type and name. If the variable is not a class, the label also contains the value.

Note: If the type is an array, we do not display the elements of the array. This would not be difficult to do; I leave it as the proverbial "exercise for the reader."

Let's move on to the tree model. The first two methods are simple.

```
public Object getRoot()
{
   return root;
}

public int getChildCount(Object parent)
{
   return ((Variable) parent).getFields().size();
}
```

The `getChild` method returns a new `Variable` object that describes the field with the given index. The `getType` and `getName` methods of the `Field` class yield the field type and

name. By using reflection, you can read the field value as `f.get(parentValue)`. That method can throw an `IllegalAccessException`. However, we made all fields accessible in the `Variable` constructor, so this won't happen in practice.

Here is the complete code of the `getChild` method:

```
public Object getChild(Object parent, int index)
{
   ArrayList fields = ((Variable) parent).getFields()
   var f = (Field) fields.get(index);
   Object parentValue = ((Variable) parent).getValue(
   try
   {
      return new Variable(f.getType(), f.getName(), f
   }
   catch (IllegalAccessException e)
   {
      return null;
   }
}
```

These three methods reveal the structure of the object tree to the `JTree` component. The remaining methods are routine—see the source code in Listing 12.13.

There is one remarkable fact about this tree model: It actually describes an *infinite* tree. You can verify this by following one of the `WeakReference` objects. Click on the variable named `referent`. It leads you right back to the original object. You get an identical subtree, and you can open its `WeakReference` object again, ad infinitum. Of course, you cannot *store* an infinite set of nodes; the tree model simply generates the nodes on demand as the user expands the parents. Listing 12.12 shows the frame class of the sample program.

Listing 1.12 treeModel/ObjectInspectorFrame.java

```
1  package treeModel;
2
3  import java.awt.*;
4  import javax.swing.*;
5
6  /**
7   * This frame holds the object tree.
8   */
9  public class ObjectInspectorFrame extends JFra
10 {
11    private JTree tree;
12    private static final int DEFAULT_WIDTH = 40
13    private static final int DEFAULT_HEIGHT = 3
```

```
14
15    public ObjectInspectorFrame()
16    {
17       setSize(DEFAULT_WIDTH, DEFAULT_HEIGHT);
18
19       // we inspect this frame object
20
21       var v = new Variable(getClass(), "this",
22       var model = new ObjectTreeModel();
23       model.setRoot(v);
24
25       // construct and show tree
26
27       tree = new JTree(model);
28       add(new JScrollPane(tree), BorderLayout.C
29    }
30 }
```

Listing 1.13 treeModel/ObjectTreeModel.java

```
1 package treeModel;
2
3 import java.lang.reflect.*;
4 import java.util.*;
5 import javax.swing.event.*;
6 import javax.swing.tree.*;
7
8 /**
```

```
 * This tree model describes the tree structure
 * that are stored in instance variables.
 */
public class ObjectTreeModel implements TreeMod
{
   private Variable root;
   private EventListenerList listenerList = new

   /**
    * Constructs an empty tree.
    */
   public ObjectTreeModel()
   {
      root = null;
   }

   /**
    * Sets the root to a given variable.
    * @param v the variable that is being descr
    */
   public void setRoot(Variable v)
   {
      Variable oldRoot = v;
      root = v;
      fireTreeStructureChanged(oldRoot);
   }

   public Object getRoot()
```

```
37    {
38       return root;
39    }
40
41    public int getChildCount(Object parent)
42    {
43       return ((Variable) parent).getFields().si
44    }
45
46    public Object getChild(Object parent, int in
47    {
48       ArrayList<Field> fields = ((Variable) par
49       var f = (Field) fields.get(index);
50       Object parentValue = ((Variable) parent)
51       try
52       {
53          return new Variable(f.getType(), f.get
54       }
55       catch (IllegalAccessException e)
56       {
57          return null;
58       }
59    }
60
61    public int getIndexOfChild(Object parent, Ob
62    {
63       int n = getChildCount(parent);
64       for (int i = 0; i < n; i++)
```

```
65          if (getChild(parent, i).equals(child))
66       return -1;
67    }
68
69    public boolean isLeaf(Object node)
70    {
71       return getChildCount(node) == 0;
72    }
73
74    public void valueForPathChanged(TreePath pat
75    {
76    }
77
78    public void addTreeModelListener(TreeModelLi
79    {
80       listenerList.add(TreeModelListener.class,
81    }
82
83    public void removeTreeModelListener(TreeMode
84    {
85       listenerList.remove(TreeModelListener.cla
86    }
87
88    protected void fireTreeStructureChanged(Obje
89    {
90       var event = new TreeModelEvent(this, new
91       for (TreeModelListener l : listenerList.g
```

```
92            l.treeStructureChanged(event);
93      }
94   }
```

Listing 1.14 treeModel/Variable.java

```
1  package treeModel;
2
3  import java.lang.reflect.*;
4  import java.util.*;
5
6  /**
7   * A variable with a type, name, and value.
8   */
9  public class Variable
10 {
11    private Class<?> type;
12    private String name;
13    private Object value;
14    private ArrayList<Field> fields;
15
16    /**
17     * Construct a variable.
18     * @param aType the type
19     * @param aName the name
20     * @param aValue the value
21     */
22    public Variable(Class<?> aType, String aName
```

```
23    {
24       type = aType;
25       name = aName;
26       value = aValue;
27       fields = new ArrayList<>();
28
29       // find all fields if we have a class typ
30       // null values
31
32       if (!type.isPrimitive() && !type.isArray(
33             && value != null)
34       {
35          // get fields from the class and all s
36          for (Class<?> c = value.getClass(); c
37          {
38             Field[] fs = c.getDeclaredFields();
39             AccessibleObject.setAccessible(fs,
40
41             // get all nonstatic fields
42             for (Field f : fs)
43                if (!Modifier.isStatic(f.getModi
44          }
45       }
46    }
47
48    /**
49     * Gets the value of this variable.
50     * @return the value
```

```
51       */
52      public Object getValue()
53      {
54         return value;
55      }
56
57      /**
58       * Gets all nonstatic fields of this variabl
59       * @return an array list of variables descri
60       */
61      public ArrayList<Field> getFields()
62      {
63         return fields;
64      }
65
66      public String toString()
67      {
68         String r = type + " " + name;
69         if (type.isPrimitive()) r += "=" + value;
70         else if (type.equals(String.class)) r +=
71         else if (value == null) r += "=null";
72         return r;
73      }
74   }
```

`javax.swing.tree.TreeModel` **1.2**

- `Object getRoot()`
  returns the root node.
- `int getChildCount(Object parent)`
  gets the number of children of the `parent` node.
- `Object getChild(Object parent, int index)`
  gets the child node of the `parent` node at the given index.
- `int getIndexOfChild(Object parent, Object child)`
  gets the index of the `child` node in the `parent` node, or `-1` if `child` is not a child of `parent` in this tree model.
- `boolean isLeaf(Object node)`
  returns `true` if `node` is conceptually a leaf of the tree.
- `void addTreeModelListener(TreeModelListener l)`
- `void removeTreeModelListener(TreeModelListener l)`
  add or remove listeners that are notified when the information in the tree model changes.
- `void valueForPathChanged(TreePath path, Object newValue)`
  is called when a cell editor has modified the value of a node.

`javax.swing.event.TreeModelListener` 1.2

- `void treeNodesChanged(TreeModelEvent e)`
- `void treeNodesInserted(TreeModelEvent e)`
- `void treeNodesRemoved(TreeModelEvent e)`
- `void treeStructureChanged(TreeModelEvent e)`

are called by the tree model when the tree has been modified.

`javax.swing.event.TreeModelEvent` 1.2

- `TreeModelEvent(Object eventSource, TreePath node)`

constructs a tree model event.

1.5. Advanced AWT

You can use the methods of the `Graphics` class to create simple drawings. Those methods are sufficient for simple applications, but they fall short when you need to create complex shapes or require complete control over the appearance of the graphics. The Java 2D API is a more sophisticated class library that you can use to produce high-quality drawings. In the following sections, I'll give you an overview of that API.

1.5.1. The Rendering Pipeline

The original JDK 1.0 had a very simple mechanism for drawing shapes. You selected color and paint mode, and called methods of the `Graphics` class such as `drawRect` or `fillOval`. The Java 2D API supports many more options.

- You can easily produce a wide variety of *shapes.*
- You have control over the *stroke*—the pen that traces shape boundaries.
- You can *fill* shapes with solid colors, varying hues, and repeating patterns.
- You can use *transformations* to move, scale, rotate, or stretch shapes.
- You can *clip* shapes to restrict them to arbitrary areas.
- You can select *composition rules* to describe how to combine the pixels of a new shape with existing pixels.

To draw a shape, go through the following steps:

1. Obtain an object of the `Graphics2D` class. This class is a subclass of the `Graphics` class. Ever since Java 1.2, methods such as `paint` and `paintComponent` automatically receive an object of the `Graphics2D` class. Simply use a cast, as follows:

```
public void paintComponent(Graphics g)
{
   var g2 = (Graphics2D) g;
   . . .
}
```

2. Use the `setRenderingHints` method to set *rendering hints*—trade-offs between speed and drawing quality.

```
RenderingHints hints = . . .;
g2.setRenderingHints(hints);
```

3. Use the `setStroke` method to set the *stroke.* The stroke draws the outline of the shape. You can select the thickness and choose among solid and dotted lines.

```
Stroke stroke = . . .;
g2.setStroke(stroke);
```

4. Use the `setPaint` method to set the *paint.* The paint fills areas such as the stroke or the interior of a shape. You can create solid color paint, paint with changing hues, or tiled fill patterns.

```
Paint paint = . . .;
```

```
g2.setPaint(paint);
```

5. Use the `clip` method to set the *clipping region*.

```
Shape clip = . . .;
g2.clip(clip);
```

6. Use the `transform` method to set a *transformation* from user space to device space. Use transformations if it is easier for you to define your shapes in a custom coordinate system than by using pixel coordinates.

```
AffineTransform transform = . . .;
g2.transform(transform);
```

7. Use the `setComposite` method to set a *composition rule* that describes how to combine the new pixels with the existing pixels.

```
Composite composite = . . .;
g2.setComposite(composite);
```

8. Create a shape. The Java 2D API supplies many shape objects and methods to combine shapes.

```
Shape shape = . . .;
```

9. Draw or fill the shape. If you draw the shape, its outline is stroked. If you fill the shape, the interior is painted.

```
g2.draw(shape);
g2.fill(shape);
```

Of course, in many practical circumstances, you don't need all these steps. There are reasonable defaults for the settings of the 2D graphics context; change the settings only if you want to deviate from the defaults.

In the following sections, you will see how to describe shapes, strokes, paints, transformations, and composition rules.

The various `set` methods simply set the state of the 2D graphics context. They don't cause any drawing. Similarly, when you construct `Shape` objects, no drawing takes place. A shape is only rendered when you call `draw` or `fill`. At that time, the new shape is computed in a *rendering pipeline* (see Figure 12.31).



Figure 1.31: The rendering pipeline

In the rendering pipeline, the following steps take place to render a shape:

1. The path of the shape is stroked.
2. The shape is transformed.
3. The shape is clipped. If there is no intersection between the shape and the clipping area, the process stops.
4. The remainder of the shape after clipping is filled.
5. The pixels of the filled shape are composed with the existing pixels. (In Figure 12.31, the circle is part of the existing pixels, and the cup shape is superimposed over it.)

In the next section, you will see how to define shapes. Then, we will turn to the 2D graphics context settings.

`java.awt.Graphics2D` **1.2**

- `void draw(Shape s)`
  draws the outline of the given shape with the current paint.

- `void fill(Shape s)`
  fills the interior of the given shape with the current paint.

1.5.2. The `Shape` Class Hierarchy

Here are some of the methods in the `Graphics` class to draw shapes:

```
drawLine
drawRectangle
drawRoundRect
draw3DRect
drawPolygon
drawPolyline
drawOval
drawArc
```

There are also corresponding `fill` methods. These methods have been in the `Graphics` class ever since JDK 1.0. The Java 2D API uses a completely different, object-oriented approach. Instead of methods, there are classes:

```
Line2D
Rectangle2D
RoundRectangle2D
Ellipse2D
Arc2D
```

```
QuadCurve2D
CubicCurve2D
GeneralPath
```

These classes all implement the `Shape` interface, which we will examine in the following sections.

The `Line2D`, `Rectangle2D`, `RoundRectangle2D`, `Ellipse2D`, and `Arc2D` classes correspond to the `drawLine`, `drawRectangle`, `drawRoundRect`, `drawOval`, and `drawArc` methods. (The concept of a "3D rectangle" has died the death it so richly deserved—there is no analog to the `draw3DRect` method.) The Java 2D API supplies two additional classes, quadratic and cubic curves, that we will discuss in this section. There is no `Polygon2D` class; instead, the `GeneralPath` class describes paths made up from lines, quadratic and cubic curves. You can use a `GeneralPath` to describe a polygon; we'll show you how later in this section.

To draw a shape, first create an object of a class that implements the `Shape` interface and then call the `draw` method of the `Graphics2D` class.

The classes

```
Rectangle2D
RoundRectangle2D
Ellipse2D
Arc2D
```

all inherit from a common superclass `RectangularShape`. Admittedly, ellipses and arcs are not rectangular, but they have a *bounding rectangle* (see Figure 12.32).



Figure 1.32: The bounding rectangle of an ellipse and an arc

Each of the classes with a name ending in "2D" has two subclasses for specifying coordinates as `float` or `double` quantities. In Volume I, you already encountered `Rectangle2D.Float` and `Rectangle2D.Double`.

The same scheme is used for the other classes, such as `Arc2D.Float` and `Arc2D.Double`.

Internally, all graphics classes use `float` coordinates because `float` numbers use less storage space but have sufficient precision for geometric computations. However, the Java programming language makes it a bit more tedious to manipulate `float` numbers. For that reason, most methods of the graphics classes use `double` parameters and return values. Only when constructing a 2D object you need to choose between the constructors with `float` and `double` coordinates. For example,

```
var floatRect = new Rectangle2D.Float(5F, 10F, 7.5F,
var doubleRect = new Rectangle2D.Double(5, 10, 7.5, 1
```

The *Xxx*`2D.Float` and *Xxx*`2D.Double` classes are subclasses of the *Xxx*`2D` classes. After object construction, essentially no benefit accrues from remembering the subclass, and you can just store the constructed object in a superclass variable as in the code example above.

As you can see from the curious names, the *Xxx*`2D.Float` and *Xxx*`2D.Double` classes are also inner classes of the *Xxx*`2D` classes. That is just a minor syntactical convenience to avoid inflation of outer class names.

Finally, the `Point2D` class describes a point with an *x* and a *y* coordinate. Points are used to define shapes, but they aren't themselves shapes.

Figure 12.33 shows the relationships between the shape classes. However, the `Double` and `Float` subclasses are omitted. Legacy classes from the pre-2D library are marked with a gray fill.



Figure 1.33: Relationships between the shape classes

1.5.3. Constructing Shapes

You already saw how to use the `Rectangle2D`, `Ellipse2D`, and `Line2D` classes in Chapter 10. In this section, you will learn how to work with the remaining 2D shapes.

For the `RoundRectangle2D` shape, specify the top left corner, width, height, and the *x* and *y* dimensions of the corner area that should be rounded (see Figure 12.34). For example, the call

```
var r = new RoundRectangle2D.Double(150, 200, 100, 50
```

produces a rounded rectangle with circles of radius 20 at each of the corners.



Figure 1.34: Constructing a `RoundRectangle2D`

To construct an arc, specify the bounding box, the start angle, the angle swept out by the arc (see Figure 12.35), and the closure type —one of `Arc2D.OPEN`, `Arc2D.PIE`, or `Arc2D.CHORD`.

```
var a = new Arc2D(x, y, width, height, startAngle, ar
```



Figure 1.35: Constructing an elliptical arc

Figure 12.36 illustrates the arc types.



Figure 1.36: Arc types

Caution: If the arc is elliptical, the computation of the arc angles is not at all straightforward. The API documentation states: "The angles are specified relative to the nonsquare framing rectangle such that 45 degrees always falls on the line from the center of the ellipse to the upper right corner of the framing rectangle. As a result, if the framing rectangle is noticeably longer along one axis than the other, the angles to the start and end of the arc segment will be skewed farther along the longer axis of the frame." Unfortunately, the

documentation is silent on how to compute this "skew." Here are the details:

Suppose the center of the arc is the origin and the point `(x, y)` lies on the arc. You can get a skewed angle with the following formula:

```
skewedAngle = Math.toDegrees(Math.atan2(-y * height,
```

The result is a value between `-180` and `180`. Compute the skewed start and end angles in this way. Then, compute the difference between the two skewed angles. If the start angle or the difference is negative, add `360` to the start angle. Then, supply the start angle and the difference to the arc constructor.

If you run the example program at the end of this section, you can visually check that this calculation yields the correct values for the arc constructor (see Figure 12.39).

The Java 2D API supports *quadratic* and *cubic* curves. In this chapter, we do not get into the mathematics of these curves. You can get a feel for how the curves look by running the program in Listing 12.15. Quadratic curves are specified by two *end points* and a *control point* (see Figure 12.37). Cubic curves (Figure 12.38) have

two control points. Moving the control points changes the shape of the curves.



Figure 1.37: A quadratic curve



Figure 1.38: A cubic curve

To construct quadratic and cubic curves, give the coordinates of the end points and the control points. For example,

```
var q = new QuadCurve2D.Double(startX, startY, contro
var c = new CubicCurve2D.Double(startX, startY, contr
   control2X, control2Y, endX, endY);
```

Quadratic curves are not very flexible, and they are not commonly used in practice. Cubic curves (such as the Bézier curves drawn by the `CubicCurve2D` class) are, however, very common. By combining many cubic curves so that the slopes at the connection points match, you can create complex, smooth-looking curved shapes. For more information, refer to *Computer Graphics: Principles and Practice, Third Edition*, by John F. Hughes et al.

You can build arbitrary sequences of line segments, quadratic curves, and cubic curves, and store them in a `GeneralPath` object. Specify the first coordinate of the path with the `moveTo` method, for example:

```
var path = new GeneralPath();
path.moveTo(10, 20);
```

You can then extend the path by calling one of the methods `lineTo`, `quadTo`, or `curveTo`. These methods extend the path by a line, a quadratic curve, or a cubic curve. To call `lineTo`, supply

the end point. For the two curve methods, supply the control points, then the end point. For example,

```
path.lineTo(20, 30);
path.curveTo(control1X, control1Y, control2X, control
```

Close the path by calling the `closePath` method. It draws a straight line back to the starting point of the path.

To make a polygon, simply call `moveTo` to go to the first corner point, followed by repeated calls to `lineTo` to visit the other corner points. Finally, call `closePath` to close the polygon. The program in Listing 12.15 shows this in more detail.

A general path does not have to be connected. You can call `moveTo` at any time to start a new path segment.

Finally, you can use the `append` method to add arbitrary `Shape` objects to a general path. The outline of the shape is added to the end to the path. The second parameter of the `append` method is `true` if the new shape should be connected to the last point on the path, `false` otherwise. For example, the call

```
Rectangle2D r = . . .;
```

```
path.append(r, false);
```

appends the outline of a rectangle to the path without connecting it to the existing path. But

```
path.append(r, true);
```

adds a straight line from the end point of the path to the starting point of the rectangle, and then adds the rectangle outline to the path.

The program in Listing 12.15 lets you create sample paths. Pick a shape maker from the combo box. The program contains shape makers for

- Straight lines
- Rectangles, rounded rectangles, and ellipses
- Arcs (showing lines for the bounding rectangle and the start and end angles, in addition to the arc itself)
- Polygons (using a `GeneralPath`)
- Quadratic and cubic curves

Use the mouse to adjust the control points. As you move them, the shape continuously repaints itself.

The program is a bit complex because it handles multiple shapes and supports dragging of the control points.

An abstract superclass `ShapeMaker` encapsulates the commonality of the shape maker classes. Each shape has a fixed number of control points that the user can move around. The `getPointCount` method returns that value. The abstract method

```
Shape makeShape(Point2D[] points)
```

computes the actual shape, given the current positions of the control points. The `toString` method returns the class name so that the `ShapeMaker` objects can simply be dumped into a `JComboBox`.

To enable dragging of the control points, the `ShapePanel` class handles both mouse and mouse motion events. If the mouse is pressed on top of a rectangle, subsequent mouse drags move the rectangle.

The majority of the shape maker classes are simple—their `makeShape` methods just construct and return the requested shapes. However, the `ArcMaker` class needs to compute the distorted start and end angles. Furthermore, to demonstrate that the computation is indeed correct, the returned shape is a `GeneralPath` containing the arc itself, the bounding rectangle, and

the lines from the center of the arc to the angle control points (see Figure 12.39).



Figure 1.39: The `ShapeTest` program

Listing 1.15 shape/ShapeTest.java

```
1  package shape;
2
3  import java.awt.*;
4  import java.awt.event.*;
5  import java.awt.geom.*;
6  import java.util.*;
```

```
 7 import java.util.random.*;
 8 import javax.swing.*;
 9
10 /**
11  * This program demonstrates the various 2D sha
12  * @version 1.05 2023-08-29
13  * @author Cay Horstmann
14  */
15 public class ShapeTest
16 {
17    public static void main(String[] args)
18    {
19       EventQueue.invokeLater(() ->
20          {
21             var frame = new ShapeTestFrame();
22             frame.setTitle("ShapeTest");
23             frame.setDefaultCloseOperation(JFra
24             frame.setVisible(true);
25          });
26    }
27 }
28
29 /**
30  * This frame contains a combo box to select a
31  */
32 class ShapeTestFrame extends JFrame
33 {
34    public ShapeTestFrame()
```

```
35    {
36       var comp = new ShapeComponent();
37       add(comp, BorderLayout.CENTER);
38       var comboBox = new JComboBox<ShapeMaker>(
39       comboBox.addItem(new LineMaker());
40       comboBox.addItem(new RectangleMaker());
41       comboBox.addItem(new RoundRectangleMaker(
42       comboBox.addItem(new EllipseMaker());
43       comboBox.addItem(new ArcMaker());
44       comboBox.addItem(new PolygonMaker());
45       comboBox.addItem(new QuadCurveMaker());
46       comboBox.addItem(new CubicCurveMaker());
47       comboBox.addActionListener(event ->
48          {
49             ShapeMaker shapeMaker = comboBox.ge
50             comp.setShapeMaker(shapeMaker);
51          });
52       add(comboBox, BorderLayout.NORTH);
53       comp.setShapeMaker((ShapeMaker) comboBox
54       pack();
55    }
56 }
57
58 /**
59  * This component draws a shape and allows the
60  */
61 class ShapeComponent extends JComponent
62 {
```

```
63    private static final Dimension PREFERRED_SIZ
64    private Point2D[] points;
65    private static RandomGenerator generator = R
66    private static int SIZE = 10;
67    private int current;
68    private ShapeMaker shapeMaker;
69
70    public ShapeComponent()
71    {
72       addMouseListener(new MouseAdapter()
73          {
74             public void mousePressed(MouseEvent
75             {
76                Point p = event.getPoint();
77                for (int i = 0; i < points.lengt
78                {
79                   double x = points[i].getX() -
80                   double y = points[i].getY() -
81                   var r = new Rectangle2D.Doubl
82                   if (r.contains(p))
83                   {
84                      current = i;
85                      return;
86                   }
87                }
88             }
89
90             public void mouseReleased(MouseEver
```

```
91              {
92                 current = -1;
93              }
94           });
95        addMouseMotionListener(new MouseMotionAda
96           {
97              public void mouseDragged(MouseEvent
98              {
99                 if (current == -1) return;
100                points[current] = event.getPoint
101                repaint();
102             }
103          });
104       current = -1;
105    }
106
107    /**
108     * Set a shape maker and initialize it with
109     * @param aShapeMaker a shape maker that def
110     */
111    public void setShapeMaker(ShapeMaker aShapeM
112    {
113       shapeMaker = aShapeMaker;
114       int n = shapeMaker.getPointCount();
115       points = new Point2D[n];
116       for (int i = 0; i < n; i++)
117       {
118          double x = generator.nextDouble() * ge
```

```
119             double y = generator.nextDouble() * ge
120             points[i] = new Point2D.Double(x, y);
121          }
122          repaint();
123       }
124
125       public void paintComponent(Graphics g)
126       {
127          if (points == null) return;
128          var g2 = (Graphics2D) g;
129          for (int i = 0; i < points.length; i++)
130          {
131             double x = points[i].getX() - SIZE / 2
132             double y = points[i].getY() - SIZE / 2
133             g2.fill(new Rectangle2D.Double(x, y, S
134          }
135
136          g2.draw(shapeMaker.makeShape(points));
137       }
138
139       public Dimension getPreferredSize() { return
140    }
141
142    /**
143     * A shape maker can make a shape from a point
144     * the makeShape method.
145     */
146    abstract class ShapeMaker
```

```
147 {
148    private int pointCount;
149
150    /**
151     * Constructs a shape maker.
152     * @param pointCount the number of points ne
153     */
154    public ShapeMaker(int pointCount)
155    {
156       this.pointCount = pointCount;
157    }
158
159    /**
160     * Gets the number of points needed to defin
161     * @return the point count
162     */
163    public int getPointCount()
164    {
165       return pointCount;
166    }
167
168    /**
169     * Makes a shape out of the given point set
170     * @param p the points that define the shape
171     * @return the shape defined by the points
172     */
173    public abstract Shape makeShape(Point2D[] p)
174
```

```
175     public String toString()
176     {
177        return getClass().getName();
178     }
179  }
180
181  /**
182   * Makes a line that joins two given points.
183   */
184  class LineMaker extends ShapeMaker
185  {
186     public LineMaker()
187     {
188        super(2);
189     }
190
191     public Shape makeShape(Point2D[] p)
192     {
193        return new Line2D.Double(p[0], p[1]);
194     }
195  }
196
197  /**
198   * Makes a rectangle that joins two given corne
199   */
200  class RectangleMaker extends ShapeMaker
201  {
202     public RectangleMaker()
```

```
203    {
204       super(2);
205    }
206
207    public Shape makeShape(Point2D[] p)
208    {
209       var s = new Rectangle2D.Double();
210       s.setFrameFromDiagonal(p[0], p[1]);
211       return s;
212    }
213 }
214
215 /**
216  * Makes a round rectangle that joins two given
217  */
218 class RoundRectangleMaker extends ShapeMaker
219 {
220    public RoundRectangleMaker()
221    {
222       super(2);
223    }
224
225    public Shape makeShape(Point2D[] p)
226    {
227       var s = new RoundRectangle2D.Double(0, 0,
228       s.setFrameFromDiagonal(p[0], p[1]);
229       return s;
230    }
```

```
231 }
232
233 /**
234  * Makes an ellipse contained in a bounding box
235  */
236 class EllipseMaker extends ShapeMaker
237 {
238    public EllipseMaker()
239    {
240       super(2);
241    }
242
243    public Shape makeShape(Point2D[] p)
244    {
245       var s = new Ellipse2D.Double();
246       s.setFrameFromDiagonal(p[0], p[1]);
247       return s;
248    }
249 }
250
251 /**
252  * Makes an arc contained in a bounding box wit
253  * and ending angles given by lines emanating f
254  * in two given points. To show the correctness
255  * contains the arc, the bounding box, and the
256  */
257 class ArcMaker extends ShapeMaker
258 {
```

```
259    public ArcMaker()
260    {
261       super(4);
262    }
263
264    public Shape makeShape(Point2D[] p)
265    {
266       double centerX = (p[0].getX() + p[1].getX
267       double centerY = (p[0].getY() + p[1].getY
268       double width = Math.abs(p[1].getX() - p[0
269       double height = Math.abs(p[1].getY() - p[
270
271       double skewedStartAngle = Math.toDegrees(
272          (p[2].getX() - centerX) * height));
273       double skewedEndAngle = Math.toDegrees(Ma
274          (p[3].getX() - centerX) * height));
275       double skewedAngleDifference = skewedEndA
276       if (skewedStartAngle < 0) skewedStartAngl
277       if (skewedAngleDifference < 0) skewedAngl
278
279       var s = new Arc2D.Double(0, 0, 0, 0,
280          skewedStartAngle, skewedAngleDifferenc
281       s.setFrameFromDiagonal(p[0], p[1]);
282
283       var g = new GeneralPath();
284       g.append(s, false);
285       var r = new Rectangle2D.Double();
286       r.setFrameFromDiagonal(p[0], p[1]);
```

```
      g.append(r, false);
      var center = new Point2D.Double(centerX,
      g.append(new Line2D.Double(center, p[2]),
      g.append(new Line2D.Double(center, p[3]),
      return g;
   }
}

/**
 * Makes a polygon defined by six corner points
 */
class PolygonMaker extends ShapeMaker
{
   public PolygonMaker()
   {
      super(6);
   }

   public Shape makeShape(Point2D[] p)
   {
      var s = new GeneralPath();
      s.moveTo((float) p[0].getX(), (float) p[0
      for (int i = 1; i < p.length; i++)
         s.lineTo((float) p[i].getX(), (float)
      s.closePath();
      return s;
   }
}
```

```
315
316 /**
317  * Makes a quad curve defined by two end points
318  */
319 class QuadCurveMaker extends ShapeMaker
320 {
321    public QuadCurveMaker()
322    {
323       super(3);
324    }
325
326    public Shape makeShape(Point2D[] p)
327    {
328       return new QuadCurve2D.Double(p[0].getX()
329          p[2].getX(), p[2].getY());
330    }
331 }
332
333 /**
334  * Makes a cubic curve defined by two end point
335  */
336 class CubicCurveMaker extends ShapeMaker
337 {
338    public CubicCurveMaker()
339    {
340       super(4);
341    }
342
```

```
343     public Shape makeShape(Point2D[] p)
344     {
345        return new CubicCurve2D.Double(p[0].getX(
346           p[2].getX(), p[2].getY(), p[3].getX(),
347     }
348  }
```

`java.awt.geom.RoundRectangle2D.Double` **1.2**

- `RoundRectangle2D.Double(double x, double y, double width, double height, double arcWidth, double arcHeight)`
  constructs a rounded rectangle with the given bounding rectangle and arc dimensions. See Figure 12.34 for an explanation of the `arcWidth` and `arcHeight` parameters.

`java.awt.geom.Arc2D.Double` **1.2**

- `Arc2D.Double(double x, double y, double w, double h, double startAngle, double arcAngle, int type)`
  constructs an arc with the given bounding rectangle, start and arc angle, and arc type. The `startAngle` and `arcAngle` are shown in Figure 12.35. The type is one of `Arc2D.OPEN`, `Arc2D.PIE`, and `Arc2D.CHORD`.

`java.awt.geom.QuadCurve2D.Double` **1.2**

- `QuadCurve2D.Double(double x1, double y1, double ctrlx, double ctrly, double x2, double y2)`
  constructs a quadratic curve from a start point, a control point, and an end point.

`java.awt.geom.CubicCurve2D.Double` **1.2**

- `CubicCurve2D.Double(double x1, double y1, double ctrlx1, double ctrly1, double ctrlx2, double ctrly2, double x2, double y2)`
  constructs a cubic curve from a start point, two control points, and an end point.

`java.awt.geom.GeneralPath` **1.2**

- `GeneralPath()`
  constructs an empty general path.

`java.awt.geom.Path2D.Float` **6**

- `void moveTo(float x, float y)`
  makes (`x` , `y`) the *current point*—that is, the starting point of the next segment.

- `void lineTo(float x, float y)`
- `void quadTo(float ctrlx, float ctrly, float x, float y)`
- `void curveTo(float ctrl1x, float ctrl1y, float ctrl2x, float ctrl2y, float x, float y)`
  draw a line, quadratic curve, or cubic curve from the current point to the end point (`x` , `y`), and make that end point the current point.

`java.awt.geom.Path2D` **6**

- `void append(Shape s, boolean connect)`
  adds the outline of the given shape to the general path. If `connect` is `true` , the current point of the general path is connected to the starting point of the added shape by a straight line.
- `void closePath()`
  closes the path by drawing a straight line from the current point to the first point in the path.

1.5.4. Areas

In the preceding section, you saw how you can specify complex shapes by constructing general paths composed of lines and curves. By using a sufficient number of lines and curves, you can draw essentially any shape. For example, the shapes of characters in the

fonts that you see on the screen and on your printouts are made up of lines and quadratic or cubic curves.

Occasionally, it is easier to describe a shape by composing it from *areas,* such as rectangles, polygons, or ellipses. The Java 2D API supports four *constructive area geometry* operations that combine two areas into a new area.

- `add` : The combined area contains all points that are in the first or the second area.
- `subtract` : The combined area contains all points that are in the first but not the second area.
- `intersect` : The combined area contains all points that are in the first and the second area.
- `exclusiveOr` : The combined area contains all points that are in either the first or the second area, but not in both.

Figure 12.40 shows these operations.



Figure 1.40: Constructive area geometry operations

To construct a complex area, start with a default area object.

```
var a = new Area();
```

Then, combine the area with any shape.

```
a.add(new Rectangle2D.Double(. . .));
a.subtract(path);
. . .
```

The `Area` class implements the `Shape` interface. You can stroke the boundary of the area with the `draw` method or paint the interior with the `fill` method of the `Graphics2D` class.

`java.awt.geom.Area`

- `void add(Area other)`
- `void subtract(Area other)`
- `void intersect(Area other)`
- `void exclusiveOr(Area other)`

  carry out the constructive area geometry operation with this area and the other area and set this area to the result.

1.5.5. Strokes

The `draw` operation of the `Graphics2D` class draws the boundary of a shape by using the currently selected *stroke.* By default, the stroke is a solid line that is 1 pixel wide. You can select a different stroke by calling the `setStroke` method and supplying an object of a class that implements the `Stroke` interface. The Java 2D API defines only one such class, called `BasicStroke`. In this section, we'll look at the capabilities of the `BasicStroke` class.

You can construct strokes of arbitrary thickness. For example, here is how to draw lines that are 10 pixels wide:

```
g2.setStroke(new BasicStroke(10.0F));
g2.draw(new Line2D.Double(. . .));
```

When a stroke is more than a pixel thick, the *end* of the stroke can have different styles. Figure 12.41 shows these so-called end cap styles. You have three choices:

- A *butt cap* simply ends the stroke at its end point.
- A *round cap* adds a half-circle to the end of the stroke.
- A *square cap* adds a half-square to the end of the stroke.



Figure 1.41: End cap styles

When two thick strokes meet, there are three choices for the *join style* (see Figure 12.42).

- A *bevel join* joins the strokes with a straight line that is perpendicular to the bisector of the angle between the two strokes.
- A *round join* extends each stroke to have a round cap.
- A *miter join* extends both strokes by adding a "spike."



Figure 1.42: Join styles

If two lines come together in a miter join at a very small angle, a bevel join is used instead, preventing extremely long spikes. The *miter limit* controls this transition. Technically, this is the ratio of the distance of the inner and outer corners of the spike divided by the

stroke width. The default miter limit of 10 corresponds to an angle of about 11 degrees.

You can specify these choices in the `BasicStroke` constructor, for example:

```
g2.setStroke(new BasicStroke(10.0F, BasicStroke.CAP_R
g2.setStroke(new BasicStroke(10.0F, BasicStroke.CAP_B
   15.0F /* miter limit */));
```

Finally, you can create dashed lines by setting a *dash pattern.* In the program in Listing 12.16, you can select a dash pattern that spells out SOS in Morse code. The dash pattern is a `float[]` array that contains the lengths of the "on" and "off" intervals (see Figure 12.43).



Figure 1.43: A dash pattern

You can specify the dash pattern and a *dash phase* when constructing the `BasicStroke`. The dash phase indicates where in

the dash pattern each line should start. A segment of this length, preceding the starting point of the stroke, is assumed to have the dash pattern already applied. Normally, you set this value to `0`.

```
float[] dashPattern = { 10, 10, 10, 10, 10, 10, 30, 1
g2.setStroke(new BasicStroke(10.0F, BasicStroke.CAP_B
   10.0F /* miter limit */, dashPattern, 0 /* dash ph
```

Note: End cap styles are applied to the ends of *each dash* in a dash pattern.

The program in Listing 12.16 lets you specify end cap styles, join styles, and dashed lines (see Figure 12.44). You can move the ends of the line segments to test the miter limit: Select the miter join, then move the line segment to form a very acute angle. You will see the miter join turn into a bevel join.



Figure 1.44: The `StrokeTest` program

The program is similar to the program in Listing 12.15. The mouse listener remembers your click on the end point of a line segment, and the mouse motion listener monitors the dragging of the end point. A set of radio buttons signal the user choices for the end cap style, join style, and solid or dashed line. The `paintComponent` method of the `StrokePanel` class constructs a `GeneralPath` consisting of the two line segments that join the three points which the user can move with the mouse. It then constructs a `BasicStroke`, according to the selections the user made, and finally draws the path.

Listing 1.16 stroke/StrokeTest.java

```
1  package stroke;
2
3  import java.awt.*;
4  import java.awt.event.*;
5  import java.awt.geom.*;
6  import javax.swing.*;
7
8  /**
9   * This program demonstrates different stroke t
10  * @version 1.05 2018-05-01
11  * @author Cay Horstmann
12  */
13 public class StrokeTest
14 {
15    public static void main(String[] args)
16    {
17       EventQueue.invokeLater(() ->
18          {
19             var frame = new StrokeTestFrame();
20             frame.setTitle("StrokeTest");
21             frame.setDefaultCloseOperation(JFra
22             frame.setVisible(true);
23          });
24    }
25 }
26
```

```
27 /**
28  * This frame lets the user choose the cap, joi
29  * stroke.
30  */
31 class StrokeTestFrame extends JFrame
32 {
33    private StrokeComponent canvas;
34    private JPanel buttonPanel;
35
36    public StrokeTestFrame()
37    {
38       canvas = new StrokeComponent();
39       add(canvas, BorderLayout.CENTER);
40
41       buttonPanel = new JPanel();
42       buttonPanel.setLayout(new GridLayout(3, 3
43       add(buttonPanel, BorderLayout.NORTH);
44
45       var group1 = new ButtonGroup();
46       makeCapButton("Butt Cap", BasicStroke.CAP
47       makeCapButton("Round Cap", BasicStroke.CA
48       makeCapButton("Square Cap", BasicStroke.C
49
50       var group2 = new ButtonGroup();
51       makeJoinButton("Miter Join", BasicStroke
52       makeJoinButton("Bevel Join", BasicStroke
53       makeJoinButton("Round Join", BasicStroke
54
```

```
55          var group3 = new ButtonGroup();
56          makeDashButton("Solid Line", false, group
57          makeDashButton("Dashed Line", true, group
58       }
59
60       /**
61        * Makes a radio button to change the cap st
62        * @param label the button label
63        * @param style the cap style
64        * @param group the radio button group
65        */
66       private void makeCapButton(String label, fin
67       {
68          // select first button in group
69          boolean selected = group.getButtonCount()
70          var button = new JRadioButton(label, sele
71          buttonPanel.add(button);
72          group.add(button);
73          button.addActionListener(event -> canvas
74          pack();
75       }
76
77       /**
78        * Makes a radio button to change the join s
79        * @param label the button label
80        * @param style the join style
81        * @param group the radio button group
82        */
```

```
83     private void makeJoinButton(String label, fi
84     {
85        // select first button in group
86        boolean selected = group.getButtonCount()
87        var button = new JRadioButton(label, sele
88        buttonPanel.add(button);
89        group.add(button);
90        button.addActionListener(event -> canvas
91     }
92
93     /**
94      * Makes a radio button to set solid or dash
95      * @param label the button label
96      * @param style false for solid, true for da
97      * @param group the radio button group
98      */
99     private void makeDashButton(String label, fi
100    {
101       // select first button in group
102       boolean selected = group.getButtonCount()
103       var button = new JRadioButton(label, sele
104       buttonPanel.add(button);
105       group.add(button);
106       button.addActionListener(event -> canvas
107    }
108 }
109
110 /**
```

```
111  * This component draws two joined lines, using
112  * to drag the three points defining the lines
113  */
114 class StrokeComponent extends JComponent
115 {
116    private static final Dimension PREFERRED_SIZ
117    private static int SIZE = 10;
118
119    private Point2D[] points;
120    private int current;
121    private float width;
122    private int cap;
123    private int join;
124    private boolean dash;
125
126    public StrokeComponent()
127    {
128       addMouseListener(new MouseAdapter()
129          {
130             public void mousePressed(MouseEvent
131             {
132                Point p = event.getPoint();
133                for (int i = 0; i < points.lengt
134                {
135                   double x = points[i].getX() -
136                   double y = points[i].getY() -
137                   var r = new Rectangle2D.Doubl
138                   if (r.contains(p))
```

```
139                  {
140                     current = i;
141                     return;
142                  }
143               }
144            }
145
146            public void mouseReleased(MouseEver
147            {
148               current = -1;
149            }
150         });
151
152      addMouseMotionListener(new MouseMotionAda
153         {
154            public void mouseDragged(MouseEvent
155            {
156               if (current == -1) return;
157               points[current] = event.getPoint
158               repaint();
159            }
160         });
161
162      points = new Point2D[3];
163      points[0] = new Point2D.Double(200, 100);
164      points[1] = new Point2D.Double(100, 200);
165      points[2] = new Point2D.Double(200, 200);
166      current = -1;
```

```
167         width = 8.0F;
168      }
169
170      public void paintComponent(Graphics g)
171      {
172         var g2 = (Graphics2D) g;
173         var path = new GeneralPath();
174         path.moveTo((float) points[0].getX(), (fl
175         for (int i = 1; i < points.length; i++)
176            path.lineTo((float) points[i].getX(),
177         BasicStroke stroke;
178         if (dash)
179         {
180            float miterLimit = 10.0F;
181            float[] dashPattern = { 10F, 10F, 10F,
182                  10F, 10F, 10F, 10F, 10F, 30F };
183            float dashPhase = 0;
184            stroke = new BasicStroke(width, cap, j
185         }
186         else stroke = new BasicStroke(width, cap,
187         g2.setStroke(stroke);
188         g2.draw(path);
189      }
190
191      /**
192       * Sets the join style.
193       * @param j the join style
194       */
```

```
195     public void setJoin(int j)
196     {
197        join = j;
198        repaint();
199     }
200
201     /**
202      * Sets the cap style.
203      * @param c the cap style
204      */
205     public void setCap(int c)
206     {
207        cap = c;
208        repaint();
209     }
210
211     /**
212      * Sets solid or dashed lines.
213      * @param d false for solid, true for dashed
214      */
215     public void setDash(boolean d)
216     {
217        dash = d;
218        repaint();
219     }
```

```
220
221     public Dimension getPreferredSize() { return
222 }
```

`java.awt.Graphics2D` **1.2**

- `void setStroke(Stroke s)`
  sets the stroke of this graphics context to the given object that implements the `Stroke` interface.

`java.awt.BasicStroke` **1.2**

- `BasicStroke(float width)`
- `BasicStroke(float width, int cap, int join)`
- `BasicStroke(float width, int cap, int join, float miterlimit)`
- `BasicStroke(float width, int cap, int join, float miterlimit, float[] dash, float dashPhase)`
  construct a stroke object with the given attributes.
  The end cap style is one of `CAP_BUTT`, `CAP_ROUND`, and `CAP_SQUARE`.
  The join style is one of `JOIN_BEVEL`, `JOIN_MITER`, and `JOIN_ROUND`.

1.5.6. Paint

When you fill a shape, its inside is covered with *paint.* Use the `setPaint` method to set the paint style to an object whose class implements the `Paint` interface. The Java 2D API provides three such classes:

- The `Color` class implements the `Paint` interface. To fill shapes with a solid color, simply call `setPaint` with a `Color` object, such as

  ```
  g2.setPaint(Color.red);
  ```

- The `GradientPaint` class varies colors by interpolating between two given color values (see Figure 12.45).



Figure 1.45: Gradient paint

- The `TexturePaint` class fills an area with repetitions of an image (see Figure 12.46).



Figure 1.46: Texture paint

You can construct a `GradientPaint` object by specifying two points and the colors that you want at these two points.

```
g2.setPaint(new GradientPaint(p1, Color.RED, p2, Colo
```

Colors are interpolated along the line joining the two points. Colors are constant along lines perpendicular to that joining line. Points beyond an end point of the line are given the color at the end point.

Alternatively, if you call the `GradientPaint` constructor with `true` for the `cyclic` parameter:

```
g2.setPaint(new GradientPaint(p1, Color.RED, p2, Colo
```

Then, the color variation *cycles* and keeps varying beyond the end points.

To construct a `TexturePaint` object, specify a `BufferedImage` and an *anchor* rectangle.

```
g2.setPaint(new TexturePaint(bufferedImage, anchorRec
```

I will introduce the `BufferedImage` class later in this chapter when images are discussed in detail. The simplest way of obtaining a buffered image is to read an image file:

```
bufferedImage = ImageIO.read(new File("blue-ball.gif"
```

The anchor rectangle is extended indefinitely in *x* and *y* directions to tile the entire coordinate plane. The image is scaled to fit into the anchor and then replicated into each tile.

`java.awt.Graphics2D` **1.2**

- `void setPaint(Paint s)`
  sets the paint of this graphics context to the given object that implements the `Paint` interface.

`java.awt.GradientPaint` **1.2**

- `GradientPaint(float x1, float y1, Color color1, float x2, float y2, Color color2)`
- `GradientPaint(float x1, float y1, Color color1, float x2, float y2, Color color2, boolean cyclic)`
- `GradientPaint(Point2D p1, Color color1, Point2D p2, Color color2)`
- `GradientPaint(Point2D p1, Color color1, Point2D p2, Color color2, boolean cyclic)`

  construct a gradient paint object that fills shapes with color such that the start point is colored with `color1`, the end point is colored with `color2`, and the colors in between are linearly interpolated. Colors are constant along lines perpendicular to the line joining the start and the end point. By default, the gradient paint is not cyclic—that is, points beyond the start and end points are colored with the same color as the start and end point. If the gradient paint is *cyclic,* then colors continue to be interpolated, first returning to the starting point color and then repeating indefinitely in both directions.

`java.awt.TexturePaint` **1.2**

- `TexturePaint(BufferedImage texture, Rectangle2D anchor)`
  creates a texture paint object. The anchor rectangle defines the tiling of the space to be painted; it is repeated indefinitely in *x* and *y* directions, and the texture image is scaled to fill each tile.

1.5.7. Coordinate Transformations

Suppose you need to draw an object, such as an automobile. You know, from the manufacturer's specifications, the height, wheelbase, and total length. You could, of course, figure out all pixel positions, assuming some number of pixels per meter. However, there is an easier way: You can ask the graphics context to carry out the conversion for you.

```
g2.scale(pixelsPerMeter, pixelsPerMeter);
g2.draw(new Line2D.Double(coordinates in meters)); //
                                                   //
```

The `scale` method of the `Graphics2D` class sets the *coordinate transformation* of the graphics context to a scaling transformation. That transformation changes *user coordinates* (user-specified units)

to *device coordinates* (pixels). Figure 12.47 shows how the transformation works.



Figure 1.47: User and device coordinates

Coordinate transformations are very useful in practice. They allow you to work with convenient coordinate values. The graphics context takes care of the dirty work of transforming them to pixels.

There are four fundamental transformations.

- Scaling: blowing up, or shrinking, all distances from a fixed point
- Rotation: rotating all points around a fixed center
- Translation: moving all points by a fixed amount
- Shear: leaving one line fixed and "sliding" the lines parallel to it by an amount that is proportional to the distance from the fixed line

Figure 12.48 shows how these four fundamental transformations act on a unit square.



Figure 1.48: The fundamental transformations

The `scale`, `rotate`, `translate`, and `shear` methods of the `Graphics2D` class set the coordinate transformation of the graphics context to one of these fundamental transformations.

You can *compose* the transformations. For example, you might want to rotate shapes *and* double their size; supply both a rotation and a scaling transformation:

```
g2.rotate(angle);
g2.scale(2, 2);
g2.draw(. . .);
```

In this case, it does not matter in which order you supply the transformations. However, with most transformations, order does

matter. For example, if you want to rotate and shear, then it makes a difference which of the transformations you supply first. You need to figure out what your intention is. The graphics context will apply the transformations in the order opposite to that in which you supplied them—that is, the last transformation you supply is applied first.

You can supply as many transformations as you like. For example, consider the following sequence of transformations:

```
g2.translate(x, y);
g2.rotate(a);
g2.translate(-x, -y);
```

The last transformation (which is applied first) moves the point (`x` , `y`) to the origin. The second transformation rotates with an angle `a` around the origin. The final transformation moves the origin back to (`x` , `y`). The overall effect is a rotation with center point (`x` , `y`) —see Figure 12.49. Since rotating about a point other than the origin is such a common operation, there is a shortcut:

```
g2.rotate(a, x, y);
```



Figure 1.49: Composing transformations

If you know some matrix theory, you are probably aware that all rotations, translations, scalings, shears, and their compositions can be expressed by transformation matrices of the form:

$$\begin{pmatrix} x_{\text{new}} \\ y_{\text{new}} \\ 1 \end{pmatrix} = \begin{pmatrix} a & c & e \\ b & d & f \\ 0 & 0 & 1 \end{pmatrix} \cdot \begin{pmatrix} x \\ y \\ 1 \end{pmatrix}$$

Such a transformation is called an *affine transformation.* In the Java 2D API, the `AffineTransform` class describes such a

transformation. If you know the components of a particular transformation matrix, you can construct it directly as

```
var t = new AffineTransform(a, b, c, d, e, f);
```

Additionally, the factory methods `getRotateInstance`, `getScaleInstance`, `getTranslateInstance`, and `getShearInstance` construct the matrices that represent these transformation types. For example, the call

```
t = AffineTransform.getScaleInstance(2.0F, 0.5F);
```

returns a transformation that corresponds to the matrix

$$\begin{matrix} 2 & 0 & 0 \\ 0 & 0.5 & 0 \\ 0 & 0 & 1 \end{matrix}$$

Finally, the instance methods `setToRotation`, `setToScale`, `setToTranslation`, and `setToShear` set a transformation object to a new type. Here is an example:

```
t.setToRotation(angle); // sets t to a rotation
```

You can set the coordinate transformation of the graphics context to an `AffineTransform` object.

```
g2.setTransform(t); // replaces current transformatio
```

However, in practice, you shouldn't call the `setTransform` operation, as it replaces any existing transformation that the graphics context may have. For example, a graphics context for printing in landscape mode already contains a 90-degree rotation transformation. If you call `setTransform`, you obliterate that rotation. Instead, call the `transform` method.

```
g2.transform(t); // composes current transformation w
```

It composes the existing transformation with the new `AffineTransform` object.

If you just want to apply a transformation temporarily, first get the old transformation, compose it with your new transformation, and finally restore the old transformation when you are done.

```
AffineTransform oldTransform = g2.getTransform(); //
g2.transform(t); // apply temporary transform
draw on g2
```

```
g2.setTransform(oldTransform); // restore old transfo
```

`java.awt.geom.AffineTransform` **1.2**

- `AffineTransform(double a, double b, double c, double d, double e, double f)`
- `AffineTransform(float a, float b, float c, float d, float e, float f)`

  construct the affine transform with matrix

$$\begin{matrix} a & c & e \\ b & d & f \\ 0 & 0 & 1 \end{matrix}$$

- `AffineTransform(double[] m)`
- `AffineTransform(float[] m)`

  construct the affine transform with matrix

$$\begin{matrix} \texttt{m[0]} & \texttt{m[2]} & \texttt{m[4]} \\ \texttt{m[1]} & \texttt{m[3]} & \texttt{m[5]} \\ 0 & 0 & 1 \end{matrix}$$

- `static AffineTransform getRotateInstance(double a)`

  creates a rotation around the origin by the angle `a` (in radians).

  The transformation matrix is

$$\begin{matrix} \cos(a) & -\sin(a) & 0 \\ \sin(a) & \cos(a) & 0 \\ 0 & 0 & 1 \end{matrix}$$

If `a` is between 0 and π / 2, the rotation moves the positive *x* axis toward the positive *y* axis.

- `static AffineTransform getRotateInstance(double a, double x, double y)`
  creates a rotation around the point `(x,y)` by the angle `a` (in radians).
- `static AffineTransform getScaleInstance(double sx, double sy)`
  creates a scaling transformation that scales the *x* axis by `sx` and the *y* axis by `sy`. The transformation matrix is
  $$\begin{matrix} sx & 0 & 0 \\ 0 & sy & 0 \\ 0 & 0 & 1 \end{matrix}$$
- `static AffineTransform getShearInstance(double shx, double shy)`
  creates a shear transformation that shears the *x* axis by `shx` and the *y* axis by `shy`. The transformation matrix is
  $$\begin{matrix} 1 & shx & 0 \\ shy & 1 & 0 \\ 0 & 0 & 1 \end{matrix}$$
- `static AffineTransform getTranslateInstance(double tx, double ty)`
  creates a translation that moves the *x* axis by `tx` and the *y* axis by `ty`. The transformation matrix is

$$\begin{matrix} 1 & 0 & tx \\ 0 & 1 & ty \\ 0 & 0 & 1 \end{matrix}$$

- `void setToRotation(double a)`
- `void setToRotation(double a, double x, double y)`
- `void setToScale(double sx, double sy)`
- `void setToShear(double sx, double sy)`
- `void setToTranslation(double tx, double ty)`

  set this affine transformation to a basic transformation with the given parameters. See the `get`*`Xxx`*`Instance` methods for an explanation of the basic transformations and their parameters.

`java.awt.Graphics2D` **1.2**

- `void setTransform(AffineTransform t)`

  replaces the existing coordinate transformation of this graphics context with `t`.
- `void transform(AffineTransform t)`

  composes the existing coordinate transformation of this graphics context with `t`.

- `void rotate(double a)`
- `void rotate(double a, double x, double y)`
- `void scale(double sx, double sy)`
- `void shear(double sx, double sy)`
- `void translate(double tx, double ty)`

  compose the existing coordinate transformation of this graphics context with a basic transformation with the given parameters. See the `AffineTransform.get`*`Xxx`*`Instance` methods for an explanation of the basic transformations and their parameters.

1.5.8. Clipping

By setting a *clipping shape* in the graphics context, you constrain all drawing operations to the interior of that clipping shape.

```
g2.setClip(clipShape); // but see below
g2.draw(shape); // draws only the part that falls ins
```

However, in practice, you don't want to call the `setClip` operation because it replaces any existing clipping shape that the graphics context might have. For example, as you will see later in this chapter, a graphics context for printing comes with a clip rectangle that ensures that you don't draw on the margins. Instead, call the `clip` method.

```
g2.clip(clipShape); // better
```

The `clip` method intersects the existing clipping shape with the new one that you supply.

If you just want to apply a clipping area temporarily, you should first get the old clip, add your new clip, and finally restore the old clip when you are done:

```
Shape oldClip = g2.getClip(); // save old clip
g2.clip(clipShape); // apply temporary clip
draw on g2
g2.setClip(oldClip); // restore old clip
```

In Figure 12.50, we show off the clipping capability with a rather dramatic drawing of a line pattern clipped by a complex shape—namely, the outline of a set of letters.



Figure 1.50: Using letter shapes to clip a line pattern

To obtain the character outlines, you need a *font render context.* Use the `getFontRenderContext` method of the `Graphics2D` class.

```
FontRenderContext context = g2.getFontRenderContext()
```

Next, using a string, a font, and the font render context, create a `TextLayout` object:

```
var layout = new TextLayout("Hello", font, context);
```

This text layout object describes the layout of a sequence of characters, as rendered by a particular font render context. The

layout depends on the font render context—the same characters will look different on a screen and on a printer.

More important for our application, the `getOutline` method returns a `Shape` object that describes the shape of the outline of the characters in the text layout. The outline shape starts at the origin (0, 0), which might not be what you want. In that case, supply an affine transform to the `getOutline` operation to specify where you would like the outline to appear.

```
AffineTransform transform = AffineTransform.getTransl
Shape outline = layout.getOutline(transform);
```

Then, append the outline to the clipping shape.

```
var clipShape = new GeneralPath();
clipShape.append(outline, false);
```

Finally, set the clipping shape and draw a set of lines. The lines appear only inside the character boundaries.

```
g2.setClip(clipShape);
var p = new Point2D.Double(0, 0);
for (int i = 0; i < NLINES; i++)
{
```

```
    double x = . . .;
    double y = . . .;
    var q = new Point2D.Double(x, y);
    g2.draw(new Line2D.Double(p, q)); // lines are cli
  }
```

`java.awt.Graphics` **1.0**

- `void setClip(Shape s)` **1.2**

  sets the current clipping shape to the shape `s`.
- `Shape getClip()` **1.2**

  returns the current clipping shape.

`java.awt.Graphics2D` **1.2**

- `void clip(Shape s)`

  intersects the current clipping shape with the shape `s`.
- `FontRenderContext getFontRenderContext()`

  returns a font render context that is necessary for constructing `TextLayout` objects.

`java.awt.font.TextLayout` **1.2**

- `TextLayout(String s, Font f, FontRenderContext`

`context)`
constructs a text layout object from a given string and font, using the font render context to obtain font properties for a particular device.

- `float getAdvance()`
  returns the width of this text layout.
- `float getAscent()`
- `float getDescent()`
  return the height of this text layout above and below the baseline.
- `float getLeading()`
  returns the distance between successive lines in the font used by this text layout.

1.5.9. Transparency and Composition

In the standard RGB color model, every color is described by its red, green, and blue components. However, it is also convenient to describe areas of an image that are *transparent* or partially transparent. When you superimpose an image onto an existing drawing, the transparent pixels do not obscure the pixels under them at all, whereas partially transparent pixels are mixed with the pixels under them. Figure 12.51 shows the effect of overlaying a partially transparent rectangle on an image. You can still see the details of the image shine through from under the rectangle.

Figure 1.51: Overlaying a partially transparent rectangle on an image

In the Java 2D API, transparency is described by an *alpha channel.* Each pixel has, in addition to its red, green, and blue color components, an alpha value between 0 (fully transparent) and 1 (fully opaque). For example, the rectangle in Figure 12.51 was filled with a pale yellow color with 50% transparency:

```
new Color(0.7F, 0.7F, 0.0F, 0.5F);
```

Now let us look at what happens if you superimpose two shapes. You need to blend or *compose* the colors and alpha values of the source and destination pixels. Porter and Duff, two researchers in the field of computer graphics, have formulated 12 possible *composition rules* for this blending process. The Java 2D API implements all of these rules. Before going any further, I'd like to point out that only two of these rules have practical significance. If you find the rules arcane or confusing, just use the `SRC_OVER` rule. It is the default rule for a `Graphics2D` object, and it gives the most intuitive results.

Here is the theory behind the rules. Suppose you have a *source pixel* with alpha value a_S. In the image, there is already a *destination pixel* with alpha value a_D. You want to compose the two. The diagram in Figure 12.52 shows how to design a composition rule.



Figure 1.52: Designing a composition rule

Porter and Duff consider the alpha value as the probability that the pixel color should be used. From the perspective of the source, there is a probability a_S that it wants to use the source color and a probability of $1 - a_S$ that it doesn't care. The same holds for the destination. When composing the colors, let us assume that the probabilities are independent. Then there are four cases, as shown

in Figure 12.52. If the source wants to use the source color and the destination doesn't care, then it seems reasonable to let the source have its way. That's why the upper right corner of the diagram is labeled "S". The probability for that event is $a_S \cdot (1 - a_D)$. Similarly, the lower left corner is labeled "D". What should one do if both destination and source would like to select their color? That's where the Porter–Duff rules come in. If we decide that the source is more important, we label the lower right corner with an "S" as well. That rule is called `SRC_OVER`. In that rule, you combine the source colors with a weight of a_S and the destination colors with a weight of $(1 - a_S) \cdot a_D$.

The visual effect is a blending of the source and destination, with preference given to the source. In particular, if a_S is 1, then the destination color is not taken into account at all. If a_S is 0, then the source pixel is completely transparent and the destination color is unchanged.

The other rules depend on what letters you put in the boxes of the probability diagram. Table 12.3 and Figure 12.53 show all rules that are supported by the Java 2D API. The images in the figure show the results of the rules when a rectangular source region with an alpha of 0.75 is combined with an elliptical destination region with an alpha of 1.0.

Table 1.3: The Porter–Duff Composition Rules

Rule	Explanation
`CLEAR`	Source clears destination.
`SRC`	Source overwrites destination and empty pixels.
`DST`	Source does not affect destination.
`SRC_OVER`	Source blends with destination and overwrites empty pixels.
`DST_OVER`	Source does not affect destination and overwrites empty pixels.
`SRC_IN`	Source overwrites destination.
`SRC_OUT`	Source clears destination and overwrites empty pixels.
`DST_IN`	Source alpha modifies destination.
`DST_OUT`	Source alpha complement modifies destination.

Rule	Explanation
`SRC_ATOP`	Source blends with destination.
`DST_ATOP`	Source alpha modifies destination. Source overwrites empty pixels.
`XOR`	Source alpha complement modifies destination. Source overwrites empty pixels.



Figure 1.53: Porter–Duff composition rules

As you can see, most of the rules aren't very useful. Consider, as an extreme case, the `DST_IN` rule. It doesn't take the source color into account at all, but uses the alpha of the source to affect the destination. The `SRC` rule is potentially useful—it forces the source color to be used, turning off blending with the destination.

Use the `setComposite` method of the `Graphics2D` class to install an object of a class that implements the `Composite` interface. The Java 2D API supplies one such class, `AlphaComposite`, that implements all the Porter–Duff rules in Figure 12.53.

The factory method `getInstance` of the `AlphaComposite` class yields an `AlphaComposite` object. You supply the rule and the alpha value to be used for source pixels. For example, consider the following code:

```
int rule = AlphaComposite.SRC_OVER;
float alpha = 0.5f;
g2.setComposite(AlphaComposite.getInstance(rule, alph
g2.setPaint(Color.blue);
g2.fill(rectangle);
```

The rectangle is then painted with blue color and an alpha value of 0.5. Since the composition rule is `SRC_OVER`, it is transparently overlaid on the existing image.

The program in Listing 12.17 lets you explore these composition rules. Pick a rule from the combo box and use the slider to set the alpha value of the `AlphaComposite` object.

Furthermore, the program displays a verbal description of each rule. Note that the descriptions are computed from the composition rule diagrams. For example, a `"DS"` in the second row stands for "blends with destination."

The program has one important twist. There is no guarantee that the graphics context that corresponds to the screen has an alpha channel. (In fact, it generally does not.) When pixels are deposited to a destination without an alpha channel, the pixel colors are multiplied with the alpha value and the alpha value is discarded. Now, several of the Porter–Duff rules use the alpha values of the destination, which means a destination alpha channel is important. For that reason, we use a buffered image with the ARGB color model to compose the shapes. After the images have been composed, we draw the resulting image to the screen.

```
var image = new BufferedImage(getWidth(), getHeight()
Graphics2D gImage = image.createGraphics();
// now draw to gImage
g2.drawImage(image, null, 0, 0);
```

Listing 12.17 shows the frame class. The component class is in Listing 12.18. The `Rule` class in Listing 12.19 provides a brief explanation for each rule—see Figure 12.54. As you run the program, move the alpha slider from left to right to see the effect on the composed shapes. In particular, note that the only difference between the `DST_IN` and `DST_OUT` rules is how the destination (!) color changes when you change the source alpha.



Figure 1.54: The `CompositeTest` program

Listing 1.17 composite/CompositeTestFrame.java

```
1  package composite;
2
3  import java.awt.*;
4  import javax.swing.*;
5
6  /**
7   * This frame contains a combo box to choose a
8   * source alpha channel, and a component that s
9   */
10 class CompositeTestFrame extends JFrame
11 {
12    private static final int DEFAULT_WIDTH = 400
13    private static final int DEFAULT_HEIGHT = 40
14
15    private CompositeComponent canvas;
16    private JComboBox<Rule> ruleCombo;
17    private JSlider alphaSlider;
18    private JTextField explanation;
19
20    public CompositeTestFrame()
21    {
22       setSize(DEFAULT_WIDTH, DEFAULT_HEIGHT);
23
24       canvas = new CompositeComponent();
25       add(canvas, BorderLayout.CENTER);
26
```

```
27        ruleCombo = new JComboBox<>(new Rule[] {
28           new Rule("SRC", " S", " S"), new Rule(
29           new Rule("SRC_OVER", " S", "DS"), new
30           new Rule("SRC_IN", "  ", " S"), new Ru
31           new Rule("DST_IN", "  ", " D"), new Ru
32           new Rule("SRC_ATOP", "  ", "DS"), new
33           new Rule("XOR", " S", "D "), });
34        ruleCombo.addActionListener(event ->
35           {
36              var r = (Rule) ruleCombo.getSelecte
37              canvas.setRule(r.getValue());
38              explanation.setText(r.getExplanatio
39           });
40
41        alphaSlider = new JSlider(0, 100, 75);
42        alphaSlider.addChangeListener(event -> ca
43        var panel = new JPanel();
44        panel.add(ruleCombo);
45        panel.add(new JLabel("Alpha"));
46        panel.add(alphaSlider);
47        add(panel, BorderLayout.NORTH);
48
49        explanation = new JTextField();
50        add(explanation, BorderLayout.SOUTH);
51
52        canvas.setAlpha(alphaSlider.getValue());
53        Rule r = ruleCombo.getItemAt(ruleCombo.ge
54        canvas.setRule(r.getValue());
```

```
55          explanation.setText(r.getExplanation());
56       }
57    }
```

Listing 1.18 composite/CompositeComponent.java

```
1  package composite;
2
3  import java.awt.*;
4  import java.awt.geom.*;
5  import java.awt.image.*;
6  import javax.swing.*;
7
8  /**
9   * This component draws two shapes, composed wi
10  */
11 class CompositeComponent extends JComponent
12 {
13    private int rule;
14    private Shape shape1;
15    private Shape shape2;
16    private float alpha;
17
18    public CompositeComponent()
19    {
20       shape1 = new Ellipse2D.Double(100, 100, 1
21       shape2 = new Rectangle2D.Double(150, 150,
22    }
```

```
23
24    public void paintComponent(Graphics g)
25    {
26       var g2 = (Graphics2D) g;
27
28       var image = new BufferedImage(getWidth(),
29       Graphics2D gImage = image.createGraphics(
30       gImage.setPaint(Color.red);
31       gImage.fill(shape1);
32       AlphaComposite composite = AlphaComposite
33       gImage.setComposite(composite);
34       gImage.setPaint(Color.blue);
35       gImage.fill(shape2);
36       g2.drawImage(image, null, 0, 0);
37    }
38
39    /**
40     * Sets the composition rule.
41     * @param r the rule (as an AlphaComposite c
42     */
43    public void setRule(int r)
44    {
45       rule = r;
46       repaint();
47    }
48
49    /**
50     * Sets the alpha of the source.
```

```
51      * @param a the alpha value between 0 and 10
52      */
53     public void setAlpha(int a)
54     {
55        alpha = (float) a / 100.0F;
56        repaint();
57     }
58  }
```

Listing 1.19 composite/Rule.java

```
1  package composite;
2
3  import java.awt.*;
4
5  /**
6   * This class describes a Porter-Duff rule.
7   */
8  class Rule
9  {
10    private String name;
11    private String porterDuff1;
12    private String porterDuff2;
13
14    /**
15     * Constructs a Porter-Duff rule.
16     * @param n the rule name
17     * @param pd1 the first row of the Porter-Du
```

```
18      * @param pd2 the second row of the Porter-D
19      */
20     public Rule(String n, String pd1, String pd2
21     {
22        name = n;
23        porterDuff1 = pd1;
24        porterDuff2 = pd2;
25     }
26
27     /**
28      * Gets an explanation of the behavior of th
29      * @return the explanation
30      */
31     public String getExplanation()
32     {
33        var r = new StringBuilder("Source ");
34        if (porterDuff2.equals("  ")) r.append("c
35        if (porterDuff2.equals(" S")) r.append("c
36        if (porterDuff2.equals("DS")) r.append("b
37        if (porterDuff2.equals(" D")) r.append("a
38        if (porterDuff2.equals("D ")) r.append("a
39        if (porterDuff2.equals("DD")) r.append("c
40        r.append(" destination");
41        if (porterDuff1.equals(" S")) r.append("
42        r.append(".");
43        return r.toString();
44     }
45
```

```
46     public String toString()
47     {
48        return name;
49     }
50
51     /**
52      * Gets the value of this rule in the AlphaC
53      * @return the AlphaComposite constant value
54      */
55     public int getValue()
56     {
57        try
58        {
59           return (Integer) AlphaComposite.class
60        }
61        catch (Exception e)
62        {
63           return -1;
64        }
65     }
66  }
```

`java.awt.Graphics2D` **1.2**

- `void setComposite(Composite s)`
  sets the composite of this graphics context to the given object that implements the `Composite` interface.

`java.awt.AlphaComposite` 1.2

- `static AlphaComposite getInstance(int rule)`
- `static AlphaComposite getInstance(int rule, float sourceAlpha)`
  construct an alpha composite object. The rule is one of `CLEAR`, `SRC`, `SRC_OVER`, `DST_OVER`, `SRC_IN`, `SRC_OUT`, `DST_IN`, `DST_OUT`, `DST`, `DST_ATOP`, `SRC_ATOP`, `XOR`.

1.6. Raster Images

The Java2D API lets you create drawings that are made up of lines, curves, and areas. It is a "vector" API because you specify the mathematical properties of the shapes. However, for processing images that are made up of pixels, you want to work with a "raster" of color data. The following sections show you how to process raster images in Java.

1.6.1. Readers and Writers for Images

The `javax.imageio` package contains out-of-the-box support for reading and writing several common file formats, as well as a framework that enables third parties to add readers and writers for other formats. The GIF, JPEG, PNG, BMP (Windows bitmap), and WBMP (wireless bitmap) file formats are supported.

The basics of the library are extremely straightforward. To load an image, use the static `read` method of the `ImageIO` class:

```
File f = . . .;
BufferedImage image = ImageIO.read(f);
```

The `ImageIO` class picks an appropriate reader, based on the file type. It may consult the file extension and the "magic number" at the beginning of the file for that purpose. If no suitable reader can be found or the reader can't decode the file contents, the `read` method returns `null`.

Writing an image to a file is just as simple:

```
File f = . . .;
String format = . . .;
ImageIO.write(image, format, f);
```

Here the format string is a string identifying the image format, such as `"JPEG"` or `"PNG"`. The `ImageIO` class picks an appropriate writer and saves the file.

1.6.2. Obtaining Readers and Writers for Image File Types

For more advanced image reading and writing operations that go beyond the static `read` and `write` methods of the `ImageIO` class, you first need to get the appropriate `ImageReader` and `ImageWriter` objects. The `ImageIO` class enumerates readers and writers that match one of the following:

- An image format (such as `"JPEG"`)
- A file suffix (such as `"jpg"`)
- A MIME type (such as `"image/jpeg"`)

Note: MIME is the Multipurpose Internet Mail Extensions standard. The MIME standard defines common data formats such as `image/jpeg` and `application/pdf`.

For example, you can obtain a reader that reads JPEG files as follows:

```
ImageReader reader = null;
Iterator<ImageReader> iter = ImageIO.getImageReadersB
if (iter.hasNext()) reader = iter.next();
```

The `getImageReadersBySuffix` and `getImageReadersByMIMEType` methods enumerate readers that

match a file extension or MIME type.

It is possible that the `ImageIO` class can locate multiple readers that can all read a particular image type. In that case, you have to pick one of them, but it isn't clear how you can decide which one is the best. To find out more information about a reader, obtain its *service provider interface*:

```
ImageReaderSpi spi = reader.getOriginatingProvider();
```

Then you can get the vendor name and version number:

```
String vendor = spi.getVendor();
String version = spi.getVersion();
```

Perhaps that information can help you decide among the choices—or you might just present a list of readers to your program users and let them choose. For now, we assume that the first enumerated reader is adequate.

In the sample program in Listing 12.20, we want to find all file suffixes of all available readers so that we can use them in a file filter. Use the static `ImageIO.getReaderFileSuffixes` method for this purpose:

```
String[] extensions = ImageIO.getWriterFileSuffixes()
chooser.setFileFilter(new FileNameExtensionFilter("Im
```

For saving files, we have to work harder. We'd like to present the user with a menu of all supported image types. Unfortunately, the `getWriterFormatNames` of the `ImageIO` class returns a rather curious list with redundant names, such as

```
jpg, BMP, bmp, JPG, jpeg, wbmp, png, JPEG, PNG, WBMP,
```

That's not something one would want to present in a menu. What is needed is a list of "preferred" format names. We supply a helper method `getWriterFormats` for this purpose (see Listing 12.20). We look up the first writer associated with each format name. Then we ask it what its format names are, in the hope that it will list the most popular one first. Indeed, for the JPEG writer, this works fine—it lists `"JPEG"` before the other options. (The PNG writer, on the other hand, lists `"png"` in lower case before `"PNG"`. We hope this behavior will be addressed at some point in the future. For now, we force all-lowercase names to upper case.) Once we pick a preferred name, we remove all alternate names from the original set. We keep going until all format names are handled.

1.6.3. Reading and Writing Files with Multiple Images

Some files—in particular, animated GIF files—contain multiple images. The `read` method of the `ImageIO` class reads a single image. To read multiple images, turn the input source (for example, an input stream or file) into an `ImageInputStream`.

```
InputStream in = . . .;
ImageInputStream imageIn = ImageIO.createImageInputSt
```

Then, attach the image input stream to the reader:

```
reader.setInput(imageIn, true);
```

The second argument indicates that the input is in "seek forward only" mode. Otherwise, random access is used, either by buffering stream input as it is read or by using random file access. Random access is required for certain operations. For example, to find out the number of images in a GIF file, you need to read the entire file. If you then want to fetch an image, the input must be read again.

This consideration is only important if you read from a stream, if the input contains multiple images, and if the image format doesn't have

the information that you request (such as the image count) in the header. If you read from a file, simply use

```
File f = . . .;
ImageInputStream imageIn = ImageIO.createImageInputSt
reader.setInput(imageIn);
```

Once you have a reader, you can read the images in the input by calling

```
BufferedImage image = reader.read(index);
```

where `index` is the image index, starting with `0`.

If the input is in the "seek forward only" mode, you keep reading images until the `read` method throws an `IndexOutOfBoundsException`. Otherwise, you can call the `getNumImages` method:

```
int n = reader.getNumImages(true);
```

Here, the argument indicates that you allow a search of the input to determine the number of images. That method throws an `IllegalStateException` if the input is in the "seek forward only"

mode. Alternatively, you can set the "allow search" parameter to `false`. Then the `getNumImages` method returns `-1` if it can't determine the number of images without a search. In that case, you'll have to switch to Plan B and keep reading images until you get an `IndexOutOfBoundsException`.

Some files contain thumbnails—smaller versions of an image for preview purposes. You can get the number of thumbnails of an image with the call

```
int count = reader.getNumThumbnails(index);
```

Then you get a particular index as

```
BufferedImage thumbnail = reader.getThumbnail(index,
```

Sometimes you may want to get the image size before actually getting the image—in particular, if the image is huge or comes from a slow network connection. Use the calls

```
int width = reader.getWidth(index);
int height = reader.getHeight(index);
```

to get the dimensions of an image with a given index.

To write a file with multiple images, you first need an `ImageWriter`. The `ImageIO` class can enumerate the writers capable of writing a particular image format:

```
String format = . . .;
ImageWriter writer = null;
Iterator<ImageWriter> iter = ImageIO.getImageWritersB
if (iter.hasNext()) writer = iter.next();
```

Next, turn an output stream or file into an `ImageOutputStream` and attach it to the writer. For example,

```
File f = . . .;
ImageOutputStream imageOut = ImageIO.createImageOutpu
writer.setOutput(imageOut);
```

You must wrap each image into an `IIOImage` object. You can optionally supply a list of thumbnails and image metadata (such as compression algorithms and color information). In this example, we just use `null` for both; see the API documentation for additional information.

```
var iioImage = new IIOImage(images[i], null, null);
```

To write out the *first* image, use the `write` method:

```
writer.write(new IIOImage(images[0], null, null));
```

For subsequent images, use

```
if (writer.canInsertImage(i))
   writer.writeInsert(i, iioImage, null);
```

The third argument can contain an `ImageWriteParam` object to set image writing details such as tiling and compression; use `null` for default values.

Not all file formats can handle multiple images. In that case, the `canInsertImage` method returns `false` for `i` > 0, and only a single image is saved.

The program in Listing 12.20 lets you load and save files in the formats for which the Java library supplies readers and writers. The program displays multiple images (see Figure 12.55), but not thumbnails.



Figure 1.55: An animated GIF image

Listing 1.20 imageIO/ImageIOFrame.java

```
1  package imageIO;
2
3  import java.awt.image.*;
4  import java.io.*;
5  import java.util.*;
6
7  import javax.imageio.*;
8  import javax.imageio.stream.*;
9  import javax.swing.*;
```

```
10 import javax.swing.filechooser.*;
11
12 /**
13  * This frame displays the loaded images. The r
14  */
15 public class ImageIOFrame extends JFrame
16 {
17    private static final int DEFAULT_WIDTH = 400
18    private static final int DEFAULT_HEIGHT = 40
19
20    private static Set<String> writerFormats = g
21
22    private BufferedImage[] images;
23
24    public ImageIOFrame()
25    {
26       setSize(DEFAULT_WIDTH, DEFAULT_HEIGHT);
27
28       var fileMenu = new JMenu("File");
29       var openItem = new JMenuItem("Open");
30       openItem.addActionListener(event -> openF
31       fileMenu.add(openItem);
32
33       var saveMenu = new JMenu("Save");
34       fileMenu.add(saveMenu);
35       Iterator<String> iter = writerFormats.ite
36       while (iter.hasNext())
37       {
```

```
38          final String formatName = iter.next();
39          var formatItem = new JMenuItem(formatN
40          saveMenu.add(formatItem);
41          formatItem.addActionListener(event ->
42       }
43
44       var exitItem = new JMenuItem("Exit");
45       exitItem.addActionListener(event -> Syste
46       fileMenu.add(exitItem);
47
48       var menuBar = new JMenuBar();
49       menuBar.add(fileMenu);
50       setJMenuBar(menuBar);
51    }
52
53    /**
54     * Open a file and load the images.
55     */
56    public void openFile()
57    {
58       var chooser = new JFileChooser();
59       chooser.setCurrentDirectory(new File(".")
60       String[] extensions = ImageIO.getReaderFi
61       chooser.setFileFilter(new FileNameExtensi
62       int r = chooser.showOpenDialog(this);
63       if (r != JFileChooser.APPROVE_OPTION) ret
64       File f = chooser.getSelectedFile();
65       Box box = Box.createVerticalBox();
```

```
66          try
67          {
68             String name = f.getName();
69             String suffix = name.substring(name.la
70             Iterator<ImageReader> iter = ImageIO.g
71             ImageReader reader = iter.next();
72             ImageInputStream imageIn = ImageIO.cre
73             reader.setInput(imageIn);
74             int count = reader.getNumImages(true);
75             images = new BufferedImage[count];
76             for (int i = 0; i < count; i++)
77             {
78                images[i] = reader.read(i);
79                box.add(new JLabel(new ImageIcon(im
80             }
81          }
82          catch (IOException e)
83          {
84             JOptionPane.showMessageDialog(this, e)
85          }
86          setContentPane(new JScrollPane(box));
87          validate();
88       }
89
90       /**
91        * Save the current image in a file.
92        * @param formatName the file format
93        */
```

```
94    public void saveFile(final String formatName
95    {
96       if (images == null) return;
97       Iterator<ImageWriter> iter = ImageIO.getI
98       ImageWriter writer = iter.next();
99       var chooser = new JFileChooser();
100      chooser.setCurrentDirectory(new File(".")
101      String[] extensions = writer.getOriginati
102      chooser.setFileFilter(new FileNameExtensi
103
104      int r = chooser.showSaveDialog(this);
105      if (r != JFileChooser.APPROVE_OPTION) ret
106      File f = chooser.getSelectedFile();
107      try
108      {
109         ImageOutputStream imageOut = ImageIO.c
110         writer.setOutput(imageOut);
111
112         writer.write(new IIOImage(images[0], n
113         for (int i = 1; i < images.length; i++
114         {
115            var iioImage = new IIOImage(images[
116            if (writer.canInsertImage(i)) write
117         }
118      }
119      catch (IOException e)
120      {
121         JOptionPane.showMessageDialog(this, e)
```

```
122         }
123      }
124
125      /**
126       * Gets a set of "preferred" format names of
127       * is the first format name that a writer sp
128       * @return the format name set
129       */
130      public static Set<String> getWriterFormats()
131      {
132         var writerFormats = new TreeSet<String>()
133         var formatNames = List.of(ImageIO.getWrit
134         while (formatNames.size() > 0)
135         {
136            String name = formatNames.iterator().n
137            Iterator<ImageWriter> iter = ImageIO.g
138            ImageWriter writer = iter.next();
139            String[] names = writer.getOriginating
140            String format = names[0];
141            if (format.equals(format.toLowerCase()
142            writerFormats.add(format);
143            formatNames.removeAll(List.of(names));
144         }
145         return writerFormats;
146      }
147   }
```

`javax.imageio.ImageIO` **1.4**

- `static BufferedImage read(File input)`
- `static BufferedImage read(InputStream input)`
- `static BufferedImage read(URL input)`
  read an image from `input`.
- `static boolean write(RenderedImage image, String formatName, File output)`
- `static boolean write(RenderedImage image, String formatName, OutputStream output)`
  write an image in the given format to `output`. Return `false` if no appropriate writer was found.
- `static Iterator<ImageReader> getImageReadersByFormatName(String formatName)`
- `static Iterator<ImageReader> getImageReadersBySuffix(String fileSuffix)`
- `static Iterator<ImageReader> getImageReadersByMIMEType(String mimeType)`
- `static Iterator<ImageWriter> getImageWritersByFormatName(String formatName)`
- `static Iterator<ImageWriter> getImageWritersBySuffix(String fileSuffix)`
- `static Iterator<ImageWriter>`

`getImageWritersByMIMEType(String mimeType)`
get all readers and writers that are able to handle the given format (e.g., `"JPEG"`), file suffix (e.g., `"jpg"`), or MIME type (e.g., `"image/jpeg"`).

- `static String[] getReaderFormatNames()`
- `static String[] getReaderMIMETypes()`
- `static String[] getWriterFormatNames()`
- `static String[] getWriterMIMETypes()`
- `static String[] getReaderFileSuffixes()` 6
- `static String[] getWriterFileSuffixes()` 6

  get all format names, MIME type names, and file suffixes supported by readers and writers.
- `ImageInputStream createImageInputStream(Object input)`
- `ImageOutputStream createImageOutputStream(Object output)`

  create an image input or image output stream from the given object. The object can be a file, a stream, a `RandomAccessFile`, or another object for which a service provider exists. Return `null` if no registered service provider can handle the object.

`javax.imageio.ImageReader` **1.4**

- `void setInput(Object input)`
- `void setInput(Object input, boolean seekForwardOnly)`
  set the input source of the reader. The `input` parameter is an `ImageInputStream` object or another object that this reader can accept. The `seekForwardOnly` parameter is `true` if the reader should read forward only. By default, the reader uses random access and, if necessary, buffers image data.
- `BufferedImage read(int index)`
  reads the image with the given image index (starting at `0`). Throws an `IndexOutOfBoundsException` if no such image is available.
- `int getNumImages(boolean allowSearch)`
  gets the number of images in this reader. If `allowSearch` is `false` and the number of images cannot be determined without reading forward, then `-1` is returned. If `allowSearch` is `true` and the reader is in the "seek forward only" mode, then an `IllegalStateException` is thrown.
- `int getNumThumbnails(int index)`
  gets the number of thumbnails of the image with the given `index`.

- `BufferedImage readThumbnail(int index, int thumbnailIndex)`
  gets the thumbnail with index `thumbnailIndex` of the image with the given `index`.
- `int getWidth(int index)`
- `int getHeight(int index)`
  get the image width and height. Throw an `IndexOutOfBoundsException` if no such image is available.
- `ImageReaderSpi getOriginatingProvider()`
  gets the service provider that constructed this reader.

`javax.imageio.spi.IIOServiceProvider` **1.4**

- `String getVendorName()`
- `String getVersion()`
  get the vendor name and version of this service provider.

`javax.imageio.spi.ImageReaderWriterSpi` **1.4**

- `String[] getFormatNames()`
- `String[] getFileSuffixes()`
- `String[] getMIMETypes()`
  get the format names, file suffixes, and MIME types supported by the readers or writers that this service provider creates.

`javax.imageio.ImageWriter` **1.4**

- `void setOutput(Object output)`
  sets the output target of this writer. The `output` parameter is an `ImageOutputStream` object or another object that this writer can accept.
- `void write(IIOImage image)`
- `void write(RenderedImage image)`
  write a single image to the output.
- `void writeInsert(int index, IIOImage image, ImageWriteParam param)`
  writes an image into a multi-image file.
- `boolean canInsertImage(int index)`
  returns `true` if it is possible to insert an image at the given index.
- `ImageWriterSpi getOriginatingProvider()`
  gets the service provider that constructed this writer.

`javax.imageio.IIOImage` **1.4**

- `IIOImage(RenderedImage image, List thumbnails, IIOMetadata metadata)`
  constructs an `IIOImage` from an image, optional thumbnails, and optional metadata.

1.6.4. Image Manipulation

Suppose you have an image and you would like to improve its appearance. You then need to access the individual pixels of the image and replace them with other pixels. Or perhaps you want to compute the pixels of an image from scratch—for example, to show the result of physical measurements or a mathematical computation. The `BufferedImage` class gives you control over the pixels in an image, and the classes that implement the `BufferedImageOp` interface let you transform images.

Note: JDK 1.0 had a completely different, and far more complex, imaging framework that was optimized for *incremental rendering* of images downloaded from the Web, a scan line at a time. However, it was difficult to manipulate those images. We do not discuss that framework in this book.

Most of the images that you manipulate are simply read in from an image file—they were either produced by a device such as a digital camera or scanner, or constructed by a drawing program. In this section, we'll show you a different technique for constructing an image—namely, building it up a pixel at a time.

To create an image, construct a `BufferedImage` object in the usual way.

```
image = new BufferedImage(width, height, BufferedImag
```

Now, call the `getRaster` method to obtain an object of type `WritableRaster`. You will use this object to access and modify the pixels of the image.

```
WritableRaster raster = image.getRaster();
```

The `setPixel` method lets you set an individual pixel. The complexity here is that you can't simply set the pixel to a `Color` value. You must know how the buffered image specifies color values. That depends on the *type* of the image. If your image has a type of `TYPE_INT_ARGB`, then each pixel is described by four values—red, green, blue, and alpha, each between `0` and `255`. You have to supply them in an array of four integers:

```
int[] black = { 0, 0, 0, 255 };
raster.setPixel(i, j, black);
```

In the lingo of the Java 2D API, these values are called the *sample values* of the pixel.

Caution: There are also `setPixel` methods with parameters of type `float[]` and `double[]`. However, the values that you need to place into these arrays are *not* normalized color values between `0.0` and `1.0`.

```
float[] red = { 1.0F, 0.0F, 0.0F, 1.0F };
raster.setPixel(i, j, red); // ERROR
```

You need to supply values between `0` and `255`, no matter what the type of the array is.

You can supply a batch of pixels with the `setPixels` method. Specify the starting pixel position and the width and height of the rectangle that you want to set. Then, supply an array that contains the sample values for all pixels. For example, if your buffered image has a type of `TYPE_INT_ARGB`, supply the red, green, blue, and alpha values of the first pixel, then the red, green, blue, and alpha values for the second pixel, and so on.

```
var pixels = new int[4 * width * height];
pixels[0] = . . .; // red value for first pixel
pixels[1] = . . .; // green value for first pixel
pixels[2] = . . .; // blue value for first pixel
```

```
pixels[3] = . . .; // alpha value for first pixel
. . .
raster.setPixels(x, y, width, height, pixels);
```

Conversely, to read a pixel, use the `getPixel` method. Supply an array of four integers to hold the sample values.

```
var sample = new int[4];
raster.getPixel(x, y, sample);
var color = new Color(sample[0], sample[1], sample[2]
```

You can read multiple pixels with the `getPixels` method.

```
raster.getPixels(x, y, width, height, samples);
```

If you use an image type other than `TYPE_INT_ARGB` and you know how that type represents pixel values, you can still use the `getPixel/setPixel` methods. However, you have to know the encoding of the sample values in the particular image type.

If you need to manipulate an image with an arbitrary, unknown image type, then you have to work a bit harder. Every image type has a *color model* that can translate between sample value arrays and the standard RGB color model.

Note: The RGB color model isn't as standard as you might think. The exact look of a color value depends on the characteristics of the imaging device. Digital cameras, scanners, monitors, and LCD displays all have their own idiosyncrasies. As a result, the same RGB value can look quite different on different devices. The International Color Consortium (https://www.color.org) recommends that all color data be accompanied by an *ICC profile* that specifies how the colors map to a standard form such as the 1931 CIE XYZ color specification. That specification was designed by the Commission Internationale de l'Eclairage, or CIE (https://www.cie.co.at), the international organization in charge of providing technical guidance in all matters of illumination and color. The specification is a standard method for representing any color that the human eye can perceive as a triplet of coordinates called X, Y, Z. (See, for example, *Computer Graphics: Principles and Practice, Third Edition*, by John F. Hughes et al., Chapter 28, for more information on the 1931 CIE XYZ specification.)

ICC profiles are complex, however. A simpler proposed standard, called sRGB

(https://www.w3.org/Graphics/Color/sRGB.html), specifies an exact mapping between RGB values and the 1931 CIE XYZ values that was designed to work well with typical color monitors. The Java 2D API uses that mapping when converting between RGB and other color spaces.

The `getColorModel` method returns the color model:

```
ColorModel model = image.getColorModel();
```

To find the color value of a pixel, call the `getDataElements` method of the `Raster` class. That call returns an `Object` that contains a color-model-specific description of the color value.

```
Object data = raster.getDataElements(x, y, null);
```

Note: The object that is returned by the `getDataElements` method is actually an array of sample values. You don't need to know this to process the object, but it explains why the method is called `getDataElements`.

The color model can translate the object to standard ARGB values. The `getRGB` method returns an `int` value that has the alpha, red, green, and blue values packed in four blocks of eight bits each. You can construct a `Color` value out of that integer with the `Color(int argb, boolean hasAlpha)` constructor:

```
int argb = model.getRGB(data);
var color = new Color(argb, true);
```

To set a pixel to a particular color, reverse these steps. The `getRGB` method of the `Color` class yields an `int` value with the alpha, red, green, and blue values. Supply that value to the `getDataElements` method of the `ColorModel` class. The return value is an `Object` that contains the color-model-specific description of the color value. Pass the object to the `setDataElements` method of the `WritableRaster` class.

```
int argb = color.getRGB();
Object data = model.getDataElements(argb, null);
raster.setDataElements(x, y, data);
```

To illustrate how to use these methods to build an image from individual pixels, we bow to tradition and draw a Mandelbrot set, as shown in Figure 12.56.



Figure 1.56: A Mandelbrot set

The idea of the Mandelbrot set is that each point of the plane is associated with a sequence of numbers. If that sequence stays bounded, you color the point. If it "escapes to infinity," you leave it transparent.

Here is how you can construct the simplest Mandelbrot set. For each point (*a*, *b*), look at sequences that start with (*x*, *y*) = (0, 0) and iterate:

$$x_{\mathbf{new}} = x^2 - y^2 + a$$

$y_{new} = 2 \cdot x \cdot y + b$

It turns out that if x or y ever gets larger than 2, then the sequence escapes to infinity. Only the pixels that correspond to points (a, b) leading to a bounded sequence are colored. (The formulas for the number sequences come ultimately from the mathematics of complex numbers; we'll just take them for granted.)

Listing 12.21 shows the code. This program demonstrates how to use the `ColorModel` class for translating `Color` values into pixel data. That process is independent of the image type. Just for fun, change the color type of the buffered image to `TYPE_BYTE_GRAY`. You don't need to change any other code—the color model of the image automatically takes care of the conversion from colors to sample values.

Listing 1.21 rasterImage/RasterImageFrame.java

```
1  package rasterImage;
2
3  import java.awt.*;
4  import java.awt.image.*;
5  import javax.swing.*;
6
7  /**
8   * This frame shows an image with a Mandelbrot
9   */
```

```
10 public class RasterImageFrame extends JFrame
11 {
12    private static final double XMIN = -2;
13    private static final double XMAX = 2;
14    private static final double YMIN = -2;
15    private static final double YMAX = 2;
16    private static final int MAX_ITERATIONS = 16
17    private static final int IMAGE_WIDTH = 400;
18    private static final int IMAGE_HEIGHT = 400;
19
20    public RasterImageFrame()
21    {
22       BufferedImage image = makeMandelbrot(IMAG
23       add(new JLabel(new ImageIcon(image)));
24       pack();
25    }
26
27    /**
28     * Makes the Mandelbrot image.
29     * @param width the width
30     * @parah height the height
31     * @return the image
32     */
33    public BufferedImage makeMandelbrot(int widt
34    {
35       var image = new BufferedImage(width, heig
36       WritableRaster raster = image.getRaster()
37       ColorModel model = image.getColorModel();
```

```
38
39          Color fractalColor = Color.RED;
40          int argb = fractalColor.getRGB();
41          Object colorData = model.getDataElements(
42
43          for (int i = 0; i < width; i++)
44             for (int j = 0; j < height; j++)
45             {
46                double a = XMIN + i * (XMAX - XMIN)
47                double b = YMIN + j * (YMAX - YMIN)
48                if (!escapesToInfinity(a, b)) raste
49             }
50          return image;
51       }
52
53       private boolean escapesToInfinity(double a,
54       {
55          double x = 0.0;
56          double y = 0.0;
57          int iterations = 0;
58          while (x <= 2 && y <= 2 && iterations < M
59          {
60             double xnew = x * x - y * y + a;
61             double ynew = 2 * x * y + b;
62             x = xnew;
63             y = ynew;
64             iterations++;
65          }
```

```
66          return x > 2 || y > 2;
67       }
68    }
```

`java.awt.image.BufferedImage` **1.2**

- `BufferedImage(int width, int height, int imageType)`
  constructs a buffered image object.
  The most common image types are `TYPE_INT_RGB`, `TYPE_INT_ARGB`, `TYPE_BYTE_GRAY`, and `TYPE_BYTE_INDEXED`.
- `ColorModel getColorModel()`
  returns the color model of this buffered image.
- `WritableRaster getRaster()`
  gets the raster for accessing and modifying pixels of this buffered image.

`java.awt.image.Raster` **1.2**

- `Object getDataElements(int x, int y, Object data)`
  returns the sample data for a raster point, in an array whose element type and length depend on the color model. If `data` is not `null`, it is assumed to be an array that is appropriate for holding sample data, and it is filled. If `data` is `null`, a new

array is allocated. Its element type and length depend on the color model.

- `int[] getPixel(int x, int y, int[] sampleValues)`
- `float[] getPixel(int x, int y, float[] sampleValues)`
- `double[] getPixel(int x, int y, double[] sampleValues)`
- `int[] getPixels(int x, int y, int width, int height, int[] sampleValues)`
- `float[] getPixels(int x, int y, int width, int height, float[] sampleValues)`
- `double[] getPixels(int x, int y, int width, int height, double[] sampleValues)`

  return the sample values for a raster point, or a rectangle of raster points, in an array whose length depends on the color model. If `sampleValues` is not `null`, it is assumed to be sufficiently long for holding the sample values, and it is filled. If `sampleValues` is `null`, a new array is allocated. These methods are only useful if you know the meaning of the sample values for a color model.

`java.awt.image.WritableRaster` **1.2**

- `void setDataElements(int x, int y, Object data)`
  sets the sample data for a raster point. `data` is an array filled with the sample data for a pixel. Its element type and length depend on the color model.
- `void setPixel(int x, int y, int[] sampleValues)`
- `void setPixel(int x, int y, float[] sampleValues)`
- `void setPixel(int x, int y, double[] sampleValues)`
- `void setPixels(int x, int y, int width, int height, int[] sampleValues)`
- `void setPixels(int x, int y, int width, int height, float[] sampleValues)`
- `void setPixels(int x, int y, int width, int height, double[] sampleValues)`
  set the sample values for a raster point or a rectangle of raster points. These methods are only useful if you know the encoding of the sample values for a color model.

`java.awt.image.ColorModel` **1.2**

- `int getRGB(Object data)`
  returns the ARGB value that corresponds to the sample data passed in the `data` array. Its element type and length depend

on the color model.

- `Object getDataElements(int argb, Object data);`
  returns the sample data for a color value. If `data` is not `null`, it is assumed to be an array that is appropriate for holding sample data, and it is filled. If `data` is `null`, a new array is allocated. `data` is an array filled with the sample data for a pixel. Its element type and length depend on the color model.

`java.awt.Color` **1.0**

- `Color(int argb, boolean hasAlpha)` **1.2**
  creates a color with the specified combined ARGB value if `hasAlpha` is `true`, or the specified RGB value if `hasAlpha` is `false`.
- `int getRGB()`
  returns the ARGB color value corresponding to this color.

1.6.5. Filtering Images

In the preceding section, you saw how to build up an image from scratch. However, often you want to access image data for a different reason: You already have an image and you want to improve it in some way.

Of course, you can use the `getPixel/getDataElements` methods that you saw in the preceding section to read the image data,

manipulate them, and write them back. Fortunately, the Java 2D API already supplies a number of *filters* that carry out common image processing operations for you.

The image manipulations all implement the `BufferedImageOp` interface. After you construct the operation, simply call the `filter` method to transform an image into another.

```
BufferedImageOp op = . . .;
BufferedImage filteredImage
   = new BufferedImage(image.getWidth(), image.getHei
op.filter(image, filteredImage);
```

Some operations can transform an image in place (`op.filter(image, image)`), but most can't.

Five classes implement the `BufferedImageOp` interface:

```
AffineTransformOp
RescaleOp
LookupOp
ColorConvertOp
ConvolveOp
```

The `AffineTransformOp` carries out an affine transformation on the pixels. For example, here is how you can rotate an image about its center:

```
AffineTransform transform = AffineTransform.getRotate
   image.getWidth() / 2, image.getHeight() / 2);
var op = new AffineTransformOp(transform, interpolati
op.filter(image, filteredImage);
```

The `AffineTransformOp` constructor requires an affine transform and an *interpolation* strategy. Interpolation is necessary to determine the target image pixels if the source pixels are transformed somewhere between target pixels. For example, if you rotate source pixels, they will generally not fall exactly onto target pixels. There are three interpolation strategies: `AffineTransformOp.TYPE_BICUBIC`, `AffineTransformOp.TYPE_BILINEAR`, and `AffineTransformOp.TYPE_NEAREST_NEIGHBOR`. Bicubic interpolation takes a bit longer but looks better than the other two.

The program in Listing 12.22 lets you rotate an image by 5 degrees (see Figure 12.57).



Figure 1.57: A rotated image

The `RescaleOp` carries out a rescaling operation

$x_{\mathbf{new}} = a \cdot x + b$

for each of the color components in the image. (Alpha components are not affected.) The effect of rescaling with $a > 1$ is to brighten the image. Construct the `RescaleOp` by specifying the scaling parameters and optional rendering hints. In Listing 12.22, we use:

```
float a = 1.1f;
float b = 20.0f;
var op = new RescaleOp(a, b, null);
```

You can also supply separate scaling values for each color component—see the API notes.

The `LookupOp` operation lets you specify an arbitrary mapping of sample values. Supply a table that specifies how each value should be mapped. In the example program, we compute the *negative* of all colors, changing the color *c* to 255 – *c*.

The `LookupOp` constructor requires an object of type `LookupTable` and a map of optional hints. The `LookupTable` class is abstract, with two concrete subclasses: `ByteLookupTable` and `ShortLookupTable`. Since RGB color values are bytes, a `ByteLookupTable` should suffice. However, because of the bug described in https://bugs.java.com/bugdatabase/view_bug.do?bug_id=6183251, we will use a `ShortLookupTable` instead. Here is how we construct the `LookupOp` for the example program:

```
var negative = new short[256];
for (int i = 0; i < 256; i++) negative[i] = (short) (
var table = new ShortLookupTable(0, negative);
var op = new LookupOp(table, null);
```

The lookup is applied to each color component separately, but not to the alpha component. You can also supply different lookup tables for each color component—see the API notes.

Note: You cannot apply a `LookupOp` to an image with an indexed color model. (In those images, each sample value is an offset into a color palette.)

The `ColorConvertOp` is useful for color space conversions. We do not discuss it here.

The most powerful of the transformations is the `ConvolveOp`, which carries out a mathematical *convolution*. Without getting too deeply into the mathematical details, the basic idea is simple. Consider, for example, the *blur filter* (see Figure 12.58).



Figure 1.58: Blurring an image

The blurring is achieved by replacing each pixel with the *average* value from the pixel and its eight neighbors. Intuitively, it makes sense why this operation would blur out the picture. Mathematically, the averaging can be expressed as a convolution operation with the following *kernel:*

$$\begin{matrix} \frac{1}{9} & \frac{1}{9} & \frac{1}{9} \\ \frac{1}{9} & \frac{1}{9} & \frac{1}{9} \\ \frac{1}{9} & \frac{1}{9} & \frac{1}{9} \end{matrix}$$

The kernel of a convolution is a matrix that tells what weights should be applied to the neighboring values. The kernel above produces a blurred image. A different kernel carries out *edge detection,* locating the areas of color changes:

$$\begin{matrix} 0 & -1 & 0 \\ -1 & 4 & -1 \\ 0 & -1 & 0 \end{matrix}$$

Edge detection is an important technique for analyzing photographic images (see Figure 12.59).

Figure 1.59: Edge detection and inversion

To construct a convolution operation, first set up an array of the values for the kernel and construct a `Kernel` object. Then, construct a `ConvolveOp` object from the kernel and use it for filtering.

```
float[] elements =
   {
      0.0f, -1.0f, 0.0f,
      -1.0f,  4.f, -1.0f,
      0.0f, -1.0f, 0.0f
   };
```

```
var kernel = new Kernel(3, 3, elements);
var op = new ConvolveOp(kernel);
op.filter(image, filteredImage);
```

The program in Listing 12.22 allows a user to load in a GIF or JPEG image and carry out the image manipulations that we discussed. Thanks to the power of the operations provided by Java 2D API, the program is very simple.

Listing 1.22 imageProcessing/ImageProcessingFrame.java

```
1  package imageProcessing;
2
3  import java.awt.*;
4  import java.awt.geom.*;
5  import java.awt.image.*;
6  import java.io.*;
7
8  import javax.imageio.*;
9  import javax.swing.*;
10 import javax.swing.filechooser.*;
11
12 /**
13  * This frame has a menu to load an image and t
14  * component to show the resulting image.
```

```
 */
public class ImageProcessingFrame extends JFra
{
   private static final int DEFAULT_WIDTH = 40
   private static final int DEFAULT_HEIGHT = 4

   private BufferedImage image;

   public ImageProcessingFrame()
   {
      setTitle("ImageProcessingTest");
      setSize(DEFAULT_WIDTH, DEFAULT_HEIGHT);

      add(new JComponent()
         {
            public void paintComponent(Graphics
            {
               if (image != null) g.drawImage(
            }
         });

      var fileMenu = new JMenu("File");
      var openItem = new JMenuItem("Open");
      openItem.addActionListener(event -> openF
      fileMenu.add(openItem);

      var exitItem = new JMenuItem("Exit");
      exitItem.addActionListener(event -> Syste
```

```
43          fileMenu.add(exitItem);
44
45          var editMenu = new JMenu("Edit");
46          var blurItem = new JMenuItem("Blur");
47          blurItem.addActionListener(event ->
48             {
49                float weight = 1.0f / 9.0f;
50                float[] elements = new float[9];
51                for (int i = 0; i < 9; i++)
52                   elements[i] = weight;
53                convolve(elements);
54             });
55          editMenu.add(blurItem);
56
57          var sharpenItem = new JMenuItem("Sharpen"
58          sharpenItem.addActionListener(event ->
59             {
60                float[] elements = { 0.0f, -1.0f, 0
61                convolve(elements);
62             });
63          editMenu.add(sharpenItem);
64
65          var brightenItem = new JMenuItem("Brighte
66          brightenItem.addActionListener(event ->
67             {
68                float a = 1.1f;
69                float b = 20.0f;
70                var op = new RescaleOp(a, b, null);
```

```
71              filter(op);
72           });
73        editMenu.add(brightenItem);
74
75        var edgeDetectItem = new JMenuItem("Edge
76        edgeDetectItem.addActionListener(event -:
77           {
78              float[] elements = { 0.0f, -1.0f, 0
79              convolve(elements);
80           });
81        editMenu.add(edgeDetectItem);
82
83        var negativeItem = new JMenuItem("Negativ
84        negativeItem.addActionListener(event ->
85           {
86              short[] negative = new short[256 *
87              for (int i = 0; i < 256; i++)
88                 negative[i] = (short) (255 - i);
89              var table = new ShortLookupTable(0,
90              var op = new LookupOp(table, null);
91              filter(op);
92           });
93        editMenu.add(negativeItem);
94
95        var rotateItem = new JMenuItem("Rotate");
96        rotateItem.addActionListener(event ->
97           {
98              if (image == null) return;
```

```
            var transform = AffineTransform.get
                  image.getWidth() / 2, image.g
            var op = new AffineTransformOp(tran
                  AffineTransformOp.TYPE_BICUBI
            filter(op);
         });
      editMenu.add(rotateItem);

      var menuBar = new JMenuBar();
      menuBar.add(fileMenu);
      menuBar.add(editMenu);
      setJMenuBar(menuBar);
   }

   /**
    * Open a file and load the image.
    */
   public void openFile()
   {
      var chooser = new JFileChooser(".");
      chooser.setCurrentDirectory(new File(getC
      String[] extensions = ImageIO.getReaderFi
      chooser.setFileFilter(new FileNameExtensi
      int r = chooser.showOpenDialog(this);
      if (r != JFileChooser.APPROVE_OPTION) ret

      try
      {
```

```
127             Image img = ImageIO.read(chooser.getSe
128             image = new BufferedImage(img.getWidth
129                   BufferedImage.TYPE_INT_RGB);
130             image.getGraphics().drawImage(img, 0,
131          }
132          catch (IOException e)
133          {
134             JOptionPane.showMessageDialog(this, e)
135          }
136          repaint();
137       }
138
139       /**
140        * Apply a filter and repaint.
141        * @param op the image operation to apply
142        */
143       private void filter(BufferedImageOp op)
144       {
145          if (image == null) return;
146          image = op.filter(image, null);
147          repaint();
148       }
149
150       /**
151        * Apply a convolution and repaint.
152        * @param elements the convolution kernel (a
153        */
154       private void convolve(float[] elements)
```

```
155     {
156        var kernel = new Kernel(3, 3, elements);
157        var op = new ConvolveOp(kernel);
158        filter(op);
159     }
160  }
```

`java.awt.image.BufferedImageOp` **1.2**

- `BufferedImage filter(BufferedImage source, BufferedImage dest)`
  applies the image operation to the source image and stores the result in the destination image. If `dest` is `null`, a new destination image is created. The destination image is returned.

`java.awt.image.AffineTransformOp` **1.2**

- `AffineTransformOp(AffineTransform t, int interpolationType)`
  constructs an affine transform operator. The interpolation type is one of `TYPE_BILINEAR`, `TYPE_BICUBIC`, or `TYPE_NEAREST_NEIGHBOR`.

`java.awt.image.RescaleOp` **1.2**

- `RescaleOp(float a, float b, RenderingHints hints)`
- `RescaleOp(float[] as, float[] bs, RenderingHints hints)`

  construct a rescale operator that carries out the scaling operation $x_{\mathbf{new}} = a \cdot x + b$. When using the first constructor, all color components (but not the alpha component) are scaled with the same coefficients. When using the second constructor, you supply either the values for each color component, in which case the alpha component is unaffected, or the values for both alpha and color components.

`java.awt.image.LookupOp` **1.2**

- `LookupOp(LookupTable table, RenderingHints hints)`

  constructs a lookup operator for the given lookup table.

`java.awt.image.ByteLookupTable` **1.2**

- `ByteLookupTable(int offset, byte[] data)`
- `ByteLookupTable(int offset, byte[][] data)`

  construct a lookup table for converting `byte` values. The offset is subtracted from the input before the lookup. The values in the first constructor are applied to all color components but not the

alpha component. When using the second constructor, supply either the values for each color component, in which case the alpha component is unaffected, or the values for both alpha and color components.

`java.awt.image.ShortLookupTable` **1.2**

- `ShortLookupTable(int offset, short[] data)`
- `ShortLookupTable(int offset, short[][] data)`
  construct a lookup table for converting `short` values. The offset is subtracted from the input before the lookup. The values in the first constructor are applied to all color components but not the alpha component. When using the second constructor, supply either the values for each color component, in which case the alpha component is unaffected, or the values for both alpha and color components.

`java.awt.image.ConvolveOp` **1.2**

- `ConvolveOp(Kernel kernel)`
- `ConvolveOp(Kernel kernel, int edgeCondition, RenderingHints hints)`
  construct a convolution operator. The edge condition specified is one of `EDGE_NO_OP` and `EDGE_ZERO_FILL`. Edge values need to be treated specially because they don't have sufficient

neighboring values to compute the convolution. The default is `EDGE_ZERO_FILL`.

`java.awt.image.Kernel` **1.2**

- `Kernel(int width, int height, float[] matrixElements)`
  constructs a kernel for the given matrix.

1.7. Printing

In the following sections, I'll show you how you can easily print a drawing on a single sheet of paper, how you can manage a multipage printout, and how you can save a printout as a PostScript file.

1.7.1. Graphics Printing

In this section, we will tackle what is probably the most common printing situation: printing a 2D graphic. Of course, the graphic can contain text in various fonts or even consist entirely of text.

To generate a printout, you have to take care of these two tasks:

- Supply an object that implements the `Printable` interface
- Start a print job

The `Printable` interface has a single method:

```
int print(Graphics g, PageFormat format, int page)
```

That method is called whenever the print engine needs to have a page formatted for printing. Your code draws the text and the images to be printed onto the graphics context. The page format tells you the paper size and the print margins. The page number tells you which page to render.

To start a print job, use the `PrinterJob` class. First, call the static `getPrinterJob` method to get a print job object. Then set the `Printable` object that you want to print.

```
Printable canvas = . . .;
PrinterJob job = PrinterJob.getPrinterJob();
job.setPrintable(canvas);
```

Caution: The class `PrintJob` handles JDK 1.1-style printing. That class is now obsolete. Do not confuse it with the `PrinterJob` class.

Before starting the print job, you should call the `printDialog` method to display a print dialog box (see Figure 12.60). That dialog box gives the user a chance to select the printer to be used (in case

multiple printers are available), the page range that should be printed, and various printer settings.



Figure 1.60: A cross-platform print dialog box

Collect printer settings in an object of a class that implements the `PrintRequestAttributeSet` interface, such as the `HashPrintRequestAttributeSet` class.

```
var attributes = new HashPrintRequestAttributeSet();
```

Add attribute settings and pass the `attributes` object to the `printDialog` method.

The `printDialog` method returns `true` if the user clicked OK and `false` if the user canceled the dialog box. If the user accepted, call the `print` method of the `PrinterJob` class to start the printing process. The `print` method might throw a `PrinterException`. Here is the outline of the printing code:

```
if (job.printDialog(attributes))
{
   try
   {
      job.print(attributes);
   }
   catch (PrinterException e)
   {
      . . .
   }
}
```

Note: Prior to JDK 1.4, the printing system used the native print and page setup dialog boxes of the host platform. To show a native print dialog box, call the `printDialog` method with no parameters. (There is no way to collect user settings in an attribute set.)

During printing, the `print` method of the `PrinterJob` class makes repeated calls to the `print` method of the `Printable` object associated with the job.

Since the job does not know how many pages you want to print, it simply keeps calling the `print` method. As long as the `print` method returns the value `Printable.PAGE_EXISTS`, the print job keeps producing pages. When the `print` method returns `Printable.NO_SUCH_PAGE`, the print job stops.

Caution: The page numbers that the print job passes to the `print` method start with page 0.

Therefore, the print job doesn't have an accurate page count until after the printout is complete. For that reason, the print dialog box can't display the correct page range—instead, it displays "Pages 1 to 1." You will see in the next section how to avoid this blemish by supplying a `Book` object to the print job.

During the printing process, the print job repeatedly calls the `print` method of the `Printable` object. The print job is allowed to make multiple calls *for the same page.* You should therefore not count pages inside the `print` method but always rely on the page number parameter. There is a good reason why the print job might call the `print` method repeatedly for the same page. Some

printers, in particular dot-matrix and inkjet printers, use *banding.* They print one band at a time, advance the paper, and then print the next band. The print job might use banding even for laser printers that print a full page at a time—it gives the print job a way of managing the size of the spool file.

If the print job needs the `Printable` object to print a band, it sets the clip area of the graphics context to the requested band and calls the `print` method. Its drawing operations are clipped against the band rectangle, and only those drawing elements that show up in the band are rendered. Your `print` method need not be aware of that process, with one caveat: It should *not* interfere with the clip area.

Caution: The `Graphics` object that your `print` method gets is already clipped against the page margins. If you replace the clip area, you can draw outside the margins. Especially in a printer graphics context, the clipping area must be respected. Call `clip`, not `setClip`, to further restrict the clipping area. If you must remove a clip area, make sure to call `getClip` at the beginning of your `print` method and restore that clip area.

The `PageFormat` parameter of the `print` method contains information about the printed page. The methods `getWidth` and `getHeight` return the paper size, measured in *points.* (One point is

1/72 of an inch; an inch equals 25.4 millimeters.) For example, A4 paper is approximately 595 × 842 points, and US Letter paper is 612 × 792 points.

Points are a common measurement in the printing trade in the United States. Much to the chagrin of the rest of the world, the printing package uses point units. There are two purposes for that: paper sizes and paper margins are measured in points, and points are the default unit for all print graphics contexts. You can verify that in the example program at the end of this section. The program prints two lines of text that are 72 units apart. Run the example program and measure the distance between the baselines; they are exactly 1 inch or 25.4 millimeters apart.

The `getWidth` and `getHeight` methods of the `PageFormat` class give you the complete paper size. Not all of the paper area is printable. Users typically select margins, and even if they don't, printers need to somehow grip the sheets of paper on which they print and therefore have a small unprintable area around the edges.

The methods `getImageableWidth` and `getImageableHeight` tell you the dimensions of the area that you can actually fill. However, the margins need not be symmetrical, so you must also know the top left corner of the imageable area (see Figure 12.61), which you obtain by the methods `getImageableX` and `getImageableY`.



Figure 1.61: Page format measurements

Tip: The graphics context that you receive in the `print` method is clipped to exclude the margins, but the origin of the coordinate system is nevertheless the top left corner of the paper. It makes sense to translate the coordinate system to the top left corner of the imageable area. Simply start your `print` method with

```
g.translate(pageFormat.getImageableX(), pageFormat.ge
```

If you want your users to choose the settings for the page margins or to switch between portrait and landscape orientation without setting other printing attributes, call the `pageDialog` method of the `PrinterJob` class:

```
PageFormat format = job.pageDialog(attributes);
```

Note: One of the tabs of the print dialog box contains the page setup dialog (see Figure 12.62). You might still want to give users an option to set the page format before printing, especially if your program presents a "what you see is what you get" display of the pages to be printed. The `pageDialog` method returns a `PageFormat` object with the user settings.



Figure 1.62: A cross-platform page setup dialog

The program at the end of this section shows how to render the same set of shapes on the screen and on the printed page. A subclass of `JPanel` implements the `Printable` interface. Both the `paintComponent` and the `print` methods call the same method to carry out the actual drawing.

```
class PrintPanel extends JPanel implements Printable
{
   public void paintComponent(Graphics g)
   {
      super.paintComponent(g);
      var g2 = (Graphics2D) g;
```

```
         drawPage(g2);
      }

      public int print(Graphics g, PageFormat pf, int pa
      {
         if (page >= 1) return Printable.NO_SUCH_PAGE;
         var g2 = (Graphics2D) g;
         g2.translate(pf.getImageableX(), pf.getImageabl
         drawPage(g2);
         return Printable.PAGE_EXISTS;
      }

      public void drawPage(Graphics2D g2)
      {
         // shared drawing code goes here
         . . .
      }
      . . .
   }
```

This example displays and prints the image shown in Figure 12.50—namely, the outline of the message "Hello, World" used as a clipping area for a pattern of lines.

Click the Print button to start printing, or click the Page setup button to open the page setup dialog box. Listing 12.23 shows the code.

Note: To show a native page setup dialog box, pass a default `PageFormat` object to the `pageDialog` method. The method clones that object, modifies it according to the user selections in the dialog box, and returns the cloned object.

```
PageFormat defaultFormat = printJob.defaul
PageFormat selectedFormat = printJob.pageD
```

Listing 1.23 print/PrintTestFrame.java

```
1  package print;
2
3  import java.awt.*;
4  import java.awt.print.*;
5
6  import javax.print.attribute.*;
7  import javax.swing.*;
8
9  /**
10  * This frame shows a panel with 2D graphics ar
11  * the page format.
12  */
13 public class PrintTestFrame extends JFrame
14 {
```

```
15    private PrintComponent canvas;
16    private PrintRequestAttributeSet attributes;
17
18    public PrintTestFrame()
19    {
20       canvas = new PrintComponent();
21       add(canvas, BorderLayout.CENTER);
22
23       attributes = new HashPrintRequestAttribut
24
25       var buttonPanel = new JPanel();
26       var printButton = new JButton("Print");
27       buttonPanel.add(printButton);
28       printButton.addActionListener(event ->
29          {
30             try
31             {
32                PrinterJob job = PrinterJob.getP
33                job.setPrintable(canvas);
34                if (job.printDialog(attributes))
35             }
36             catch (PrinterException e)
37             {
38                JOptionPane.showMessageDialog(Pr
39             }
40          });
41
42       var pageSetupButton = new JButton("Page s
```

```
43          buttonPanel.add(pageSetupButton);
44          pageSetupButton.addActionListener(event -
45             {
46                PrinterJob job = PrinterJob.getPrin
47                job.pageDialog(attributes);
48             });
49
50          add(buttonPanel, BorderLayout.NORTH);
51          pack();
52       }
53    }
```

Listing 1.24 print/PrintComponent.java

```
1  package print;
2
3  import java.awt.*;
4  import java.awt.font.*;
5  import java.awt.geom.*;
6  import java.awt.print.*;
7  import javax.swing.*;
8
9  /**
10  * This component generates a 2D graphics image
11  */
12 public class PrintComponent extends JComponent
13 {
14    private static final Dimension PREFERRED_SIZ
```

```
15
16    public void paintComponent(Graphics g)
17    {
18       var g2 = (Graphics2D) g;
19       drawPage(g2);
20    }
21
22    public int print(Graphics g, PageFormat pf,
23    {
24       if (page >= 1) return Printable.NO_SUCH_P
25       var g2 = (Graphics2D) g;
26       g2.translate(pf.getImageableX(), pf.getIm
27       g2.draw(new Rectangle2D.Double(0, 0, pf.g
28
29       drawPage(g2);
30       return Printable.PAGE_EXISTS;
31    }
32
33    /**
34     * This method draws the page both on the sc
35     * @param g2 the graphics context
36     */
37    public void drawPage(Graphics2D g2)
38    {
39       FontRenderContext context = g2.getFontRen
40       var f = new Font("Serif", Font.PLAIN, 72)
41       var clipShape = new GeneralPath();
42
```

```
43          var layout = new TextLayout("Hello", f, c
44          AffineTransform transform = AffineTransfo
45          Shape outline = layout.getOutline(transfo
46          clipShape.append(outline, false);
47
48          layout = new TextLayout("World", f, conte
49          transform = AffineTransform.getTranslateI
50          outline = layout.getOutline(transform);
51          clipShape.append(outline, false);
52
53          g2.draw(clipShape);
54          g2.clip(clipShape);
55
56          final int NLINES = 50;
57          var p = new Point2D.Double(0, 0);
58          for (int i = 0; i < NLINES; i++)
59          {
60             double x = (2 * getWidth() * i) / NLIN
61             double y = (2 * getHeight() * (NLINES
62             var q = new Point2D.Double(x, y);
63             g2.draw(new Line2D.Double(p, q));
64          }
65       }
66
67       public Dimension getPreferredSize() { return
68    }
```

`java.awt.print.Printable` **1.2**

- `int print(Graphics g, PageFormat format, int pageNumber)`
  renders a page and returns `PAGE_EXISTS`, or returns `NO_SUCH_PAGE`.

`java.awt.print.PrinterJob` **1.2**

- `static PrinterJob getPrinterJob()`
  returns a printer job object.
- `PageFormat defaultPage()`
  returns the default page format for this printer.
- `boolean printDialog(PrintRequestAttributeSet attributes)`
- `boolean printDialog()`
  open a print dialog box to allow a user to select the pages to be printed and to change print settings. The first method displays a cross-platform dialog box, the second a native dialog box. The first method modifies the `attributes` object to reflect the user settings. Both methods return `true` if the user accepts the dialog box.

- `PageFormat pageDialog(PrintRequestAttributeSet attributes)`
- `PageFormat pageDialog(PageFormat defaults)`
  display a page setup dialog box. The first method displays a cross-platform dialog box, the second a native dialog box. Both methods return a `PageFormat` object with the format that the user requested in the dialog box. The first method modifies the `attributes` object to reflect the user settings. The second method does not modify the `defaults` object.
- `void setPrintable(Printable p)`
- `void setPrintable(Printable p, PageFormat format)`
  set the `Printable` of this print job and an optional page format.
- `void print()`
- `void print(PrintRequestAttributeSet attributes)`
  print the current `Printable` by repeatedly calling its `print` method and sending the rendered pages to the printer, until no more pages are available.

`java.awt.print.PageFormat` **1.2**

- `double getWidth()`
- `double getHeight()`
  return the width and height of the page.

- `double getImageableWidth()`
- `double getImageableHeight()`
  return the width and height of the imageable area of the page.
- `double getImageableX()`
- `double getImageableY()`
  return the position of the top left corner of the imageable area.
- `int getOrientation()`
  returns one of `PORTRAIT`, `LANDSCAPE`, or `REVERSE_LANDSCAPE`. Page orientation is transparent to programmers because the page format and graphics context settings automatically reflect the page orientation.

1.7.2. Multiple-Page Printing

In practice, you usually don't pass a raw `Printable` object to a print job. Instead, you should obtain an object of a class that implements the `Pageable` interface. The Java platform supplies one such class, called `Book`. A book is made up of sections, each of which is a `Printable` object. To make a book, add `Printable` objects and their page counts.

```
var book = new Book();
Printable coverPage = . . .;
Printable bodyPages = . . .;
book.append(coverPage, pageFormat); // append 1 page
```

```
book.append(bodyPages, pageFormat, pageCount);
```

Then, use the `setPageable` method to pass the `Book` object to the print job.

```
printJob.setPageable(book);
```

Now the print job knows exactly how many pages to print, so the print dialog box displays an accurate page range and the user can select the entire range or subranges.

Caution: When the print job calls the `print` methods of the `Printable` sections, it passes the current page number of the *book*, and not of each *section*, as the current page number. That is a huge pain—each section must know the page counts of the preceding sections to make sense of the page number parameter.

From your perspective as a programmer, the biggest challenge of using the `Book` class is that you must know how many pages each section will have when you print it. Your `Printable` class needs a *layout algorithm* that computes the layout of the material on the printed pages. Before printing starts, invoke that algorithm to compute the page breaks and the page count. You can retain the layout information so you have it handy during the printing process.

You must guard against the possibility that the user has changed the page format. If that happens, you must recompute the layout, even if the information that you want to print has not changed.

Listing 12.26 shows how to produce a multipage printout. This program prints a message in very large characters on a number of pages (see Figure 12.63). You can then trim the margins and tape the pages together to form a banner.



Figure 1.63: A banner

The `layoutPages` method of the `Banner` class computes the layout. We first lay out the message string in a 72-point font. We then compute the height of the resulting string and compare it with the imageable height of the page. We derive a scale factor from these two measurements. When printing the string, we magnify it by that scale factor.

Caution: To lay out your information precisely, you usually need access to the printer graphics context. Unfortunately, there is no way

to obtain that graphics context before printing actually starts. In our example program, we make do with the screen graphics context and hope that the font metrics of the screen and printer match.

The `getPageCount` method of the `Banner` class first calls the layout method. Then it scales up the width of the string and divides it by the imageable width of each page. The quotient, rounded up to the next integer, is the page count.

It sounds like it might be difficult to print the banner because characters can be broken across multiple pages. However, thanks to the power of the Java 2D API, this turns out not to be a problem at all. When a particular page is requested, we simply use the `translate` method of the `Graphics2D` class to shift the top left corner of the string to the left. Then, we set a clip rectangle that equals the current page (see Figure 12.64). Finally, we scale the graphics context with the scale factor that the layout method computed.



Figure 1.64: Printing a page of a banner

This example shows the power of transformations. The drawing code is kept simple, and the transformation does all the work of placing the drawing in the appropriate place. Finally, the clip cuts away the part of the image that falls outside the page. This program shows another compelling use of transformations—to display a print preview.

Listing 1.25 book/BookTestFrame.java

```
1  package book;
2
3  import java.awt.*;
4  import java.awt.print.*;
5
```

```
6  import javax.print.attribute.*;
7  import javax.swing.*;
8
9  /**
10  * This frame has a text field for the banner t
11  * print preview.
12  */
13 public class BookTestFrame extends JFrame
14 {
15    private JTextField text;
16    private PageFormat pageFormat;
17    private PrintRequestAttributeSet attributes;
18
19    public BookTestFrame()
20    {
21       text = new JTextField();
22       add(text, BorderLayout.NORTH);
23
24       attributes = new HashPrintRequestAttribut
25
26       var buttonPanel = new JPanel();
27
28       var printButton = new JButton("Print");
29       buttonPanel.add(printButton);
30       printButton.addActionListener(event ->
31          {
32             try
33             {
```

```
34                PrinterJob job = PrinterJob.getP
35                job.setPageable(makeBook());
36                if (job.printDialog(attributes))
37                {
38                   job.print(attributes);
39                }
40             }
41             catch (PrinterException e)
42             {
43                JOptionPane.showMessageDialog(Bo
44             }
45          });
46
47       var pageSetupButton = new JButton("Page s
48       buttonPanel.add(pageSetupButton);
49       pageSetupButton.addActionListener(event -
50          {
51             PrinterJob job = PrinterJob.getPrin
52             pageFormat = job.pageDialog(attribu
53          });
54
55       var printPreviewButton = new JButton("Pri
56       buttonPanel.add(printPreviewButton);
57       printPreviewButton.addActionListener(ever
58          {
59             var dialog = new PrintPreviewDialog
60             dialog.setVisible(true);
61          });
```

```
62
63          add(buttonPanel, BorderLayout.SOUTH);
64          pack();
65       }
66
67       /**
68        * Makes a book that contains a cover page a
69        */
70       public Book makeBook()
71       {
72          if (pageFormat == null)
73          {
74             PrinterJob job = PrinterJob.getPrinter
75             pageFormat = job.defaultPage();
76          }
77          var book = new Book();
78          String message = text.getText();
79          var banner = new Banner(message);
80          int pageCount = banner.getPageCount((Grap
81          book.append(new CoverPage(message + " ("
82          book.append(banner, pageFormat, pageCount
83          return book;
84       }
85    }
```

Listing 1.26 book/Banner.java

```
1  package book;
2
3  import java.awt.*;
4  import java.awt.font.*;
5  import java.awt.geom.*;
6  import java.awt.print.*;
7
8  /**
9   * A banner that prints a text string on multip
10  */
11 public class Banner implements Printable
12 {
13    private String message;
14    private double scale;
15
16    /**
17     * Constructs a banner.
18     * @param m the message string
19     */
20    public Banner(String m)
21    {
22       message = m;
23    }
24
25    /**
26     * Gets the page count of this section.
```

```
27      * @param g2 the graphics context
28      * @param pf the page format
29      * @return the number of pages needed
30      */
31     public int getPageCount(Graphics2D g2, PageF
32     {
33        if (message.equals("")) return 0;
34        FontRenderContext context = g2.getFontRen
35        var f = new Font("Serif", Font.PLAIN, 72)
36        Rectangle2D bounds = f.getStringBounds(me
37        scale = pf.getImageableHeight() / bounds
38        double width = scale * bounds.getWidth();
39        int pages = (int) Math.ceil(width / pf.ge
40        return pages;
41     }
42
43     public int print(Graphics g, PageFormat pf,
44     {
45        var g2 = (Graphics2D) g;
46        if (page > getPageCount(g2, pf)) return P
47        g2.translate(pf.getImageableX(), pf.getIm
48
49        drawPage(g2, pf, page);
50        return Printable.PAGE_EXISTS;
51     }
52
53     public void drawPage(Graphics2D g2, PageForm
54     {
```

```
55          if (message.equals("")) return;
56          page--; // account for cover page
57
58          drawCropMarks(g2, pf);
59          g2.clip(new Rectangle2D.Double(0, 0, pf.g
60          g2.translate(-page * pf.getImageableWidth
61          g2.scale(scale, scale);
62          FontRenderContext context = g2.getFontRen
63          var f = new Font("Serif", Font.PLAIN, 72)
64          var layout = new TextLayout(message, f, c
65          AffineTransform transform = AffineTransfo
66          Shape outline = layout.getOutline(transfo
67          g2.draw(outline);
68       }
69
70       /**
71        * Draws 1/2" crop marks in the corners of t
72        * @param g2 the graphics context
73        * @param pf the page format
74        */
75       public void drawCropMarks(Graphics2D g2, Pag
76       {
77          final double C = 36; // crop mark length
78          double w = pf.getImageableWidth();
79          double h = pf.getImageableHeight();
80          g2.draw(new Line2D.Double(0, 0, 0, C));
81          g2.draw(new Line2D.Double(0, 0, C, 0));
82          g2.draw(new Line2D.Double(w, 0, w, C));
```

```
83          g2.draw(new Line2D.Double(w, 0, w - C, 0)
84          g2.draw(new Line2D.Double(0, h, 0, h - C)
85          g2.draw(new Line2D.Double(0, h, C, h));
86          g2.draw(new Line2D.Double(w, h, w, h - C)
87          g2.draw(new Line2D.Double(w, h, w - C, h)
88       }
89    }
90
91    /**
92     * This class prints a cover page with a title
93     */
94    class CoverPage implements Printable
95    {
96       private String title;
97
98       /**
99        * Constructs a cover page.
100       * @param t the title
101       */
102      public CoverPage(String t)
103      {
104         title = t;
105      }
106
107      public int print(Graphics g, PageFormat pf,
108      {
109         if (page >= 1) return Printable.NO_SUCH_P
110         var g2 = (Graphics2D) g;
```

```
111         g2.setPaint(Color.black);
112         g2.translate(pf.getImageableX(), pf.getIm
113         FontRenderContext context = g2.getFontRen
114         Font f = g2.getFont();
115         var layout = new TextLayout(title, f, con
116         float ascent = layout.getAscent();
117         g2.drawString(title, 0, ascent);
118         return Printable.PAGE_EXISTS;
119      }
120   }
```

Listing 1.27 book/PrintPreviewDialog.java

```
1  package book;
2
3  import java.awt.*;
4  import java.awt.print.*;
5
6  import javax.swing.*;
7
8  /**
9   * This class implements a generic print previe
10  */
11 public class PrintPreviewDialog extends JDialog
12 {
13    private static final int DEFAULT_WIDTH = 300
14    private static final int DEFAULT_HEIGHT = 30
15
```

```
16    private PrintPreviewCanvas canvas;
17
18    /**
19     * Constructs a print preview dialog.
20     * @param p a Printable
21     * @param pf the page format
22     * @param pages the number of pages in p
23     */
24    public PrintPreviewDialog(Printable p, PageF
25    {
26       var book = new Book();
27       book.append(p, pf, pages);
28       layoutUI(book);
29    }
30
31    /**
32     * Constructs a print preview dialog.
33     * @param b a Book
34     */
35    public PrintPreviewDialog(Book b)
36    {
37       layoutUI(b);
38    }
39
40    /**
41     * Lays out the UI of the dialog.
42     * @param book the book to be previewed
43     */
```

```
44      public void layoutUI(Book book)
45      {
46         setSize(DEFAULT_WIDTH, DEFAULT_HEIGHT);
47
48         canvas = new PrintPreviewCanvas(book);
49         add(canvas, BorderLayout.CENTER);
50
51         var buttonPanel = new JPanel();
52
53         var nextButton = new JButton("Next");
54         buttonPanel.add(nextButton);
55         nextButton.addActionListener(event -> car
56
57         var previousButton = new JButton("Previou
58         buttonPanel.add(previousButton);
59         previousButton.addActionListener(event ->
60
61         var closeButton = new JButton("Close");
62         buttonPanel.add(closeButton);
63         closeButton.addActionListener(event -> se
64
65         add(buttonPanel, BorderLayout.SOUTH);
66      }
67   }
```

Listing 1.28 book/PrintPreviewCanvas.java

```
1  package book;
2
3  import java.awt.*;
4  import java.awt.geom.*;
5  import java.awt.print.*;
6  import javax.swing.*;
7
8  /**
9   * The canvas for displaying the print preview
10  */
11 class PrintPreviewCanvas extends JComponent
12 {
13    private Book book;
14    private int currentPage;
15
16    /**
17     * Constructs a print preview canvas.
18     * @param b the book to be previewed
19     */
20    public PrintPreviewCanvas(Book b)
21    {
22       book = b;
23       currentPage = 0;
24    }
25
26    public void paintComponent(Graphics g)
```

```
27      {
28         var g2 = (Graphics2D) g;
29         PageFormat pageFormat = book.getPageForma
30
31         double xoff; // x offset of page start in
32         double yoff; // y offset of page start in
33         double scale; // scale factor to fit page
34         double px = pageFormat.getWidth();
35         double py = pageFormat.getHeight();
36         double sx = getWidth() - 1;
37         double sy = getHeight() - 1;
38         if (px / py < sx / sy) // center horizont
39         {
40            scale = sy / py;
41            xoff = 0.5 * (sx - scale * px);
42            yoff = 0;
43         }
44         else
45         // center vertically
46         {
47            scale = sx / px;
48            xoff = 0;
49            yoff = 0.5 * (sy - scale * py);
50         }
51         g2.translate((float) xoff, (float) yoff);
52         g2.scale((float) scale, (float) scale);
53
54         // draw page outline (ignoring margins)
```

```
55          var page = new Rectangle2D.Double(0, 0, p
56          g2.setPaint(Color.white);
57          g2.fill(page);
58          g2.setPaint(Color.black);
59          g2.draw(page);
60
61          Printable printable = book.getPrintable(c
62          try
63          {
64             printable.print(g2, pageFormat, curren
65          }
66          catch (PrinterException e)
67          {
68             g2.draw(new Line2D.Double(0, 0, px, py
69             g2.draw(new Line2D.Double(px, 0, 0, py
70          }
71       }
72
73       /**
74        * Flip the book by the given number of page
75        * @param by the number of pages to flip by
76        */
77       public void flipPage(int by)
78       {
79          int newPage = currentPage + by;
80          if (0 <= newPage && newPage < book.getNum
81          {
82             currentPage = newPage;
```

```
            repaint();
        }
    }
}
```

1.7.3. Print Services

So far, you have seen how to print 2D graphics. However, the printing API affords far greater flexibility. The API defines a number of data types and lets you find print services that are able to print them. Among the data types are

- Images in GIF, JPEG, or PNG format
- Documents in text, HTML, PostScript, or PDF format
- Raw printer code data
- Objects of a class that implements `Printable`, `Pageable`, or `RenderableImage`

The data themselves can be stored in a source of bytes or characters such as an input stream, a URL, or an array. A *document flavor* describes the combination of a data source and a data type. The `DocFlavor` class defines a number of inner classes for the various data sources. Each of the inner classes defines constants to specify the flavors. For example, the constant

```
DocFlavor.INPUT_STREAM.GIF
```

describes a GIF image that is read from an input stream. Table 12.4 lists the combinations.

Table 1.4: Document Flavors for Print Services

Data Source	Data Type	MIME Type
`INPUT_STREAM`	`GIF`	`image/gif`
`URL`	`JPEG`	`image/jpeg`
`BYTE_ARRAY`	`PNG`	`image/png`
	`POSTSCRIPT`	`applicati`
	`PDF`	`applicati`
	`TEXT_HTML_HOST`	`text/html` encoding)
	`TEXT_HTML_US_ASCII`	`text/html` `ascii`

Data Source	Data Type	MIME Type
	`TEXT_HTML_UTF_8`	`text/html` `charset=ut`
	`TEXT_HTML_UTF_16`	`text/html` `charset=ut`

	`TEXT_HTML_UTF_16LE`	`text/html`
		`charset=ut`
		endian)

	`TEXT_HTML_UTF_16BE`	`text/html`
		`charset=ut`
		endian)

	`TEXT_PLAIN_HOST`	`text/plai` encoding)
	`TEXT_PLAIN_US_ASCII`	`text/plai` `charset=us`
	`TEXT_PLAIN_UTF_8`	`text/plai`

Data Source	Data Type	MIME Type
		`charset=ut`
	`TEXT_PLAIN_UTF_16`	`text/plai` `charset=ut`
	`TEXT_PLAIN_UTF_16LE`	`text/plai` `charset=ut` endian)
	`TEXT_PLAIN_UTF_16BE`	`text/plai` `charset=ut` endian)
	`PCL`	`applicati` (Hewlett Pac Control Lang
	`AUTOSENSE`	`applicati` `stream` (rav
`READER`	`TEXT_HTML`	`text/html` `charset=ut`

Data Source	Data Type	MIME Type
`STRING`	`TEXT_PLAIN`	`text/plai charset=ut`
`CHAR_ARRAY`		
`SERVICE_FORMATTED`	`PRINTABLE`	N/A
	`PAGEABLE`	N/A
	`RENDERABLE_IMAGE`	N/A

Suppose you want to print a GIF image located in a file. First, find out whether there is a *print service* that is capable of handling the task. The static `lookupPrintServices` method of the `PrintServiceLookup` class returns an array of `PrintService` objects that can handle the given document flavor.

```
DocFlavor flavor = DocFlavor.INPUT_STREAM.GIF;
PrintService[] services = PrintServiceLookup.lookupPr
```

The second argument of the `lookupPrintServices` method is `null` to indicate that we don’t want to constrain the search by specifying printer attributes. We'll cover attributes in the next section.

If the lookup yields an array with more than one element, select from the listed print services. You can call the `getName` method of the `PrintService` class to get the printer names and let the user choose.

Next, get a document print job from the service:

```
DocPrintJob job = services[i].createPrintJob();
```

For printing, you need an object that implements the `Doc` interface. The Java library supplies a class `SimpleDoc` for that purpose. The `SimpleDoc` constructor requires the data source object, the document flavor, and an optional attribute set. For example,

```
var in = new FileInputStream(fileName);
var doc = new SimpleDoc(in, flavor, null);
```

Finally, you are ready to print:

```
job.print(doc, null);
```

As before, the `null` argument can be replaced by an attribute set.

Note that this printing process is quite different from that of the preceding section. There is no user interaction through print dialog boxes. For example, you can implement a server-side printing mechanism in which users submit print jobs through a web form.

`javax.print.PrintServiceLookup` **1.4**

- `PrintService[] lookupPrintServices(DocFlavor flavor, AttributeSet attributes)`
  looks up the print services that can handle the given document flavor and attributes. The `attributes` parameter can be `null` if there are no attributes to consider.

`javax.print.PrintService` **1.4**

- `DocPrintJob createPrintJob()`
  creates a print job for printing an object of a class that implements the `Doc` interface, such as a `SimpleDoc`.

`javax.print.DocPrintJob` 1.4

- `void print(Doc doc, PrintRequestAttributeSet attributes)`
  prints the given document with the given attributes. The `attributes` parameter can be `null` if no printing attributes are required.

`javax.print.SimpleDoc` 1.4

- `SimpleDoc(Object data, DocFlavor flavor, DocAttributeSet attributes)`
  constructs a `SimpleDoc` object that can be printed with a `DocPrintJob`. The `data` parameter is the object with the print data, such as an input stream or a `Printable`. The `attributes` parameter can be `null` if attributes are not required.

1.7.4. Stream Print Services

A print service sends print data to a printer. A stream print service generates the same print data but instead sends them to a stream, perhaps for delayed printing or because the print data format can be interpreted by other programs. In particular, if the print data format is PostScript, it may be useful to save the print data to a file because

many programs can process PostScript files. The Java platform includes a stream print service that can produce PostScript output from images and 2D graphics. You can use that service on all systems, even if there are no local printers.

Enumerating stream print services is a bit more tedious than locating regular print services. You need both the `DocFlavor` of the object to be printed and the MIME type of the stream output. You then get a `StreamPrintServiceFactory` array of factories.

```
DocFlavor flavor = DocFlavor.SERVICE_FORMATTED.PRINTA
String mimeType = "application/postscript";
StreamPrintServiceFactory[] factories
   = StreamPrintServiceFactory.lookupStreamPrintServi
```

The `StreamPrintServiceFactory` class has no methods that would help us distinguish any one factory from another, so we just take `factories[0]`. We call the `getPrintService` method with an output stream parameter to get a `StreamPrintService` object.

```
var out = new FileOutputStream(fileName);
StreamPrintService service = factories[0].getPrintSer
```

The `StreamPrintService` class is a subclass of `PrintService`. To produce a printout, simply follow the steps of the preceding section.

`javax.print.StreamPrintServiceFactory` **1.4**

- `StreamPrintServiceFactory[] lookupStreamPrintServiceFactories(DocFlavor flavor, String mimeType)`
  looks up the stream print service factories that can print the given document flavor and produce an output stream of the given MIME type.
- `StreamPrintService getPrintService(OutputStream out)`
  gets a print service that sends the printing output to the given output stream.

The program in Listing 12.29 demonstrates how to use a stream print service to print Java 2D shapes to a PostScript file. You can replace the sample drawing code with code that generates any Java 2D shapes and have the shapes converted to PostScript. Then you can easily convert the result to PDF or EPS, using an external tool. (Unfortunately, Java does not support printing to PDF directly.)

Note: In this example, we call a `draw` method that draws Java 2D shapes onto a `Graphics2D` object. If you want to draw the surface of a component (for example, a table or tree), use the following code:

```
  private static int IMAGE_WIDTH = component
  private static int IMAGE_HEIGHT = componen
  public static void draw(Graphics2D g2) { c
```

Listing 1.29 printService/PrintServiceTest.java

```
1  package printService;
2
3  import java.awt.*;
4  import java.awt.font.*;
5  import java.awt.geom.*;
6  import java.awt.print.*;
7  import java.io.*;
8  import javax.print.*;
9  import javax.print.attribute.*;
10
11 /**
12  * This program demonstrates the use of stream
13  * Java 2D shapes to a PostScript file. If you
14  * line, the output is saved to out.ps.
```

```
 * @version 1.0 2018-06-01
 * @author Cay Horstmann
 */
public class PrintServiceTest
{
   // Set your image dimensions here
   private static int IMAGE_WIDTH = 300;
   private static int IMAGE_HEIGHT = 300;

   public static void draw(Graphics2D g2)
   {
      // Your drawing instructions go here
      FontRenderContext context = g2.getFontRen
      var f = new Font("Serif", Font.PLAIN, 72)
      var clipShape = new GeneralPath();

      var layout = new TextLayout("Hello", f, c
      AffineTransform transform = AffineTransfo
      Shape outline = layout.getOutline(transfo
      clipShape.append(outline, false);

      layout = new TextLayout("World", f, conte
      transform = AffineTransform.getTranslateI
      outline = layout.getOutline(transform);
      clipShape.append(outline, false);

      g2.draw(clipShape);
      g2.clip(clipShape);
```

```
43
44          final int NLINES = 50;
45          var p = new Point2D.Double(0, 0);
46          for (int i = 0; i < NLINES; i++)
47          {
48             double x = (2 * IMAGE_WIDTH * i) / NLI
49             double y = (2 * IMAGE_HEIGHT * (NLINES
50             var q = new Point2D.Double(x, y);
51             g2.draw(new Line2D.Double(p, q));
52          }
53       }
54
55       public static void main(String[] args) throw
56       {
57          String fileName = args.length > 0 ? args|
58          DocFlavor flavor = DocFlavor.SERVICE_FORM
59          String mimeType = "application/postscript
60          StreamPrintServiceFactory[] factories
61             = StreamPrintServiceFactory.lookupStre
62          var out = new FileOutputStream(fileName);
63          if (factories.length > 0)
64          {
65             PrintService service = factories[0].ge
66             var doc = new SimpleDoc(new Printable(
67                {
68                   public int print(Graphics g, Pag
69                   {
70                      if (page >= 1) return Printab
```

```
71                   else
72                   {
73                      double sf1 = pf.getImageab
74                      double sf2 = pf.getImageab
75                      double s = Math.min(sf1, s
76                      var g2 = (Graphics2D) g;
77                      g2.translate((pf.getWidth(
78                         (pf.getHeight() - pf.ge
79                      g2.scale(s, s);
80
81                      draw(g2);
82                      return Printable.PAGE_EXIS
83                   }
84                }
85             }, flavor, null);
86          DocPrintJob job = service.createPrintJ
87          var attributes = new HashPrintRequestA
88          job.print(doc, attributes);
89       }
90       else
91          System.out.println("No factories for "
92    }
93 }
```

1.7.5. Printing Attributes

The print service API contains a complex set of interfaces and classes to specify various kinds of attributes. There are four

important groups of attributes. The first two specify requests to the printer.

- *Print request attributes* request particular features for all `doc` objects in a print job, such as two-sided printing or the paper size.
- *Doc attributes* are request attributes that apply only to a single `doc` object.

The other two attributes contain information about the printer and job status.

- *Print service attributes* give information about the print service, such as the printer make and model or whether the printer is currently accepting jobs.
- *Print job attributes* give information about the status of a particular print job, such as whether the job is already completed.

To describe the various attributes, there is an interface `Attribute` with subinterfaces:

```
PrintRequestAttribute
DocAttribute
PrintServiceAttribute
PrintJobAttribute
```

```
  SupportedValuesAttribute
```

Individual attribute classes implement one or more of these interfaces. For example, objects of the `Copies` class describe the number of copies of a printout. That class implements both the `PrintRequestAttribute` and the `PrintJobAttribute` interfaces. Clearly, a print request can contain a request for multiple copies. Conversely, an attribute of the print job might be how many of these copies were actually printed. That number might be lower, perhaps because of printer limitations or because the printer ran out of paper.

The `SupportedValuesAttribute` interface indicates that an attribute value does not reflect actual request or status data but rather the capability of a service. For example, the `CopiesSupported` class implements the `SupportedValuesAttribute` interface. An object of that class might describe that a printer supports 1 through 99 copies of a printout.

Figure 12.65 shows a class diagram of the attribute hierarchy.



Figure 1.65: The attribute hierarchy

In addition to the interfaces and classes for individual attributes, the print service API defines interfaces and classes for attribute sets. A superinterface, `AttributeSet`, has four subinterfaces:

```
PrintRequestAttributeSet
DocAttributeSet
PrintServiceAttributeSet
PrintJobAttributeSet
```

Each of these interfaces has an implementing class, yielding the five classes:

```
HashAttributeSet
HashPrintRequestAttributeSet
HashDocAttributeSet
HashPrintServiceAttributeSet
HashPrintJobAttributeSet
```

Figure 12.66 shows a class diagram of the attribute set hierarchy.



Figure 1.66: The attribute set hierarchy

For example, you can construct a print request attribute set like this:

```
var attributes = new HashPrintRequestAttributeSet();
```

After constructing the set, you are freed from worrying about the `Hash` prefix.

Why have all these interfaces? They make it possible to check for correct attribute usage. For example, a `DocAttributeSet` accepts only objects that implement the `DocAttribute` interface. Any attempt to add another attribute results in a runtime error.

An attribute set is a specialized kind of map where the keys are of type `Class` and the values belong to a class that implements the `Attribute` interface. For example, if you insert an object

```
new Copies(10)
```

into an attribute set, then its key is the `Class` object `Copies.class`. That key is called the *category* of the attribute. The `Attribute` interface declares a method

```
Class getCategory()
```

that returns the category of an attribute. The `Copies` class defines the method to return the object `Copies.class`, but it isn't a requirement that the category be the same as the class of the attribute.

When an attribute is added to an attribute set, the category is extracted automatically. Just add the attribute value:

```
attributes.add(new Copies(10));
```

If you subsequently add another attribute with the same category, it overwrites the first one.

To retrieve an attribute, you need to use the category as the key, for example:

```
AttributeSet attributes = job.getAttributes();
var copies = (Copies) attribute.get(Copies.class);
```

Finally, attributes are organized by the values they can have. The `Copies` attribute can have any integer value. The `Copies` class extends the `IntegerSyntax` class that takes care of all integer-valued attributes. The `getValue` method returns the integer value of the attribute, for example:

```
int n = copies.getValue();
```

The classes

```
TextSyntax
DateTimeSyntax
URISyntax
```

encapsulate a string, a date and time value, or a URI.

Finally, many attributes can take a finite number of values. For example, the `PrintQuality` attribute has three settings: draft, normal, and high. They are represented by three constants:

```
PrintQuality.DRAFT
PrintQuality.NORMAL
PrintQuality.HIGH
```

Attribute classes with a finite number of values extend the `EnumSyntax` class, which provides a number of convenience methods to set up these enumerations in a typesafe manner. You need not worry about the mechanism when using such an attribute. Simply add the named values to attribute sets:

```
attributes.add(PrintQuality.HIGH);
```

Here is how you check the value of an attribute:

```
if (attributes.get(PrintQuality.class) == PrintQualit
   . . .
```

Table 12.5 lists the printing attributes. The second column lists the superclass of the attribute class (for example, `IntegerSyntax` for the `Copies` attribute) or the set of enumeration values for the attributes with a finite set of values. The last four columns indicate whether the attribute class implements the `DocAttribute` (DA), `PrintJobAttribute` (PJA), `PrintRequestAttribute` (PRA), and `PrintServiceAttribute` (PSA) interfaces.

Table 1.5: Printing Attributes

Attribute	Superclass or Enumeration
`Chromaticity`	`MONOCHROME`, `COLOR`
`ColorSupported`	`SUPPORTED`, `NOT_SUPPOR`
`Compression`	`COMPRESS`, `DEFLATE`, `GZ`
`Copies`	`IntegerSyntax`
`DateTimeAtCompleted`	`DateTimeSyntax`

Attribute	Superclass or Enumeration
`DateTimeAtCreation`	`DateTimeSyntax`
`DateTimeAtProcessing`	`DateTimeSyntax`
`Destination`	`URISyntax`
`DocumentName`	`TextSyntax`
`Fidelity`	`FIDELITY_TRUE`, `FIDELI`
`Finishings`	`NONE`, `STAPLE`, `EDGE_ST` `SADDLE_STITCH`, `COVER`,
`JobHoldUntil`	`DateTimeSyntax`
`JobImpressions`	`IntegerSyntax`
`JobImpressionsCompleted`	`IntegerSyntax`
`JobKOctets`	`IntegerSyntax`
`JobKOctetsProcessed`	`IntegerSyntax`

Attribute	Superclass or Enumeration
`JobMediaSheets`	`IntegerSyntax`
`JobMediaSheetsCompleted`	`IntegerSyntax`
`JobMessageFromOperator`	`TextSyntax`
`JobName`	`TextSyntax`
`JobOriginatingUserName`	`TextSyntax`
`JobPriority`	`IntegerSyntax`
`JobSheets`	`STANDARD`, `NONE`
`JobState`	`ABORTED`, `CANCELED`, `COM` `PENDING`, `PENDING_HELD` `PROCESSING_STOPPED`
`JobStateReason`	`ABORTED_BY_SYSTEM`, `DOCUMENT_FORMAT_ERROR`

Attribute	Superclass or Enumeration
`JobStateReasons`	`HashSet`
`MediaName`	`ISO_A4_WHITE`, `ISO_A4_T` `NA_LETTER_WHITE`, `NA_LETTER_TRANSPARENT`
`MediaSize`	`ISO.A0` – `ISO.A10`, `ISO.E` `ISO.C0` – `ISO.C10`, `NA.LE` `NA.LEGAL`, various other p envelope sizes
`MediaSizeName`	`ISO_A0` – `ISO_A10`, `ISO_E` `ISO_C0` – `ISO_C10`, `NA_LE` `NA_LEGAL`, various other p envelope size names
`MediaTray`	`TOP`, `MIDDLE`, `BOTTOM`, `S` `LARGE_CAPACITY`, `MAIN`,
`MultipleDocumentHandling`	`SINGLE_DOCUMENT`, `SINGLE_DOCUMENT_NEW_SH`

Attribute	Superclass or Enumeration
	`SEPARATE_DOCUMENTS_COL` `SEPARATE_DOCUMENTS_UNC`
`NumberOfDocuments`	`IntegerSyntax`
`NumberOfInterveningJobs`	`IntegerSyntax`
`NumberUp`	`IntegerSyntax`
`OrientationRequested`	`PORTRAIT`, `LANDSCAPE`, `REVERSE_PORTRAIT`, `REVE`
`OutputDeviceAssigned`	`TextSyntax`
`PageRanges`	`SetOfInteger`
`PagesPerMinute`	`IntegerSyntax`
`PagesPerMinuteColor`	`IntegerSyntax`
`PDLOverrideSupported`	`ATTEMPTED`, `NOT_ATTEMPT`

Attribute	Superclass or Enumeration

`PresentationDirection`	`TORIGHT_TOBOTTOM`, `TORI`
	`TOBOTTOM_TORIGHT`, `TOBO`
	`TOLEFT_TOBOTTOM`, `TOLEF`
	`TOTOP_TORIGHT`, `TOTOP_T`

`PrinterInfo`	`TextSyntax`
`PrinterIsAcceptingJobs`	`ACCEPTING_JOBS`, `NOT_AC`
`PrinterLocation`	`TextSyntax`
`PrinterMakeAndModel`	`TextSyntax`
`PrinterMessageFromOperator`	`TextSyntax`
`PrinterMoreInfo`	`URISyntax`
`PrinterMoreInfoManufacturer`	`URISyntax`
`PrinterName`	`TextSyntax`
`PrinterResolution`	`ResolutionSyntax`

Attribute	Superclass or Enumeration
`PrinterState`	`PROCESSING`, `IDLE`, `STOP`
`PrinterStateReason`	`COVER_OPEN`, `FUSER_OVER` `MEDIA_JAM`, and many oth
`PrinterStateReasons`	`HashMap`
`PrinterURI`	`URISyntax`
`PrintQuality`	`DRAFT`, `NORMAL`, `HIGH`
`QueuedJobCount`	`IntegerSyntax`
`ReferenceUriSchemesSupported`	`FILE`, `FTP`, `GOPHER`, `HTT` `NEWS`, `NNTP`, `WAIS`
`RequestingUserName`	`TextSyntax`
`Severity`	`ERROR`, `REPORT`, `WARNING`
`SheetCollate`	`COLLATED`, `UNCOLLATED`

Attribute	Superclass or Enumeration
`Sides`	`ONE_SIDED`, `DUPLEX` (= `TWO_SIDED_LONG_EDGE`), `TWO_SIDED_SHORT_EDGE`)

Note: As you can see, there are lots of attributes, many of which are quite specialized. The source for most of the attributes is the Internet Printing Protocol 1.1 (RFC 2911).

Note: An earlier version of the printing API introduced the `JobAttributes` and `PageAttributes` classes, whose purpose was similar to the printing attributes covered in this section. These classes are now obsolete.

`javax.print.attribute.Attribute` **1.4**

- `Class getCategory()`
  gets the category of this attribute.

- `String getName()`
  gets the name of this attribute.

`javax.print.attribute.AttributeSet` **1.4**

- `boolean add(Attribute attr)`
  adds an attribute to this set. If the set has another attribute with the same category, that attribute is replaced by the given attribute. Returns `true` if the set changed as a result of this operation.
- `Attribute get(Class category)`
  retrieves the attribute with the given category key, or `null` if no such attribute exists.
- `boolean remove(Attribute attr)`
- `boolean remove(Class category)`
  remove the given attribute, or the attribute with the given category, from the set. Return `true` if the set changed as a result of this operation.
- `Attribute[] toArray()`
  returns an array with all attributes in this set.

`javax.print.PrintService` **1.4**

- `PrintServiceAttributeSet getAttributes()`
  gets the attributes of this print service.

`javax.print.DocPrintJob` **1.4**

- `PrintJobAttributeSet getAttributes()`
  gets the attributes of this print job.

You have now reached the end of this long chapter covering advanced Swing and AWT features. In the final chapter, we will turn to a different aspect of Java programming: interacting, on the same machine, with "native" code in a different programming language.

1. Native Methods

While a "100% Pure Java" solution is nice in principle, there are situations in which you will want to write (or use) code in another language. Such code is usually called *native* code.

Particularly in the early days of Java, many people assumed that it would be a good idea to use C or C++ to speed up critical parts of a Java application. However, in practice, this was rarely useful. A presentation at the 1996 JavaOne conference showed this clearly. The developers of the cryptography library at Sun Microsystems reported that a pure Java platform implementation of their cryptographic functions was more than adequate. It was true that the code was not as fast as a C implementation would have been, but it turned out not to matter. The Java platform implementation was far faster than the network I/O. This turned out to be the real bottleneck.

Of course, there are drawbacks to going native. If a part of your application is written in another language, you must supply a separate native library for every platform you want to support. Code written in C or C++ offers no protection against overwriting memory through invalid pointer usage. It is easy to write native methods that corrupt your program or infect the operating system.

Thus, I suggest using native code only when you need to. In particular, there are three reasons why native code might be the right choice:

- Your application requires access to system features or devices that are not accessible through the Java platform.
- You have substantial amounts of tested and debugged code in another language, and you know how to port it to all desired target platforms.
- You have found, through benchmarking, that the Java code is much slower than the equivalent code in another language.

The Java platform has an API for interoperating with native C code called the Java Native Interface (JNI). We'll discuss JNI programming in this chapter.

C++ Note: You can also use C++ instead of C to write native methods. There are a few advantages—type checking is slightly stricter, and accessing the JNI functions is a bit more convenient. However, JNI does not support any mapping between Java and C++ classes.

As you will see, there is a certain amount of tedium involved in providing a binding layer between Java and native code. Java 17 has, as a preview feature, an API to access "foreign" functions and

memory that is quite a bit more convenient than JNI. At the end of this chapter, you will get a glimpse into this API.

1.1. Calling a C Function from a Java Program

Suppose you have a C function that does something you like and, for one reason or another, you don't want to bother reimplementing it in Java. For the sake of illustration, we'll start with a simple C function that prints a greeting.

The Java programming language uses the keyword `native` for a native method, and you will obviously need to place a method in a class. The result is shown in Listing 13.1.

The `native` keyword alerts the compiler that the method will be defined externally. Of course, native methods will contain no Java code, and the method header is followed immediately by a terminating semicolon. Therefore, native method declarations look similar to abstract method declarations.

Listing 1.1 helloNative/HelloNative.java

```
1 /**
2  *  @version 1.11 2007-10-26
3  *  @author Cay Horstmann
4  */
```

```
5  class HelloNative
6  {
7     public static native void greeting();
8  }
```

Note: We do not use packages here to keep examples simple.

In this particular example, the native method is also declared as `static`. Native methods can be both static and nonstatic. We'll start with a static method because we do not yet want to deal with parameter passing.

You can actually compile this class, but if you try to use it in a program, the virtual machine will tell you it doesn't know how to find `greeting`—reporting an `UnsatisfiedLinkError`. To implement the native code, write a corresponding C function. You must name that function *exactly* the way the Java virtual machine expects. Here are the rules:

1. Use the full Java method name, such as `HelloNative.greeting`. If the class is in a package, prepend the package name, such as `com.horstmann.HelloNative.greeting`.

2. Replace every period with an underscore, and append the prefix `Java_`. For example, `Java_HelloNative_greeting` or `Java_com_horstmann_HelloNative_greeting`.
3. If the class name contains characters that are not ASCII letters or digits—that is, `'_'`, `'$'`, or Unicode characters with codes greater than `\u007F`—replace them with `_0xxxx`, where `xxxx` is the sequence of four hexadecimal digits of the character's Unicode value.

Note: If you *overload* native methods—that is, if you provide multiple native methods with the same name—you must append a double underscore followed by the encoded argument types. (I'll describe the encoding of the argument types later in this chapter.) For example, if you have a native method `greeting` and another native method `greeting(int repeat)`, then the first one is called `Java_HelloNative_greeting__` and the second, `Java_HelloNative_greeting__I`.

Actually, nobody does this by hand; instead, run `javac` with the `-h` flag, providing the directory in which the header files should be placed:

```
javac -h . HelloNative.java
```

This command creates a header file `HelloNative.h` in the current directory, as shown in Listing 13.2.

Listing 1.2 helloNative/HelloNative.h

```
1  /* DO NOT EDIT THIS FILE - it is machine genera
2  #include <jni.h>
3  /* Header for class HelloNative */
4
5  #ifndef _Included_HelloNative
6  #define _Included_HelloNative
7  #ifdef __cplusplus
8  extern "C" {
9  #endif
10 /*
11  * Class:     HelloNative
12  * Method:    greeting
13  * Signature: ()V
14  */
15 JNIEXPORT void JNICALL Java_HelloNative_greetin
16    (JNIEnv *, jclass);
17
18 #ifdef __cplusplus
```

```
}
#endif
#endif
```

As you can see, this file contains the declaration of a function `Java_HelloNative_greeting`. (The macros `JNIEXPORT` and `JNICALL` are defined in the header file `jni.h`. They denote compiler-dependent specifiers for exported functions that come from a dynamically loaded library.)

Now, simply copy the function prototype from the header file into a source file and give the implementation code for the function, as shown in Listing 13.3.

Listing 1.3 helloNative/HelloNative.c

```
/*
   @version 1.10 1997-07-01
   @author Cay Horstmann
*/

#include "HelloNative.h"
#include <stdio.h>

JNIEXPORT void JNICALL Java_HelloNative_greetir
```

```
10 {
11    printf("Hello, Native World!\n");
12 }
```

In this simple function, ignore the `env` and `cl` arguments. You'll see their use later.

C++ Note: You can use C++ to implement native methods. However, you must then declare the functions that implement the native methods as `extern "C"`. (This stops the C++ compiler from "mangling" the method name.) For example,

```
extern "C"
JNIEXPORT void JNICALL Java_HelloNative_greeting(JNIE
{
   cout << "Hello, Native World!" << endl;
}
```

Compile the native C code into a dynamically loaded library. The details depend on your compiler.

For example, with the GNU C compiler on Linux, use these commands:

```
gcc -fPIC -I jdk/include -I jdk/include/linux -shared
```

With the Microsoft compiler under Windows, the command is

```
cl -I jdk\include -I jdk\include\win32 -LD HelloNative
```

Here, `jdk` is the directory that contains the JDK.

Tip: If you use the Microsoft compiler from a command shell, first run a batch file such as `vsvars32.bat` or `vcvarsall.bat`. That batch file sets up the path and the environment variables needed by the compiler. You can find it in the directory `c:\Program Files\Microsoft Visual Studio 14.0\Common7\Tools` or a similar monstrosity. Check the Visual Studio documentation for details.

You can also use the freely available Cygwin programming environment from https://www.cygwin.com. It contains the GNU C compiler and libraries for UNIX-style programming on Windows. With Cygwin, use the command

```
gcc -mno-cygwin -D __int64="long long" -I jdk/include/
   -shared -Wl,--add-stdcall-alias -o HelloNative.dll
```

Note: The Windows version of the header file `jni_md.h` contains the type declaration

```
typedef __int64 jlong;
```

which is specific to the Microsoft compiler. If you use the GNU compiler, you might want to edit that file, for example,

```
#ifdef __GNUC__
   typedef long long jlong;
#else
   typedef __int64 jlong;
#endif
```

Alternatively, compile with `-D __int64="long long"`, as shown in the sample compiler invocation.

Finally, add a call to the `System.loadLibrary` method in your program. To ensure that the virtual machine will load the library

before the first use of the class, use a static initialization block, as in Listing 13.4.

Figure 13.1 gives a summary of the native code processing.



Figure 1.1: Processing native code

Listing 1.4 helloNative/HelloNativeTest.java

```
1  /**
2   *  @version 1.11 2007-10-26
3   *  @author Cay Horstmann
4   */
5  class HelloNativeTest
6  {
7     public static void main(String[] args)
8     {
9        HelloNative.greeting();
10    }
11
12    static
13    {
14       System.loadLibrary("HelloNative");
15    }
16 }
```

After you compile and run this program, the message "Hello, Native World!" is displayed in a terminal window.

Note: If you run Linux, you must add the current directory to the library path. Either set the `LD_LIBRARY_PATH` environment variable:

```
export LD_LIBRARY_PATH=.:$LD_LIBRARY_PATH
```

or set the `java.library.path` system property:

```
java -Djava.library.path=. HelloNativeTest
```

Of course, this is not particularly impressive by itself. Keep in mind, however, that this message is generated by the C `printf` command and not by any Java code. We have taken the first step toward bridging the gap between the two languages!

In summary, follow these steps to link a native method to a Java program:

1. Declare a native method in a Java class.
2. Run `javac -h` to get a header file with a C declaration for the method.
3. Implement the native method in C.
4. Place the code in a shared library.
5. Load that library in your Java program.

`java.lang.System` **1.0**

- `void loadLibrary(String libname)`
  loads the library with the given name. The library is located in the library search path. The exact method for locating the library depends on the operating system.

Note: Some shared libraries for native code must execute certain initializations. You can place any initialization code into a `JNI_OnLoad` method. Similarly, when the virtual machine (VM) shuts down, it will call the `JNI_OnUnload` method if you provide it. The prototypes are

```
jint JNI_OnLoad(JavaVM* vm, void* reserved
void JNI_OnUnload(JavaVM* vm, void* reserv
```

The `JNI_OnLoad` method needs to return the minimum version of the VM it requires, such as `JNI_VERSION_1_2`.

1.2. Numeric Parameters and Return Values

When passing numbers between C and Java, you should understand which types correspond to each other. For example, although C does have data types called `int` and `long`, their implementation is platform-dependent. On some platforms, an `int` is a 16-bit quantity, on others it is a 32-bit quantity. On the Java platform, of course, an `int` is *always* a 32-bit integer. For that reason, JNI defines types `jint`, `jlong`, and so on.

Table 13.1 shows the correspondence between Java types and C types.

Table 1.1: Java Types and C Types

Java Programming Language	C Programming Language	Bytes
`boolean`	`jboolean`	1
`byte`	`jbyte`	1
`char`	`jchar`	2
`short`	`jshort`	2
`int`	`jint`	4

Java Programming Language	C Programming Language	Bytes
`long`	`jlong`	8
`float`	`jfloat`	4
`double`	`jdouble`	8

In the header file `jni.h`, these types are declared with `typedef` statements as the equivalent types on the target platform. That header file also defines the constants `JNI_FALSE = 0` and `JNI_TRUE = 1`.

Until Java 5, Java had no direct analog of the C `printf` function. In the following examples, we will pretend you are stuck with an ancient JDK release and decide to implement the same functionality by calling the C `printf` function in a native method.

Listing 13.5 shows a class called `Printf1` that uses a native method to print a floating-point number with a given field width and precision.

Listing 1.5 printf1/Printf1.java

```
1  /**
2   * @version 1.10 1997-07-01
3   * @author Cay Horstmann
4   */
5  class Printf1
6  {
7     public static native int print(int width, ir
8
9     static
10    {
11       System.loadLibrary("Printf1");
12    }
13 }
```

Notice that when the method is implemented in C, all `int` and `double` parameters are changed to `jint` and `jdouble`, as shown in Listing 13.6.

Listing 1.6 printf1/Printf1.c

```
1  /**
2     @version 1.10 1997-07-01
3     @author Cay Horstmann
4  */
```

```
5
6  #include "Printf1.h"
7  #include <stdio.h>
8
9  JNIEXPORT jint JNICALL Java_Printf1_print(JNIEr
10       jint width, jint precision, jdouble x)
11 {
12    char fmt[30];
13    jint ret;
14    sprintf(fmt, "%%%d.%df", width, precision);
15    ret = printf(fmt, x);
16    fflush(stdout);
17    return ret;
18 }
```

The function simply assembles a format string `"%w.pf"` in the variable `fmt`, then calls `printf`. It returns the number of characters printed.

Listing 13.7 shows the test program that demonstrates the `Printf1` class.

Listing 1.7 printf1/Printf1Test.java

```
1  /**
2   * @version 1.10 1997-07-01
3   * @author Cay Horstmann
```

```
 */
class Printf1Test
{
   public static void main(String[] args)
   {
      int count = Printf1.print(8, 4, 3.14);
      count += Printf1.print(8, 4, count);
      System.out.println();
      for (int i = 0; i < count; i++)
         System.out.print("-");
      System.out.println();
   }
}
```

1.3. String Parameters

Next, let's look at how to transfer strings to and from native methods. Strings are quite different in the two languages: In Java, they are sequences of UTF-16 code points, whereas C strings are null-terminated sequences of bytes. JNI has two sets of functions for manipulating strings: One converts Java strings to "modified UTF-8" byte sequences and another converts them to arrays of UTF-16 values—that is, to `jchar` arrays. (The UTF-8, "modified UTF-8," and UTF-16 formats were discussed in Chapter 2. Recall that the UTF-8 and "modified UTF-8" encodings leave ASCII characters unchanged,

but all other Unicode characters are encoded as multibyte sequences.)

Note: The standard UTF-8 encoding and the "modified UTF-8" encoding differ only for characters with codes higher than `0xFFFF`. In the standard UTF-8 encoding, these characters are encoded as 4-byte sequences. In the "modified" encoding, each such character is first encoded as a pair of "surrogates" in the UTF-16 encoding, and then each surrogate is encoded with UTF-8, yielding a total of 6 bytes. This is clumsy, but it is a historical accident—the JVM specification was written when Unicode was still limited to 16 bits.

If your C code already uses Unicode, you'll want to use the second set of conversion functions. On the other hand, if all your strings are restricted to ASCII characters, you can use the "modified UTF-8" conversion functions.

A native method with a `String` parameter actually receives a value of an opaque type called `jstring`. A native method with a return value of type `String` must return a value of type `jstring`. JNI functions read and construct these `jstring` objects. For example, the `NewStringUTF` function makes a new `jstring` object out of a

`char` array that contains ASCII characters or, more generally, "modified UTF-8"-encoded byte sequences.

JNI functions have a somewhat odd calling convention. Here is a call to the `NewStringUTF` function:

```
JNIEXPORT jstring JNICALL Java_HelloNative_getGreetin
{
   jstring jstr;
   char greeting[] = "Hello, Native World\n";
   jstr = (*env)->NewStringUTF(env, greeting);
   return jstr;
}
```

Note: Unless explicitly mentioned otherwise, all code in this chapter is C code.

All calls to JNI functions use the `env` pointer that is the first argument of every native method. The `env` pointer is a pointer to a table of function pointers (see Figure 13.2). Therefore, you must prefix every JNI call with `(*env)->` to actually dereference the function pointer. Furthermore, `env` is the first parameter of every JNI function.



Figure 1.2: The `env` pointer

C++ Note: It is simpler to access JNI functions in C++. The C++ version of the `JNIEnv` class has inline member functions that take care of the function pointer lookup for you. For example, you can call the `NewStringUTF` function as

```
jstr = env->NewStringUTF(greeting);
```

Note that you omit the `JNIEnv` pointer from the parameter list of the call.

The `NewStringUTF` function lets you construct a new `jstring`. To read the contents of an existing `jstring` object, use the `GetStringUTFChars` function. This function returns a `const`

`jbyte*` pointer to the "modified UTF-8" characters that describe the character string. Note that a specific virtual machine is free to choose this character encoding for its internal string representation, so you might get a character pointer into the actual Java string. Since Java strings are meant to be immutable, it is *very* important that you treat the `const` seriously and do not try to write into this character array. On the other hand, if the virtual machine uses UTF-16 or UTF-32 characters for its internal string representation, this function call allocates a new memory block that will be filled with the "modified UTF-8" equivalents.

The virtual machine must know when you are finished using the string so that it can garbage-collect it. (The garbage collector runs in a separate thread, and it can interrupt the execution of native methods.) For that reason, you must call the `ReleaseStringUTFChars` function.

Alternatively, you can supply your own buffer to hold the string characters by calling the `GetStringRegion` or `GetStringUTFRegion` methods.

Finally, the `GetStringUTFLength` function returns the number of characters needed for the "modified UTF-8" encoding of the string.

Note: You can find the JNI API at https://docs.oracle.com/javase/7/docs/technotes/guides/jni.

`Accessing Java Strings from C Code`

- `jstring NewStringUTF(JNIEnv* env, const char bytes[])`
  returns a new Java string object from a zero byte-terminated "modified UTF-8" byte sequence, or `NULL` if the string cannot be constructed.
- `jsize GetStringUTFLength(JNIEnv* env, jstring string)`
  returns the number of bytes required for the "modified UTF-8" encoding (not counting the zero byte terminator).
- `const jbyte* GetStringUTFChars(JNIEnv* env, jstring string, jboolean* isCopy)`
  returns a pointer to the "modified UTF-8" encoding of a string, or `NULL` if the character array cannot be constructed. The pointer is valid until `ReleaseStringUTFChars` is called. `isCopy` points to a `jboolean` filled with `JNI_TRUE` if a copy is made, or with `JNI_FALSE` otherwise.
- `void ReleaseStringUTFChars(JNIEnv* env, jstring`

`string, const jbyte bytes[])`
informs the virtual machine that the native code no longer needs access to the Java string through `bytes` (a pointer returned by `GetStringUTFChars`).

- `void GetStringRegion(JNIEnv *env, jstring string, jsize start, jsize length, jchar *buffer)`
  copies a sequence of UTF-16 double bytes from a string to a user-supplied buffer of size at least 2 × `length`.
- `void GetStringUTFRegion(JNIEnv *env, jstring string, jsize start, jsize length, jbyte *buffer)`
  copies a sequence of "modified UTF-8" bytes from a string to a user-supplied buffer. The buffer must be long enough to hold the bytes. In the worst case, 3 × `length` bytes are copied.
- `jstring NewString(JNIEnv* env, const jchar chars[], jsize length)`
  returns a new Java string object from a Unicode string, or `NULL` if the string cannot be constructed.
- `jsize GetStringLength(JNIEnv* env, jstring string)`
  returns the number of characters in the string.
- `const jchar* GetStringChars(JNIEnv* env, jstring string, jboolean* isCopy)`
  returns a pointer to the Unicode encoding of a string, or `NULL` if the character array cannot be constructed. The pointer is valid until `ReleaseStringChars` is called. `isCopy` is either `NULL` or

points to a `jboolean` filled with `JNI_TRUE` if a copy is made, or with `JNI_FALSE` otherwise.

- `void ReleaseStringChars(JNIEnv* env, jstring string, const jchar chars[])`
  informs the virtual machine that the native code no longer needs access to the Java string through `chars` (a pointer returned by `GetStringChars`).

Let us put these functions to work and write a class that calls the C function `sprintf`. We would like to call the function as shown in Listing 13.8.

Listing 1.8 printf2/Printf2Test.java

```
1  /**
2   * @version 1.10 1997-07-01
3   * @author Cay Horstmann
4   */
5  class Printf2Test
6  {
7     public static void main(String[] args)
8     {
9        double price = 44.95;
10       double tax = 7.75;
11       double amountDue = price * (1 + tax / 100
12
13       String s = Printf2.sprint("Amount due = %
```

```
14          System.out.println(s);
15       }
16    }
```

Listing 13.9 shows the class with the native `sprint` method.

Listing 1.9 printf2/Printf2.java

```
1  /**
2   * @version 1.10 1997-07-01
3   * @author Cay Horstmann
4   */
5  class Printf2
6  {
7     public static native String sprint(String fo
8
9     static
10    {
11       System.loadLibrary("Printf2");
12    }
13 }
```

Therefore, the C function that formats a floating-point number has the prototype

```
JNIEXPORT jstring JNICALL Java_Printf2_sprint(JNIEnv*
      jstring format, jdouble x)
```

Listing 13.10 shows the code for the C implementation. Note the calls to `GetStringUTFChars` to read the format argument, `NewStringUTF` to generate the return value, and `ReleaseStringUTFChars` to inform the virtual machine that access to the string is no longer required.

Listing 1.10 printf2/Printf2.c

```
1  /**
2     @version 1.10 1997-07-01
3     @author Cay Horstmann
4  */
5
6  #include "Printf2.h"
7  #include <string.h>
8  #include <stdlib.h>
9  #include <float.h>
10
11 /**
12    @param format a string containing a printf f
13    (such as "%8.2f"). Substrings "%%" are skipp
14    @return a pointer to the format specifier (s
15    or NULL if there wasn't a unique format spec
```

```
*/
char* find_format(const char format[])
{
   char* p;
   char* q;

   p = strchr(format, '%');
   while (p != NULL && *(p + 1) == '%') /* skip
      p = strchr(p + 2, '%');
   if (p == NULL) return NULL;
   /* now check that % is unique */
   p++;
   q = strchr(p, '%');
   while (q != NULL && *(q + 1) == '%') /* skip
      q = strchr(q + 2, '%');
   if (q != NULL) return NULL; /* % not unique
   q = p + strspn(p, " -0+#"); /* skip past fla
   q += strspn(q, "0123456789"); /* skip past f
   if (*q == '.') { q++; q += strspn(q, "12345
      /* skip past precision */
   if (strchr("eEfFgG", *q) == NULL) return NUL
      /* not a floating-point format */
   return p;
}

JNIEXPORT jstring JNICALL Java_Printf2_sprint(J
      jstring format, jdouble x)
{
```

```
    const char* cformat;
    char* fmt;
    jstring ret;

    cformat = (*env)->GetStringUTFChars(env, for
    fmt = find_format(cformat);
    if (fmt == NULL)
       ret = format;
    else
    {
       char* cret;
       int width = atoi(fmt);
       if (width == 0) width = DBL_DIG + 10;
       cret = (char*) malloc(strlen(cformat) + w
       sprintf(cret, cformat, x);
       ret = (*env)->NewStringUTF(env, cret);
       free(cret);
    }
    (*env)->ReleaseStringUTFChars(env, format, c
    return ret;
}
```

In this function, we chose to keep error handling simple. If the format code to print a floating-point number is not of the form `%w.pc`, where `c` is one of the characters `e`, `E`, `f`, `g`, or `G`, then we simply do not format the number. We'll show you later how to make a native method throw an exception.

1.4. Accessing Fields

All the native methods you saw so far were static methods with number and string parameters. We'll now consider native methods that operate on objects. As an exercise, we will reimplement as native a method of the `Employee` class that was introduced in Chapter 4 of Volume I. Again, this is not something you would normally want to do, but it does illustrate how to access fields from a native method when you need to do so.

1.4.1. Accessing Instance Fields

To see how to access instance fields from a native method, we will reimplement the `raiseSalary` method. Here is the code in Java:

```
public void raiseSalary(double byPercent)
{
   salary *= 1 + byPercent / 100;
}
```

Let us rewrite this as a native method. Unlike the previous examples of native methods, this is not a static method. Running `javac -h` gives the following prototype:

```
JNIEXPORT void JNICALL Java_Employee_raiseSalary(JNIE
```

Note the second argument. It is no longer of type `jclass` but of type `jobject`. In fact, it is an equivalent of the `this` reference. Static methods obtain a reference to the class, whereas nonstatic methods obtain a reference to the implicit `this` argument object.

Now we access the `salary` field of the implicit argument. In the "raw" Java-to-C binding of Java 1.0, this was easy—a programmer could directly access instance fields. However, direct access requires all virtual machines to expose their internal data layout. For that reason, the JNI requires programmers to get and set the values of instance fields by calling special JNI functions.

In our case, we need to use the `GetDoubleField` and `SetDoubleField` functions because the type of `salary` is `double`. There are other functions— `GetIntField/SetIntField`, `GetObjectField/SetObjectField`, and so on for other field types. The general syntax is:

```
x = (*env)->GetXxxField(env, this_obj, fieldID);
(*env)->SetXxxField(env, this_obj, fieldID, x);
```

Here, `fieldID` is a value of a special type, `jfieldID`, that identifies a field in a structure, and `Xxx` represents a Java data type (`Object`, `Boolean`, `Byte`, and so on). To obtain the `fieldID`, you must first get a value representing the class, which you can do in one of two ways. The `GetObjectClass` function returns the class of any object. For example:

```
  jclass class_Employee = (*env)->GetObjectClass(env, t
```

The `FindClass` function lets you specify the class name as a string (curiously, with `/` characters instead of periods as package name separators).

```
  jclass class_String = (*env)->FindClass(env, "java/la
```

Use the `GetFieldID` function to obtain the `fieldID`. You must supply the name of the field and its *signature*, an encoding of its type. For example, here is the code to obtain the field ID of the `salary` field:

```
  jfieldID id_salary = (*env)->GetFieldID(env, class_Em
```

The string `"D"` denotes the type `double`. You'll learn the complete rules for encoding signatures in the next section.

You might be thinking that accessing an instance field is quite convoluted. The designers of the JNI did not want to expose the instance fields directly, so they had to supply functions for getting and setting field values. To minimize the cost of these functions, computing the field ID from the field name—which is the most expensive step—is factored out into a separate step. That is, if you repeatedly get and set the value of a particular field, you can incur the cost of computing the field identifier only once.

Let us put all the pieces together. The following code reimplements the `raiseSalary` method as a native method:

```
JNIEXPORT void JNICALL Java_Employee_raiseSalary(JNIE
      jdouble byPercent)
{
   /* get the class */
   jclass class_Employee = (*env)->GetObjectClass(env

   /* get the field ID */
   jfieldID id_salary = (*env)->GetFieldID(env, class

   /* get the field value */
   jdouble salary = (*env)->GetDoubleField(env, this_
```

```
    salary *= 1 + byPercent / 100;

    /* set the field value */
    (*env)->SetDoubleField(env, this_obj, id_salary, s
}
```

Caution: Class references are only valid until the native method returns. You cannot cache the return values of `GetObjectClass` in your code. Do *not* store away a class reference for reuse in a later method call. You must call `GetObjectClass` every time the native method executes. If this is intolerable, you can lock the reference with a call to `NewGlobalRef`:

```
static jclass class_X = 0;
static jfieldID id_a;
. . .
if (class_X == 0)
{
   jclass cx = (*env)->GetObjectClass(env, obj);
   class_X = (*env)->NewGlobalRef(env, cx);
   id_a = (*env)->GetFieldID(env, class_X, "a", ". .
}
```

Now you can use the class reference and field IDs in subsequent calls. When you are done using the class, make sure to call

```
(*env)->DeleteGlobalRef(env, class_X);
```

Listing 13.11 shows the Java code for a test program. The `Employee` class is in Listing 13.12. Listing 13.13 contains the C code for the native `raiseSalary` method.

Listing 1.11 employee/EmployeeTest.java

```
1  /**
2   * @version 1.11 2018-05-01
3   * @author Cay Horstmann
4   */
5
6  public class EmployeeTest
7  {
8     public static void main(String[] args)
9     {
10       var staff = new Employee[3];
11
12       staff[0] = new Employee("Harry Hacker", 3
13       staff[1] = new Employee("Carl Cracker", 7
14       staff[2] = new Employee("Tony Tester", 38
15
```

```
16          for (Employee e : staff)
17             e.raiseSalary(5);
18          for (Employee e : staff)
19             e.print();
20       }
21    }
```

Listing 1.12 employee/Employee.java

```
1  /**
2   * @version 1.10 1999-11-13
3   * @author Cay Horstmann
4   */
5
6  public class Employee
7  {
8     private String name;
9     private double salary;
10
11    public native void raiseSalary(double byPerc
12
13    public Employee(String n, double s)
14    {
15       name = n;
16       salary = s;
17    }
18
19    public void print()
```

```
20    {
21       System.out.println(name + " " + salary);
22    }
23
24    static
25    {
26       System.loadLibrary("Employee");
27    }
28 }
```

Listing 1.13 employee/Employee.c

```
1  '/**
2     @version 1.10 1999-11-13
3     @author Cay Horstmann
4  */
5
6  #include "Employee.h"
7
8  #include <stdio.h>
9
10 JNIEXPORT void JNICALL Java_Employee_raiseSalar
11       JNIEnv* env, jobject this_obj, jdouble by
12 {
13    /* get the class */
14    jclass class_Employee = (*env)->GetObjectCla
15
16    /* get the field ID */
```

```
17      jfieldID id_salary = (*env)->GetFieldID(env,
18
19      /* get the field value */
20      jdouble salary = (*env)->GetDoubleField(env,
21
22      salary *= 1 + byPercent / 100;
23
24      /* set the field value */
25      (*env)->SetDoubleField(env, this_obj, id_sal
26  }
```

1.4.2. Accessing Static Fields

Accessing static fields is similar to accessing nonstatic fields. Use the `GetStaticFieldID` and `GetStaticXxxField/SetStaticXxxField` functions that work almost identically to their nonstatic counterparts, with two differences:

- Since you have no object, you must use `FindClass` instead of `GetObjectClass` to obtain the class reference.
- You have to supply the class, not the instance object, when accessing the field.

For example, here is how you can get a reference to `System.out`:

```
/* get the class */
jclass class_System = (*env)->FindClass(env, "java/la

/* get the field ID */
jfieldID id_out = (*env)->GetStaticFieldID(env, class
   "Ljava/io/PrintStream;");

/* get the field value */
jobject obj_out = (*env)->GetStaticObjectField(env, c
```

Accessing Fields

- `jfieldID GetFieldID(JNIEnv *env, jclass cl, const char name[], const char fieldSignature[])`
  returns the identifier of a field in a class.
- `Xxx GetXxxField(JNIEnv *env, jobject obj, jfieldID id)`
  returns the value of a field. The field type `Xxx` is one of `Object`, `Boolean`, `Byte`, `Char`, `Short`, `Int`, `Long`, `Float`, or `Double`.
- `void SetXxxField(JNIEnv *env, jobject obj, jfieldID id, Xxx value)`
  sets a field to a new value. The field type `Xxx` is one of `Object`, `Boolean`, `Byte`, `Char`, `Short`, `Int`, `Long`, `Float`, or `Double`.

- `jfieldID GetStaticFieldID(JNIEnv *env, jclass cl, const char name[], const char fieldSignature[])`
  returns the identifier of a static field in a class.
- `Xxx GetStaticXxxField(JNIEnv *env, jclass cl, jfieldID id)`
  returns the value of a static field. The field type `Xxx` is one of `Object`, `Boolean`, `Byte`, `Char`, `Short`, `Int`, `Long`, `Float`, or `Double`.
- `void SetStaticXxxField(JNIEnv *env, jclass cl, jfieldID id, Xxx value)`
  sets a static field to a new value. The field type `Xxx` is one of `Object`, `Boolean`, `Byte`, `Char`, `Short`, `Int`, `Long`, `Float`, or `Double`.

1.5. Encoding Signatures

To access instance fields and call methods defined in the Java programming language, you need to learn the rules for "mangling" the names of data types and method signatures. (A method signature describes the parameters and return type of the method.) Here is the encoding scheme:

`B`	`byte`
`C`	`char`

`D`	`double`
`F`	`float`
`I`	`int`
`J`	`long`
`Lclassname;`	a class type
`S`	`short`
`V`	`void`
`Z`	`boolean`

To describe an array type, use a `[`. For example, an array of strings is

```
[Ljava/lang/String;
```

A `float[][]` is mangled into

```
[[F
```

For the complete signature of a method, list the parameter types inside a pair of parentheses and then list the return type. For example, a method receiving two integers and returning an integer is encoded as

```
(II)I
```

The `sprint` method in Section 13.3 has a mangled signature of

```
(Ljava/lang/String;D)Ljava/lang/String;
```

That is, the method receives a `String` and a `double` and returns a `String`.

Note that the semicolon at the end of the `L` expression is the terminator of the type expression, not a separator between parameters. For example, the constructor

```
Employee(java.lang.String, double, java.util.Date)
```

has a signature

```
"(Ljava/lang/String;DLjava/util/Date;)V"
```

Note that there is no separator between the `D` and `Ljava/util/Date;`. Also note that in this encoding scheme, you must use `/` instead of `.` to separate the package and class names. The `V` at the end denotes a return type of `void`. Even though you don't specify a return type for constructors in Java, you need to add a `V` to the virtual machine signature.

Tip: You can use the `javap` command with option `-s` to generate the method signatures from class files. For example, run

```
javap -s -private Employee
```

You will get the following output, displaying the signatures of all fields and methods:

```
Compiled from "Employee.java"
public class Employee extends java.lang.Object{
private java.lang.String name;
  Signature: Ljava/lang/String;
private double salary;
  Signature: D
public Employee(java.lang.String, double);
  Signature: (Ljava/lang/String;D)V
```

```
public native void raiseSalary(double);
  Signature: (D)V
public void print();
  Signature: ()V
static {};
  Signature: ()V
}
```

Note: There is no rationale whatsoever for forcing programmers to use this mangling scheme for signatures. The designers of the native calling mechanism could have just as easily written a function that reads signatures in the Java programming language style, such as `void(int,java.lang.String)`, and encodes them into whatever internal representation they prefer. Then again, using the mangled signatures lets you partake in the mystique of programming close to the virtual machine.

1.6. Calling Java Methods

Of course, Java programming language functions can call C functions —that is what native methods are for. Can we go the other way? Why would we want to do this anyway? It often happens that a native method needs to request a service from an object that was passed to it. I'll first show you how to do it for instance methods, then for static methods.

1.6.1. Instance Methods

As an example of calling a Java method from native code, let's enhance the `Printf` class and add a method that works similarly to the C function `fprintf`. That is, it should be able to print a string on an arbitrary `PrintWriter` object. Here is the definition of the method in Java:

```
class Printf3
{
   public native static void fprint(PrintWriter out,
   . . .
}
```

We'll first assemble the string to be printed into a `String` object `str`, as in the `sprint` method that we already implemented. Then, from the C function that implements the native method, we'll call the `print` method of the `PrintWriter` class.

You can call any Java method from C by using the function call

```
(*env)->CallXxxMethod(env, implicit argument, methodID,
```

Replace `Xxx` with `Void`, `Int`, `Object`, and so on, depending on the return type of the method. Just as you need a `fieldID` to access a field of an object, you need a method ID to call a method. To obtain a method ID, call the JNI function `GetMethodID` and supply the class, the name of the method, and the method signature.

In our example, we want to obtain the ID of the `print` method of the `PrintWriter` class. The `PrintWriter` class has several overloaded methods called `print`. For that reason, you must also supply a string describing the parameters and the return value of the specific function that you want to use. For example, we want to use `void print(java.lang.String)`. As described in the preceding section, we must now "mangle" the signature into the string `"(Ljava/lang/String;)V"`.

Here is the complete code to make the method call:

```
/* get the class of the implicit parameter */
class_PrintWriter = (*env)->GetObjectClass(env, out);
```

```
/* get the method ID */
id_print = (*env)->GetMethodID(env, class_PrintWriter

/* call the method */
(*env)->CallVoidMethod(env, out, id_print, str);
```

Listing 13.14 shows he Java code for a test program. The `Printf3` class is in Listing 13.15. Listing 13.16 contains the C code for the native `fprint` method.

Note: The numerical method IDs and field IDs are conceptually similar to `Method` and `Field` objects in the reflection API. You can convert between them with the following functions:

```
jobject ToReflectedMethod(JNIEnv* env, jcl
   // returns Method object
methodID FromReflectedMethod(JNIEnv* env,
jobject ToReflectedField(JNIEnv* env, jcla
   // returns Field object
fieldID FromReflectedField(JNIEnv* env, jo
```

1.6.2. Static Methods

Calling static methods from native methods is similar to calling instance methods. There are two differences:

- Use the `GetStaticMethodID` and `CallStaticXxxMethod` functions
- Supply a class object, not an implicit argument object, when invoking the method

As an example of this, let's make the call to the static method

```
System.getProperty("java.class.path")
```

from a native method. The return value of this call is a string that gives the current class path.

First, we have to find the class to use. As we have no object of the class `System` readily available, we use `FindClass` rather than `GetObjectClass`.

```
jclass class_System = (*env)->FindClass(env, "java/la
```

Next, we need the ID of the static `getProperty` method. The encoded signature of that method is

```
"(Ljava/lang/String;)Ljava/lang/String;"
```

because both the parameter and the return value are strings. Hence, we obtain the method ID as follows:

```
jmethodID id_getProperty = (*env)->GetStaticMethodID(
   "(Ljava/lang/String;)Ljava/lang/String;");
```

Finally, we can make the call. Note that the class object is passed to the `CallStaticObjectMethod` function.

```
jobject obj_ret = (*env)->CallStaticObjectMethod(env,
   (*env)->NewStringUTF(env, "java.class.path"));
```

The return value of this method is of type `jobject`. If we want to manipulate it as a string, we must cast it to `jstring`:

```
jstring str_ret = (jstring) obj_ret;
```

C++ Note: In C, the types `jstring` and `jclass`, as well as the array types to be introduced later, are all type-equivalent to `jobject`. The cast of the preceding example is therefore not strictly necessary in C. But in C++, these types are defined as

pointers to “dummy classes” that have the correct inheritance hierarchy. For example, assigning a `jstring` to a `jobject` is legal without a cast in C++, but an assignment from a `jobject` to a `jstring` requires a cast.

1.6.3. Constructors

A native method can create a new Java object by invoking its constructor. Invoke the constructor by calling the `NewObject` function.

```
  jobject obj_new = (*env)->NewObject(env, class, method
```

You can obtain the method ID needed for this call from the `GetMethodID` function by specifying the method name as `"<init>"` and the encoded signature of the constructor (with return type `void`). For example, here is how a native method can create a `FileOutputStream` object:

```
  const char[] fileName = ". . .";
  jstring str_fileName = (*env)->NewStringUTF(env, file
  jclass class_FileOutputStream = (*env)->FindClass(env
  jmethodID id_FileOutputStream
```

```
    = (*env)->GetMethodID(env, class_FileOutputStream,
jobject obj_stream
    = (*env)->NewObject(env, class_FileOutputStream, i
```

Note that the signature of the constructor has a parameter of type `java.lang.String` and has a return type of `void`.

1.6.4. Alternative Method Invocations

Several variants of the JNI functions can be used to call a Java method from native code. These are not as important as the functions that we already discussed, but they are occasionally useful.

The `CallNonvirtualXxxMethod` functions receive an implicit argument, a method ID, a class object (which must correspond to a superclass of the implicit argument), and explicit arguments. The function calls the version of the method in the specified class, bypassing the normal dynamic dispatch mechanism.

All call functions have versions with suffixes "A" and "V" that receive the explicit arguments in an array or a `va_list` (as defined in the C header `stdarg.h`).

Listing 1.14 printf3/Printf3Test.java

```
1  import java.io.*;
2
3  /**
4   * @version 1.11 2018-05-01
5   * @author Cay Horstmann
6   */
7  class Printf3Test
8  {
9     public static void main(String[] args)
10    {
11       double price = 44.95;
12       double tax = 7.75;
13       double amountDue = price * (1 + tax / 100
14       var out = new PrintWriter(System.out);
15       Printf3.fprint(out, "Amount due = %8.2f\r
16       out.flush();
17    }
18 }
```

Listing 1.15 printf3/Printf3.java

```
1  import java.io.*;
2
3  /**
```

```
 * @version 1.10 1997-07-01
 * @author Cay Horstmann
 */
class Printf3
{
   public static native void fprint(PrintWriter
   static
   {
      System.loadLibrary("Printf3");
   }
}
```

Listing 1.16 printf3/Printf3.c

```
/**
   @version 1.10 1997-07-01
   @author Cay Horstmann
*/

#include "Printf3.h"
#include <string.h>
#include <stdlib.h>
#include <float.h>

/**
   @param format a string containing a printf f
   (such as "%8.2f"). Substrings "%%" are skipp
```

```
   @return a pointer to the format specifier (s
   or NULL if there wasn't a unique format spec
*/
char* find_format(const char format[])
{
   char* p;
   char* q;

   p = strchr(format, '%');
   while (p != NULL && *(p + 1) == '%') /* skip
      p = strchr(p + 2, '%');
   if (p == NULL) return NULL;
   /* now check that % is unique */
   p++;
   q = strchr(p, '%');
   while (q != NULL && *(q + 1) == '%') /* skip
      q = strchr(q + 2, '%');
   if (q != NULL) return NULL; /* % not unique
   q = p + strspn(p, " -0+#"); /* skip past fla
   q += strspn(q, "0123456789"); /* skip past f
   if (*q == '.') { q++; q += strspn(q, "12345
      /* skip past precision */
   if (strchr("eEfFgG", *q) == NULL) return NUL
      /* not a floating-point format */
   return p;
}

JNIEXPORT void JNICALL Java_Printf3_fprint(JNIE
```

```
42          jobject out, jstring format, jdouble x)
43  {
44     const char* cformat;
45     char* fmt;
46     jstring str;
47     jclass class_PrintWriter;
48     jmethodID id_print;
49
50     cformat = (*env)->GetStringUTFChars(env, for
51     fmt = find_format(cformat);
52     if (fmt == NULL)
53        str = format;
54     else
55     {
56        char* cstr;
57        int width = atoi(fmt);
58        if (width == 0) width = DBL_DIG + 10;
59        cstr = (char*) malloc(strlen(cformat) + w
60        sprintf(cstr, cformat, x);
61        str = (*env)->NewStringUTF(env, cstr);
62        free(cstr);
63     }
64     (*env)->ReleaseStringUTFChars(env, format, c
65
66     /* now call out.print(str) */
67
68     /* get the class */
69     class_PrintWriter = (*env)->GetObjectClass(e
```

```
70
71      /* get the method ID */
72      id_print = (*env)->GetMethodID(env, class_Pr
73
74      /* call the method */
75      (*env)->CallVoidMethod(env, out, id_print, s
76  }
```

Executing Java Methods

- `jmethodID GetMethodID(JNIEnv *env, jclass cl, const char name[], const char methodSignature[])`
  returns the identifier of a method in a class.
- `Xxx CallXxxMethod(JNIEnv *env, jobject obj, jmethodID id, args)`
- `Xxx CallXxxMethodA(JNIEnv *env, jobject obj, jmethodID id, jvalue args[])`
- `Xxx CallXxxMethodV(JNIEnv *env, jobject obj, jmethodID id, va_list args)`
  call a method. The return type `Xxx` is one of `Object`, `Boolean`, `Byte`, `Char`, `Short`, `Int`, `Long`, `Float`, or `Double`. The first function has a variable number of arguments—simply append the method arguments after the method ID. The second function receives the method arguments in an array of `jvalue`, where `jvalue` is a union defined as

```
typedef union jvalue
{
    jboolean z;
    jbyte b;
    jchar c;
    jshort s;
    jint i;
    jlong j;
    jfloat f;
    jdouble d;
    jobject l;
} jvalue;
```

The third function receives the method arguments in a `va_list`, as defined in the C header `stdarg.h`.

- `Xxx CallNonvirtualXxxMethod(JNIEnv *env, jobject obj, jclass cl, jmethodID id, args)`
- `Xxx CallNonvirtualXxxMethodA(JNIEnv *env, jobject obj, jclass cl, jmethodID id, jvalue args[])`
- `Xxx CallNonvirtualXxxMethodV(JNIEnv *env, jobject obj, jclass cl, jmethodID id, va_list args)`

call a method, bypassing dynamic dispatch. The return type `Xxx` is one of `Object`, `Boolean`, `Byte`, `Char`, `Short`, `Int`, `Long`, `Float`, or `Double`. The first function has a variable number of arguments. The second function receives the method

arguments in an array of `jvalue`. The third function receives the method arguments in a `va_list`, as defined in the C header `stdarg.h`.

- `jmethodID GetStaticMethodID(JNIEnv *env, jclass cl, const char name[], const char methodSignature[])` returns the identifier of a static method in a class.
- `Xxx CallStaticXxxMethod(JNIEnv *env, jclass cl, jmethodID id, args)`
- `Xxx CallStaticXxxMethodA(JNIEnv *env, jclass cl, jmethodID id, jvalue args[])`
- `Xxx CallStaticXxxMethodV(JNIEnv *env, jclass cl, jmethodID id, va_list args)`
  call a static method. The return type `Xxx` is one of `Object`, `Boolean`, `Byte`, `Char`, `Short`, `Int`, `Long`, `Float`, or `Double`. The first function has a variable number of arguments. The second function receives the method arguments in an array of `jvalue`. The third function receives the method arguments in a `va_list`, as defined in the C header `stdarg.h`.
- `jobject NewObject(JNIEnv *env, jclass cl, jmethodID id, args)`
- `jobject NewObjectA(JNIEnv *env, jclass cl, jmethodID id, jvalue args[])`
- `jobject NewObjectV(JNIEnv *env, jclass cl, jmethodID`

`id, va_list args)`
call a constructor. The method ID is obtained from `GetMethodID` with a method name of `"<init>"` and a return type of `void`. The first function has a variable number of arguments. The second function receives the method arguments in an array of `jvalue`. The third function receives the method arguments in a `va_list`, as defined in the C header `stdarg.h`.

1.7. Accessing Array Elements

All array types of the Java programming language have corresponding C types, as shown in Table 13.3.

Table 1.2: Correspondence between Java Array Types and C Types

Java Type	C Type	Java Type	C Type
`boolean[]`	`jbooleanArray`	`long[]`	`jlongArray`
`byte[]`	`jbyteArray`	`float[]`	`jfloatArray`
`char[]`	`jcharArray`	`double[]`	`jdoubleArra`
`int[]`	`jintArray`	`Object[]`	`jobjectArra`

Java Type	C Type	Java Type	C Type
`short[]`	`jshortArray`		

C++ Note: In C, all these array types are actually type synonyms of `jobject`. In C++, however, they are arranged in the inheritance hierarchy shown in Figure 13.3. The type `jarray` denotes a generic array.



Figure 1.3: Inheritance hierarchy of array types

The `GetArrayLength` function returns the length of an array.

```
jarray array = . . .;
```

```
jsize length = (*env)->GetArrayLength(env, array);
```

How you access elements in an array depends on whether the array stores objects or values of a primitive type (`bool`, `char`, or a numeric type). To access elements in an object array, use the `GetObjectArrayElement` and `SetObjectArrayElement` methods.

```
jobjectArray array = . . .;
int i, j;
jobject x = (*env)->GetObjectArrayElement(env, array,
(*env)->SetObjectArrayElement(env, array, j, x);
```

Although simple, this approach is also clearly inefficient; you want to be able to access array elements directly, especially when doing vector and matrix computations.

The `GetXxxArrayElements` function returns a C pointer to the starting element of an array. As with ordinary strings, you must remember to call the corresponding `ReleaseXxxArrayElements` function to tell the virtual machine when you no longer need that pointer. Here, the type `Xxx` must be a primitive type—that is, not `Object`. You can then read and write the array elements directly. However, since the pointer *might point to a copy*, any changes that

you make are guaranteed to be reflected in the original array only after you call the corresponding `ReleaseXxxArrayElements` function!

Note: You can find out if an array is a copy by passing a pointer to a `jboolean` variable as the third argument to a `GetXxxArrayElements` method. The variable is filled with `JNI_TRUE` if the array is a copy. If you aren't interested in that information, just pass a `NULL` pointer.

Here is an example that multiplies all elements in an array of `double` values by a constant. We obtain a C pointer `a` into the Java array and then access individual elements as `a[i]`.

```
jdoubleArray array_a = . . .;
double scaleFactor = . . .;
double* a = (*env)->GetDoubleArrayElements(env, array
for (i = 0; i < (*env)->GetArrayLength(env, array_a);
   a[i] = a[i] * scaleFactor;
(*env)->ReleaseDoubleArrayElements(env, array_a, a, 0
```

Whether the virtual machine actually copies the array depends on how it allocates arrays and does its garbage collection. Some

“copying” garbage collectors routinely move objects around and update object references. That strategy is not compatible with “pinning” an array to a particular location, because the collector cannot update the pointer values in native code.

Note: In the Oracle JVM implementation, `boolean` arrays are represented as packed arrays of 32-bit words. The `GetBooleanArrayElements` method copies them into unpacked arrays of `jboolean` values.

To access just a few elements of a large array, use the `GetXxxArrayRegion` and `SetXxxArrayRegion` methods that copy a range of elements from the Java array into a C array and back.

You can create new Java arrays in native methods with the `NewXxxArray` function. To create a new array of objects, specify the length, the type of the array elements, and an initial element for all entries (typically, `NULL`). Here is an example:

```
jclass class_Employee = (*env)->FindClass(env, "Emplo
jobjectArray array_e = (*env)->NewObjectArray(env, 10
```

Arrays of primitive types are simpler: Just supply the length of the array.

```
jdoubleArray array_d = (*env)->NewDoubleArray(env, 10
```

The array is then filled with zeroes.

Note: The following methods are used for working with "direct buffers":

```
jobject NewDirectByteBuffer(JNIEnv* env, v
void* GetDirectBufferAddress(JNIEnv* env,
jlong GetDirectBufferCapacity(JNIEnv* env,
```

Direct buffers are used in the `java.nio` package to support more efficient input/output operations and to minimize the copying of data between native and Java arrays.

`Manipulating Java Arrays`

- `jsize GetArrayLength(JNIEnv *env, jarray array)` returns the number of elements in the array.

- `jobject GetObjectArrayElement(JNIEnv *env, jobjectArray array, jsize index)`
  returns the value of an array element.
- `void SetObjectArrayElement(JNIEnv *env, jobjectArray array, jsize index, jobject value)`
  sets an array element to a new value.
- `Xxx* GetXxxArrayElements(JNIEnv *env, jarray array, jboolean* isCopy)`
  yields a C pointer to the elements of a Java array. The field type `Xxx` is one of `Boolean`, `Byte`, `Char`, `Short`, `Int`, `Long`, `Float`, or `Double`. The pointer must be passed to `ReleaseXxxArrayElements` when it is no longer needed. `isCopy` is either `NULL` or points to a `jboolean` that is filled with `JNI_TRUE` if a copy is made, with `JNI_FALSE` otherwise.
- `void ReleaseXxxArrayElements(JNIEnv *env, jarray array, Xxx elems[], jint mode)`
  notifies the virtual machine that a pointer obtained by `GetXxxArrayElements` is no longer needed. `mode` is one of `0` (free the `elems` buffer after updating the array elements), `JNI_COMMIT` (do not free the `elems` buffer after updating the array elements), or `JNI_ABORT` (free the `elems` buffer without updating the array elements).
- `void GetXxxArrayRegion(JNIEnv *env, jarray array,`

`jint start, jint length, Xxx elems[])`
copies elements from a Java array to a C array. The field type `Xxx` is one of `Boolean`, `Byte`, `Char`, `Short`, `Int`, `Long`, `Float`, or `Double`.

- `void SetXxxArrayRegion(JNIEnv *env, jarray array, jint start, jint length, Xxx elems[])`
copies elements from a C array to a Java array. The field type `Xxx` is one of `Boolean`, `Byte`, `Char`, `Short`, `Int`, `Long`, `Float`, or `Double`.

1.8. Handling Errors

Native methods are a significant security risk to Java programs. The C runtime system has no protection against array bounds errors, indirection through bad pointers, and so on. It is particularly important that programmers of native methods handle all error conditions to preserve the integrity of the Java platform. In particular, when your native method diagnoses a problem it cannot handle, it should report this problem to the Java virtual machine.

Normally, you would throw an exception in this situation. However, C has no exceptions. Instead, you must call the `Throw` or `ThrowNew` function to create a new exception object. When the native method exits, the Java virtual machine throws that exception.

To use the `Throw` function, call `NewObject` to create an object of a subtype of `Throwable`. For example, here we allocate an `EOFException` object and throw it:

```
jclass class_EOFException = (*env)->FindClass(env, "j
jmethodID id_EOFException = (*env)->GetMethodID(env,
   /* ID of no-argument constructor */
jthrowable obj_exc = (*env)->NewObject(env, class_EOF
(*env)->Throw(env, obj_exc);
```

It is usually more convenient to call `ThrowNew`, which constructs an exception object, given a class and a "modified UTF-8" byte sequence.

```
(*env)->ThrowNew(env, (*env)->FindClass(env, "java/io
   "Unexpected end of file");
```

Both `Throw` and `ThrowNew` merely *post* the exception; they do not interrupt the control flow of the native method. Only when the method returns does the Java virtual machine throw the exception. Therefore, every call to `Throw` and `ThrowNew` should be immediately followed by a `return` statement.

C++ Note: If you implement native methods in C++, you cannot throw a Java exception object in your C++ code. In a C++ binding, it would be possible to implement a translation between exceptions in C++ and Java; however, this is not currently done. Use `Throw` or `ThrowNew` to throw a Java exception in a native C++ method, and make sure your native methods throw no C++ exceptions.

Normally, native code need not be concerned with catching Java exceptions. However, when a native method calls a Java method, that method might throw an exception. Moreover, a number of the JNI functions throw exceptions as well. For example, `SetObjectArrayElement` throws an `ArrayIndexOutOfBoundsException` if the index is out of bounds, and an `ArrayStoreException` if the class of the stored object is not a subclass of the element class of the array. In situations like these, a native method should call the `ExceptionOccurred` method to determine whether an exception has been thrown. The call

```
jthrowable obj_exc = (*env)->ExceptionOccurred(env);
```

returns `NULL` if no exception is pending, or a reference to the current exception object. If you just want to check whether an

exception has been thrown, without obtaining a reference to the exception object, use

```
jboolean occurred = (*env)->ExceptionCheck(env);
```

Normally, a native method should simply return when an exception has occurred so that the virtual machine can propagate it to the Java code. However, a native method *may* analyze the exception object to determine if it can handle the exception. If it can, then the function

```
(*env)->ExceptionClear(env);
```

must be called to turn off the exception.

In our next example, we implement the `fprint` native method with all the paranoia appropriate for a native method. Here are the exceptions that we throw:

- A `NullPointerException` if the format string is `NULL`
- An `IllegalArgumentException` if the format string doesn't contain a `%` specifier that is appropriate for printing a `double`
- An `OutOfMemoryError` if the call to `malloc` fails

Finally, to demonstrate how to check for an exception when calling a Java method from a native method, we send the string to the

stream, a character at a time, and call `ExceptionOccurred` after each call. Listing 13.17 shows the code for the native method, and Listing 13.18 shows the definition of the class containing the native method. Notice that the native method does not immediately terminate when an exception occurs in the call to `PrintWriter.print`—it first frees the `cstr` buffer. When the native method returns, the virtual machine again raises the exception. The test program in Listing 13.19 demonstrates how the native method throws an exception when the formatting string is not valid.

Listing 1.17 printf4/Printf4.c

```
1  /**
2     @version 1.10 1997-07-01
3     @author Cay Horstmann
4  */
5
6  #include "Printf4.h"
7  #include <string.h>
8  #include <stdlib.h>
9  #include <float.h>
10
11 /**
12    @param format a string containing a printf f
13    (such as "%8.2f"). Substrings "%%" are skipp
```

```
   @return a pointer to the format specifier (s
   or NULL if there wasn't a unique format spec
 */
char* find_format(const char format[])
{
   char* p;
   char* q;

   p = strchr(format, '%');
   while (p != NULL && *(p + 1) == '%') /* skip
      p = strchr(p + 2, '%');
   if (p == NULL) return NULL;
   /* now check that % is unique */
   p++;
   q = strchr(p, '%');
   while (q != NULL && *(q + 1) == '%') /* skip
      q = strchr(q + 2, '%');
   if (q != NULL) return NULL; /* % not unique
   q = p + strspn(p, " -0+#"); /* skip past fla
   q += strspn(q, "0123456789"); /* skip past f
   if (*q == '.') { q++; q += strspn(q, "01234
      /* skip past precision */
   if (strchr("eEfFgG", *q) == NULL) return NUL
      /* not a floating-point format */
   return p;
}

JNIEXPORT void JNICALL Java_Printf4_fprint(JNIE
```

```
42    jobject out, jstring format, jdouble x)
43 {
44    const char* cformat;
45    char* fmt;
46    jclass class_PrintWriter;
47    jmethodID id_print;
48    char* cstr;
49    int width;
50    int i;
51
52    if (format == NULL)
53    {
54       (*env)->ThrowNew(env,
55          (*env)->FindClass(env,
56          "java/lang/NullPointerException"),
57          "Printf4.fprint: format is null");
58       return;
59    }
60
61    cformat = (*env)->GetStringUTFChars(env, for
62    fmt = find_format(cformat);
63
64    if (fmt == NULL)
65    {
66       (*env)->ThrowNew(env,
67          (*env)->FindClass(env,
68          "java/lang/IllegalArgumentException"),
69          "Printf4.fprint: format is invalid");
```

```
70          return;
71      }
72
73      width = atoi(fmt);
74      if (width == 0) width = DBL_DIG + 10;
75      cstr = (char*)malloc(strlen(cformat) + width
76
77      if (cstr == NULL)
78      {
79          (*env)->ThrowNew(env,
80              (*env)->FindClass(env, "java/lang/OutO
81              "Printf4.fprint: malloc failed");
82          return;
83      }
84
85      sprintf(cstr, cformat, x);
86
87      (*env)->ReleaseStringUTFChars(env, format, c
88
89      /* now call ps.print(str) */
90
91      /* get the class */
92      class_PrintWriter = (*env)->GetObjectClass(e
93
94      /* get the method ID */
95      id_print = (*env)->GetMethodID(env, class_Pr
96
97      /* call the method */
```

```
98    for (i = 0; cstr[i] != 0 && !(*env)->Excepti
99       (*env)->CallVoidMethod(env, out, id_print
100
101   free(cstr);
102}
```

Listing 1.18 printf4/Printf4.java

```
1  import java.io.*;
2
3  /**
4   * @version 1.10 1997-07-01
5   * @author Cay Horstmann
6   */
7  class Printf4
8  {
9     public static native void fprint(PrintWriter
10
11    static
12    {
13       System.loadLibrary("Printf4");
14    }
15 }
```

Listing 1.19 printf4/Printf4Test.java

```
1  import java.io.*;
2
3  /**
4   * @version 1.11 2018-05-01
5   * @author Cay Horstmann
6   */
7  class Printf4Test
8  {
9     public static void main(String[] args)
10    {
11       double price = 44.95;
12       double tax = 7.75;
13       double amountDue = price * (1 + tax / 100
14       var out = new PrintWriter(System.out);
15       /* This call will throw an exception--not
16       Printf4.fprint(out, "Amount due = %%8.2f%
17       out.flush();
18    }
19 }
```

`Handling Java Exceptions`

- `jint Throw(JNIEnv *env, jthrowable obj)`
  prepares an exception to be thrown upon exiting from the native code. Returns `0` on success, a negative value on failure.
- `jint ThrowNew(JNIEnv *env, jclass cl, const char msg[])`
  prepares an exception of type `cl` to be thrown upon exiting from the native code. Returns `0` on success, a negative value on failure. `msg` is a "modified UTF-8" byte sequence denoting the `String` construction argument of the exception object.
- `jthrowable ExceptionOccurred(JNIEnv *env)`
  returns the exception object if an exception is pending, or `NULL` otherwise.
- `jboolean ExceptionCheck(JNIEnv *env)`
  returns `true` if an exception is pending.
- `void ExceptionClear(JNIEnv *env)`
  clears any pending exceptions.

1.9. Using the Invocation API

Up to now, we have considered programs in the Java programming language that made a few C calls, presumably because C was faster or allowed access to functionality inaccessible from the Java platform. Suppose you are in the opposite situation. You have a C or

C++ program and would like to make calls to Java code. The *invocation API* enables you to embed the Java virtual machine into a C or C++ program. Here is the minimal code that you need to initialize a virtual machine:

```
JavaVMOption options[1];
JavaVMInitArgs vm_args;
JavaVM *jvm;
JNIEnv *env;

options[0].optionString = "-Djava.class.path=.";

memset(&vm_args, 0, sizeof(vm_args));
vm_args.version = JNI_VERSION_1_2;
vm_args.nOptions = 1;
vm_args.options = options;

JNI_CreateJavaVM(&jvm, (void**) &env, &vm_args);
```

The call to `JNI_CreateJavaVM` creates the virtual machine and fills in a pointer `jvm` to the virtual machine and a pointer `env` to the execution environment.

You can supply any number of options to the virtual machine. Simply increase the size of the `options` array and the value of `vm_args.nOptions`. For example,

```
options[i].optionString = "-Djava.compiler=NONE";
```

deactivates the just-in-time compiler.

Tip: When you run into trouble and your program crashes, refuses to initialize the JVM, or can't load your classes, turn on the JNI debugging mode. Set an option to

```
options[i].optionString = "-verbose:jni";
```

You will see a flurry of messages that indicate the progress in initializing the JVM. If you don't see your classes loaded, check both your path and class path settings.

Once you have set up the virtual machine, you can call Java methods as described in the preceding sections. Simply use the `env` pointer in the usual way.

You'll need the `jvm` pointer only to call other functions in the invocation API. Currently, there are only four such functions. The most important one is the function to terminate the virtual machine:

```
(*jvm)->DestroyJavaVM(jvm);
```

Unfortunately, under Windows, it has become difficult to dynamically link to the `JNI_CreateJavaVM` function in the `jre/bin/client/jvm.dll` library, due to the changed linking rules in Vista and Oracle's reliance on an older C runtime library. Our sample program overcomes this problem by loading the library manually. This is the same approach used by the `java` program—see the file `launcher/java_md.c` in the `src.jar` file that is a part of the JDK.

The C program in Listing 13.20 sets up a virtual machine and calls the `main` method of the `Welcome` class, which was discussed in Chapter 2 of Volume I. (Make sure to compile the `Welcome.java` file before starting the invocation test program.)

Listing 1.20 invocation/InvocationTest.c

```
1  /**
2     @version 1.20 2007-10-26
3     @author Cay Horstmann
4  */
5
6  #include <jni.h>
7  #include <stdlib.h>
```

```
 8
 9 #ifdef _WINDOWS
10
11 #include <windows.h>
12 static HINSTANCE loadJVMLibrary(void);
13 typedef jint (JNICALL *CreateJavaVM_t)(JavaVM *
14
15 #endif
16
17 int main()
18 {
19    JavaVMOption options[2];
20    JavaVMInitArgs vm_args;
21    JavaVM *jvm;
22    JNIEnv *env;
23    long status;
24
25    jclass class_Welcome;
26    jclass class_String;
27    jobjectArray args;
28    jmethodID id_main;
29
30 #ifdef _WINDOWS
31    HINSTANCE hjvmlib;
32    CreateJavaVM_t createJavaVM;
33 #endif
34
35    options[0].optionString = "-Djava.class.path
```

```
36
37    memset(&vm_args, 0, sizeof(vm_args));
38    vm_args.version = JNI_VERSION_1_2;
39    vm_args.nOptions = 1;
40    vm_args.options = options;
41
42 #ifdef _WINDOWS
43    hjvmlib = loadJVMLibrary();
44    createJavaVM = (CreateJavaVM_t) GetProcAddre
45    status = (*createJavaVM)(&jvm, (void **) &en
46 #else
47    status = JNI_CreateJavaVM(&jvm, (void **) &e
48 #endif
49
50    if (status == JNI_ERR)
51    {
52       fprintf(stderr, "Error creating VM\n");
53       return 1;
54    }
55
56    class_Welcome = (*env)->FindClass(env, "Welc
57    id_main = (*env)->GetStaticMethodID(env, cla
58
59    class_String = (*env)->FindClass(env, "java/
60    args = (*env)->NewObjectArray(env, 0, class_
61    (*env)->CallStaticVoidMethod(env, class_Welc
62
63    (*jvm)->DestroyJavaVM(jvm);
```

```
64
65      return 0;
66  }
67
68  #ifdef _WINDOWS
69
70  static int GetStringFromRegistry(HKEY key, cons
71  {
72      DWORD type, size;
73
74      return RegQueryValueEx(key, name, 0, &type,
75          && type == REG_SZ
76          && size < (unsigned int) bufsize
77          && RegQueryValueEx(key, name, 0, 0, buf,
78  }
79
80  static void GetPublicJREHome(char *buf, jint bu
81  {
82      HKEY key, subkey;
83      char version[MAX_PATH];
84
85      /* Find the current version of the JRE */
86      char *JRE_KEY = "Software\\JavaSoft\\Java Ru
87      if (RegOpenKeyEx(HKEY_LOCAL_MACHINE, JRE_KEY
88      {
89          fprintf(stderr, "Error opening registry k
90          exit(1);
91      }
```

```
92
93    if (!GetStringFromRegistry(key, "CurrentVers
94    {
95       fprintf(stderr, "Failed reading value of
96          JRE_KEY);
97       RegCloseKey(key);
98       exit(1);
99    }
100
101   /* Find directory where the current version
102   if (RegOpenKeyEx(key, version, 0, KEY_READ,
103   {
104     fprintf(stderr, "Error opening registry ke
105      RegCloseKey(key);
106      exit(1);
107   }
108
109   if (!GetStringFromRegistry(subkey, "JavaHome
110   {
111      fprintf(stderr, "Failed reading value of
112         JRE_KEY, version);
113      RegCloseKey(key);
114      RegCloseKey(subkey);
115      exit(1);
116   }
117
118   RegCloseKey(key);
119   RegCloseKey(subkey);
```

```
120 }
121
122 static HINSTANCE loadJVMLibrary(void)
123 {
124    HINSTANCE h1, h2;
125    char msvcdll[MAX_PATH];
126    char javadll[MAX_PATH];
127    GetPublicJREHome(msvcdll, MAX_PATH);
128    strcpy(javadll, msvcdll);
129    strncat(msvcdll, "\\bin\\msvcr71.dll", MAX_P
130    msvcdll[MAX_PATH - 1] = '\0';
131    strncat(javadll, "\\bin\\client\\jvm.dll", M
132    javadll[MAX_PATH - 1] = '\0';
133
134    h1 = LoadLibrary(msvcdll);
135    if (h1 == NULL)
136    {
137       fprintf(stderr, "Can't load library msvcr
138       exit(1);
139    }
140
141    h2 = LoadLibrary(javadll);
142    if (h2 == NULL)
143    {
144       fprintf(stderr, "Can't load library jvm.d
145       exit(1);
146    }
147    return h2;
```

```
148 }
149
150 #endif
```

To compile this program under Linux, use

```
gcc -I jdk/include -I jdk/include/linux -o InvocationT
   -L jdk/jre/lib/i386/client -ljvm InvocationTest.c
```

When compiling in Windows with the Microsoft compiler, use the command line

```
cl -D_WINDOWS -I jdk\include -I jdk\include\win32 Invo
   jdk\lib\jvm.lib advapi32.lib
```

You will need to make sure that the `INCLUDE` and `LIB` environment variables include the paths to the Windows API header and library files.

Using Cygwin, compile with

```
gcc -D_WINDOWS -mno-cygwin -I jdk\include -I jdk\inclu
   -I c:\cygwin\usr\include\w32api -o InvocationTest
```

Before you run the program under Linux/UNIX, make sure that the `LD_LIBRARY_PATH` contains the directories for the shared libraries. For example, if you use the `bash` shell on Linux, issue the following command:

```
export LD_LIBRARY_PATH=jdk/jre/lib/i386/client:$LD_LIB
```

`Invocation API Functions`

- `jint JNI_CreateJavaVM(JavaVM** p_jvm, void** p_env, JavaVMInitArgs* vm_args)`
  initializes the Java virtual machine. The function returns `0` if successful, `JNI_ERR` on failure. The `p_jvm` parameter is filled with a pointer to the invocation API function table, and `p_env` is filled with a pointer to the JNI function table.
- `jint DestroyJavaVM(JavaVM* jvm)`
  destroys the virtual machine. Returns `0` on success, a negative number on failure. This function must be called through a virtual machine pointer, that is, `(*jvm)->DestroyJavaVM(jvm)`.

1.10. A Complete Example: Accessing the Windows Registry

In this section, I describe a full, working example that covers everything we discussed in this chapter: using native methods with strings, arrays, objects, constructor calls, and error handling. I'll show you how to put a Java platform wrapper around a subset of the ordinary C-based APIs used to work with the Windows registry. Of course, the Windows registry being a Windows-specific feature, such a program is inherently nonportable. For that reason, the standard Java library has no support for the registry, and it makes sense to use native methods to gain access to it.

1.10.1. Overview of the Windows Registry

The Windows registry is a data depository that holds configuration information for the Windows operating system and application programs. It provides a single point for administration and backup of system and application preferences. On the downside, the registry is also a single point of failure—if you mess up the registry, your computer could malfunction or even fail to boot!

We don’t suggest that you use the registry to store configuration parameters for your Java programs. The Java preferences API is a better solution (see Chapter 10 of Volume I for more information). We'll simply use the registry to demonstrate how to wrap a nontrivial native API into a Java class.

The principal tool for inspecting the registry is the *registry editor.* Because of the potential for error by naive but enthusiastic users, there is no icon for launching the registry editor. Instead, start a DOS shell (or open the Start -> Run dialog box) and type `regedit`. Figure 13.4 shows the registry editor in action.



Figure 1.4: The registry editor

The left side shows the keys, which are arranged in a tree structure. Note that each key starts with one of the `HKEY` nodes like

```
HKEY_CLASSES_ROOT
HKEY_CURRENT_USER
HKEY_LOCAL_MACHINE
```

```
. . .
```

The right side shows the name/value pairs associated with a particular key. For example, if you installed Java 17, the key

```
HKEY_LOCAL_MACHINE\Software\JavaSoft\Java Runtime Env
```

contains a name/value pair such as

```
CurrentVersion="17.0_10"
```

In this case, the value is a string. The values can also be integers or arrays of bytes.

1.10.2. A Java Platform Interface for Accessing the Registry

We create a simple interface to access the registry from Java code, and then implement this interface with native code. The interface allows only a few registry operations; to keep the code size down, I omitted some important operations such as adding, deleting, and enumerating keys. (It should be easy to add the remaining registry API functions.)

Even with the limited subset that we supply, you can

- Enumerate all names stored in a key
- Read the value stored with a name
- Set the value stored with a name

Here is the Java class that encapsulates a registry key:

```
public class Win32RegKey
{
   public Win32RegKey(int theRoot, String thePath) {
   public Enumeration names() { . . . }
   public native Object getValue(String name);
   public native void setValue(String name, Object va

   public static final int HKEY_CLASSES_ROOT = 0×8000
   public static final int HKEY_CURRENT_USER = 0×8000
   public static final int HKEY_LOCAL_MACHINE = 0×800
   . . .
}
```

The `names` method returns an enumeration that holds all the names stored with the key. You can get at them with the familiar `hasMoreElements/nextElement` methods. The `getValue` method returns an object that is either a string, an `Integer` object,

or a byte array. The value parameter of the `setValue` method must also be of one of these three types.

1.10.3. Implementation of Registry Access Functions as Native Methods

We need to implement three actions:

- Get the value of a name
- Set the value of a name
- Iterate through the names of a key

In this chapter, you have seen essentially all the tools that are required, such as the conversion between Java strings and arrays and those of C. You also saw how to raise a Java exception in case something goes wrong.

Two issues make these native methods more complex than the preceding examples. The `getValue` and `setValue` methods deal with the type `Object`, which can be one of `String`, `Integer`, or `byte[]`. The enumeration object stores the state between successive calls to `hasMoreElements` and `nextElement`.

Let us first look at the `getValue` method. The method (shown in Listing 13.22) goes through the following steps:

1. Opens the registry key. To read their values, the registry API requires that keys be open.
2. Queries the type and size of the value associated with the name.
3. Reads the data into a buffer.
4. Calls `NewStringUTF` to create a new string with the value data if the type is `REG_SZ` (a string).
5. Invokes the `Integer` constructor if the type is `REG_DWORD` (a 32-bit integer).
6. Calls `NewByteArray` to create a new byte array, then `SetByteArrayRegion` to copy the value data into the byte array, if the type is `REG_BINARY`.
7. If the type is none of these or if an error occurred when an API function was called, throws an exception and releases all resources that had been acquired up to that point.
8. Closes the key and returns the object (`String`, `Integer`, or `byte[]`) that had been created.

As you can see, this example illustrates quite nicely how to generate Java objects of different types.

In this native method, coping with the generic return type is not difficult. The `jstring`, `jobject`, or `jarray` reference is simply returned as a `jobject`. However, the `setValue` method receives a reference to an `Object` and must determine the `Object`'s exact type to save the `Object` as a string, integer, or byte array. We can

make this determination by querying the class of the `value` object, finding the class references for `java.lang.String`, `java.lang.Integer`, and `byte[]`, and comparing them with the `IsAssignableFrom` function.

If `class1` and `class2` are two class references, then the call

```
(*env)->IsAssignableFrom(env, class1, class2)
```

returns `JNI_TRUE` when `class1` and `class2` are the same class or when `class1` is a subclass of `class2`. In either case, references to objects of `class1` can be cast to `class2`. For example, when

```
(*env)->IsAssignableFrom(env, (*env)->GetObjectClass(
   (*env)->FindClass(env, "[B"))
```

is `true`, we know that `value` is a byte array.

Here is an overview of the steps in the `setValue` method:

1. Open the registry key for writing.
2. Find the type of the value to write.
3. Call `GetStringUTFChars` to get a pointer to the characters if the type is `String`.

4. Call the `intValue` method to get the integer stored in the wrapper object if the type is `Integer`.
5. Call `GetByteArrayElements` to get a pointer to the bytes if the type is `byte[]`.
6. Pass the data and length to the registry.
7. Close the key.
8. Release the pointer to the data if the type is `String` or `byte[]`.

Finally, let us turn to the native methods that enumerate keys. These are methods of the `Win32RegKeyNameEnumeration` class (see Listing 13.21). When the enumeration process starts, we must open the key. For the duration of the enumeration, we must retain the key handle—that is, the key handle must be stored with the enumeration object. The key handle is of type `DWORD` (a 32-bit quantity), so it can be stored in a Java integer. We store it in the `hkey` field of the enumeration class. When the enumeration starts, the field is initialized with `SetIntField`. Subsequent calls read the value with `GetIntField`.

In this example, we store three other data items with the enumeration object. When the enumeration first starts, we can query the registry for the count of name/value pairs and the length of the longest name, which we need so we can allocate C character arrays to hold the names. These values are stored in the `count` and `maxsize` fields of the enumeration object. Finally, the `index` field,

initialized with `-1` to indicate the start of the enumeration, is set to `0` once the other instance fields are initialized, and is incremented after every enumeration step.

Let's walk through the native methods that support the enumeration. The `hasMoreElements` method is simple:

1. Retrieve the `index` and `count` fields.
2. If the index is `-1`, call the `startNameEnumeration` function which opens the key, queries the count and maximum length, and initializes the `hkey`, `count`, `maxsize`, and `index` fields.
3. Return `JNI_TRUE` if `index` is less than `count`, and `JNI_FALSE` otherwise.

The `nextElement` method needs to work a little harder:

1. Retrieve the `index` and `count` fields.
2. If the index is `-1`, call the `startNameEnumeration` function, which opens the key, queries the count and maximum length, and initializes the `hkey`, `count`, `maxsize`, and `index` fields.
3. If `index` equals `count`, throw a `NoSuchElementException`.
4. Read the next name from the registry.
5. Increment `index`.
6. If `index` equals `count`, close the key.

Before compiling, remember to run `javac -h` on both `Win32RegKey` and `Win32RegKeyNameEnumeration`. The complete command line for the Microsoft compiler is

```
cl -I jdk\include -I jdk\include\win32 -LD Win32RegKey
```

With Cygwin, use

```
gcc -mno-cygwin -D __int64="long long" -I jdk\include
   -I c:\cygwin\usr\include\w32api -shared -Wl,--add-
Win32RegKey.c
```

As the registry API is specific to Windows, this program will not work on other operating systems.

Listing 13.23 shows a program to test our new registry functions. We add three name/value pairs, a string, an integer, and a byte array to the key

```
HKEY_CURRENT_USER\Software\JavaSoft\Java Runtime Envi
```

We then enumerate all names of that key and retrieve their values. The program will print

```
Default user=Harry Hacker
Lucky number=13
Small primes=2 3 5 7 11 13
```

Although adding these name/value pairs to that key probably does no harm, you might want to use the registry editor to remove them after running this program.

Listing 1.21 win32reg/Win32RegKey.java

```
1  import java.util.*;
2
3  /**
4   * A Win32RegKey object can be used to get and
5   * registry.
6   * @version 1.00 1997-07-01
7   * @author Cay Horstmann
8   */
9  public class Win32RegKey
10 {
11    public static final int HKEY_CLASSES_ROOT =
12    public static final int HKEY_CURRENT_USER =
13    public static final int HKEY_LOCAL_MACHINE =
14    public static final int HKEY_USERS = 0x80000
15    public static final int HKEY_CURRENT_CONFIG
16    public static final int HKEY_DYN_DATA = 0x80
17
```

```
18    private int root;
19    private String path;
20
21    /**
22     * Gets the value of a registry entry.
23     * @param name the entry name
24     * @return the associated value
25     */
26    public native Object getValue(String name);
27
28    /**
29     * Sets the value of a registry entry.
30     * @param name the entry name
31     * @param value the new value
32     */
33    public native void setValue(String name, Obj
34
35    /**
36     * Construct a registry key object.
37     * @param theRoot one of HKEY_CLASSES_ROOT,
38     * HKEY_USERS, HKEY_CURRENT_CONFIG, HKEY_DYN
39     * @param thePath the registry key path
40     */
41    public Win32RegKey(int theRoot, String thePa
42    {
43       root = theRoot;
44       path = thePath;
45    }
```

```
46
47      /**
48       * Enumerates all names of registry entries
49       * @return an enumeration listing all entry
50       */
51      public Enumeration<String> names()
52      {
53         return new Win32RegKeyNameEnumeration(roo
54      }
55
56      static
57      {
58         System.loadLibrary("Win32RegKey");
59      }
60  }
61
62  class Win32RegKeyNameEnumeration implements Enu
63  {
64      public native String nextElement();
65      public native boolean hasMoreElements();
66      private int root;
67      private String path;
68      private int index = -1;
69      private int hkey = 0;
70      private int maxsize;
71      private int count;
72
73      Win32RegKeyNameEnumeration(int theRoot, Stri
```

```
74      {
75         root = theRoot;
76         path = thePath;
77      }
78   }
79
80   class Win32RegKeyException extends RuntimeExcep
81   {
82      public Win32RegKeyException()
83      {
84      }
85
86      public Win32RegKeyException(String why)
87      {
88         super(why);
89      }
90   }
```

Listing 1.22 win32reg/Win32RegKey.c

```
1   /**
2      @version 1.00 1997-07-01
3      @author Cay Horstmann
4   */
5
6   #include "Win32RegKey.h"
7   #include "Win32RegKeyNameEnumeration.h"
8   #include <string.h>
```

```
#include <stdlib.h>
#include <windows.h>

JNIEXPORT jobject JNICALL Java_Win32RegKey_getV
      JNIEnv* env, jobject this_obj, jobject na
{
   const char* cname;
   jstring path;
   const char* cpath;
   HKEY hkey;
   DWORD type;
   DWORD size;
   jclass this_class;
   jfieldID id_root;
   jfieldID id_path;
   HKEY root;
   jobject ret;
   char* cret;

   /* get the class */
   this_class = (*env)->GetObjectClass(env, thi

   /* get the field IDs */
   id_root = (*env)->GetFieldID(env, this_class
   id_path = (*env)->GetFieldID(env, this_class

   /* get the fields */
   root = (HKEY) (*env)->GetIntField(env, this_
```

```
37    path = (jstring)(*env)->GetObjectField(env,
38    cpath = (*env)->GetStringUTFChars(env, path,
39
40    /* open the registry key */
41    if (RegOpenKeyEx(root, cpath, 0, KEY_READ, &
42    {
43       (*env)->ThrowNew(env, (*env)->FindClass(e
44             "Open key failed");
45       (*env)->ReleaseStringUTFChars(env, path,
46       return NULL;
47    }
48
49    (*env)->ReleaseStringUTFChars(env, path, cpa
50    cname = (*env)->GetStringUTFChars(env, name,
51
52    /* find the type and size of the value */
53    if (RegQueryValueEx(hkey, cname, NULL, &type
54    {
55       (*env)->ThrowNew(env, (*env)->FindClass(e
56             "Query value key failed");
57       RegCloseKey(hkey);
58       (*env)->ReleaseStringUTFChars(env, name,
59       return NULL;
60    }
61
62    /* get memory to hold the value */
63    cret = (char*)malloc(size);
64
```

```
65    /* read the value */
66    if (RegQueryValueEx(hkey, cname, NULL, &type
67    {
68       (*env)->ThrowNew(env, (*env)->FindClass(e
69             "Query value key failed");
70       free(cret);
71       RegCloseKey(hkey);
72       (*env)->ReleaseStringUTFChars(env, name,
73       return NULL;
74    }
75
76    /* depending on the type, store the value in
77       integer, or byte array */
78    if (type == REG_SZ)
79    {
80       ret = (*env)->NewStringUTF(env, cret);
81    }
82    else if (type == REG_DWORD)
83    {
84       jclass class_Integer = (*env)->FindClass(
85       /* get the method ID of the constructor *
86       jmethodID id_Integer = (*env)->GetMethodI
87       int value = *(int*) cret;
88       /* invoke the constructor */
89       ret = (*env)->NewObject(env, class_Intege
90    }
91    else if (type == REG_BINARY)
92    {
```

```
93          ret = (*env)->NewByteArray(env, size);
94          (*env)->SetByteArrayRegion(env, (jarray)
95       }
96       else
97       {
98          (*env)->ThrowNew(env, (*env)->FindClass(e
99                "Unsupported value type");
100         ret = NULL;
101      }
102
103      free(cret);
104      RegCloseKey(hkey);
105      (*env)->ReleaseStringUTFChars(env, name, cna
106
107      return ret;
108   }
109
110   JNIEXPORT void JNICALL Java_Win32RegKey_setValu
111         jstring name, jobject value)
112   {
113      const char* cname;
114      jstring path;
115      const char* cpath;
116      HKEY hkey;
117      DWORD type;
118      DWORD size;
119      jclass this_class;
120      jclass class_value;
```

```
121     jclass class_Integer;
122     jfieldID id_root;
123     jfieldID id_path;
124     HKEY root;
125     const char* cvalue;
126     int ivalue;
127
128     /* get the class */
129     this_class = (*env)->GetObjectClass(env, thi
130
131     /* get the field IDs */
132     id_root = (*env)->GetFieldID(env, this_class
133     id_path = (*env)->GetFieldID(env, this_class
134
135     /* get the fields */
136     root = (HKEY)(*env)->GetIntField(env, this_c
137     path = (jstring)(*env)->GetObjectField(env,
138     cpath = (*env)->GetStringUTFChars(env, path,
139
140     /* open the registry key */
141     if (RegOpenKeyEx(root, cpath, 0, KEY_WRITE,
142     {
143        (*env)->ThrowNew(env, (*env)->FindClass(e
144              "Open key failed");
145        (*env)->ReleaseStringUTFChars(env, path,
146        return;
147     }
148
```

```
149     (*env)->ReleaseStringUTFChars(env, path, cpa
150     cname = (*env)->GetStringUTFChars(env, name,
151
152     class_value = (*env)->GetObjectClass(env, va
153     class_Integer = (*env)->FindClass(env, "java
154     /* determine the type of the value object */
155     if ((*env)->IsAssignableFrom(env, class_valu
156     {
157        /* it is a string--get a pointer to the d
158        cvalue = (*env)->GetStringUTFChars(env, (
159        type = REG_SZ;
160        size = (*env)->GetStringLength(env, (jstr
161     }
162     else if ((*env)->IsAssignableFrom(env, class
163     {
164        /* it is an integer--call intValue to get
165        jmethodID id_intValue = (*env)->GetMethod
166        ivalue = (*env)->CallIntMethod(env, value
167        type = REG_DWORD;
168        cvalue = (char*)&ivalue;
169        size = 4;
170     }
171     else if ((*env)->IsAssignableFrom(env, class
172     {
173        /* it is a byte array--get a pointer to t
174        type = REG_BINARY;
175        cvalue = (char*)(*env)->GetByteArrayEleme
176        size = (*env)->GetArrayLength(env, (jarra
```

```
177     }
178     else
179     {
180        /* we don't know how to handle this type
181        (*env)->ThrowNew(env, (*env)->FindClass(e
182              "Unsupported value type");
183        RegCloseKey(hkey);
184        (*env)->ReleaseStringUTFChars(env, name,
185        return;
186     }
187
188     /* set the value */
189     if (RegSetValueEx(hkey, cname, 0, type, cval
190     {
191        (*env)->ThrowNew(env, (*env)->FindClass(e
192              "Set value failed");
193     }
194
195     RegCloseKey(hkey);
196     (*env)->ReleaseStringUTFChars(env, name, cna
197
198     /* if the value was a string or byte array,
199     if (type == REG_SZ)
200     {
201        (*env)->ReleaseStringUTFChars(env, (jstri
202     }
203     else if (type == REG_BINARY)
204     {
```

```
205         (*env)->ReleaseByteArrayElements(env, (ja
206     }
207 }
208
209 /* helper function to start enumeration of name
210 static int startNameEnumeration(JNIEnv* env, jo
211 {
212     jfieldID id_index;
213     jfieldID id_count;
214     jfieldID id_root;
215     jfieldID id_path;
216     jfieldID id_hkey;
217     jfieldID id_maxsize;
218
219     HKEY root;
220     jstring path;
221     const char* cpath;
222     HKEY hkey;
223     DWORD maxsize = 0;
224     DWORD count = 0;
225
226     /* get the field IDs */
227     id_root = (*env)->GetFieldID(env, this_class
228     id_path = (*env)->GetFieldID(env, this_class
229     id_hkey = (*env)->GetFieldID(env, this_class
230     id_maxsize = (*env)->GetFieldID(env, this_cl
231     id_index = (*env)->GetFieldID(env, this_clas
232     id_count = (*env)->GetFieldID(env, this_clas
```

```
233
234     /* get the field values */
235     root = (HKEY)(*env)->GetIntField(env, this_c
236     path = (jstring)(*env)->GetObjectField(env,
237     cpath = (*env)->GetStringUTFChars(env, path,
238
239     /* open the registry key */
240     if (RegOpenKeyEx(root, cpath, 0, KEY_READ, &
241     {
242        (*env)->ThrowNew(env, (*env)->FindClass(e
243              "Open key failed");
244        (*env)->ReleaseStringUTFChars(env, path,
245        return -1;
246     }
247     (*env)->ReleaseStringUTFChars(env, path, cpa
248
249     /* query count and max length of names */
250     if (RegQueryInfoKey(hkey, NULL, NULL, NULL,
251            NULL, NULL, NULL) != ERROR_SUCCESS)
252     {
253        (*env)->ThrowNew(env, (*env)->FindClass(e
254              "Query info key failed");
255        RegCloseKey(hkey);
256        return -1;
257     }
258
259     /* set the field values */
260     (*env)->SetIntField(env, this_obj, id_hkey,
```

```
261     (*env)->SetIntField(env, this_obj, id_maxsiz
262     (*env)->SetIntField(env, this_obj, id_index,
263     (*env)->SetIntField(env, this_obj, id_count,
264     return count;
265 }
266
267 JNIEXPORT jboolean JNICALL Java_Win32RegKeyName
268         jobject this_obj)
269 {
270     jclass this_class;
271     jfieldID id_index;
272     jfieldID id_count;
273     int index;
274     int count;
275     /* get the class */
276     this_class = (*env)->GetObjectClass(env, thi
277
278     /* get the field IDs */
279     id_index = (*env)->GetFieldID(env, this_clas
280     id_count = (*env)->GetFieldID(env, this_clas
281
282     index = (*env)->GetIntField(env, this_obj, i
283     if (index == -1) /* first time */
284     {
285         count = startNameEnumeration(env, this_ob
286         index = 0;
287     }
288     else
```

```
289         count = (*env)->GetIntField(env, this_obj
290     return index < count;
291 }
292 
293 JNIEXPORT jobject JNICALL Java_Win32RegKeyNameE
294         jobject this_obj)
295 {
296     jclass this_class;
297     jfieldID id_index;
298     jfieldID id_hkey;
299     jfieldID id_count;
300     jfieldID id_maxsize;
301 
302     HKEY hkey;
303     int index;
304     int count;
305     DWORD maxsize;
306 
307     char* cret;
308     jstring ret;
309 
310     /* get the class */
311     this_class = (*env)->GetObjectClass(env, thi
312 
313     /* get the field IDs */
314     id_index = (*env)->GetFieldID(env, this_clas
315     id_count = (*env)->GetFieldID(env, this_clas
316     id_hkey = (*env)->GetFieldID(env, this_class
```

```
317     id_maxsize = (*env)->GetFieldID(env, this_cl
318
319     index = (*env)->GetIntField(env, this_obj, i
320     if (index == -1) /* first time */
321     {
322        count = startNameEnumeration(env, this_ob
323        index = 0;
324     }
325     else
326        count = (*env)->GetIntField(env, this_obj
327
328     if (index >= count) /* already at end */
329     {
330        (*env)->ThrowNew(env, (*env)->FindClass(e
331              "past end of enumeration");
332        return NULL;
333     }
334
335     maxsize = (*env)->GetIntField(env, this_obj,
336     hkey = (HKEY)(*env)->GetIntField(env, this_o
337     cret = (char*)malloc(maxsize);
338
339     /* find the next name */
340     if (RegEnumValue(hkey, index, cret, &maxsize
341     {
342        (*env)->ThrowNew(env, (*env)->FindClass(e
343              "Enum value failed");
344        free(cret);
```

```
345         RegCloseKey(hkey);
346         (*env)->SetIntField(env, this_obj, id_inc
347         return NULL;
348      }
349
350      ret = (*env)->NewStringUTF(env, cret);
351      free(cret);
352
353      /* increment index */
354      index++;
355      (*env)->SetIntField(env, this_obj, id_index,
356
357      if (index == count) /* at end */
358      {
359         RegCloseKey(hkey);
360      }
361
362      return ret;
363   }
```

Listing 1.23 win32reg/Win32RegKeyTest.java

```
1  import java.util.*;
2
3  /**
4     @version 1.04 2021-05-30
5     @author Cay Horstmann
6  */
```

```
7  public class Win32RegKeyTest
8  {
9     public static void main(String[] args)
10    {
11       var key = new Win32RegKey(
12          Win32RegKey.HKEY_CURRENT_USER, "Softwa
13
14       key.setValue("Default user", "Harry Hacke
15       key.setValue("Lucky number", Integer.valu
16       key.setValue("Small primes", new byte[] {
17
18       Enumeration<String> e = key.names();
19
20       while (e.hasMoreElements())
21       {
22          String name = e.nextElement();
23          System.out.print(name + "=");
24
25          Object value = key.getValue(name);
26
27          if (value instanceof byte[] bytes)
28             for (byte b : bytes) System.out.pri
29          else
30             System.out.print(value);
31
32          System.out.println();
```

```
        }
    }
}
```

`Type Inquiry Functions`

- `jboolean IsAssignableFrom(JNIEnv *env, jclass cl1, jclass cl2)`
  returns `JNI_TRUE` if objects of the first class can be assigned to objects of the second class, and `JNI_FALSE` otherwise. This tests if the classes are the same, or `cl1` is a subclass of `cl2`, or `cl2` represents an interface implemented by `cl1` or one of its superclasses.
- `jclass GetSuperclass(JNIEnv *env, jclass cl)`
  returns the superclass of a class. If `cl` represents the class `Object` or an interface, returns `NULL`.

1.11. Foreign Functions: A Glimpse into the Future

When using JNI, you have to write C code to access Java data structures, call the desired C functions, and to convert the result back to Java. Then you have to link the C code into platform-specific libraries. An API for accessing “foreign” functions and memory,

developed under the code name "Project Panama," allows you to write this code in Java.

In Java 21, the API is a preview feature, and the details may change before the final release. The program in Listing 13.24 is a very simple demonstration of the preview API.

The program simply calls the `printf` function. No additional C code is necessary. The function is invoked through a Java `MethodHandle`, which is normally used to call Java functions.

To access C functions, you first create a `Linker` object. The `Linker` can produce a Java method handle for a C function, given its address and type description.

The API has methods for translating Java objects into memory blocks that you can pass to the C function. In the demo, you need to provide a `char*` with the characters from a Java `String`.

The memory is allocated in an `Arena`, so that its deallocation can be managed. Here, we use a *confined* arena. It is autocloseable, and the `close` method deallocates all allocated memory.

As you can see, this API is much simpler and more convenient than JNI. This demo only scratches the surface of the API. There are

many methods for reading, writing, and managing memory blocks. You can also pass Java functions as callbacks to C functions.

To compile the demo program, use these options:

```
javac --enable-preview --source 21 panama/PanamaDemo.
```

The foreign function and memory API is inherently unsafe because it provides access to unmanaged memory. You use a runtime flag to permit a module to use the API. Typically, one would place the bridge code between a Java API and a C library into a separate module. However, in the demo, the native access happens in the unnamed module. Here is the command line to run it:

```
java --enable-preview --enable-native-access=ALL-UNNA
```

As a more realistic example, the companion code contains another demo program that calls an external library implementing the Argon 2 password hash algorithm, which is not currently a part of the JDK.

For now, you will still need to use JNI as a stable API for interoperating with native code. As the foreign function and memory API matures, it will provide a superior replacement for JNI.

Listing 1.24 panama/PanamaDemo.java

```
1  package panama;
2
3  import java.lang.invoke.*;
4  import java.lang.foreign.*;
5
6  /*
7
8  javac --enable-preview --source 21 panama/Panam
9
10 java --enable-preview --enable-native-access=AL
11
12 */
13
14 public class PanamaDemo
15 {
16    public static void main(String[] args) throw
17    {
18       Linker linker = Linker.nativeLinker();
19       MethodHandle printf = linker.downcallHand
20          linker.defaultLookup().find("printf")
21          FunctionDescriptor.of(ValueLayout.JAVA
22
23       try (Arena arena = Arena.ofConfined())
24       {
25          MemorySegment str = arena.allocateUtf8
26          int result = (int) printf.invoke(str);
```

```
27            System.out.printf("Printed %d characte
28         }
29      }
30   }
```

You have now reached the end of the second volume of *Core Java*, completing a long journey in which you encountered many advanced APIs. I started out with topics that every Java programmer needs to know: streams, XML, networking, databases, and internationalization. I concluded with very technical chapters on security, annotation processing, advanced graphics, and native methods. I hope that you enjoyed your tour through the vast breadth of the Java APIs, and that you will be able to apply your newly gained knowledge in your projects.